SR 227 Operations Study

Public Workshop 3
Sept. 15, 2016
Los Ranchos Elementary

San Luis Obispo Council of Governments



What the study addresses



Source: SLO Tribune



What the study addresses



Congestion

Side street access

Safety

Multimodal access

Source: SLO Tribune



Date	Activity
June 2015	Public comments expressed concerns about safety, access and other factors; Board authorized study
September	Kickoff East Airport Business Alliance presentation
November	Public Workshop 1 @ Los Ranchos Elementary
Jan-Feb 2016	Traffic counts
Jan-Apr	Travel time data collection
Feb-May	Traffic assessments and other analyses
May	Public Workshop 2 @ Los Ranchos Elementary
June	First (admin) draft
July-Aug	Stakeholder review
Aug-Sept	Second draft (public review)
September	Public Workshop 3 @ Los Ranchos Elementary



Date	Activity
September	Public Workshop 3 @ Los Ranchos Elementary
September 28	Advisory committee review
October 12	Board reviews draft, releases for final public comment
November 16	Advisory committee review
December 7	Board consideration of adoption



What the study measures

- Intersection delay and level of service (LOS)
- Volume/capacity ratio
- Corridor travel times
- Travel time reliability
- Local vs. regional traffic
- Location and type of recent crashes
- Bicycle and pedestrian traffic volumes

- Relinquishment assessment
- Environmental screening technical memo
- Future transit service assessment
- Signal warrant analysis
- Intersection Control Evaluations (ICE)



Finding the most cost-effective alternative Benefit-Cost Analysis

Monetized benefits







Policy Consistency Environmental Sensitivity

Community Support

Social Equity

Ancillary Benefits





Analysis years

- Existing conditions
- 2025
- 2035


Alternatives evaluated

Widening with Coordinated Adaptive Signal Control






Roundabout Corridor






Recommended alternative: Roundabout Corridor Delay





Recommended alternative: Roundabout Corridor Average speed at intersections, PM peak (mph)





Corridor travel time

Scenario	Corridor Concept	AM peak travel time (min)	PM peak travel time (min)	% change from 2035 "no build"
2015 Existing Conditions	Signals, stop signs	7.9	6.6	
2035 Existing Corridor	Signals, stop signs	8.5	9.0	
2035	Signal Corridor	2.4	2.4	(72%)
2035	Roundabout Corridor	2.2	2.3	(74%)



What it's like to... turn left from Crestmont





What it's like to... turn left from Crestmont

	AM peak		PM peak	
Scenario	Delay (sec)	LOS	Delay (sec)	LOS
Today	>300	F	280	F
2025 (no build	>300	F	>300	F
2035	>300	F	>300	F
2035 Signal Corridor	40.1	D	40.9	D
2035 Roundabout Corridor	7.4	Α	14.2	В



What it's like to... turn left from Los Ranchos




What it's like to... turn left from Los Ranchos

	AM peak		PM peak	
Scenario	Delay (sec)	LOS	Delay (sec)	LOS
Today	34.7	С	68.5	E
2025 (no build	35.3	D	69.9	E
2035	32.4	С	72.3	Е
2035 Signal Corridor	38.9	D	38.7	D
2035 Roundabout Corridor	12.0	В	26.6	D




Recommended alternative: Roundabout Corridor Safety






Roundabouts *Proven safety countermeasure*

- Reduce intersection vehicle and pedestrian conflict points
- Reduce intersection speeds
- Reduce overall crashes
- Reduce severity of crashes
- Reduce road widths






Roundabout Characteristics








Roundabout Characteristics








Recommended alternative: Roundabout Corridor Emissions






Recommended alternative: Roundabout Corridor Operations and Maintenance Costs





Recommended alternative: Roundabout Corridor Initial Capital Costs



- Total initial costs
 - Signal Corridor: \$11.3 million
 - Roundabout Corridor: \$10.8 million



Total costs

Item	Signal Corridor	Roundabout Corridor
Total initial cost	11,300,000	10,800,000
Operations and maintenance (over 20 years) – intersections	650,000	250,000
Maintenance (over 20 years) – segments	>2,400,000	2,400,000
Total	>14,350,000	13,450,000



Recommended alternative: Roundabout Corridor Footprint



Signal Corridor

- Add channelization (turn lanes)
 at all four intersections
- Given 45-55 mph design speeds, widening to four lanes is required
- Roundabout Corridor
 - 200 ft. taper at intersection approaches
 - Between intersections,
 maintain two-lane road



Funding scenarios

- Existing funding: \$1,750,000 (at risk of being reallocated)
- Projected funding: Best case: \$3,000,000 total
- Supplemental funding: Measure J: \$1,750,000 + \$8,000,000 = \$9,750,000



Improvement phasing: Short term (0-5 yrs)

- Begin preliminary engineering for Los Ranchos and Buckley roundabouts; build Los Ranchos roundabout, subject to Caltrans process
- **Begin coordination** on Rolling Hills secondary access
- Interim channelization improvements at Crestmont Dr. (assess / install?)
- Rehabilitate pathway from Los Ranchos to Crestmont to become part of the Edna-Price Canyon Trail, extend trail on west side of road from Crestmont to Tank Farm (begin preliminary engineering)
- Re-align Airport Dr. with Farmhouse
- Widen <u>northbound</u> 227 to four through lanes from Farmhouse to just south of Kendall
- Right-in/right-out/left-in at Kendall (left-outs at Farmhouse)
- Install rumble strips from Airport Dr. to Los Ranchos

Bold text = immediate action (0-1 yrs)



Improvement phasing: Mid term (0-10 yrs)

- Build Buckley Rd. roundabout
- Construct secondary access connecting Rolling Hills to Buckley Rd.
 - With traffic calming treatments to reduce speeds and discourage cut-through traffic



Improvement phasing: Long term (10-20 yrs)

- Build Crestmont Dr. roundabout
- Build Farmhouse Ln. roundabout



CONTACT INFORMATION

Jeff Brubaker, AICP
Transportation Planner

805-788-2104 jbrubaker@slocog.org