VOLUME I

FINAL ENVIRONMENTAL IMPACT REPORT

Cold Canyon Landfill Expansion
Conditional Use Permit
ED06-126; DRC2005-00170

SCH# 2006101173

Prepared by:

SWCA ENVIRONMENTAL CONSULTANTS
1422 Monterey Street, Suite C200
San Luis Obispo, CA 93401

Prepared for:

COUNTY OF SAN LUIS OBISPO
Department of Planning and Building
County Government Center, Room 200
San Luis Obispo, CA 93408

MAY 2012

VOLUME I – FINAL ENVIRONMENTAL IMPACT REPORT

Cold Canyon Landfill Expansion
Conditional Use Permit
ED06-126; DRC2005-00170
SCH# 2006101173

FINAL

ENVIRONMENTAL IMPACT REPORT

Prepared for:

Mr. John Nall
County of San Luis Obispo
Department of Planning & Building
County Government Center, Room 200
San Luis Obispo, CA 93408

Prepared by:

SWCA®
ENVIRONMENTAL CONSULTANTS
Sound Science. Creative Solutions.®

May 2012

1422 MONTEREY STREET, SUITE C200 • SAN LUIS OBISPO, CA 93401• (805)543-7095 FAX 543-2367

VOLUME I
TABLE OF CONTENTS

I. INTRODUCTION I-1

A. Purpose of the EIR I-1
B. EIR Structure I-2
1. Scoping Process I-2
2. EIR Contents I-2
3. EIR Terminology I-3
C. Agency Use of the Document I-3
1. California Integrated Waste Management Board I-4
D. Project Sponsors and Contact Persons I-4
E. Review of the Draft EIR I-5
F. Recirculation of the 2009 Draft EIR (2011 RDEIR) I-5
1. Water Resources I-6
2. Compost Operation Review and Revocation Process I-6
3. Other Technical Reports I-7
G. Alternative Composting Technologies I-7

II. SUMMARY II-1

A. Project Location II-1
B. Project Objectives II-1
C. Project Components II-2
D. Project Definitions and Common Acronyms II-2
E. Areas of Controversy II-3
F. Impact Summary Tables II-4
G. Summary of Alternatives II-63

III. PROJECT DESCRIPTION III-1

A. Project Summary III-1
B. Project Location III-1
C. Project Background III-1
1. Existing Operations III-2
2. Existing Permit Conditions of Approval III-16
D. Proposed Project III-18
1. Expansion of Landfill Capacity III-18
2. Increase in Permitted Tonnage Limits III-19
~~3. Expansion and Modification of Compost Operation ..... III-20~~
3~~4~~. Expansion and Relocation of Resource Recovery Park III-27
4~~5~~. Expansion and Enhancement of Materials Recovery Facility III-27
5~~6~~. Construction of New Entrance/Scalehouse III-27

6~~7~~. Modification of Hours of Operation III-28
7~~8~~. Increase Staffing III-29
8~~9~~. Miscellaneous Improvements III-29
9~~10~~. Landfill Closure and Long-term Maintenance III-30
10~~11~~. Earthwork III-30

E. Required Permits III-31

F. Project Timing and Phasing III-32

IV. ENVIRONMENTAL SETTING IV-1

A. Physical Setting and Existing Uses IV-1
1. Existing Landfill IV-1
2. Expansion Area IV-2

B. Surrounding Land Uses IV-2

C. Consistency With Plans and Policies IV-5
1. Overview IV-5
2. Relevant Land Use Plans IV-5

D. Cumulative Analysis IV-12
1. CEQA Requirements IV-12
2. Cumulative Development Scenario IV-12

V. ENVIRONMENTAL IMPACTS AND MITIGATION MEASURES V-1

A. Aesthetic Resources V-3
1. Existing Conditions V-3
2. Regulatory Setting V-4
3. Thresholds of Significance V-6
4. Impact Assessment and Methodology V-8
5. Project Visibility V-9
6. Project-specific Impacts and Mitigation Measures V-10
7. Cumulative Impacts V-19

B. Agricultural Resources V-51
1. Existing Conditions V-51
2. Regulatory Setting V-58
3. Thresholds of Significance V-59
4. Impact Assessment and Methodology V-60
5. Project-specific Impacts and Mitigation Measures V-65
6. Cumulative Impacts V-72

C. Air Quality V-73
1. Existing Conditions V-73
2. Regulatory Setting V-77
3. Thresholds of Significance V-78
4. Impact Assessment and Methodology V-81
5. Project-specific Impacts and Mitigation Measures V-82
6. Cumulative Impacts V-96

D. Biological Resources V-97
1. Existing Conditions V-97
2. Special-status Species and Sensitive Natural Communities V-104
3. Regulatory Setting V-107
4. Thresholds of Significance V-111
5. Impact Assessment and Methodology V-111
6. Project-specific Impacts and Mitigation Measures V-112
7. Cumulative Impacts V-123

E. Climate Change/Greenhouse Gas Emissions V-125
1. Existing Conditions V-125
2. Regulatory Setting V-128
3. Thresholds of Significance V-131
4. Impact Assessment and Methodology V-132
5. Project-specific Impacts and Mitigation Measures V-132
6. Cumulative Impacts V-138

F. Cultural Resources V-139
1. Paleontological Resources V-139
2. Pre-historic and Historic Resources V-143

G. Geology and Soils V-151
1. Existing Conditions V-151
2. Regulatory Setting V-169
3. Thresholds of Significance V-170
4. Impact Assessment and Methodology V-171
5. Project-specific Impacts and Mitigation Measures V-171
6. Cumulative Impacts V-177

H. Hazards and Hazardous Materials V-179
1. Existing Conditions V-180
2. Regulatory Setting V-186
3. Thresholds of Significance V-189
4. Impact Assessment and Methodology V-190
5. Project-specific Impacts and Mitigation Measures V-190
6. Cumulative Impacts V-207

I. Noise V-209
1. Existing Conditions V-209
2. Regulatory Setting V-216
3. Thresholds of Significance V-217
4. Impact Assessment and Methodology V-223
5. Project-specific Impacts and Mitigation Measures V-223
6. Cumulative Impacts V-237

J. Transportation and Circulation V-239
1. Existing Conditions V-239
2. Regulatory Setting V-243
3. Thresholds of Significance V-243

4. Impact Assessment and Methodology V-245
5. Project-specific Impacts and Mitigation Measures V-245
6. Cumulative Impacts V-251

K. Water Resources V-255

1. Existing Conditions V255
2. Regulatory Setting V-266
3. Thresholds of Significance V-269
4. Impact Assessment and Methodology V-270
5. Project-specific Impacts and Mitigation Measures V-270
6. Cumulative Impacts V-286

VI. ALTERNATIVES ANALYSIS VI-1

A. Introduction VI-1
B. Alternatives Selection VI-1
C. Alternatives Analysis VI-4

1. No Project Alternative VI-5
2. Redesigned Project – Onsite Relocation of Disposal Area and Entrance Alternative VI-5
3. Alternative Project Location VI-10
4. Waste Diversion Alternative VI-14

D. Alternatives Comparison VI-20
E. Environmentally Superior Alternative VI-22

VII. ENVIRONMENTAL ANALYSIS VII-1

A. Growth Inducing Impacts VII-1
B. Significant Irreversible Environmental Changes VII-1

1. Irreversible Commitment of Resources VII-2
2. Loss of Aesthetic/Visual Resources VII-2
3. ~~Loss of Agricultural Resources ..... VII-2~~

C. Energy Conservation (Appendix F) VII-2

1. Energy Setting VII-3

VIII. MITIGATION MONITORING AND REPORTING PLAN VIII-1

A. Introduction VIII-1
B. Mitigation Measures VIII-1

IX. REFERENCES AND REPORT PREPARATION IX-1

A. References IX-1

1. Aesthetic Resources IX-1
2. Agricultural Resources IX-1
3. Air Quality IX-1
4. Biological Resources IX-2

5. Climate Change/Greenhouse Gas Emissions IX-3
6. Cultural Resources IX-4
7. Geology and Soils IX-4
8. Hazards and Hazardous Materials IX-5
9. Noise IX-6
10. Transportation and Circulation IX-7
11. Water Resources IX-7
12. Alternative Analysis IX-7

B. EIR Preparers IX-8

TABLES

Table II-1: List of Common Terms and Acronyms II-2
Table II-2: Class I Impacts II-5
Table II-3: Class II Impacts II-24
Table II-4: Secondary Impacts II-58

Table III-1: Existing Permits III-17
Table III-2: Existing and Proposed Facility Footprints III-18
Table III-3: Existing and Proposed Daily Tonnage Limits III-20
Table III-4: Existing and Proposed Hours of Operation III-28
Table III-5: Existing and Anticipated Staffing Levels III-29
Table III-6: Estimated Earthwork Required III-31
Table III-7: Responsible Agencies and Associated Permits III-31

Table IV-1: Proposed Landfill Expansion Project Site Land Use IV-1
Table IV-2: Adjacent Properties Land Use IV-2
Table IV-3: Consistency with Plans and Policies IV-7
Table IV-4: Cumulative Development Scenario IV-13

Table V.B.-1: Land Capability Classifications V-54
Table V.B.-2: California Revised Storie Index V-54
Table V.B.-3: Soil Types V-55
Table V.B.-4: San Luis Obispo County Farmland Conversion 2002-2004 ..... V-58

Table V.C.-1: State and National Criteria Air Pollutant Standards, Effects, and Sources V-74
Table V.C.-2: APCD Thresholds of Significance for Operational Emissions Impacts V-80
Table V.C.-3: Mitigation Threshold Guide V-80
Table V.C.-4: Level of Construction Activity Requiring Mitigation V-81
Table V.C.-5: Construction-Related Earthwork Totals V-84
~~Table V.C.-5: Earthwork Totals (cy) ..... V-85~~
~~Table V.C.-6: Reasonable Worst Case Scenario Construction Emissions ..... V-87~~
Table V.C.-6: Area Source and Vehicle Emissions V-92
~~Table V.C.-7: Area Source Emissions ..... V-92~~
Table V.C.-7~~8~~: Heavy Equipment Emissions Year 2007 and Year 2020 ..... V-93

Figure V.E.-1: GHG Emissions Resulting from the Proposed Project V-134

Table V.G.-1: Geologic Conditions of the Northeast Expansion Area V-151
Table V.G.-2: Significant Regional Faults V-162

Table V.I.-1: Comparison of Measured and Predicted Noise Levels – Highway 227 near Cold Canyon Landfill V-211
Table V.I.-2: Summary of Reference Noise Level Measurements V-212
Table V.I.-3: 2010 Noise Study Results V-215
Table V.I.-4: County of San Luis Obispo Stationary Noise Standards V-218
Table V.I.-5: Typical Construction Equipment Noise Levels V-236

Table V.J.-1: Existing Landfill Trip Generation V-240
Table V.J.-2: Existing Peak Hour LOS Analysis V-242
Table V.J.-3: Highway 227 LOS Thresholds (Caltrans Two-Lane Rural Highway) V-244
Table V.J.-4: Expanded Landfill Trip Generation (Average Weekday) V-246
Table V.J.-5: Existing Plus Project Peak Hour LOS Analysis V-249
Table V.J.-6: Vehicle Speed and Sight Distance Data V-251
Table V.J.-7: Cumulative Peak Hour LOS Analysis V-252

Table V.K.-1: Weir Well Pump Test Capacities V-258
Table V.K.-2: Potential Water Supply V-260
Table V.K.-3: Water Demand 7-Month Period V-262
Table V.K.-4: Existing Water Demand V-262
Table V.K.-5: Summary of Existing Groundwater Monitoring Requirements V-266
Table V.K.-6: Interference Effects (Drawdown) from Pumping Tests V-275
Table V.K.-7: Summary of Estimated Landscape Water Demand V-278
Table V.K.-8: Existing and Estimated Potential Future Water Demand V-278
Table V.K.-9: Potential On-site Water Supply V-279
Table V.K.-10: Potential On-site Water Supply During Dry Years V-279
Table V.K.-11~~10~~: Estimated Current and Maximum Future Groundwater Demand within the Groundwater Basin V-288

Table VI-1: Maximum Permitted Tonnage per Day VI-17
Table VI-2: Impact Comparison of Project Alternatives VI-21

Table VIII-1: Mitigation Monitoring Program VIII-2

FIGURES

Figure III-1: Vicinity Map III-3
Figure III-2: Location Map III-4
Figure III-3: Aerial of Project Site III-5
Figure III-4: Approximate Service Area III-7
Figure III-5: Permitted Landfill and Existing Facilities III-21
Figure III-6: Module Construction Detail III-23
Figure III-7: Existing Monitoring System III-25
Figure III-8: Proposed Final Contours and Facilities III-33
Figure III-9: Proposed Module Detail III-35
Figure III-9a: Module Construction Detail III-37
Figure III-9b: Module Construction Detail III-39
Figure III-10: Proposed Monitoring System III-41
Figure III-11: Landscape Plan III-43

Figure IV-1: Land Use Category Map IV-3

Figure V.A.-1: KVA Location Map V-21
Figure V.A.-2: Project Visibility Map – Key Viewing Area 1 ..... V-23
Figure V.A.-3: Photo Simulations – Key Viewing Area 1 ..... V-25
Figure V.A.-4: Project Visibility Map – Key Viewing Area 2 ..... V-27
Figure V.A.-5: Photo Simulations – Key Viewing Area 2 ..... V-29
Figure V.A.-6: Project Visibility Map – Key Viewing Area 3 ..... V-31
Figure V.A.-7: Photo Simulations – Key Viewing Area 3 ..... V-33
Figure V.A.-8: Project Visibility Map – Key Viewing Area 4 ..... V-35
Figure V.A.-9: Photo Simulations – Key Viewing Area 4 ..... V-37
Figure V.A.-10: Project Visibility Map – Key Viewing Area 5 ..... V-39
Figure V.A.-11: Photo Simulations – Key Viewing Area 5 ..... V-41
Figure V.A.-12: Project Visibility Map – Key Viewing Area 6 ..... V-43
Figure V.A.-13: Photo Simulations – Key Viewing Area 6 ..... V-45
Figure V.A.-14: Project Visibility Map – Key Viewing Area 7 ..... V-47
Figure V.A.-15: Photo Simulations – Key Viewing Area 7 ..... V-49

Figure V.B.-1: Soils and Important Farmland Map V-61
Figure V.B.-2: Parcels with Williamson Act Contracts V-63

Figure V.D.-1: Updated Habitat and Impacts Map V-99

Figure V.G.-1: Regional Geologic Map V-153
Figure V.G.-2: Local Geologic Map V-155
Figure V.G.-3: Regional Fault Map V-163

Figure V.I.-1: Noise Monitoring Sites, 2008 Study V-213
Figure V.I.-2: Long-term Noise Monitoring Sites, 2010 Study V-219
Figure V.I.-3: Short-term Noise Monitoring Sites, 2010 Study V-221

Figure V.J.-1: Existing Weekday Traffic Volumes V-241
Figure V.J.-2: Proposed Weekday Project Traffic Volumes V-248
Figure V.J.-3: Cumulative Weekday Traffic Volumes V-253

Figure V.K.-1 Well Testing Program V-273
Figure V.K.-2: Surrounding Wells and Land Use Categories V-291

Figure VI-1: Alternative 2: Redesigned Project – Onsite Relocation of Disposal Area and Entrance Alternative VI-7
Figure VI-2: Alternative 3: Alternative Project Location VI-15

APPENDICES

Appendix A: Notice of Preparation (NOP) and Response Letters

Appendix B: Air Quality Background Information
--URBEMIS Datasheets
--Heavy Equipment Emissions Calculations
--California Climate Action Registry Reports

Appendix C: Biological Resources Background Information
--Biological Report, Althouse and Meade, Inc. (August 2006, revised May 2007)
--Species Tables
--Species Descriptions

Appendix D: Cultural Resources Background Information

Appendix E: Noise Background Information
--Environmental Noise Assessment, Brown-Buntin Associates, Inc. (April 2008)
--Acoustical Analysis, Brown-Buntin Associates, Inc. (May 2010)
--Updated Traffic Noise Analysis (September 30, 2011)
--Response to Noise Section Comments (October 6, 2011)

Appendix F: Transportation and Circulation Background Information
--Traffic Impact Report, Pinnacle Traffic Engineering (March 2008)
--Traffic Impact Report – Response to Comments Memo (June 2009)

Appendix G: Water Resources Background Information
--Water Resources Assessment, Fugro West, Inc. (March 2008)
--Technical Memorandum, Fugro West, Inc. (February 8, 2010; Revised November 4, 2010)
--Revised Water Discharge Requirements Order No. R3-2002-0065 (November 1, 2002)

Appendix H: Acronym Table

Appendix I: Hazards and Hazardous Materials Background Information

--An Assessment of Potential Impacts to Public and Worker Health – Occupational Safety and Health Audit of the Composting Facility (October 2010)

--An Assessment of Potential Impacts to Public and Worker Health – Public Impacts (November 2010; Revised January 2011)

--Environmental Health Memo (December 2010)

Appendix J: Revocation Hearing Staff Report (November 2010)

This page intentionally left blank.