

SECTION 9. DESCRIPTION OF WORK

This project involves maintenance work along Cholame Valley Road pursuant to an agreement with FEMA. Work includes removal of existing CMP cross-culverts, installation of new HDPE cross-culverts, excavation of excess siltation in roadside ditches, an asphalt overlay and shoulder backing, and such other items or detail work not mentioned herein that are required by the Plans, the Standard Specifications, Standard Plans, or these Special Provisions.