



SAN LUIS OBISPO COUNTY
DEPARTMENT OF PUBLIC WORKS

Paavo Ogren, Director

County Government Center, Room 207 • San Luis Obispo CA 93408 • (805) 781-5252
Fax (805) 781-1229 email address: pwd@co.slo.ca.us

January 8, 2013

**FAX AND EMAIL &
ATTACH TO CONTRACT**

**ADDENDUM NO. 4 TO
OAK WOODLAND HABITAT MITIGATION
FOR THE WILLOW ROAD EXTENSION
AND HWY 101 INTERCHANGE PROJECT
NIPOMO, CA
CONTRACT NO. 300129.09.04**

**The final day, time and location for submittal of bid proposal remain unchanged:
Date / Time: Thursday, January 17, 2013 at 3:00 p.m.**

At: Office of the County Clerk
1055 Monterey Street, Room D-120
San Luis Obispo, California 93408

Certain revisions are hereby incorporated into the Contract Documents for the subject project.
These revisions are as follows:

The section titled "Notice and Instructions to Bidders" is hereby amended as follows:

1) Replace the last paragraph at the end of the section on page A-6 with the following:

The bidder's attention is directed to Section 10-1.01, "Order of Work," of the Special Provisions regarding the requirement for native oak acorns to be planted prior to the April 15.

The section titled "Bid Proposal" is hereby amended as follows:

1) Replace "BID PROPOSAL", Page A-8(a) with new "BID PROPOSAL" attached hereto.
(This change alters the quantities of "Quarterly Report" and "Annual Report".)

The section titled “Contract Agreement” is hereby amended as follows:

- 1) On page A-20, replace the last sentence of Article 3 – Contract Times, with the following:

This Contract requires work over a period of at least three (3) years.

The section titled “Special Provisions” is hereby amended as follows:

- 2) Section 4-1.01, “General,” replace the fourth paragraph at the end of the section on page A-45 with the following:

Complete all quarterly reporting, annual reporting, and plant establishment work within 750 WORKING DAYS from the completion date of all work required to be completed within 60 WORKING DAYS.

- 3) Section 10-1.01, “Order of Work”, replace the second paragraph at the top of page 10-1 with the following:

Attention is directed to “Native Oak Acorn Planting” of these Special Provisions regarding the requirement for the native oak acorns to be planted prior to April 15. Planting of native oak acorns after April 15 will only be allowed if a time extension is approved by the Engineer. The Contractor shall be responsible to plan and coordinate all work activities to ensure that all of the native oak acorns are planted prior to this date, and shall submit a detailed schedule of this work to the Engineer for review and approval in advance of beginning this phase of construction.

- 4) Section 10-2.01, “General”, replace the eighth paragraph at the bottom of page 10-28 with the following:

Plant Establishment progress inspections will be performed at the following stages of work:

A. At intervals of 90 days during the three years of plant establishment.

- 5) Section 10-2.02A, “Native Oak Acorn Planting”, replace the second paragraph of the section in the middle of page 10-33 with the following:

The Contractor shall be responsible for ensuring that all native oak acorns are planted prior to April 15. The Contractor shall be responsible to plan and coordinate all work activities to ensure that all of the native oak acorns are planted prior to this date, and shall submit a detailed schedule of this work to the Engineer for review and approval in advance of beginning this phase of construction. Planting of native oak acorns after April 15 will only be allowed if a time extension is approved in advance by the Engineer.

- 6) Section 10-2.05, “Plant Establishment Work”, replace the first paragraph of the section at the bottom of page 10-41 with the following:

The plant establishment period shall be Type 1 and shall be 3 years.

- 7) Section 10-2.05, “Plant Establishment Work”, replace the table at the top of page 10-42 with the following:

YEAR 1	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
Weed Abatement/ Watering (as needed)			X	X	X		X		X		X	
YEAR 2												
Weed Abatement/ Watering (as needed)			X	X	X		X		X		X	
YEAR 3												
Weed Abatement/ Watering (as needed)			X	X	X		X		X		X	

- 8) Section 10-2.05, “Plant Establishment Work”, replace the table at the middle of page 10-44 with the following:

	Year 1	Year 2	Year 3
Surviving Oaks	3,710	3,599	3,491
Overall Vigor Rating	1,2	1,2	1,2
% Cover Exotic species	<60	<60	<50

- 9) Section 10-2.07, “Quantitative Assessments and Annual Reporting”, replace the table at the bottom of page 10-46 with the following:

	Year 1	Year 2	Year 3
Surviving Oaks	3,710	3,599	3,491
Overall Vigor Rating	1,2	1,2	1,2
% Cover Exotic species	<60	<60	<50

The following attachments are included in this addendum:

- 1) "BID PROPOSAL", Page A-8(a)
-

All bidders shall acknowledge acceptance of this correction notice. **PLEASE FAX TO US, TODAY, A SIGNED COPY OF THIS SHEET INDICATING CONFIRMATION OF RECEIPT OF THIS ADDENDUM (FAX (805) 781-1229).** If you are unable to read the fax, please call Jeff Werst in the Public Works Department at (805) 781-5252.



PAAVO OGREN
Director of Public Works

File: Contract No. 300129.09.04

ACKNOWLEDGMENT

Company Name

Printed Name

Signature

Date

L:\DESIGN\JAN13\300129.09.04 Addendum No. 4.doc.JWerst.taw

**OAK WOODLAND HABITAT MITIGATION
FOR THE WILLOW ROAD EXTENSION AND HWY 101 INTERCHANGE PROJECT
NIPOMO, CA
CONTRACT NO. 300129.09.04
BID PROPOSAL**

ITEM NO.	CODE NO.	DESCRIPTION OF ITEM	ESTIMATED QUANTITY	UNIT	BID UNIT PRICE	BID PRICE
1	74056	WATER POLLUTION CONTROL	1	LS	LUMP SUM	
2	74033	TEMPORARY CONSTRUCTION ENTRANCE	1	EA		
3	150606	REMOVE FENCE (TYPE BW)	181	LF		
4	152XXX	RELOCATE CATTLE TROUGH	1	LS		
5	200001	HIGHWAY PLANTING	1	LS	LUMP SUM	
6	200117	DECOMPOSED GRANITE (MISCELLANEOUS AREAS)	525	SF		
7	204099	PLANT ESTABLISHMENT	1	LS	LUMP SUM	
8	-	QUARTERLY REPORT	12	EA		
9	-	ANNUAL REPORTING	3	EA		
10	208000	IRRIGATION SYSTEM	1	LS	LUMP SUM	
11	208310	IRRIGATION SLEEVE	371	LF		
12	209503A	WATER BOOSTER PUMPING STATION & TANK FILL SYSTEM	1	LS	LUMP SUM	
13	566011	ROADSIDE SIGN - ONE POST	2	EA		
14	731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION)	1	CY		
15	800007	FENCE (TYPE BW, 5-STRAND, METAL POST)	8369	LF		
16	860797	ELECTRIC SERVICE (IRRIGATION)	1	LS	LUMP SUM	
17	860798	BOOSTER PUMP ELECTRIC SYSTEM	1	LS	LUMP SUM	
18	991040A	ELECTRICAL FACILITY (SERVICE POLE AND METER/MAIN PANEL)	1	LS	LUMP SUM	
TOTAL BID						

Bidder's Name: _____