



SAN LUIS OBISPO COUNTY
DEPARTMENT OF PUBLIC WORKS

Paavo Ogren, Director

County Government Center, Room 207 • San Luis Obispo CA 93408 • (805) 781-5252

Fax (805) 781-1229

email address: pwd@co.slo.ca.us

May 15, 2014

**SIDEWALK IMPROVEMENTS FOR
CROCKER STREET
TEMPLETON, CA
CONTRACT NO. 300495
BIDDER'S INQUIRIES**

This memo is to inform the Contractors listed on the planholder's list that the response to bidder's inquires have been posted to the website at

http://www.slocounty.ca.gov/PW/Design_Division/Projects_Out_To_Bid.htm.

For those Contractor's that do not have access to internet, attached is the response.

The response to bidder's inquires, unless incorporated into a formal addendum to the contract, are not a part of the contract and are provided for the bidder's convenience only. In some instances, the question and answer may represent a summary of the matters discussed rather than a word-for-word recitation. The availability or use of information provided in the responses to bidder's inquiries is not to be construed in any way as a waiver of the provisions of Section 2-1.03 of the Standard Specifications or any other provision of the contract, the plans, Standard Specifications or Special Provisions, nor to excuse the contractor from full compliance with those contract requirements. Bidders are cautioned that subsequent responses or contract addenda may affect or vary from a response previously given.

To submit a "Request For Information (RFI)", please fill out the form located on the San Luis Obispo County's Public Work's website at

http://www.slocounty.ca.gov/PW/Design_Division/Projects_Out_To_Bid/Bidder_Request_For_Information_-_PCR.htm.

Please contact me with any questions at (805) 781-4480.

Sincerely,

JEFF WERST, PE
Design Division Manager

Enclosures: Answers to Bidder Questions last updated May 15, 2014 (2 page)

c: Michael Britton

File: Contract No. 300495

L:\DESIGN\MAY14\300495 RFI No. 2.doc.jwerst.taw

Sidewalk Improvements for Crocker Street

CONTRACT NO. 300495

ANSWERS TO BIDDER QUESTIONS

LAST UPDATED: 15 May 2014

NOTICE: The Contract Documents govern. Responses are for information only and are not part of the Contract Documents.

SECTION	PAGE	DWG	RESPONSE DATE	QUESTION ¹	ANSWER
N/A	N/A	C2 & C3 Cons. Note No. 7	7-May-14	Plan Sheet C2 & C3, Construction Note 7 - Remove 2' wide existing asphalt concrete and replace in kind. What is the thickness of the existing asphalt? The Bid Schedule Item No. 13 Hot Mix Asphalt (Type A) is by the ton and Bid Item No. 14 Place Hot Mix Asphalt (Miscellaneous Areas) is by the square yard. What thickness of asphalt is intended for this item?	The thickness of the existing asphalt is assumed to be 3-inches. In checking our assumptions minor errors in the Bid Sheet were found, and will be addressed in an upcoming addendum.
Bid Proposal and Forms	A-8(a)	N/A	15-May-14	Note 14 on Plan Sheet C3 identifies fence to be relocated. However the bid item for this work (14 LF) does not appear to be long enough to match what was drawn. What is the quantity of fence to be relocated?	The quantity of fence to be relocated will be addressed in an upcoming addendum.
NA	N/A	C2 & C3	15-May-14	On Plan Sheet C2 the typical section for the sidewalk and driveway shows #4 rebar at 12" each way for the driveway concrete. SLO County Standard Detail B-2a shows residential driveways that serve more than one residence to use rebar at 24" spacing each way. Which rebar detail are we supposed to use for the concrete driveways?	The plans specify one proposed driveway as referenced by Construction Note #17 shown on Sheet C2 near Station 6+95.00. See County Standard Detail B-2a for reinforcement requirements. Sidewalk reinforcement is specified on Sheets C2 and C3 per Construction Note #1 and per the Typical Section on Sheet C2.
NA	N/A	C3	15-May-14	On Plan Sheet C3 at approximate station 10+80 in the new sidewalk it says "6" Concrete". The limits of this 6" concrete are not clear as shown in the driveway locations where there is also a note "6" Concrete". The typical section on plan sheet C2 shows regular sidewalk to be 4" thick. Please clarify if this section of sidewalk is to be 4" or 6" thick, including the limits for each section.	The 6" Concrete label is shown in error and will be removed from the plan set. This will be addressed in an upcoming addendum.
10-1.19	PG 10-36	N/A	15-May-14	In Section 10-1.19 of the Project Specifications it states that the truncated dome mats are to be placed with the following dimensions, 12 feet long by 3 feet wide. The plans do not show any areas of truncated dome mats as shown on the plans?	Section 10-1.19 shall be clarified in an upcoming addendum.
NA	NA	C2 & C3	15-May-14	Note 6 of the project plans says to conform to existing sidewalk or driveway per County Standard R-4. Note 5 on County Standard R-4 states that the road structural section adjacent to the repair or replacement shall be constructed in conformance with standard drawing R-3. Table 1 on Standard drawing R-3 shows the repair to be done in multiple steps and for the repair limits to possibly require the asphalt repair to go to the lane edge, the lane center, or only 12". What is the PCI for Crocker Street and will we be required to replace asphalt outside the limits shown on the plans?	This will be addressed in an upcoming addendum.

¹ The COUNTY rephrases questions for clarity and consistency.

Sidewalk Improvements for Crocker Street

CONTRACT NO. 300495

ANSWERS TO BIDDER QUESTIONS

LAST UPDATED: 15 May 2014

NOTICE: The Contract Documents govern. Responses are for information only and are not part of the Contract Documents.

SECTION	PAGE	DWG	RESPONSE DATE	QUESTION ¹	ANSWER
10-1.5	PG 10-29	N/A	15-May-14	Note 3 of the project plans says to adjust existing water meters to grade. Does this include adjusting the water meter to grade, or the water meter box only? Under which item is this work paid?	Please refer to Section 10-1.5 "Obstructions" page 10-28. It is the responsibility of the Templeton CSD to adjust their water meter boxes to grade.

¹ The COUNTY rephrases questions for clarity and consistency.