



SAN LUIS OBISPO COUNTY  
**DEPARTMENT OF PUBLIC WORKS**

Wade Horton, Director

---

County Government Center, Room 207 • San Luis Obispo CA 93408 • (805) 781-5252

Fax (805) 781-1229

email address: [pwd@co.slo.ca.us](mailto:pwd@co.slo.ca.us)

---

March, 19 2015

**FAX AND EMAIL &  
ATTACH TO CONTRACT**

**ADDENDUM NO. 2 TO  
2014-2015 ASPHALT OVERLAY VARIOUS ROADS  
LOS OSOS, CA  
CONTRACT NO. 300519**

**The final day, time and location for submittal of bid proposal remain unchanged:  
Date / Time: Thursday, March 26, 2015 at 3:00 p.m.**

At: Office of the County Clerk  
1055 Monterey Street, Room D-120  
San Luis Obispo, California 93408

Certain revisions are hereby incorporated into the Contract Documents for the subject project. These revisions are as follows:

---

The section titled "SECTION 10. CONSTRUCTION DETAILS" is hereby amended as follows:

- 1) Section 10-1.01, "Order of Work," insert the following paragraph after the first paragraph on Page 10-2:

"In accordance with Noise Standards as specified in Title 23.06.042 of the County Code, construction may take place between the hours of 7:00 AM – 9:00 PM Monday through Friday and 8:00 AM – 5:00 PM Saturday and Sunday. Construction operations outside said hours are subject to the approval of the Engineer and shall satisfy the exterior noise level standards per Title 23.06.044."

- 2) Section 10-1.02, "Temporary Fences (ESA)," Page 10-3, replace the first sentence under the Summary heading with the following:

"This work includes constructing, maintaining, and removing approximately 1240 linear feet of temporary fence (Type ESA). Exact locations for fence placement will be as directed in the field by the Engineer."

- 3) Section 10-1.02, "Temporary Fences (ESA)," Page 10-5, replace the last paragraph with the following:

"Full compensation for temporary fence (Type ESA) including furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in providing and installing the temporary fence (Type ESA), complete in place, including maintenance, removal of materials, and backfilling and repairing holes, depressions and other ground disturbance, as shown on the plans, as specified in the Standard Specifications and these Special Provisions, and as ordered by the Engineer, shall be included in the contract price paid for the various items of work involved and no separate payment will be made therefore."

- 4) Section 10-1.11E, "Cold Plane Asphalt Concrete Pavement," Page 10-40, add the following to the end of the first paragraph:

"Actual locations and dimensions of cold planning required for conforms and digouts shall be as determined in the field by the Engineer."

- 5) Section 10-1.17B, "HMA Overlay (Type A)," Page 10-48, add the following to the end of the first paragraph:

"Actual locations and dimensions of placing HMA for leveling shall be as determined in the field by the Engineer."

- 6) Section 10-1.18, "Minor Concrete," Page 10-51, delete the last two paragraphs of the section in their entirety and replace with the following:

"The contract price paid per cubic yard for "MINOR CONCRETE (CURB RAMP)", "MINOR CONCRETE (CURB AND GUTTER)", "MINOR CONCRETE (SIDEWALK)", "MINOR CONCRETE (CROSS GUTTER)", "MINOR CONCRETE (SPANDREL)", "MINOR CONCRETE (MEDIAN)" shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals for constructing concrete curb ramps, curbs and gutters, sidewalks, cross gutters, spandrels, and medians, complete in place, including saw cutting, removing and disposal of existing concrete and/or existing asphalt roadway, sidewalks, and berms within the footprint of the concrete improvements and as required for conforming to the concrete improvements; clearing and grubbing, removal and disposal of existing vegetation; minor slope grading; removal and disposal of surplus or unsuitable material; subgrade preparation; providing and installing class 2 aggregate base for concrete improvements and conforming asphalt; adjusting or replacing existing surface utilities within the footprint of and/or conforming areas for the concrete improvements; drilling and dowelling into existing concrete as required; provision, placement and finishing of concrete and reinforcing steel; providing and constructing HMA conforms, HMA sidewalk conforms, and HMA berm conforms; resetting signs impacted by the construction; and all appurtenant work and materials, as shown on the plans, as specified in the Standard Specifications and these Special Provisions, and as directed by the Engineer.

The contract price paid per linear foot for "MINOR CONCRETE (MEDIAN CURB)" shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals for constructing concrete median curbs complete in place, including saw cutting, removing and


disposal of existing concrete and/or existing asphalt roadway, sidewalks, and berms within the footprint of the concrete improvements and as required for conforming to the concrete improvements; clearing and grubbing, removal and disposal of existing vegetation; removal and disposal of surplus or unsuitable material; subgrade preparation; providing and installing class 2 aggregate base for concrete improvements and conforming asphalt; adjusting or replacing existing surface utilities within the footprint of and/or conforming areas for the concrete improvements; drilling and dowelling into existing concrete as required; provision, placement and finishing of concrete and reinforcing steel; providing and constructing HMA conforms, HMA sidewalk conforms, and HMA berm conforms, as required; resetting signs impacted by the construction; and all appurtenant work and materials, as shown on the plans, as specified in the Standard Specifications and these Special Provisions, and as directed by the Engineer.”

---

The section titled “APPENDIX A, WORK LOCATION SCHEDULE,” is hereby amended as follows:

- 7) Amend “Minor Concrete (Spandrel)” under Site 1 – Los Osos Valley Road (South Bay Boulevard to Rodman Avenue) by removing the 10<sup>th</sup> Street location (shown on page 6.)
  
- 8) Amend “Minor Concrete (Curb Ramp)” under Site 1 – Los Osos Valley Road (South Bay Boulevard to Rodman Avenue) by removing all items (except Dome Mat) from the Northwest Corner of 10<sup>th</sup> Street location (shown on page 7.)

All bidders shall acknowledge acceptance of this correction notice. **PLEASE FAX TO US, TODAY, A SIGNED COPY OF THIS SHEET INDICATING CONFIRMATION OF RECEIPT OF THIS ADDENDUM (FAX (805) 781-1229).** If you are unable to read the fax, please call Jeff Werst in the Public Works Department at (805) 781-5252.

*SBW* 

WADE HORTON  
Director of Public Works

File: Contract No. 300519

**ACKNOWLEDGMENT**

---

Company Name	Printed Name	Signature	Date
--------------	--------------	-----------	------

L:\DESIGN\MAR15\300519 - Addendum No. 2.doc.jwerst.taw