



SAN LUIS OBISPO COUNTY  
**DEPARTMENT OF PUBLIC WORKS**

Wade Horton, Director

---

County Government Center, Room 206 • San Luis Obispo CA 93408 • (805) 781-5252

---

Fax (805) 781-1229

email address: pwd@co.slo.ca.us



July 31, 2015

**FAX AND EMAIL &  
ATTACH TO CONTRACT**

**ADDENDUM NO. 2 TO  
2015-16 ASPHALT OVERLAY  
VARIOUS ROADS  
NIPOMO, CA  
CONTRACT NO. 300550**

**The final day, time and location for submittal of bid proposal remain unchanged:  
Date / Time: Thursday, August 6<sup>th</sup>, 2015 at 3:00 p.m.**

At: Office of the County Clerk  
1055 Monterey Street, Room D-120  
San Luis Obispo, California 93408

Certain revisions are hereby incorporated into the Contract Documents for the subject project. These revisions are as follows:

---

The Section titled "Bid Proposal and Forms" is hereby amended as follows:

- 1) Replace Page A-8(d) of the BID PROPOSAL with attached hereon. The following changes were made to the Bid Sheet:
  - a. Bid Item #68 "IMPORTED MATERIAL (SHOULDER BACKING)", shall be revised from 60 TON to 310 TON

---

The section titled "Project Plans" is hereby amended as follows:

- 2) Sheet 5 and Sheet 6 of the project plans, add the following general note to each "Typical Section" as follows:

The purpose of the "Cold Plane Mainline" is to remove the existing HMA overlay within the traveled way, as directed by the Engineer. HMA leveling within portions of the mainline after the cold planing will be determined in the field by the Engineer.

- 3) Sheet 28 of the project plans, the "Shoulder Backing" quantity table shall be revised as follows;

Northbound Side: Avg Depth = 0.33 LF (changed from 1 LF), Volume= 70 CY (changed from 210 CY), Weight = 124 TON (changed from 15 TON)

Southbound Side: Avg Depth = 0.33 LF (changed from 2 LF), Volume = 105 CY (changed from 640 CY), Weight = 186 TON (changed from 45 TON)

Total: Volume = 175 CY (changed from 850 CY), Weight = 310 TON (changed from 60 TON)

---

All bidders shall acknowledge acceptance of this correction notice. **PLEASE FAX TO US, TODAY, A SIGNED COPY OF THIS SHEET INDICATING CONFIRMATION OF RECEIPT OF THIS ADDENDUM (FAX (805) 781-1229).** If you are unable to read the fax, please call Jeff Werst in the Public Works Department at (805) 781-5252.

*for* Dave Flynn *JBW for DF*

Wade Horton  
Director of Public Works

Attachment: Bid Proposal Page A-8(d)

File: Contract No. 300550

**ACKNOWLEDGMENT**

_____	_____	_____	_____
Company Name	Printed Name	Signature	Date

L:\DESIGN\JUL15\300550 Addendum No. 2.docxJW.mj

60	152422	ADJUST SURVEY MONUMENT WELL	6	EA		
61	152422	ADJUST WATER VALVE COVER	19	EA		
62	152422	ADJUST SEWER MANHOLE AND CLEANOUT COVER	7	EA		
63	153103	COLD PLANE ASPHALT CONCRETE CONFORMS (0.15' MAX.)	7535	SY		
64	153103	COLD PLANE ASPHALT CONCRETE DIGOUTS (0.25' MAX.)	3300	SY		
65	260201	CLASS 2 AGGREGATE BASE (WIDENING)	100	CY		
66	190101	ROADWAY EXCAVATION (WIDENING)	155	CY		
67	190101	PLACE SHOULDER BACKING	28.6	STA		
68	198007	IMPORTED MATERIAL (SHOULDER BACKING)	310	TON		
69	390132	HOT MIX ASPHALT (TYPE A) OVERLAY	3300	TON		
70	390132	HOT MIX ASPHALT (TYPE A) WIDENING	110	TON		
71	390132	HOT MIX ASPHALT (TYPE A) DIGOUTS	570	TON		
72	394002	PLACE HOT MIX ASPHALT (DIKE)	1780	LF		
73	731502 (F)	MINOR CONCRETE (SPANDREL)	1.2	CY		
74	731623 (F)	MINOR CONCRETE (CURB RAMP)	57.9	CY		
75	731656	TRUNCATED DOME MAT	13	EA		
76	860611	DETECTOR LOOPS	4	EA		
77		ALLOWANCE FOR SUPPLEMENTAL FLAGGING AND TRAFFIC CONTROL	1	LS	LUMP SUM	\$ 44,000.00
78		ALLOWANCE FOR PAVING ASPHALT PRICE INDEX INCREASE	1	LS	LUMP SUM	\$ 10,000.00
<b>TOTAL SITE 4</b>						

**SITE 5 - DIVISION STREET**

ITEM NO.	CODE NO.	DESCRIPTION OF ITEM	APPROX. QUANTITY	UNIT OF MEASURE	UNIT PRICE (IN FIGURES) DOLLARS. CENTS	TOTAL AMOUNT DOLLARS. CENTS
79	120090	CONSTRUCTION AREA SIGNS	1	LS	LUMP SUM	
80	120100	TRAFFIC CONTROL SYSTEM	1	LS	LUMP SUM	
81	152422	ADJUST SURVEY MONUMENT WELL	8	EA		