

## **Erosion Control Notes:**

1. Erosion control measures shall be implemented on all projects and shall include source control, including protection of stockpiles, protection of slopes, protection of all disturbed areas, and protection of accesses. In addition, perimeter containment measures shall be placed prior to the commencement of grading and site disturbance activities unless the Public Works Department determines temporary measures to be unnecessary based upon location, site characteristics or time of year. The intent of erosion control measures shall be to keep all sediment from entering a swale, drainageway, watercourse, or onto adjacent properties.
2. Site inspections and appropriate maintenance of erosion control devices shall be conducted and documented prior to, during, and after rain events.
3. The developer shall be responsible for the placement and maintenance of all erosion control devices as specified by the approved plan until such time that the project is accepted as complete by the Public Works Department. Erosion control devices may be relocated, deleted or additional items may be required depending on the actual soil conditions encountered. Additional erosion control devices shall be placed at the discretion of the Engineer of Work, County Inspector, SWPPP Monitor, or RWQCB Inspector. Guidelines for determining appropriate erosion control devices are included in the appendix of the Public Improvement Standards.
4. All erosion control devices shall be the first order of work and shall be in place between October 15 and April 15 or anytime when the rain probability exceeds 30%. This work shall be installed or applied after each area is graded and no later than five (5) working days after completion of each area.
5. The Engineer of Work and the Public Works Department shall be notified before October 15 for inspection of installed erosion control devices.
6. A standby crew for emergency work shall be available at all times during the rainy season (October 15 through April 15). Necessary materials shall be available and stock piled at convenient locations to facilitate rapid construction or maintenance of temporary devices when rain is imminent.
7. Permanent erosion control shall be placed and established with 90% coverage on all disturbed surfaces other than paved or gravel surfaces, prior to final inspection. Permanent erosion control shall be fully established prior to final acceptance. Temporary erosion control measures shall remain in place until permanent measures are established.
8. In the event of a failure, the developer and/or his representative shall be responsible for cleanup and all associated costs or damages. In the event that damage occurs within the right of way and the County is required to perform cleanup, all work shall cease on the project until cleanup costs are fully paid.
9. If any work is not in compliance with the plans or permits approved for the project, the Department shall revoke all active permits and recommend

- that County Code Enforcement provide a written notice or stop work order in accordance with Section 22.52.140 [23.10] of the Land Use Ordinance.
10. All projects involving site disturbance of one acre or greater shall comply with the requirements of the National Pollutant Discharge Elimination System (NPDES). The developer shall submit a Notice of intent (NOI) to comply with the General Permit for Construction Activity with the Regional Water Quality Control Board (RWQCB). The developer shall provide the County with the Waste Discharge Identification Number (WDID #) or with verification that an exemption has been granted by RWQCB.
- WDID # \_\_\_\_\_

11. Person to contact 24 hours a day in the event there is an erosion control/sedimentation problem (Storm Water Compliance Officer):
- Name \_\_\_\_\_
- Local Phone Number \_\_\_\_\_