



- P. Condition 66. Botanical Surveys. The CONTRACTOR is directed to Specification 01561 – Biological and Cultural Resource Environmental Controls.
- Q. Condition 68. Worker Education Program. The CONTRACTOR is directed to Specification 01561 – Biological and Cultural Resource Environmental Controls.
- R. Condition 69. Nesting Bird Survey. The CONTRACTOR is directed to Specification 01561 – Biological and Cultural Resource Environmental Controls.
- S. Condition 70. Nesting Raptor Survey. The CONTRACTOR is directed to Specification 01561 – Biological and Cultural Resource Environmental Controls.
- T. Condition 73. Discovery of Human Remains. The CONTRACTOR is directed to Specification 01561 – Biological and Cultural Resource Environmental Controls.
- U. Condition 74. Paleontological Resources. Although unlikely, should any vertebrate fossils or potentially significant finds (e.g., numerous well-preserved invertebrate or plant fossils) be encountered by anyone working on the site, all activities in the immediate vicinity of the find are to cease until a qualified paleontologist evaluates the find for its scientific value. If deemed significant, the paleontological resource(s) shall be salvaged and deposited in an accredited and permanent scientific institution where they will be properly curated and preserved for the benefit of current and future generations.
- V. Condition 75. APCD Equipment Requirements. Prior to initiating activities, the CONTRACTOR shall:
  - 1. Use one catalyzed diesel particulate filter (CDPF) on the piece of equipment estimated to generate the greatest emissions. If a CDPF is unsuitable for the potential equipment to be controlled, five diesel oxidation catalysts (DOC) shall be used.
  - 2. Identify equipment to be operated during construction as early as possible in order to place the order for the appropriate filter and avoid any project delays. This is necessary so that contractors bidding on the project can include the purchase, proper installation, and maintenance costs in their bids.
  - 3. Contact the SLOAPCD Compliance Division to initiate implementation of this mitigation measure at least two months prior to start of construction.
- W. Condition 76. Dust Control. The CONTRACTOR shall comply with Section 1562 – Dust Control.
- X. Condition 78. Noise Abatement Requirements. The CONTRACTOR shall adhere to the following noise attenuation requirements:
  - 1. A construction noise control plan shall be developed for the project that identifies the nature and timing of operations designed to minimize noise exposure to noise sensitive receptors including natural resource areas.



Re: LOWWP CAMP 

Tim Fuhs to: Kerry Brown

Cc: Kate Ballantyne, Eric Wier, Meghan Field, Karen Brooks

04/20/2012 01:27 PM

Hi Kerry: Pursuant to Eric's email, I just wanted to confirm with you that Public Works has contacted the District with reference to condition 76.c below. We are working through the items in addition to the odor control plan.

Thank you -

Tim

Tim Fuhs  
San Luis Obispo County  
Air Pollution Control District  
3433 Roberto Court SLO, CA 93401  
805-781-5912 o  
805.235.3398 c  
805.781.1002 f  
web: slocleanair.org



Eric Wier

Greetings Tim, We're working with Planning Dep...

04/20/2012 11:45:10 AM

From: Eric Wier/PubWorks/COSLO  
To: Tim Fuhs/APCD/COSLO@Wings  
Cc: Kate Ballantyne/PubWorks/COSLO@Wings  
Date: 04/20/2012 11:45 AM  
Subject: LOWWP CAMP

---

Greetings Tim,

We're working with Planning Dept. on Coastal Development Permit condition compliance for Los Osos. Condition 75 states:

*Prior to initiating grading activities, the proponent's contractor or engineer shall:*

- a. *Include the following specifications on all project plans: One catalyzed diesel particulate filter (CDPF) shall be used on the piece of equipment estimated to generate the greatest emissions. If a CDPF is unsuitable for the potential equipment to be controlled, five diesel oxidation catalysts (DOC) shall be used.*
- b. *Identify equipment to be operated during construction as early as possible in order to place the order for the appropriate filter and avoid any project delays. This is necessary so that contractors bidding on the project can include the purchase, proper installation, and maintenance costs in their bids.*
- c. *Contact the SLOAPCD Compliance Division to initiate implementation of this mitigation measure at least two months prior to start of construction.*

We provided the following as evidence of compliance:

*The project specifications (Contract Documents) for the Los Osos Waste Water Project incorporate the APCD Equipment Requirements noted in Condition 75. Specifically, Section 1060-1.03 V attached hereto includes the above requirements in their entirety.*

In order to sign off on this condition, Planning has asked that we provide documentation from APCD that item "c." above has been initiated with the Air District. As you know, we have been working with APCD on the CAMP for the Project. Could you please respond to this email stating we have contacted your Division to initiate this condition?

Thank you,

Eric Wier  
Environmental Programs Division  
Department of Public Works  
County of San Luis Obispo  
ewier@co.slo.ca.us  
(805) 788-2766