

SECTION 9. DESCRIPTION OF WORK

Traffic signal standards, poles, luminaries, and controller cabinets shall be installed; all appurtenant hardware, signal heads, accessible pedestrian signals and signs shall be mounted; the system shall be tested; and such other items or detail work not mentioned herein that are required by the Plans, the Standard Specifications, Standard Plans, or these Special Provisions shall be performed, constructed, furnished and/or installed.