

ORDINANCE NO. _____
AN ORDINANCE AMENDING TITLE 22 OF THE SAN LUIS OBISPO COUNTY CODE, THE
LAND USE ORDINANCE, BY AMENDING AND REPLACING THE SIGN ORDINANCE TO
COMPLY WITH FIRST AMENDMENT CONTENT NEUTRALITY

The Board of Supervisors of the County of San Luis Obispo, State of California, ordains as follows:

SECTION 1: Article 3, Chapter 22.20 (Signs) of Title 22 of the San Luis Obispo County Code, is hereby amended to read as follows:

22.20.010 - Sign Ordinance

The standards this Chapter shall be known and may be cited as the “San Luis Obispo County Sign Ordinance.” These requirements apply to all signs constructed or altered after the effective date of this Title, except as otherwise provided by Section 22.20.040. These requirements apply to proposed signs in addition to all applicable provisions of the California Outdoor Advertising Act (Business and Professions Code Sections 5200 et seq., and California Administrative Code Title 4, Sections 2240 et seq.).

22.20.020 - Purpose Of Chapter

This Chapter establishes sign regulations that are intended to:

- A. Support the use of signs to aid orientation, identify businesses and activities, express local history and character, or serve other information purposes; and
- B. Protect the ability of the public to identify uses and premises without confusion by encouraging signs to be designed with a scale, graphic character and type of lighting compatible with the appearance of the buildings or uses identified by signs, as well as other buildings and uses in the vicinity; and
- C. Support the use of signs that are maintained in a safe and attractive condition that do not:
 - 1. Create distractions that may jeopardize pedestrian or vehicular traffic safety; or
 - 2. Produce glare that adversely affects residential uses.

D. Allow adequate avenues for both commercial and non-commercial messages, and protect the constitutionally guaranteed right of free speech; and

E. Protect the character of the various communities within the County and safeguard the public health and safety.

22.20.030 - General Principles Sign Code Adopted

~~The Sign Code published by the International Conference of Building Officials entitled the “Uniform Sign Code” 1991 edition, or subsequent edition adopted by the State of California, is hereby adopted and incorporated into this Title by reference as though it were fully set forth here. In the event of any conflict with the Uniform Sign Code, this Chapter shall prevail.~~

A. Applicability.

1. **Applicable codes.** In addition to complying with the provisions of this Chapter, all signs must be constructed in accordance with the Uniform Building Code, the Uniform Sign Code, the Electrical Code, the California Manual on Uniform Traffic Control Devices, and all other applicable laws, rules, regulations, and policies.
 2. **Applicable County regulations.** In addition to complying with the provisions of this Chapter, all signs must comply with other regulations of this Title, including Planning Area Standards (Article 9), Community Planning Standards (Article 10), and the Highway Corridor Design Standards (Section 22.10.095).
- B. Regulatory interpretations.** The County shall apply this Chapter in a content-neutral manner. This Chapter shall be interpreted in a manner consistent with the free speech protections guaranteed by the First Amendment to the United States Constitution and Article 1, Section 2 of the California Constitution. The noncommunication aspects of all signs shall comply with the regulations and standards set forth in this Title. “Noncommunicative aspects” includes regulations that do not relate to the content of the sign, including the time, place, manner, location, size, height, illumination, spacing, and orientation of signs.
- C. Message substitution.** A non-commercial message of any type may be substituted, in whole or in part, for any duly permitted commercial message; and any non-commercial message may be substituted for any non-commercial message.
1. **No additional approval required.** Such substitution of message may be made without any additional approval, permitting, registration, or notice to the County. This provision prevents any inadvertent favoring of commercial speech over non-commercial speech or favoring any non-commercial message over any other non-commercial message.
 2. **Limitations.** This provision does not allow the following:
 - a. Create the right to increase the total amount of signage for a parcel, lot, or land use;
 - b. Affect the requirement that a sign structure or mounting device be properly permitted; or
 - c. Allow a change in the physical structure of a sign or its mounting device.
- D.** Nothing in this Section shall be construed to prohibit a person from holding a sign while picketing or protesting on public property that has been determined to be a traditional or designated public forum, so long as the person holding the sign does not block ingress and egress from buildings, create a safety hazard by impeding travel, or violate any other reasonable time, place, and manner restrictions adopted by the County.
- E. Severability.** If any section, sentence, clause, phrase, word, portion, or provision of this Chapter is held invalid, unconstitutional, or unenforceable by any court of competent jurisdiction, such holding shall not affect, impair, or invalidate any other section, sentence, clause, phrase, word, portion, or provision of this Title which can be given effect without the invalid portion. In adopting this Title, the Board of Supervisors affirmatively declares that it would have approved and adopted the Title even without any portion which may be held invalid, unconstitutional, or unenforceable.

22.20.040 - Sign Permit Requirements

No sign shall be constructed, displayed or altered without first obtaining a sign permit (~~Zoning Clearance~~) as required by this Section, except where a sign is exempted from permit requirements by Subsection B (Authorized Signs).

A. Permit procedures.

1. **Zoning Clearance.** The application, processing, review and approval of a land use permit for a sign shall be as set forth in Section 22.62.030 (Zoning Clearance), except where otherwise provided by Section 22.20.060 (~~Sign Area Standards~~)(Signs Allowed – Type and Area), for signs of specific size or height or where signs are approved as part of an overall development project land use permit.
2. **Minor Use Permit.** Greater numbers of signs or areas of signing larger than the allowances permitted by Section 22.20.060, including modifications to an existing sign, require a Minor Use Permit as set forth in Section 22.62.050 (Minor Use Permit).
- 3.2. **Concurrent Review.** Where signs are proposed for a project subject to land use permit approval, a separate sign permit (~~Zoning Clearance~~) is not required. The land use permit application shall include complete information about the type, area, location and number of signs proposed, or such information is provided for Department review for conformity with the regulations of this Title before installation.
- 4.3. **Construction Permit.** If required by the Uniform Sign Code, a construction permit shall also be obtained in compliance with Title 19 of this code before the installation of any sign.

B. **Authorized Exempt signs.** The following signs are allowed without a land use permit, and shall not be included in determinations on the allowable number, type or area of signs in compliance with Section 22.20.060 (~~Sign Area Standards~~)(Signs Allowed – Type and Area), provided that they conform to the specified standards. Nothing in this Subsection shall exempt a sign from the necessity of construction permit approval if an electrical or building permit is required by the Building and Construction Ordinance or Uniform Sign Code. This Subsection supersedes Section 303 of the Uniform Sign Code.

- ~~1. **Agricultural signs.** Two signs with a total aggregate area not exceeding 32 square feet and a height not to exceed 10 feet for each lot or parcel, identifying and advertising agricultural products produced on the premises.~~
1. **Temporary signs.** Temporary signs are allowed on a property for a total of 120 calendar days per year. Each sign is allowed for up to 60 consecutive days, and shall be removed within 14 days after the conclusion of the purpose served by the sign. The height of any temporary sign shall not exceed 10 feet. Temporary signs shall adhere to the setback standards of the land use category of the property they are located in. The maximum aggregate sign area for temporary signage is as follows.
 - a. **Agriculture and Rural Lands Land Use Categories.** In the Agriculture and Rural Lands Land Use Categories, temporary signage is allowed up to a maximum aggregate sign area of 32 square feet.

- b. Residential Land Use Categories. In the Residential Rural, Residential Suburban, Residential Single-Family, and Residential Multi-Family Land Use Categories, temporary signage is allowed up to a maximum aggregate sign area of four square feet.
- c. Commercial and Industrial Land Use Categories. In the Office and Professional, Commercial Retail, Commercial Service, and Industrial Land Use Categories, temporary signage is allowed up to a maximum aggregate sign area of 24 square feet.
- d. Special Purpose Land Use Categories. In the Open Space, Recreation, and Public Facilities Land Use Categories, temporary signage is allowed up to a maximum aggregate sign area of 16 square feet.

~~2. Construction signs.~~ Two signs up to a combined total of 32 square feet not exceeding a height of eight feet, identifying parties involved in construction on the premises and future activity for which the construction is intended. Such signing shall not include the advertisement of any products. Removal is required within 14 days following completion of the construction.

~~2.3. Directory signs.~~ Wall-mounted building directory signs ~~for pedestrian use, listing the tenants or occupants~~ located at or within the entrance of a building that rents or leases space to tenants, provided that such directories do not exceed 20 square feet on any single building wall, nor a height of eight feet.

~~3.4. Hazard signs.~~ Signs warning of construction, excavation, or similar hazards so long as the hazard exists.

~~4.5. Historical markers.~~ Signs including historical plaques, memorial signs or tablets, or commemorative signs not exceeding four square feet in area, identifying located on historical sites, buildings or areas, placed by a historical society, chamber of commerce or public agency, and approved by the Director.

~~6. Holiday decorations.~~ Temporary holiday decorations, provided that decorations for a single holiday or season are not in place for a period exceeding 90 days.

~~5.7. Information kiosks.~~ Free-standing structures, located outdoors and adjacent to a building open to the public, or in a space open to the public, on which pamphlets, leaflets, and guides may be providing information for pedestrians, including permanent copy and temporary information such as handbills, posters and flyers affixed to a bulletin-board type surface. The total area of kiosk display surfaces shall not exceed 40 square feet or a height of eight feet. Kiosks shall be separated from adjacent structures by a minimum of six feet.

~~6.8. Internal signs.~~ Signs not intended to be viewed from public streets and are located in interior areas of a building or site, and intended to be not visible or legible from public streets or adjacent properties, such as signs in interior areas of shopping centers, commercial buildings and structures, ball parks, stadiums and similar uses of a recreational or entertainment nature.

~~7.9. Miscellaneous information signs.~~ Miscellaneous permanent information signs in nonresidential categories, with an aggregate area not to exceed four square feet at each public entrance nor 12 square feet total, which may indicate indicating address, hours and days of operation, whether a business is open or closed, credit card information and emergency address and telephone numbers.

8.10. **Official flags.** Official federal, state or local government flags, emblems and historical markers.

9.11. **Official signs/government signs.** Official federal, state or local government traffic, directional guide and other informational signs and notices issued by any court, person or officer in performance of a public duty; notices posted by a utility or other quasi-public agency; or other signs required or authorized by law.

12. **Political signs.** Temporary political signs are allowed as follows:

- a. ~~**Residential land use categories within urban or village areas.** Political signs shall not exceed four square feet total for each site.~~
- b. ~~**Other land use categories within urban or village areas.** Political signs shall not exceed 16 square feet total for each site.~~
- c. ~~**Rural areas.** Political signs shall not exceed 32 square feet total for each site.~~
- d. ~~**Measurement of sign area.** For the purposes of this Subsection, each side of a sign may equal the maximum square foot total as defined in Subsections A., B., and C where the sign has two faces which are oriented back to back and separated by no more than 36 inches at any point.~~
- e. ~~**Timing of posting.** Political signs shall not be posted more than 60 days preceding the election and shall be removed within 14 days following the election. The primary and general elections are considered separate elections for the purposes of this Title.~~
- f. ~~**Location of posting.** Political signs attached or placed adjacent to any utility pole, parking meter, traffic sign post, traffic signal, official traffic control device or within the right-of-way are prohibited. Signs placed in these locations will be removed immediately by county employees.~~
- g. ~~**Enforcement.** If a sign which does not meet the provisions of this Section is not removed within 48 hours of receipt of written notice to the property owner, then the owner of the property may be subject to citation or fine or both.~~

10.13. **Prohibition signs.** “No Trespassing”, “No Parking”, and similar warning signs.

14. ~~**Reader board.** Reader boards for community, charitable or religious organizations, provided such signs do not exceed 20 square feet per face and are not illuminated.~~

15. ~~**Real estate signs.**~~

- a. ~~**For sale signs.** Temporary signs indicating the property on which the sign is located is for sale, rent or lease. Only one sign is permitted to face each street adjacent to the property. Such signs may be a maximum of four square feet or less on property in residential categories and 32 square feet or less in nonresidential categories.~~
- b. ~~**Model homes.** Temporary signs, banners and decorations attracting attention to a model home and sales office within a new subdivision, provided that the aggregate area of each signing shall not exceed 32 square feet.~~

- ~~e. **Open house.** Temporary signs or banners attracting attention to an open house, with signing having a maximum aggregate area of 32 square feet, to be in place a maximum of seven days.~~

11.16. Residential identification signs. ~~The following residential identification signs are allowed without permit approval:~~

- a. ~~Signs located on individual residences and home occupations, Individual residence identification signs, including but not limited to names of occupants and home occupations, limited to a total aggregate area of two square feet.~~
- b. ~~One permanent identification signs with a maximum area of 20 square feet for each lot or parcel containing multi-family dwellings or subdivisions, identifying apartment projects, subdivision names, etc., provided such signing is approved as part of a subdivision map or land use permit for the project.~~

12.17. Safety and directional signing. Parking lot and other private traffic directional signs, including handicapped access and parking signs, each not exceeding five square feet in area. Such signs shall be limited to guidance of pedestrian or vehicular traffic within the premises on which they are located, and shall not display any logo or name of a product, establishment, service, or any other advertising.

~~18. **Sign copy.** Changing the sign copy of an approved sign, provided that where the signing is not in conformity with the provisions of this Title, any change shall be in accordance with Section 22.72.070.C (Nonconforming Signs – Sign Copy).~~

~~19. **Sign maintenance.** Any maintenance which does not involve structural changes (See also Section 22.20.080).~~

~~20. **Temporary sales and events.** Banners, signs, decorative materials, or helium or other air filled objects in conjunction with an event conducted in compliance with Sections 22.30.350 (Outdoor Retail Sales), 22.30.610 (Temporary Events), or grand openings. Banners, signs, decorative materials and helium or other air filled objects shall not be posed more than 30 days preceding the event, shall be removed within seven days following the event, and are limited to a maximum aggregate area of 100 square feet per site.~~

13.21. Vehicle signs. Displays on commercial vehicles and public transit/public carrier graphics on properly licensed buses, taxicabs, and similar vehicles for hire that legally pass through the County. Signs on public transportation vehicles regulated by a political subdivision, including but not limited to buses and taxicabs, and signs on licensed commercial vehicles, provided such vehicles are not used or intended for use as portable signs.

14.22. Window signs. Temporary window signs constructed of paper, cloth or similar expendable material, provided the total area of such signs shall not exceed 25 percent of the window area.

15.23. Exterior wall murals. A hand-painted work of visual art that is either affixed to or painted directly on the exterior wall of a structure with the permission of the property owner. An original art display does not include: mechanically produced or computer generated prints or images, including but not limited to digitally printed vinyl; electrical or mechanical components; or changing image art display. Wall murals are allowed on exterior walls and building faces that do not contain any commercial signage. A wall mural includes images or pictorial elements and does

~~not include trademarks, logos, or text; has no commercial context; does not represent any product for sale and is consistent with community character. The applicant shall provide an illustration of the proposed mural to the community advisory group and mural society where such group(s) exist for review and comment, and to the Director prior to a determination that the mural is exempt. If the mural is deemed to not be exempt by the Director, the applicant shall meet all standards and obtain a sign permit (Zoning Clearance) as required by Chapter 22.20.~~

C. **Prohibited signs and sign materials.** In addition to any sign or sign materials not specifically in accordance with the provisions of this Title, the following are prohibited:

1. **Signs creating traffic or pedestrian safety hazards.** Signs placed, located, or displayed in such a manner as to constitute a traffic or pedestrian safety hazard shall be prohibited, including:

a.1- Any sign which simulates or imitates in size, color, lettering or design any traffic sign or signal, or makes use of words, symbols or characters so as to interfere with, mislead or confuse pedestrian or vehicular traffic.

b.2- Signs attached or placed adjacent to any utility pole, parking meter, traffic sign post, traffic signal or any other official traffic control device, as prohibited by Section 21464 of the California Vehicle Code.

c. Signs that obstruct use of any door, window, or fire escape.

d. Signs that impede normal pedestrian use of public sidewalks.

e. Signs that constitute a traffic hazard or obstruct the view of traffic, any authorized traffic sign, or signal device.

~~3.— Except as provided by Section 22.20.060, any off-premise sign that directs attention to a business, service, product, or entertainment not sold or offered on the premises on which the sign is located, including but not limited to billboards and other off-premise outdoor advertising signs.~~

2.4. **Animated or moving signs.** Signs consisting of any moving, rotating, flashing, or otherwise animated light or component, ~~except for time and temperature displays and barber poles.~~

3.5. **Signs for discontinued uses.** Any sign or sign structure identifying a use or activity that has not occupied the site for a period greater than six months.

4. **Signs located in the public right-of-way or on public property.** Other than official government signs or hazard or prohibition signs required by law, no sign can be placed in or project into the public right-of-way or on public property unless authorized by a County encroachment permit and/or agreement with a public agency such as the California Department of Transportation.

5. **Signs affixed to trees or terrain.** Signs cut, burned, marked, or displayed in any manner on a tree, sidewalk, cliff, hillside, or other terrain feature shall be prohibited.

6. **Billboards.** Any permanent sign structure that is located adjacent to an Interstate or State highway, typically constructed of steel, concrete or wood that is freestanding or attached to the side of another structure that contains an advertising space that is leased, rented, or donated to advertisers other than the operator of the billboard, shall be prohibited.

22.20.050 - Measurement Of Sign Area

For the purpose of evaluating whether a sign is in conformity with the provisions of this Title, the area of a sign shall be measured as the number of square feet of the smallest rectangle within which a single sign face can be enclosed, as follows:

- A. **Sign faces counted.** Where a sign has two faces containing sign copy, which are oriented back-to-back and separated by not more than 36 inches at any point, the area of the sign shall be measured using one sign face only.
- B. **Wall-mounted letters.** Where a sign is composed of letters individually mounted or painted on a building wall, without a border or decorative enclosure, the sign area is that of the smallest single rectangle within which all letters and words can be enclosed.
- C. **Three-dimensional signs.** Where a sign consists of one or more three-dimensional objects such as balls, cubes, clusters of objects or sculptural or statue-type trademarks, the sign area shall be measured as the area of the smallest rectangle within which the object(s) can be enclosed, when viewed from a point where the largest area of the object(s) can be seen.

22.20.060 - Signs Allowed - Type And Area

The following permanent signs are allowed on a site subject to approval of a sign permit (~~Zoning Clearance~~) ~~Section 22.20.040.A~~, in addition to any exempt-authorized signs allowed by Section 22.20.040.B.

- A. **Sign area limitations by land use category.** The number and area of signs allowed on a site shall be as follows, based upon the land use category of the site, except where Subsection C. would also allow specialized signing:
 1. Agricultural and Rural land use categories. Two signs with a total aggregate area not exceeding 32 square feet and a height not to exceed 10 feet for each lot or parcel. Each sign may not exceed 16 square feet.
 2. Commercial Retail, Commercial Service, and Industrial land use categories. The following signs are allowed in the Commercial Retail, Commercial Service and Industrial categories, with a maximum aggregate area of 100 square feet of signing per site, or one square foot per one linear foot of the lot's largest street frontage on a public street, whichever is greater:
 - a. Wall signs for each business or tenant, with the number of such signs allowed being equivalent to the number of building faces having a public entrance to the business. The allowed area for the wall signs shall be 15 percent of the building face, up to a maximum of 80 square feet. Such wall signs may be located on building faces other than those with public entrances.
 - b. One suspended sign with a maximum area of 10 square feet for each business or tenant.
 - c. One free-standing or monument sign for each 300 linear feet of site frontage or portion thereof, with a maximum area of 60 square feet each.
 - d. One projecting sign with a maximum area of 20 square feet for each business or tenant.
 - e. Marquee signing for each business or tenant, with a maximum area of 40 square feet.

3.2. Office and Professional, Recreation, and Public Facilities land use categories. The following signs are allowed in the Office and Professional, ~~and~~ Recreation, and Public Facilities land use categories, with a maximum aggregate area of 100 square feet of signing per site, or one square foot per one linear foot of the lot's largest street frontage on a public street, whichever is greater:

- a. Wall signs for each business or tenant, with the number of such signs allowed being equivalent to the number of building faces having a public entrance to the business. The allowed area for the wall signs shall be 10 percent of the building face, up to a maximum of 50 square feet. Such wall signs may be located on building faces other than those with public entrances.
- b. One suspended sign with a maximum area of 10 square feet for each business or tenant.
- c. One monument sign for each business or tenant with a maximum area of 40 square feet and a maximum height of five feet.

4.3. Commercial or public assembly uses in other land use categories. Where commercial or public assembly uses (~~churches, sports facilities, etc.~~) are located in the Agriculture, Rural Lands or Residential land use categories, signing is allowed as set forth in Subsection A.3 A-2 for the Office and Professional, Recreation, and Public Facilities land use category.

B. Location of freestanding signs. Freestanding signs may be located within the setback areas required by Section 22.10.140, provided that the signs are:

1. Monument signs with a maximum height of three feet or less; or
2. Signs elevated above 12 feet; or
3. Authorized through Conditional-Minor Use Permit approval.

Freestanding signs with a height between three and 12 feet shall be located outside of the setback areas required by Sections 22.10.140 et seq.

C. Specialized sign requirements.

1. **Shopping, business or industrial center signing.** When approved as part of a Minor the Conditional Use Permit, a shopping, business or industrial center with five or more separate uses or tenancies on a single site sharing common driveways and parking areas, is allowed one common identification sign with a maximum area of 60 square feet, in addition to the total sign area allowed by Subsection A. Where visible from a public street, signing on shopping center sites shall be of a uniform design throughout the center as to the size, finished framing materials and location on buildings of such signs.
2. **Community identification signs.** One community identification sign is allowed at or within an urban or village reserve line on each arterial street entering a community, with a maximum area of 100 square feet and a maximum height of 12 feet. ~~The sign(s) may include the community name, slogans or mottos, names of civic or religious organizations, but no names of businesses or commercial products.~~
3. **Freeway identification signs.** In addition to the signs allowed by Subsection A., sites located in Commercial-Office and Professional, Commercial Retail, and Commercial Service land use

categories adjacent to Highway 101 or a Highway 101 Frontage Road may be authorized through Conditional Use Permit approval to use an on-site freeway identification sign with a maximum area not to exceed 125 square feet. The maximum height for freeway identification signs shall be 50 feet above grade, provided that the Commission may require a reduced or increased height where deemed appropriate.

4. **Viticultural area signing.** Each area of the county recognized as an American Viticultural Area by the U.S. Department of the Treasury, Bureau of Alcohol, Tobacco and Firearms (BATF), may be identified by roadside signs:

- a. **Required sign location.** On private property along a state highway, at or within the boundary of the viticultural area as determined by BATF.
- b. **Maximum area and height.** A maximum area of 80 square feet and a maximum height of 12 feet above the elevation of the adjoining roadway.
- c. ~~Sign copy. Shall consist only of the phrase "Entering the (Applicable Name) Viticultural Area", or equivalent approved by the Director.~~

~~5. **Winery directional signs.** In addition to any signs allowed by Subsection A., approved wineries or winery tasting rooms in rural areas may also establish a maximum of two off premise signs on private property, where allowed by state law adjacent to roads leading to the winery and/or tasting room, for the purpose of directing patrons to the site.~~

- a. ~~Maximum area and height. A maximum area of 32 square feet and a maximum height of 10 feet above the elevation of the adjoining roadway.~~
- b. ~~Appearance. All winery directional signs shall be of a uniform design, to be approved by the Director.~~
- c. ~~Sign copy. Shall consist only of the name of the winery, the distance and direction from the sign.~~

~~5. **Off-premise signs.** In addition to any signs allowed by Subsection A, any existing use in the Agriculture and Rural Lands Land Use Category may also establish a maximum of two off-premise signs on private property. Each sign shall not exceed a maximum area of 32 square feet and a maximum height of 10 feet. No more than one off-premise sign shall be established per site.~~

~~D. **Exceptions to sign standards.** Greater numbers of signs or areas of signing larger than the requirements of Subsections A. or C. require Conditional Use Permit approval.~~




Figure 10-54 - Sign Types

22.20.070 - Sign Construction Standards

The design and construction of signs shall comply with Uniform Sign Code Sections 401 through 1402, and the following:

- A. **Height.** ~~The height of any sign or sign support structure shall be a maximum of 24 feet, or no higher than the building, whichever is less, except where otherwise provided by Section 22.20.060 (Sign Design Standards). The height of any building-mounted sign shall be no higher than the height of the building, except where otherwise provided by Section 22.20.060 (Signs Allowed – Type and Area). All other signs may not exceed a maximum of 24 feet in height.~~
- B. **Lighting and Illumination.** Signs shall be indirectly lighted by continuous, stationary, shielded light sources, directed solely at the sign, or internal to it.

22.20.100 22.20.080 - Sign Maintenance Required

All signs shall be properly maintained in a safe and legible condition at all times. ~~Whenever any sign, by virtue of its physical nature and condition, poses an immediate and serious threat to the public safety, the sign may be removed by County personnel, or repaired to the satisfaction of the County. In the event that a use having signing is discontinued for a period exceeding six months, all signs identifying the use and associated structures shall be removed from the site, or in the case of painted signs, painted out.~~ Signing that is not in conformity with the provisions of this Chapter is subject to Section 22.72.070 (Nonconforming Signs).

SECTION 2: Article 4, Section 22.30.130.C.5 (Automobile Service Stations and Gas Stations) of Title 22 of the San Luis Obispo County Code, is hereby amended to read as follows:

5. ~~**Signs.** **ing.** Service station signing is allowed as follows. Signage shall be as provided by Chapter 22.20 (Signs) of this title.~~
- a. ~~**Total area.** The total area of all signs on an automobile service station site shall not exceed one square foot per two feet of public street frontage on the site, up to a maximum of 125 square feet. Signs measured include but are not limited to all freestanding signs and all wall-mounted signs.~~
 - b. ~~**Freestanding signs.** Freestanding signs are permitted, provided that there shall not be more than one pole sign on each service station site, nor more than two monument signs. Freestanding signs may be up to 20 feet in height, not to exceed the height of the building. The total area of all freestanding signs shall not exceed 60 square feet.~~
 - c. ~~**Price signs.** One price sign is allowed for each site frontage, not to exceed 12 square feet.~~
 - d. ~~**Service signs.** Signs indicating whether pump islands are "Full Service" or "Self Service" are permitted, provided that there are not to be more than two such signs for each pump island, do not project beyond the edge of the pump island curb, and do not exceed four square feet in area.~~
 - e. ~~**Freeway identification signs.** See Chapter 22.20~~

SECTION 3: Article 4, Section 22.30.230.H (Home Occupations) of Title 22 of the San Luis Obispo County Code, is hereby amended to read as follows:

- H. ~~**Signs.** Signage shall be as provided by Chapter 22.20 (Signs) of this title. Signs shall be limited to one non-illuminated identification sign with a maximum area of two square feet, in compliance with Chapter 22.20 (Sign Standards). A commercial vehicle displaying any sign identifying the home occupation and parked on or adjacent to the residential site visible from the public street is included in determining the maximum allowable area of on-site fixed signs.~~

SECTION 4: Article 4, Section 22.30.240.C.1.F (Indoor Amusement and Recreation Facilities) of Title 22 of the San Luis Obispo County Code, is hereby amended to read as follows:

- f. ~~**Signs.** Signage shall be as provided by Chapter 22.20 (Signs) of this title. Areades shall be posted with readily visible signs, with their location, size and text described in the Minor Use Permit application, indicating that persons under the age of 16 shall not be permitted on the premises during normal school hours.~~

SECTION 5: Article 4, Section 22.30.390.E.4 (Recycling – Collection Station) of Title 22 of the San Luis Obispo County Code, is hereby amended to read as follows:

4. ~~**Signs.** Signage shall be as provided by Chapter 22.20 (Signs) of this title. **Signing.** All recycling collection stations shall be provided instructional signing indicating how materials shall be separated, and stating any limitations on the types of material accepting for recycling.~~

SECTION 6: Article 8, Section 22.80.030 (Definitions of Land Uses, and Specialized Terms and Phrases) of Title 22 of the San Luis Obispo County Code, is hereby amended to read as follows:

B. **Definitions, “B.”**

Billboard. A permanent sign structure, located adjacent to an Interstate or State highway, typically constructed of steel, concrete or wood that is freestanding or attached to the side of another structure that contains an advertising space that is leased, rented, or donated to advertisers other than the operator of the billboard. See “Sign, Off-Premise”.

C. **Definitions, “C.”**

Commercial Message. A message on a sign, or portion of a sign, that promotes, informs, or proposes an economic transaction, primarily concerns the economic interests of the sign sponsor and/or audience, or is intended to further discuss in the marketplace of goods and services.

M. **Definitions, “M.”**

Mural. A hand-painted work of visual art that is either affixed to or painted directly on the exterior wall of a structure with the permission of the property owner. An original art display does not include: mechanically produced or computer generated prints or images, including but not limited to digitally printed vinyl; electrical or mechanical components; or changing image art display.

N. **Definitions, “N.”**

Non-commercial Message. A message or image on a sign that directs public attention to or advocates an idea or issue of public interest or concern that does not serve to advertise or promote any business, product, activity, service, interest, or entertainment.

S. **Definitions, “S.”**

Sign. Any visual device or representation designed or used for communicating a message, or identifying or attracting attention to a premise, product, service, person, organization, business, or event. A display, device, or object need not contain lettering to be a sign. ~~not including such devices visible only from within a building.~~

Sign Area. The area contained within the smallest rectangle enclosing all parts of sign copy, excluding any structural elements outside the limits of the sign required to support the sign. ~~The area of the smallest rectangle within which a single sign face can be enclosed.~~

Sign Face. The entire display surface area of a sign upon, against, or through which sign copy is placed. ~~The visible portions of a sign including all characters and symbols, but excluding structural elements not an integral part of the display.~~

Sign, Freestanding. A sign not attached to any buildings, erected and maintained with ~~and having~~ its own support structure, frame, mast, or pole.

Sign, Freeway Identification. An on-site sign permitted for a highway-oriented use, that is erected and maintained within the view of highway motorists (see Chapter 22.20 (Signs)).

Sign, Government. A sign constructed, placed, or maintained by local, state, or federal government or issued by any court, person, or officer in performance of a public duty; notices posted by a utility or other quasi-public agency; or other signs required or authorized by law.

Sign, Permanent. A sign that is intended to be and is so constructed as to be of a lasting and enduring condition, remaining unchanged in character, condition (beyond normal wear) and position, and in a permanent manner affixed to the ground, wall, or building.

Sign, Temporary. A structure or device used for the public display of visual messages or images, which is typically made of lightweight or flimsy materials (e.g. paper, cloth, canvas, plastic sheet, cardboard) which is not intended for or suitable for long term or permanent display. ~~A sign used not more than 60 days, or other period limited by the duration of an activity specified in Section 22.30.580 (Temporary Uses—General Standards).~~

SECTION 7: If any section, subsection, clause, phrase or portion of this ordinance is for any reason held to be invalid or unconstitutional by the decision of a court of competent jurisdiction, such decision shall not affect the validity or constitutionality of the remaining portion of this ordinance. The Board of Supervisors hereby declares that it would have passed this ordinance and each section, subsection, clause, phrase or portion thereof irrespective of the fact that any one or more sections, subsections, sentences, clauses, phrases or portions be declared invalid or unconstitutional.

SECTION 8: Before the expiration of 15 days after the adoption of this ordinance by the San Luis Obispo County Board of Supervisors, it shall be published once in a newspaper of general circulation published in the County of San Luis Obispo, State of California, together with the names of the members of the Board of Supervisors voting for and against the ordinance.

SECTION 9: This Ordinance shall become effective thirty (30) days after its enactment by the Board of Supervisors.

SECTION 10: This project is covered under the general rule that the California Environmental Quality Act (CEQA) applies only to projects which have the potential for causing a significant effect on the environment. It can be seen with certainty that there is no possibility that this project may have a significant effect on the environment; therefore, the activity is not subject to CEQA.

SECTION 11: In accordance with Government Code Section 25131, after reading the title of this Ordinance, further reading of the Ordinance in full is waived.

RECOMMENDED at a hearing of the San Luis Obispo County Planning Commission held on the 11th day of June, 2020, and PASSED AND ADOPTED by the Board of Supervisors of the County of San Luis Obispo, State of California, on the ___ day of _____, 2020, by the following roll call to vote, to wit:

AYES:

NOES:

ABSENT:

ABSTAINING:

Chairman of the Board of Supervisors

ATTEST:

WADE HORTON
Ex-Officio Clerk of the Board of Supervisors

By:
Deputy Clerk

[SEAL]

ORDINANCE CODE PROVISIONS APPROVED

AS TO FORM AND CODIFICATION:

RITA L. NEAL
County Counsel

By: _____
Deputy County Counsel

Dated: _____