

## MID-CENTURY MODERN **ACCESSORY DWELLING UNIT - PLAN 1A**

## **PROJECT GENERAL NOTES**

THESE NOTES APPLY TO ALL PORTIONS, PHASES AND SUBCONTRACTORS OF THIS PROJECT. APPLICABLE CODES AND STANDARDS:

- 2022 CALIFORNIA BUILDING CODE AND ITS APPENDICES AND -STANDARDS.
- 2022 CALIFORNIA PLUMBING CODE AND ITS APPENDICES AND STANDARDS.
- 2022 CALIFORNIA MECHANICAL CODE AND ITS APPENDICES AND
- STANDARDS. 2022 CALIFORNIA FIRE CODE AND ITS APPENDICES AND STANDARDS.
- 2022 CALIFORNIA ELECTRICAL CODE AND ITS APPENDICES AND STANDARDS. 2022 CALIFORNIA BUILDING ENERGY EFFICIENCY STANDARDS.
- 2022 CALIFORNIA GREEN BUILDING STANDARDS CODE AND ITS APPENDICIES AND STANDARDS.

CURRENT COUNTY OF SAN LUIS OBISPO MUNICIPAL CODE.

## **PROJECT DIRECTORY**

\*FOR PLANNING STAFF ONLY

INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS

**APPLICANT** (TO BE PROVIDED BY OWNER/APPLICANT)

PROJECT ADDRESS:

EMAIL PHONE:

ARCHITECT

ADDRESS:

CONTACT:

ADDRESS: 3765 S HIGUERA ST, SUITE 102 SAN LUIS OBISPO, CA 93401 CONTACT: RANDY RUSSOM

EMAIL: RWRUSSOM@RRMDESIGN.COM PHONE: P:(805) 543-1794

## **SUPPORTING DOCUMENTS**

\*FOR PLANNING STAFF ONLY INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS

UTILITY, GRADING, AND DRAINAGE PLAN TO BE PROVIDED BY OTHERS. PLEASE PROVIDE THE WASTE RECYCLE FORM FILLED OUT AND SIGNED PRIOR TO ISSUANCE. THE OWNER/APPLICANT/CONTRACTOR/PERSON DOING THE WORK IS REQUIRED TO RECYCLE 75% OF ALL PROJECT CONSTRUCTION AND DEMOLITION DEBRIS.

#### **ENERGY COMPLIANCE**

PREPARED BY: DATE PREPARED: JOB NUMBER:

IN BALANCE GREEN CONSULTING SEPTEMBER 27, 2023 CF1R-PRF-01E

#### HERS QII

HERS VCHP: HERS RATER WILL NEED TO FOLLOW THE VERIFICATION AND TESTING PROTOCOL FOR THE VARIABLE CAPACITY HEAT PUMP CREDIT REQUIREMENTS, INCLUDING BUT NOT LIMITED TO, VERIFIED REFRIGERANT CHARGE, VERIFIED MINIMUM HSPF AND EER/SEER, AND CAPACITY; DUCTLESS INDOOR UNITS AND THE COMPONENTS ARE WITHIN THE CONDITIONED ENVELOPE; AND AIRFLOW PROVIDED TO ALL HABITABLE SPACES (BDRMS AND LIVING SPACE).

## **SOILS & FOUNDATIONS**

\*FOR PLANNING STAFF ONLY INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS

NOTE: THESE PRE-APPROVED PLANS ARE INTENDED FOR FLAT LOTS, WITHOUT THE PRESENCE OF EXPANSIVE OR LIQUEFIABLE SOILS. THE BUILDING OFFICIAL SHALL MAKE THIS DETERMINATION PRIOR TO ISSUING THE PERMIT. A NOTE HAS BEEN ADDED TO THE FOUNDATION PLAN AND FOUNDATION NOTES TO CLEARLY OUTLINE THIS REQUIREMENT. PLEASE REFER TO GENERAL FOUNDATION NOTE 11 ON S-102 AND FOUNDATION PLAN NOTE 17 ON S-201.

PROJECT INFORMATION	PROJECT CHECKLIST	
*FOR PLANNING STAFF ONLY	*FOR PLANNING STAFF ONLY	WILDLAND-URBAN INTERFACE FIRE AREA
INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS:	INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS:	1. PORTIONS OF THE COUNTY OF SAN LUIS OBISPO COUNTY ARE LOCATED IN WITHIN THE WILDLAND-URBAN INTERFACE FIRE AREA (AS DEFINED BY <b>CRC</b>
PROJECT SCOPE: 1. CONSTRUCTION OF A NEW DETACHED ONE STORY 1,200 SF ACCESSORY DWELLING UNIT WITH 4 BEDROOMS AND 2 BATHS.	WASTE WATER SEWER SEPTIC - *A SEPARATE REVIEW & PERMIT IS REQUIRED FOR SEPTIC.	R337.2). a. AREA DEFINED BY STATE AS A "FIRE HAZARD SEVERITY ZONE" (FHSZ). b. AREA DESIGNATED BY ENFORCING AGENCY TO BE AT A SIGNIFICANT RISK FROM WILDFIRES.
2. ALL SITE WORK WITHIN THE PROPERTY LINE. 3. ALL THE WORK SHOWN IN THE DRAWINGS AND SPECIFICATIONS.	FIRE SPRINKLERS	2. MORE INFORMATION ABOUT FIRE HAZARD SEVERITY ZONES, INCLUDING AN INTERACITVE MAP, BUILDING MATERIALS LISTINGS, AND WUI REQUIREMENTS CAN BE FOUND ON THE OFFICE OF THE STATE FIRE MARSHAL WEBSITE
SITE INFORMATION (TO BE PROVIDED BY COUNTY OF SAN LUIS OBISPO):	DOES THE PRIMARY RESIDENCE HAVE NFPA 13D SPRINKLERS?	<ul> <li>(HTTPS://OSFM.FIRE.CA.GOV).</li> <li>3. AN ADU WITHIN THE WILDLAND-URBAN INTERFACE FIRE AREA SHALL COMPLY WITH THE CRC SECTION R337.</li> </ul>
ADNI:	AUTOMATIC SPRINKLER SYSTEM DESIGN (CRC R313.3)	4. THIS PROTOTYPE PLAN PROVIDES DESIGNS THAT COMPLY WITH THE PROVISIONS REQUIRED BY THE <b>CRC SECTION R337</b> .
APN: ZONING:	REQUIRED AT PROPOSED ADU: COUNTY OF SAN LUIS OBISPO FIRE SPRINKLERS SYSTEM REQUIREMENTS FOR ADU BLD-3044	FIRE HAZARD SEVERITY ZONE LEVEL
LOT SIZE:	<b>NO</b> (NOT REQUIRED IF THE PRIMARY RESIDENCE IS UNSPRINKLERED)	□ NONE □ MODERATE □ HIGH □ VERY HIGH
EXISTING USE:	YES (REQUIRED IF THE PRIMARY RESIDENCE IS SPRINKLERED)	1. IN ACCORDANCE WITH THE <b>CFC SECTION 4904</b> , STRUCTURES LOCATED IN THE VERY HIGH FIRE HAZARD SEVERITY ZONE SHALL PROVIDE & MAINTAIN A FUEL
	FIRE SPRINKLERS NOTES	MODIFICATION ZONE. FUEL MODIFICATION ZONES: THE APPLICANT SHALL PROVIDE & MAINTAIN FIRE/FUEL BREAKS TO THE SATISFACTION OF THE LOCAL
FLOOR AREA RATIO (TO BE PROVIDED BY COUNTY OF SAN LUIS OBISPO) MAXIMUM FAR: PROPOSED FAR:	1. IF FIRE SPRINKLERS ARE REQUIRED AT PROPOSED ADU THEN THE FOLLOWING NOTES APPLY.	FIRE DEPARTMENT. FIRE/FUEL BREAKS SHALL BE SHOWN ON THE GRADING, MAP, AND BUILDING PLANS.
LOT COVERAGE (TO BE PROVIDED BY OWNER / APPLICANT) BUILDING:	2. AUTOMATIC FIRE SPRINKLER SYSTEM - AN AUTOMATIC FIRE SPRINKLER SYSTEM SHALL BE INSTALLED AS PER NFPA 13D THE MOST CURRENT EDITION. DETAILED SPRINKLER PLANS SHALL BE SUBMITTED TO THE FIRE	<b>OPTIONS SELECTIONS</b>
HARDSACPE/PAVING:	PREVENTION BUREAU AND APPROVED PRIOR TO INSTALLATION. PLANS AND INSTALLATION MUST BE BY A C16 LICENSED SPRINKLER CONTRACTOR.	*OWNER OR APPLICANT REQUIRED TO PROVIDE SELECTIONS FOR EACH OF THE FOLLOWING CATAGORIES. ADDITIONALLY, OWNER/APPLICANT TO PROVIDE MANUFACTURER, COLOR/FINISH SPECIFICATIONS, & W.U.I. PRODUCT LISTING (WHEN
SETBACKS (TO BE PROVIDED BY COUNTY OF SAN LUIS OBISPO)  REQUIRED  PROPOSED  FRONT:	3. SECTION 903.2.1 GROUP R AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 9033 SHALL BE PROVIDED THROUGHOUT ALL BUILDINGS WITH A GROUP R FIRE AREA. THIS	APPLICABLE) IN THE MATERIALS LEGEND. <b>NOTE:</b> OWNER/APPLICANT TO STRIKE THROUGH UNSELECTED OPTIONS THROUGHOUT THE PLAN SET WHEN APPLICABLE FOR CLARITY.
REAR: 4' - 0" (A.B. NO. 86)	INCLUDES SINGLE FAMILY DWELLINGS, MULTI-FAMILY DWELLINGS AND ALL RESIDENTIAL CARE FACILITIES REGARDLESS OF OCCUPANT LOAD.	TRUSS SELECTION (SELECT ONE)
SIDES: 4' - 0" (A.B. NO. 86)	4. SECTION 903.2.1.1 ADDITIONS AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH 903.3 MAY BE REQUIRED TO BE	A) RAISED CEILING     TRUSS PACKAGE REF: 313073     B) FLAT CEILING     TRUSS PACKAGE REF: 313077
NUMBER OF STORIES: 1	INSTALLED THROUGHOUT STRUCTURES WHEN THE ADDITION IS MORE THAN 50% OF THE EXISTING BUILDING OR WHEN THE ALTERED BUILDING WILL EXCEED A FIRE FLOW OF 1,500 GALLONS PER MINUTE AS CALCULATED PER SECTION 507.3. THE FIRE CODE OFFICIAL MAY REQUIRE	<b>FRONT PORCH</b> (SELECT ONE) <b>A)</b> FRONT (COVERED) PORCH <b>B)</b> NO FRONT PORCH
OCCUPANCY GROUP:R-3 1 & 2 FAMILY DWELLINGSCONSTRUCTION TYPE:VBSPRINKLERED:SEE FIRE SPRINKLER SECTION ON SHEET	AN AUTOMATIC SPRINKLER SYSTEM BE INSTALLED IN BUILDINGS WHERE NO WATER MAIN EXISTS TO PROVIDE THE REQUIRED FIRE FLOW OR WHERE A SPECIAL HAZARD EXISTS SUCH AS: POOR ACCESS ROADS,	RAKE & EAVE DETAILS       (SELECT ONE)       A) ENCLOSED       B) OPEN EXPOSED         Image: Select one of the select one of
IF YES, A SEPARATE REVIEW/PERMIT IS REQUIRED FOR AUTO SPRINKLER SYSTEM DESIGN [CRC R313.3] MAX. HEIGHT ALLOWED:(PER CBC TABLE 504.3) 16' - 0"	GRADE, BLUFFS AND CANYON RIMS, HAZARDOUS BRUSH AND RESPONSE TIMES GREATER THAN 5 MINUTES BY A FIRE DEPARTMENT.	EXTERIOR RAKES, EAVES, & PORCH SOFFITS & OVERHANGS MATERIALS       (MARK ALL THAT APPLY)         A) 2X TOUNGE & GROOVED (SOLID SAWN LUMBER)
MAX. HEIGHT ALLOWED: (PER CALIFORNIA ASSEMBLY BILL NO. 86) 16' - 0" MAX. HEIGHT PROPOSED:	5. SECTION 903.2.1.2 REMODELS OR RECONSTRUCTION AN AUTOMATIC	□ B) FIBER CEMENT SOFFIT PANELS
ROOF RATING:REFER TO 'WILDLAND-URBAN INTERFACE FIREHIGH FIRE ZONE:AREA' AND 'FIRE HAZARD SEVERITY ZONE LEVEL'	SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 903.3 MAY BE REQUIRED IF THE SCOPE OF WORK INCLUDES SIGNIFICANT MODIFICATION TO THE INTERIOR AND/OR ROOF OF THE BUILDING, AND	<ul> <li>C) HARDBOARD SOFFIT PANELS</li> <li>D) EXT. GRADE FIRE RETARDANT TREATED SHEATHING</li> </ul>
	THE COST OF THE INSTALLATION DOES NOT EXCEED 15 PERCENT OF THE CONSTRUCTION COSTS OF THE REMODEL.	WALL COVERINGS (MARK ALL THAT APPLY)
UTILITIES	<ol> <li>LOCATION AND SIZE OF WATER SERVICE UNDERGROUND SHALL BE INSTALLED AS SHOWN ON APPROVED FIRE SPRINKLER PLANS. A MINIMUM 1 INCH WATER SHALL BE INSTALLED.</li> </ol>	NOTE: WALL COVERINGS TO MEET ALL REQUIREMENTS OF CRC R703.3. SEE CRC TABLE R703.3(1) FOR MIN. ATTACHMENT AND MIN. THICKNESS REQUIREMENTS.
WATER AND SEWER SERVICE COUNTY OF SAN LUIS OBISPO UTILITIES	7. A FIRE UNDERGROUND FLUSH CERTIFICATION SHALL BE REQUIRED AT FINAL INSPECTION.	E) FIBER CEMENT HORIZONTAL LAP SIDING
ELECTRICAL SERVICEPACIFIC GAS & ELECTRICGAS SERVICEPACIFIC GAS & ELECTRICTELEPHONE SERVICEPACIFIC GAS & ELECTRIC	8. A HYDRO INSPECTION OF THE FIRE SPRINKLER SYSTEM IS REQUIRED PRIOR TO FRAME INSPECTION. ONLY THE NEW PIPING SHALL BE TESTED.	F) EXT. GRADE WOOD HORIZONTAL LAP SIDING
GARBAGE SERVICE	ONSITE PARKING REQUIRED	EXTERIOR TRIM ELEMENTS (SELECT ONE) A) FIBER CEMENT B) EXT. GRADE WOOL
		BASE TRIM 24/A-901 (SELECT ONE) A) YES B) NO
BUILDING AREAS	THE ADU IS LOCATED WITHIN 1/2 MILE OF PUBLIC TRANSIT.	<b>EXTERIOR LIGHT</b> (SELECT ONE) A) LNC - MODERN B) LUTEC BARN LIGHT
REAS - PLAN 1	OFF STREET PARKING PERMITS ARE REQUIRED BUT NOT OFFERED TO THE OCCUPANT OF THE ADU.	DOOR MATERIAL       (SELECT ONE)         A) VINYL       B) FIBERGLASS       C) WOOD       D) ALUMINUM CLAD WOOD
PLAN 1 - GROUND FLOOR 1200 SF	WHEN THERE IS A CAR SHARE VEHICLE LOCATED WITHIN ONE BLOCK OF THE ADU.	WINDOW MATERIAL       (SELECT ONE)         A) VINYL       B) FIBERGLASS       C) WOOD       D) ALUMINUM CLAD WOOD
FRONT PORCH OPTION (EXTERIOR) 92 SF	<ul> <li>ONE PARKING SPACE (STUDIO OR 1-BEDROOM ADU)</li> <li>TWO PARKING SPACES (2-BEDROOM ADU)</li> </ul>	DECORATIVE FAUX GABLE VENTS (SELECT ONE) A) NO B) YES LABEL LOCATIONS ON ELEV.

 PROPOSED:	
:	EFER TO 'WILDLAND-URB
NE: A	A' AND 'FIRE HAZARD SEV

SAN LUIS OBISPO COUNTY, CA

## **USER LICENSE AGREEMENT**

BY USING THESE PERMIT READY ACCESSORY DWELLING UNIT CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE, HOLD HARMLESS, AND INDEMNIFY THE COUNTY OF SAN LUIS OBISPO, ITS ELECTED OFFICIALS AND EMPLOYEES, RRM DESIGN GROUP, AND THE ARCHITECT OR ENGINEER WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.

THE PLANS ATTACHED HERE ARE APPROVED FOR ONLY USE IN SAN LUIS OBISPO COUNTY. NO DEVIATIONS, ALTERATIONS, OR OPTIONS BEYOND THOSE SPECIFICALLY INDICATED IN THE PLANS ARE ALLOWED WITHOUT PRIOR APPROVAL BY THE ISSUING JURISDICTION AND CHIEF BUILDING OFFICIAL. ANY UNAPPROVED PLAN MODIFICATIONS MAY BE DEVELOPED THROUGH RRM DESIGN GROUP AND THE APPROVING JURISDICTION IF REQUIRED.

## SHEET INDEX

SIGNATURE

DATE

G-011	TITLE SHEET - PLAN 1A
G-101	GENERAL NOTES
G-102	INDEX, ABBREVIATIONS, & SYMBOLS
G-103	2022 SINGLE-FAMILY RESIDENTIAL MANDATORY REQUIREMENTS
G-201	CAL GREEN RESIDENTIAL REQUIREMENTS
G-202	CAL GREEN RESIDENTIAL REQUIREMENTS
AS-101	ARCHITECTURAL SITE PLAN (EXAMPLE & INSTRUCTIONS)
A1-101	FLOOR PLAN
A1-111	FINISH, MECHANICAL, & ELECTRICAL PLANS
A1-121	ROOF PLAN & REFLECTED CEILING PLAN
A1-201	ELEVATIONS & BUILDING SECTIONS
A-901	ARCHITECTURAL DETAILS
A-902	ARCHITECTURAL DETAILS
A-903	ARCHITECTURAL DETAILS
A-911	ARCHITECTURAL DETAILS
A-912	ARCHITECTURAL DETAILS - ROOF
S-101	SHEET INDEX, ABBREVIATIONS & SYMBOLS
S-102	GENERAL NOTES
S-103	GENERAL NOTES, SPECIAL INSPECTION & TESTS
S-201	FOUNDATION PLAN - MID-CENTURY MODERN
S-202	ROOF FRAMING PLAN - MID-CENTURY MODERN
S-301	TYPICAL CONCRETE DETAILS
S-311	CONCRETE DETAILS
S-312	CONCRETE DETAILS
S-401	TYPICAL WOOD DETAILS
S-402	TYPICAL WOOD DETAILS
S-403	TYPICAL WOOD DETAILS
S-404	TYPICAL WOOD DETAILS
S-421	ROOF FRAMING DETAILS
S-422	ROOF FRAMING DETAILS
T24 - 101	
T24 - 102	ENERGY COMPLIANCE - PLAN 1A

T24 - 103 ENERGY COMPLIANCE - PLAN 1A T24 - 104 ENERGY COMPLIANCE - PLAN 1A T24 - 113 ENERGY COMPLIANCE - PLAN 1 Grand total: 35

#### TED IN THE IN A FUEL SHALL THE LOCAL RADING,

313077 RONT PORCH

GRADE WOOD

CLAD WOOD

#### SPECIAL INSTRUCTIONS REQUIRED

OWNER/APPLICANT HAS COMPLETED SPECIAL INSPECTION FORM

**OWNER/APPLICANT SIGNATURE:** SEE SHEET S-103 FOR REQUIRED SPECIAL INSPECTIONS

A REGISTERED DESIGN PROFESSIONAL SHALL COMPLETE THE COUNTY OF SAN LUIS OBISPO STATEMENT OF REQUIRED SPECIAL INSPECTIONS CERTIFICATE (FORM BLD-1032) PRIOR TO PERMIT ISSUANCE. IDENTIFY THE TYPE OF WORK REQUIRING SPECIAL INSPECTIONS IN THE PLANS AND THE INDIVIDUALS OR FIRMS RESPONSIBLE FOR THE SPECIAL INSPECTION ELEMENT(S). FURTHER INSTRUCTIONS ARE IDENTIFIED IN THE STATEMENT OF SPECIAL INSPECTION AGREEMENT (FORM BLD-1031).

## **VICINITY MAP**


\*FOR PLANNING STAFF ONLY


INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS:

(TO BE PROVIDED BY OWNER/APPLICANT)



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALI ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.





- FORM
- e. FANS SHALL BE A MAXIMUM OF 1 SONE.
- a. PROVIDE 30" MIN. HEADROOM IN THE ATTIC SPACE (2019 CRC R807.1) b. IN ATTIC, PROVIDE LIGHT AND SWITCH, AND ALL NECESSARY ELECTRICAL. PROVIDE UNOBSTRUCTED PASSAGEWAY 24" WIDE OF SOLID CONTINUOUS FLOORING FROM ACCESS TO EQUIPMENT AND IT'S CONTROLS. ALSO PROVIDE UNOBSTRUCTED WORK SPACE IN FRONT OF EQUIPMENT 30" DEPTH MINIMUM. PROVIDE COMBUSTION AIR AND CONDENSATE LINE TO OUTSIDE OR AN APPROVED DRAIN FOR OPTIONAL
- FRAMING MEMBERS.
- SHALL BE LOCATED NOT OVER 20 FEET FROM THE EQUIPMENT. (2022 CRC R807.1)
- e. PROVIDE A 120V RECEPTACLE AND A LIGHT NEAR THE EQUIPMENT WITH LIGHT SWITCH LOCATED AT THE ATTIC ACCESS.

- AWAY FROM THE BUILDING. CONTRACTOR TO FIELD VERIFY EXISTING DRAINAGE. IF THE EXISTING DRAINAGE SYSTEM IS DAMAGED DURING EXCAVATION, CONTRACTOR SHALL REPAIR AND/OR REROUTE DRAINAGE SYSTEM AND CONNECT TO EXISTING DRAINAGE FACILITY AS NECESSARY.
- EXISTING PUBLIC IMPROVEMENTS THAT ARE DAMAGED BY THE PROJECT CONSTRUCTION SHALL BE REPAIRED OR REPLACED. EXISTING DAMAGED PUBLIC IMPROVEMENTS WITHIN THE PROJECT LIMITS SHALL BE REPAIRED OR REPLACED EVEN IF THE DAMAGE OCCURRED PRIOR TO THE START OF CONSTRUCTION.
- EROSION AND SEDIMENT CONTROL FACILITIES SHALL BE INSTALLED PRIOR TO OCTOBER 1 AND SHALL BE MAINTAINED DAILY UNTIL APRIL 30. THESE FACILITIES SHALL CONTROL AND CONTAIN EROSION-CAUSED SILT DEPOSITS AND PROVIDE FOR THE SAFE DISCHARGE OF SILT-FREE STORM WATERS INTO EXISTING STORM DRAIN FACILITIES. EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON-SITE DURING THE DRY SEASON AND EMPLOYED, AS NECESSARY PRIOR TO AND
- DURING RAIN EVENTS. SEASONALLY APPROPRIATE BEST MANAGEMENT PRACTICES FOR THE FOLLOWING SITE MANAGEMENT CATEGORIES MUST BE IMPLEMENTED YEAR-ROUND: 1) EROSION CONTROL; 2) RUN-ON AND RUN-OFF CONTROL; 3) SEDIMENT CONTROL; 4) GOOD SITE MANAGEMENT; AND 5)
- NON-STORMWATER MANAGEMENT. AN ENCROACHMENT PERMIT WILL BE REQUIRED FOR ANY CONSTRUCTION ACTIVITY WITHIN A PUBLIC STREET RIGHT OF WAY THAT HAS BEEN ACCEPTED BY THE CITY/COUNTY.

- 1. WATER HEATER (REFER TO BUILDING ENERGY ANALYSIS REPORT): a. ALL DOMESTIC HOT WATER PIPING SHALL BE INSULATED. (2022 CPC
  - PIPES UP TO 2 INCHES IN DIAMETER: INSULATION WALL THICKNESS NOT LESS THAN DIAMETER OF PIPE. (2022 CPC 609.12.2) PIPES GREATER THAN 2 INCHES IN DIAMETER: INSULATION WALL
  - THICKNESS NOT LESS THAN 2 INCHES. (2022 CPC 609.12.2) EXCEPTIONS:
  - 1. PIPING THAT PENETRATES FRAMING MEMBERS SHALL NOT BE REQUIRED TO HAVE PIPE INSULATION FOR THE DISTANCE OF THE FRAMING PENETRATION. (2022 CPC 609.12.2) SUPPLY STOP AND THE FIXTURE OR APPLIANCE SHALL NOT BE REQUIRED TO BE INSULATED. (2022 CPC 609.12.2)
  - 2. HOT WATER PIPING BETWEEN THE FIXTURE CONTROL VALVE OR
  - a. PROVIDE A TEMPERATURE AND PRESSURE RELIEF VALVE WITH A FULL SIZE DRAIN OF GALVANIZED STEEL OR HARD DRAWN COPPER TO THE OUTSIDE OF THE BUILDING WITH THE END OF THE PIPE PROTRUDING 6" MINIMUM @ 2' MAX. ABOVE GRADE POINTING DOWNWARD TO THE TERMINATION - UNTHREADED.
  - . COMBUSTION AIR PER MANUFACTURE REQUIREMENTS.
  - c. CLEARANCES PER MANUFACTURE REQUIREMENTS. INSULATION FOR PIPING AND TANKS (2022 CEC 105.0(j)):
  - A. WATER PIPING, SOLAR WATER-HEATING SYSTEM PIPING, AND SPACE-CONDITIONING SYSTEM LINE INSULATION THICKNESS AND CONDUCTIVITY. PIPING SHALL BE INSULATED AS FOLLOWS: a. DOMESTIC HOT WATER PIPING, SEE NOTES ABOVE.
  - b. PIPING FOR SPACE-CONDITIONING SYSTMES, SOLAR WATERHEATER SYSTEM COLLECTOR LOOP, SEE 2022 CEC SECTION 120.3(c).

  - 1. PIPING SURROUNDED WITH A MINIMUM OF 1 INCH OF WALL INSULATION, 2 INCHES OF CRAWLSPACE INSULATION, OR 4 INCHES OF ATTIC INSULATION SHALL NOT BE REQUIRED TO HAVE
  - PIPE INSULATION.
  - A. INSULATION PROTECTION. PIPE INSULATION SHALL BE PROTECTED
  - FROM DAMAGE DUE TO SUNLIGHT, MOISTURE, EQUIPMENT MAINTENANCE AND WIND. PROTECTION SHALL, AT MINIMUM, INCLUDE THE FOLLOWING (2022 CEC SECTION 120.3(B)): a. PIPE INSULATION EXPOSED TO WEATHER SHALL BE PROTECTED BY A COVER SUITABLE FOR OUTDOOR SERVICE. THE COVER SHALL BE
  - WATER RETARDANT AND PROVIDES SHIELDING FROM SOLAR RADIATION THAT CAN CAUSE DEGRADATION OF THE MATERIAL PROTECTION.
  - ADHESIVE TAPE SHALL NOT BE USED TO PROVIDE THIS b. PIPE INSULATION COVERING CHILLED WATER PIPING AND REFRIGERANT SUCTION PIPING LOCATED OUTSIDE THE CONDITIONED SPACE SHALL INCLUDE, OR BE PROTECTED BY, A CLASS I OR CLASS II VAPOR RETARDER. ALL PENETRATIONS AND JOINTS SHALL BE SEALED.

  - c. PIPE INSULATION BURIED BELOW GRADE MUST BE INSTALLED IN A WATER PROOF AND NONCRUSHABLE CASING OR SLEEVE. WEATHER BARRIERS. A. NOT FEWER THAN ONE-LAYER WATER-RESISTIVE BARRIER SHALL BE APPLIED OVER STUDS OR SHEATHING OF ALL EXTERIOR WALLS CONTINUOUS FROM TOP OF WALS AND TERMINATED AT PENETRATIONS AND BUILDING APPENDAGES WITH FLASHING. MINIMUM NO. 15 FELT
  - COMPLYING WITH ASTM D226, TYPE 1.
  - B. PROVIDE (2) LAYERS OF GRADE D PAPER OR EQUAL WHEN PLASTER IS INSTALLED OVER WOOD BASED SHEATHING. (2022 CRC R703.7.3) DOMESTIC RANGE VENTILATION DUCTS SHALL HAVE SMOOTH INTERIOR SURFACES. (2022 CMC 504.3)

  - . CLOTHES DRYER MOISTURE EXHAUST DUCTS SHALL TERMINATE OUTSIDE THE BUILDING AND HAVE A BACK-DRAFT DAMPER. EXHAUST DUCT IS LIMITED TO 14'-0" W/ TWO ELBOWS. THIS SHALL BE REDUCED 2'-0" FOR
  - EVERY ELBOW IN EXCESS OF TWO. MIN. DIA. 4", SMOOTH, METAL DUCT.(2022 ALL MANUFACTURED EQUIPMENT SHALL BE INSTALLED AS PER MANUFACTURER'S SPECIFICATION AND DIMENSIONS VERIFIED WITH
  - INSTALLATION REQUIREMENTS. ALL MANUFACTURER'S INSTALLATION INSTRUCTIONS SHOULD BE ON SITE FOR INSPECTIONS. SHOWERS AND TUB-SHOWER COMBINATIONS: CONTROL VALVES MUST BE PRESSURE BALANCED OR THERMOSTATIC MIXING VALVES. (2022 CPC 417.0.) 6. WET-ROOM GLAZING. PROVIDE TEMPERED GLAZING IN DOORS AND ENCLOSURES FOR SHOWERS BATHTUBS SAUNAS STEAM ROOMS HOT

  - TUBS & SIMILAR USES WHERE THE BOTTOM EXPOSED EDGE IS LESS THAN 60-INCHES ABOVE A STANDING SURFACE. (2022 CRC R308.4.5) HEATING AND AIR-CONDITIONING SYSTEM DESIGN SHALL CONFORM TO CALGREEN SEC. 4.507. ENVIRONMENTAL COMFORT.

  - a. CLEARANCES: 24" MIN. FRONT, 30" MIN COMPARTMENT WIDTH.
  - b. PROVIDE A MIN 3 SF WINDOW, 1/2 OF WHICH SHALL BE OPENABLE OR AN EXHAUST FAN 50 CFM FOR INTERMITTENT OR 20 CFM FOR CONTINUOUS. DIRECT VENT TO OUTSIDE WITH BACKDRAFT DAMPER. (2022 CRC R303.3) c. NEW WATER CLOSETS AND ASSOCIATED FLUSHOMETER VALVES, IF ANY SHALL USE NO MORE THAN 1.28 GALLONS PER FLUSH AND SHALL MEET PERFORMANCE STANDARDS ESTABLISHED BY THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS STANDARD A112.19.2. H & S CODE,
  - SECTION 17921.3(B). BATH ACCESSORIES: PROVIDE MINIMUM 1 TOILET PAPER HOLDER AND 1 TOWEL BAR PER BATHROOM, PROVIDE NECESSARY BLOCKNG FOR TOILET
  - PAPER HOLDER AND TOWEL BARS. 0. WHOLE-BUILDING MECHANICAL VENTILATION SYSTEM PER ASHRAE STANDARD 62.2. PROVIDE THE COUNTY INSPECTOR THE FOLLOWING
  - INFORMATION AT OR BEFORE THE TIME OF INSPECTION: a. CALCULATIONS FOR REQUIRED VENTING RATES.
  - b. CALCULATION ADJUSTMENTS FOR INTERMITTENT SYSTEMS IF

  - c. DUCT DIAMETER AND MAXIMUM DUCT LENGTH PER ASHRAE 62.2 TABLE
  - d. TYPE OF SYSTEM USED AND PROVIDE COMPLETED CF-6R-MECH-05

  - f. FANS SHALL BE PROVIDED A COVER OF R-4.2 WHEN OFF. 11. ATTIC ACCESS:
  - AIR CONDITIONING.
  - c. BUILDINGS WITH COMBUSTIBLE CEILING OR ROOF CONSTRUCTION SHALL HAVE AN ATTIC ACCESS OPENING TO ATTIC AREAS THAT EXCEED 30 SQUARE FEET AND HAVE A VERTICAL HEIGHT OF 30-INCHES OR GREATER. THE VERTICAL HEIGHT SHALL BE MEASURED FROM TOP OF THE CEILING FRAMING MEMBERS TO THE UNDERSIDE OF THE ROOF d. THE ROUGH-FRAMED OPENING SHALL NOT BE LESS THAN 22" X 30" AND

### **ELECTRICAL NOTES**

- 1. CONFORM WITH CURRENT CEC, NFPA, MFR'S, AND LOCAL REQUIREMENTS.
- 2. ELECTRICAL SYSTEM GROUND TO BE PROVIDED PER NEC ARTICLE 250-81. 3. ALL MATERIALS TO BE U.L. LABELED.
- 4. METER: "SQUARE D", 120 VOLT/ 240 VOLT, 1 AND 3 WIRE GROUND OR EQUAL. 5. ELECTRICAL SUB PANEL: FLUSH MOUNT, 30" CLEARANCE. 100 AMP.
- 6. CONDUCTORS: TW, THW, COPPER, MINIMUM 14 AT LIGHTING, 12 AT OTHER CIRCUITS.
- . LAMPS: FOR GENERAL LIGHTING IN KITCHENS AND BATH SHALL HAVE AN EFFICIENCY OF NOT LESS THAN 40 LUMENS/ WATT. ALL SOCKETS FILLED WITH SOFT-WHITE, 55 WATT FLUORESCENT: COOL WHITE, RS, SOUND RATING "A", 40 WATT (U.O.N.).
- 8. ALL ELECTRICAL OUTLETS INSTALLED IN BATHROOMS, GARAGES, BASEMENTS, CRAWL SPACES, OUTDOORS, KITCHEN COUNTERS, AND AT WET BAR SINKS SHALL HAVE GROUND-FAULT CIRCUIT-INTERRUPTER PROTECTION IN COMPLIANCE WITH NEC Art. 210-8, CONSISTING OF 125 VOLT. SINGLE-PHASE, 15- AND 20- AMPERE RECEPTACLES.
- 9. ALL BATHROOM RECEPTACLE OUTLETS SHALL BE SUPPLIED BY A MINIMUM OF ONE 120-VOLT, 20-AMPERE BRANCH CIRCUIT. SUCH CIRCUITS SHALL HAVE NO OTHER OUTLETS. THIS DEDICATED CIRCUIT MAY SERVE MORE THAN ONE BATHROOM. (2022 CEC 210.11(C))
- 10. PROVIDE ELECTRIC OUTLET AND PUSH-BUTTON WIRE FOR GARAGE OPENER (INCLUDE OPENER) 11. THERMOSTAT SHALL BE A PROGRAMMABLE TYPE, HONEYWELL TH8320 OR EQUAL
- 12. RECESSED LUMINAIRES INSTALLED IN AREAS TO RECEIVE INSULATION SHALL BE "IC" LUMINAIRES AND ARE CERTIFIED AND LABELED AS AIRTIGHT TO THE STANDARDS PRESCRIBED BY THE RESIDENTIAL ENERGY CODE.
- 13. CEILING-SUSPENDED (PADDLE) FANS SHALL BE SUPPORTED INDEPENDENTLY OF AN OUTLET BOX OR BY LISTED OUTLET BOX OR OUTLET BOX SYSTEMS IDENTIFIED FOR THE USE AND INSTALLED IN ACCORDANCE WITH 2022 CEC 314.27(C) (2022 CEC 422.18).
- 14. ALL LUMINARIES, LAMPHOLDERS, AND RETROFIT KITS SHALL BE LISTED (2022 CEC 410.6).
- 15. ALL 120-VOLT, SINGLE PHASE 15- AND 20- AMPERE BRANCH CIRCUITS SUPPLYING OUTLETS INSTALLED IN DWELLING UNIT KITCHENS, FAMILY ROOMS, LIVING ROOMS, DINING ROOMS, PARLORS, LIBRARIES, DENS, BEDROOMS, SUNROOMS, RECREATION ROOMS, CLOSETS, HALLWAYS OR SIMILAR ROOMS OR AREAS SHALL BE PROTECTED BY A LISTED ARC-FAULT CIRCUIT INTERRUPTER, COMBINATION-TYPE, INSTALLED TO PROVIDE PROTECTION OF THE BRANCH CIRCUIT. (2022 CEC 210-12(A)).
- 16. ALL NON-LOCKING TYPE 125-VOLT, 15 AND 20 AMPERE RECEPTACLES IN A DWELLING UNIT SHALL BE LISTED TAMPER-RESISTANT RECEPTACLES. EXCEPTIONS: (1) RECEPTACLES MORE THAN 5'6" ABOVE THE FLOOR. (2) RECEPTACLES PART OF A LUMINAIRE OR APPLIANCE, (3) A SINGLE RECEPTACLE OR A DUPLEX RECEPTACLE FOR TWO APPLIANCES THAT ARE NOT EASILY MOVED AND LOCATED WITHIN DEDICATED SPACE AND ARE CHORD-AND-PLUG CONNECTED AS PER CEC 400.7, AND (4) NON-GROUNDING RECEPTACLES USED FOR REPLACEMNETS AS PERMITTED IN
- CEC 406.4(D)(2)(A) 17. HIGH EFFICACY LUMINAIRES OTHER THAN OUTDOOR HID LIGHTING CONTAIN ONLY ONLY HIGH EFFICACY LAMPS AS OUTLINED IN TABLE 150-C OF THE RESIDENTIAL ENERGY CODE AND NOT CONTAIN A MEDIUM SCREW BASE SOCKET
- 18. BALLAST FOR LAMPS 13 WATTS OR GREATER SHALL BE ELECTRONIC AND HAVE AN OUTPUT FREQUENCY NO LESS THAT 20 kHz. 19. SMOKE DETECTORS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING AND PROVIDED WITH A BATTERY BACK-UP. ALL SMOKE DETECTORS SHALL BE INTERCONNECTEED. ALL SMOKE DETECTORS SHALL MAINTAIN A MINIMUM 3 FOOT CLEARANCE TO HVAC SUPPLY OR RETURN AIR REGISTERS
- 20. CARBON MONOXIDE ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING AND PROVIDED WITH A BATTERY BACK-UP. ALL CARBON MONOXIDE ALARAMS SHALL BE INTERCONNECTEED.
- 21. LIGHTS IN OTHER THAN KITCHENS, BATHROOMS, GARAGES, LAUNDRY ROOMS, AND UTILITY ROOMS MUST BE CONTROLLED BY A DIMMER OR CONTROLLED BY A MANUAL-ON OCCUPANT SENSOR. SUCH SENSORS SHALL BE CAPABLE OF AUTOMATICALLY TURNING OFF THE LIGHTS NO MORE THAN 30 MINUTES AFTER THE AREA HAS BEEN VACATED. 22. EXHAUST FANS WILL BE CONTROLLED BY A HUMIDISTAT PER THE GREEN
- BUILDING STANDARDS CODE SECTION 4.506. EXHAUST FANS MUST BE SWITCHED SEPARATELY FROM LIGHTS (CEngC 150.0(k)(2)) 23. OUTDOOR LIGHTING PERMANENTLY MOUNTED TO A RESIDENTIAL BUILDING OR TO OTHER BUILDINGS ON THE SAME LOT SHALL BE HIGH EFFICACY AND
- MUST MEET THE REQUIREMENTS IN ITEM I AND THE REQUIREMENTS IN EITHER ITEM II OR ITEM III: • i) CONTROLLED BY A MANUAL **ON** AND **OFF** SWITCH THAT PERMITS THE AUTOMATIC ACTIONS OF ITEMS II OR III BELOW; AND
- ii) CONTROLLED BY A PHOTOCELL AND EITHER A MOTION SENSOR OR AN AUTOMATIC TIME SWITCH CONTROL' OR iii) CONTROLLED BY AN ASTRONOMICAL TIME CLOCK CONTROL.

NOTE: CONTROLS THAT OVERRIDE TO ON SHALL NOT BE ALLOWED UNLESS THE OVERRIDE AUTOMATICALLY RETURNS THE AUTOMATIC CONTROL TO ITS NORMAL OPERATION WITHIN 6 HOURS. AN ENERGY MANAGEMENT CONTROL SYSTEM THAT PROVIDES THE SPECIFIED LIGHTING CONTROL FUNCTIONALITY AND COMPLIES WITH ALL REQUIREMENTS APPLICABLE TO THE SPECIFIED CONTROLS MAY BE USED TO MEET THESE REQUIREMENTS.

- 1. AT LEAST ONE LUMINAIRE EACH BATHROOM, LAUNDRY ROOM, AND UTILITY ROOM SHALL BE CONTROLLED BY A MANUAL ON/AUTOMATIC-OFF VACANCY
- SENSOR 2. EXCEPT FOR CLOSETS LESS THAN 70 SQUARE FEET AND HALLWAYS, ALL LUMINAIRES THAT ARE INSTALLED WITH JA8-CERTIFIED LIGHT SOURCES ARE REQUIRED TO BE CONTROLLED BY EITHER A DIMMER, VACANCY SENSOR OR FAN SPEED CONTROL.

## **PLUMBING NOTES**

- CONFORM WITH CURRENT CPC AND LOCAL REQUIREMENTS. 2. PIPING:
- a. DOMESTIC WATER (WITHIN BUILDING): COPPER OR PEX PIPE OR APPROVED EQUAL. b. GAS, EXPOSED TO WEATHER: GALVANIZED
- . AIR CHAMBERS: 12" LONG CAPPED NIPPLE AT END OF EACH BRANCH TO EACH FIXTURE. d. DIELECTRIC UNIONS "F.P.C.O." REQUIREMENT AT ALL DISSIMILAR
- MATERIAL CONNECTIONS. e. WHEN "OPTIONAL" SOFT-WATER LOOP INTALLED, PROVIDE WITH 2 GATE VALVES.
- 3. WATER SERVICE PIPE SHALL BE PER CIVIL PLANS OR AS REQUIRED BY THE JURISDICTION. 4. WATER METER: PER WATER DISTRICT (REFER SIZE W/ FIRE SPRINKLER
- PLANS IF APPLICABLE) 5. SHOWER HEADS AND FAUCETS: FLOW RATES PER 2022 CGBSC SECTION
- 4.303.
- 6. PIPE INSULATION: REFER TO TITLE 24 MANDATORY MEASURES "SPACE CONDITIONING, WATER HEATING & PLUMBING SYSTEM MEASURES"
- 7. STRAPS AND HANGERS: PROVIDE AS NECESSARY TO INSURE A STABLE INSTALLATION. SEE TITLE-24 FOR WATER HEATER REQUIREMENTS.
- . ALL HOSE BIBS SHALL HAVE APPROVED BACK FLOW PREVENTION DEVICES. 9. PLUMBING FIXTURES (WATER CLOSETS) AND FITTINGS (FAUCETS AND SHOWERHEADS) SHALL MEET THE STANDARDS REFERENCED IN CALGREEN TABLE 4.303.3.
- 10. WATER HEATER SHALL BE PROVIDED WITH A TEMPERATURE AND PRESSURE RELIEF VALVE. PER [2022 CPC 505.2] THE RELIEF VALVE SHALL BE PROVIDED WITH A DRAIN LINE WHICH EXTENDS FROM THE VALVES TO THE OUTSIDE OF THE BUILDING. PER [2022 608.5 CPC]
- 11. PER 2022 CPC 603.5.7 OUTLETS WITH HOSE ATTATCHMENTS. POTABLE WATER OUTLETS WITH HOSE ATTACHMENTS. OTHER THAN WATER HEATER DRAINS, BOILER DRAINS, AND CLOTHES WASHER CONNECTIONS, SHALL BE PROTECTED BY A NONREMOVABLE HOSE BIBB TYPE BACKFLOW PREVENTER, A NONREMOVABLE HOSE BIBB TYPE VACUMM BREAKER, OR BY AN ATMOSPHERE VACUUM BREAKER INSTALLED NOT LESS THAN 6 INCHES ABOVE THE HIGHEST POINT OF USAGE LOCATED ON THE DISCHARGE SIDE OF THE LAST VALVE. IN CLIMATES WHERE FREEZING TEMPERATURES OCCUR, A LISTED SELF DRAINING FROST-PROOF HOSE BIBB WITH AN INTEGRAL BACKFLOW PREVENTER OR VACUUM BREAKER SHALL BE USED.

## **MECHANICAL NOTES**

- 1. CONFORM WITH CURRENT ADOPTED CRC, CMC, SMACCNA, NFPA AND LOCAL REQUIREMENTS.
- DUCTWORK: SMACCNA "LOW VELOCITY DUCT CONSTRUCTION" NFPA STANDARD #90A. ALL TRANSVERSE DUCT PLENUM AND FITTING JOINTS SHALL BE SEALED WITH PRESSURE SENSITIVE NON-CLOTH TAPE MEETING THE REQUIREMENTS OF UL181, 181A, OR 181B, OR MASTIC TO PREVENT AIR LOSS. DUCTS SHALL BE INSULATED AS REQUIRED BY THE UMC. SEE FLOOR PLAN FOR F.A.U. AND FIREPLACES. DUCTS PENETRATING A WALL OR FLOOR-CEILING BETWEEN GARAGE & DWELLING TO BE MINIMUM 26 GAUGE METAL WITHOUT OPENING IN GARAGE. FIRE DAMPER REQUIRED OTHERWISE.
- GRILLES AND REGISTERS, DIFFUSERS, ETC: SUBJECT TO OWNERS APPROVAL. "CARNES" OR EQUAL FANS: DIRECTLY VENTED TO OUTSIDE,
- BACK DRAFT DAMPERS ARE REQUIRED (PER TABLE 2-53V, TITLE 24 C.A.C.). THE RETURN AIR PLENUM SERVING THE MECHANICAL EQUIPMENT MUST BE FULLY DUCTED FROM THE EQUIPMENT TO THE CONDITIONED SPACE. DROP CEILINGS, WALL CAVITIES AND EQUIPMENT PLATFORMS MAY NOT BE USED AS PLENUMS.
- LAUNDRY DRYER VENT TO EXTERIOR TO BE 14 FEET MAXIMUM, LESS 2 FEET PER 90 DEGREE TURN PER CMC 504.3.2.2. IF VENT IS OVER 14' AN APPROVED POWER ASSISTED DEVICE IS REQUIRED.
- BATHROOM EXHAUST FANS (BATHROOM APPLIES TO ROOMS CONTAINING BATHTUB, SHOWER, OR TUB/SHOWER COMBINATION) WHICH EXHAUST DIRECTLY FROM BATHROOMS SHALL COMPLY WITH THE
- FOLLOWING (2022 CGBSC SEC. 4.506.1): a. FANS SHALL BE ENERGY STAR COMPLIANT AND BE DUCTED TO
- TERMINATE OUTSIDE THE BUILDING MIN 3' FROM OPENINGS. b. UNLESS FUNCTIONING AS A COMPONENT OF A WHOLE HOUSE VENTILATION SYSTEM, FANS MUST BE CONTROLLED BY A HUMIDITY CONTROL
- HUMIDITY CONTROLS SHALL BE CAPABLE OF ADJUSTMENT BETWEEN A RELATIVE HUMIDITY RANGE OF ≤ 50 PERCENT TO A MAXIMUM OF 80 PERCENT. A HUMIDITY CONTROL MAY UTILIZE MANUAL OR AUTOMATIC MEANS OF ADJUSTMENT.
- A HUMIDITY CONTROL MAY BE A
- SEPARATE COMPONENT TO EXHAUST FAN AND IS NOT REQUIRED TO BE INTEGRAL(I.E. BUILT IN) 7. BATHROOM EXHAUST FANS SHALL PROVIDE MINIMUM 50 CFM EXHAUST
- RATE (2022 CMC TABLE 403.7). 8. KITCHEN EXHAUST FANS SHALL PROVIDE MINIMUM 100 CFM EXHAUST RATE
- (2022 CMC TABLE 403.7) 9. PER 2022 CEnC 150(m) PORTIONS OF SUPPLY-AIR AND RETURN-AIR DUCTS
- PLENUMS SHALL BE INSULATED TO A MINIMUM INSTALLED LEVEL OF R-6.0 (OR ANY LEVEL HIGHER LEVEL REQUIRED BY 2022 CMC SECTION 605) OR BE ENCLOSED ENTIRELY IN CONDITIONED SPACE.

## **TITLE 24 COMPLIANCE**

- ALL INTERIOR RESIDENTIAL LIGHTING IS TO BE HIGH EFFICACY. 2. THE FOLLOWING LIGHTING IS HIGH EFFICACY: PIN BASED LINEAR FLUORESCENT, PIN BASED COMPACT FLUORESCENT, PULSE-START METAL HALIDE, HIGH PRESSURE SODIUM, GU-24 (OTHER THAN LED'S), INSEPARABLE SOLID STATE LUMINAIRES (SSL'S) INSTALLED OUTDOORS OR
- INSEPARABLE SSL LUMINAIRES WITH COLORED LIGHT SOURCES FOR DECORATIVE LIGHTING PURPOSES. (2022 CEnC TABLE 150.0-A) THE FOLLOWING LAMPS AND LIGHT SOURCES ARE HIGH EFFICACY IF THEY ARE JOINT APPENDIX JA8-CERTIFIED. JA-8 CERTIFIED LAMPS AND LIGHT SOURCES ARE MARKED AS "JA8-2016" OR "JA8-2016-E". THESE FIXTURES INCLUDE: LED LUMINAIRES WITH INTEGRAL SOURCES THAT ARE CERRTIFIED TO THE ENERGY COMMISION, SCREW-BASED LED LAMPS (A-LAMPS, PAR LAMPS, ETC.), PIN BASED LED LAMPS (MR-16, AR-111, ETC.), GU-24 BASED LED LIGHT SOURCES AND OTHER LUMINAIRES. (2022 CEnC TABLE 150.0-A) LISTING OF CA CERTIFIED FIXTURES IS LOCATED ON THE CALIFORNIA ENERGY COMMISSION WEBSITE AT:
- HTTP://APPLIANCES.ENERGY.CA.GOV/ADVANCEDSEARCH/ASPX RECESSED LUMINAIRES INSTALLED IN AREAS TO RECEIVE INSULATION SHALL BE "IC" LUMINAIRES AND ARE CERTIFIED AND LABELED AS AIRTIGHT TO THE STANDARDS PRESCRIBED BY THE RESIDENTIAL ENERGY CODE
- 5. ADDITIONAL REQUIREMENTS FOR ANY RECESSED DOWNLIGHTS IN CEILINGS ARE AS FOLLOWS. THEY a. SHALL NOT HAVE SCREW BASED SOCKETS,
- b. SHALL CONTAIN JA8-CERTIFIED LIGHT SOURCES AND
- c. SHALL MEET PERFORMANCE REQUIREMENTS OF 2022 CEnC SECTION 150.0(K)1C THE NUMBER OF ELECTRICAL BOXES LOCATED MORE THAN 5 FEET ABOVE FINISHED FLOOR THAT DO NOT CONTAIN ALUMINAIRE OR OTHER DEVICE SHALL NOT EXCEED THE NUMBER OF BEDROOMS. THESE BOXES MUST BE
- SERVED BY A DIMMER. VACANCY SENSOR OR FAN SPEED CONTROL. (2022 CEnC SECTION 150(K)1(B)) UNDERCABINET LIGHTING MUST BE SWITCHED SEPARATE FROM ALL OTHER
- LIGHTING. 8. ALL LIGHTING MUST HAVE READILY ACCESSIBLE MANUAL CONTROLS
- 9. EXHAUST FANS MUST BE SWITCHED SEPARATE FROM LIGHTING OR UTILIZE A DEVICE WHERE LIGTING CAN BE TURNED OFF WHILE THE FAN IS RUNNING.
- 10. FOR ALL SPACE TYPES EXCEPT HALLWAYS AND CLOSETS THAT ARE 70 SF OR SMALLER, VANCANY SENSORS OR DIMMERS ARE REQUIRED WHEN USING A SOURCE REGULATED BY JA8.
- 11. IN KITCHENS, IF THE LUMINAIRE IS AN ENCLOSED OR RECESSED LUMINAIRE. YOU MUST USE A DIMMER OR VACANY SENSOR. 12. AT LEAST ONE LUMINAIRE IN THE BATHROOM, GARAGE, LAUNDRY ROOM
- AND UTILITY ROOM MUST BE CONTROLLED BY A VACANY SENSOR.
- 13. THE BUILDER MUST PROVIDE NEW HOMEWONERS WITH A LUMINAIRE SCHEDULE THAT INCLUDES A LIST OF INSTALLED LAMPS AND LUMINARIES. 14. ALL JOINTS, PENETRATIONS AND OTHER OPENINGS IN THE BUILDING ENVELOPE THAT ARE POTENTIAL SOURCES OF AIR LEAKAGE SHALL BE
- CAULKED, GASKETED, WEATHER-STRIPPED OR OTHERWISE SEALED TO LIMIT INFILTRATION AND EXFILTRATION (2022 CEnC 110.7). 15. ATTIC ACCESS DOORS SHALL HAVE PERMANENTLY ATTACHED INSULATION
- USING ADHESIVE OR MECHANICAL FASTENERS. THE ATTIC ACCESS SHALL BE GASKETED TO PREVENT AIR LEAKAGE (2022 CEnC 150.0(a)2) 16. ALL INSTALLED LUMINAIRES SHALL BE HIGH EFFICACY IN ACCORDANCE
- WITH CEnC TABLE 150.0-A. (2022 CEnC 150(k)1A).
- 17. THE NUMBER OF ELECTRICAL BOXES THAT ARE MORE THAN 5 FEET ABOVE THE FINISHED FLOOR AND DO NOT CONTAIN A LUMINAIRE OR OTHER DEVICE SHALL BE NO GREATER THAN THE NUMBER OF BEDROOMS. THESE ELECTRICAL BOXES MUST BE SERVED BY A DIMMER, VACANCY SENSOR CONTROL, OR FAN SPEED CONTROL. (2022 CEnC 150(k)1B).

## SOLAR READY NOTES

SOLAR READY REQUIREMENTS PER CeNC 110.10(b) THROUGH 110.10(e) SOLAR ZONE:

- MINIMUM AREA. THE SOLAR ZONE SHALL HAVE A MINIMUM TOTAL AREA AS DESCRIBED BELOW. THE SOLAR ZONE SHALL COMPLY WITH ACCESS, PATHWAY, SMOKE VENTILATION, AND SPACING REQUIREMENTS AS SPECIFIED IN TITLE 24, PART 9 OR OTHER PARTS OF TITLE 24 OR IN ANY
- REQUIREMENTS ADOPTED BY A LOCAL JURISDICTION. THE SOLAR ZONE TOTAL AREA SHALL BE COMPRISED OF AREAS THAT HAVE NO DIMENSION LESS THAN FIVE FEET AND ARE NO LESS THAN 80 SQUARE FEET EACH FOR BUILDINGS WITH ROOF AREAS LESS THAN OR EQUAL TO 10,000 SQUARE FEET OR NO LESS THAN 160 SQUARE FEET EACH FOR BUILDINGS WITH ROOF AREAS GREATER THAN 10,000 SQUARE FEET. A. SINGLE FAMILY RESIDENCES. THE SOLAR ZONE SHALL BE LOCATED ON THE ROOF OR OVERHANG OF THE BUILDING AND HAVE A TOTAL AREA NO LESS THAN 250 SQUARE FEET.

**EXCEPTION 1** TO SECTION 110.10(B)1A: SINGLE FAMILY RESIDENCES WITH A PERMANENTLY INSTALLED DOMESTIC SOLAR WATER-HEATING SYSTEM MEETING THE INSTALLATION CRITERIA SPECIFIED IN THE REFERENCE RESIDENTIAL APPENDIX RA4 AND WITH A MINIMUM SOLAR SAVINGS FRACTION OF 0.50.

**EXCEPTION 5** TO SECTION 110.10(B)1A: SINGLE FAMILY RESIDENCES HAVING A SOLAR ZONE TOTAL AREA NO LESS THAN 150 SQUARE FEET AND WHERE ALL THERMOSTATS ARE DEMAND RESPONSIVE CONTROLS AND COMPLY WITH SECTION 110.12(A), AND ARE CAPABLE OF RECEIVING AND RESPONDING TO DEMAND RESPONSE SIGNALS PRIOR TO GRANTING OF AN OCCUPANCY PERMIT BY THE ENFORCING AGENCY

**EXCEPTION 6** TO SECTION 110.10(B)1A: SINGLE-FAMILY RESIDENCES MEETING THE FOLLOWING CONDITIONS: A. ALL THERMOSTATS ARE DEMAND RESPONSIVE CONTROLS THAT

- COMPLY WITH SECTION 110.12(A). AND ARE CAPABLE OF RECEIVING AND RESPONDING TO DEMAND RESPONSE SIGNALS PRIOR TO GRANTING OF AN OCCUPANCY PERMIT BY THE ENFORCING AGENCY. B. COMPLY WITH ONE OF THE FOLLOWING MEASURES:
- a. INSTALL A DISHWASHER THAT MEETS OR EXCEEDS THE ENERGY STAR® PROGRAM REQUIREMENTS WITH A REFRIGERATOR THAT MEETS OR EXCEEDS THE ENERGY STAR PROGRAM REQUIREMENTS, A WHOLE HOUSE FAN DRIVEN BY AN ELECTRONICALLY COMMUTATED MOTOR, OR AN SAE J1772 LEVEL 2 ELECTRIC VEHICLE SUPPLY EQUIPMENT (EVSE OR EV
- CHARGER) WITH A MINIMUM OF 40 AMPERES; OR b. INSTALL A HOME AUTOMATION SYSTEM CAPABLE OF, AT A MINIMUM, CONTROLLING THE APPLIANCES AND LIGHTING OF THE DWELLING AND RESPONDING TO DEMAND RESPONSE SIGNALS;
- c. INSTALL ALTERNATIVE PLUMBING PIPING TO PERMIT THE DISCHARGE FROM THE CLOTHES WASHER AND ALL SHOWERS AND BATHTUBS TO BE USED FOR AN IRRIGATION SYSTEM IN COMPLIANCE WITH THE CALIFORNIA PLUMBING CODE AND ANY APPLICABLE LOCAL ORDINANCES; OR d. INSTALL A RAINWATER CATCHMENT SYSTEM DESIGNED TO
- COMPLY WITH THE CALIFORNIA PLUMBING CODE AND ANY APPLICABLE LOCAL ORDINANCES, AND THAT USES RAINWATER FLOWING FROM AT LEAST 65 PERCENT OF THE AVAILABLE ROOF AREA.

# COUNTY **់ SAN LUIS** OBISPO

THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

## WILDLAND-URBAN INTERFACE

- ROOF COVERING SHALL COMPLY WITH 2022 CRC R337.5.2. UNDERLAYMENT SHALL BE ONE LAYER OF OF MINUMIM 72 POUND MINERAL-SURFACED NONPERFORATED CAP SHEET COMPLYING WITH ASTM D3909 INSTALLED OVER THE COMBUSTIBLE DECKING, ALTERNATELY, A CLASS A FIRE RATED ROOF UNDERLAYMENT, TESTED IN ACCORDANCE WITH ASTM E108, SHALL BE PERMITTED TO BE USED.
- ROOF VALLEYS SHALL COMPLY WITH 2022 CRC R337.5.3. VALLEY FLASHING SHALL BE NOT LESS THAN 26 GAGE GALVANIZED SHEET CORROSIVE RESISTANT METAL INSTALLED OVER NOT LESS THAN ONE LAYER OF MINUMIM 72 POUND MINERAL-SURFACED NONPERFORATED CAP SHEET COMPLYING WITH ASTM D3909, AT LEAST 36 INCHES WIDE RUNNING THE FULL LENGTH OF THE VALLEY.
- ROOF GUTTERS SHALL COMPLY WITH 2022 CRC R337.5.4. ROOF GUTTERS SHALL BE PROVIDE WITH THE MEANS TO PREVENT THE ACCUMULATION OF LEAVES AND DEBRIS IN THE GUTTER
- 4. VENTILATION OPENINGS SHALL COMPLY WITH 2022 CRC R337.6 -VENTILATION OPENINGS FOR ENCLOSED ATTICS. ENCLOSED EAVE SOFFIT SPACES, ENCLOSED RAFTER SPACES FORMED WHERE CEILINGS ARE APPLIED DIRECTLY TO THE UNDERSIDE OF ROOF RAFTERS, AND UNDERFLOOR VENTILATION OPENINGS SHALL BE FULLY COVERED WITH METAL WIRE MESH, VENTS, OTHER MATEIALS, OR OTHER DEVICES. REFER
- TO SECTIONS R337.6.1 THROUGH R337.6.3 FOR ADDITIONAL INFORMATION. EXTERIOR COVERINGS SHALL COMPLY WITH 2022CRC R337.7 EXTERIOR WALL COVERINGS OR WALL ASSEMBLIES SHALL COMPLY WITH ONE OF THE FOLLOWING REQUIREMENTS: BE OF NONCOMBUSTIBLE MATERIAL, IGNITION-RESISTANT MATERIAL, HEAVY TIMBER EXTERIOR WALL ASSEMBLY, LOG WALL CONSTRUCTION ASSEMBLY, OR WALL ASSEMBLIES THAT MEET THE PERFORMANCE CRITERIA IN ACCORDANCE WITH THE TEST PROCEDURES FOR A 10-MINUTE DIRECT FLAME CONTACT EXPOSURE TEST SET FORTH IN SFM STANDARD 12-7A-1. REFER TO SECTIONS R337.7.1 THROUGH R337.7.9 FOR ADDITIONAL INFORMATION.


FIRE-RESISTANT CONSTRUCTION			
SELE	CT THE APPROPRIATE BOX BELOW (ONLY 1): NOTE: EXTERIOR WALLS SHALL HAVE A MIN DISTANCE OF 4'-0" FROM PROPERTY LINE. A DEEP. NON-SPRINKLERED		
	FIRE SEPARATION DISTANCE: ≥5'-0" (EXTERIOR WALLS, PROJECTIONS, OPENINGS, AND PENETRATIONS)	NO FIRE-RESISTANCE RATING REQUIRED	
	FIRE SEPARATION DISTANCE: 4'-0" - 5'-0" (EXTERIOR WALLS, OPENINGS, AND PENETRATIONS) PROJECTION SEPARATION DIST.: ≥3'-0"		
	OPENINGS, AND PENETRATIONS	NO FIRE-RESISTANCE RATING REQUIRED	
	EXTERIOR WALLS AND PROJECTIONS	1-HR FIRE-RESISTANCE	
	<u>SPRINKLERED</u>		
	FIRE SEPARATION DISTANCE: ≥4'-0" (EXTERIOR WALLS, OPENINGS, AND PENETRATIONS)	NO FIRE-RESISTANCE RATING REQUIRED	

COUNTY OF SAN LUIS OBISPO ACCESSORY DWELLING UNIT SAN LUIS OBISPO, CA GENERAL NOTES GENERAL NOTES

## **CLIMATE ZONE**

2022 Building Energy Efficiency Standards

Page 97




## ABBREVIATIONS


A/C	AIR CONDITIONING	EXT	EXTERIOR	MAX	MAXIMUM
ABV	ABOVE	FACP	FIRE ALARM CONTROL PANEL	MDF	MEDIUM DENSITY
ACOUS	ACOUSTICAL	FAU		MECH	MECHANICAL
ACT	ACOUSTICAL CEILING TILE	FAWP	FLUID APPLIED WATERPROOFING	MEMB	MEMBRANE
ADA	AMERICANS WITH DISABILITIES ACT	FD	FLOOR DRAIN	MEP	MECHANICAL, ELE
AFCI		FDC	FIRE DEPARTMENT CONNECTION	MFR	MANUFACTURER
AFF	ABOVE FINISH FLOOR	FE		MIN	
AL		FEC		MISC	MISCELLANEOUS
ALT		FF		MO	MASONRY OPENIN
ARCH	ARCHITECT(URAL)	FG FH		MTD	MOUNTED
BD BDRM	BOARD BEDROOM	FHC	FIRE HYDRANT FIRE HOSE CABINET	MTL N	METAL NORTH
BET	BETWEEN	FIN	FINISH	NIC	NOT IN CONTRACT
BIT	BITUMINOUS	FIN	FIXTURE	NO	NUMBER
BLDG	BUILDNG	FLR	FLOOR	NOM	NOMINAL
BLKG	BLOCKING	FLUOR	FLOURESCENT	NTS	NOT TO SCALE
BLW	BELOW	FND	FOUNDATION	O.P.	OVERFLOW PIPE
BM	BEAM	FO	FACE OF	OC OC	ON CENTER
BOT	BOTTOM	FOC	FACE OF CONCRETE	OD	OVERFLOW DRAIN
BUR	BUILT UP ROOF	FOF	FACE OF FINISH	OFF	OFFICE
CB	CATCH BASIN	FOIC	FURNISHED BY OWNER INSTALLED BY	OH	OPPOSITE HAND
CBC	CALIFORNIA BUILDING CODE		CONTRACTOR	OPG	OPENING
CEM	CEMENT	FOM	FACE OF MASONRY	OPP	OPPOSITE
CFM	CUBIC FEET PER MINUTE	FOS	FACE OF STUD	(P)	PROPOSED
CIP	CAST IN PLACE	FRP	FIBERGLASS REINFORCED PANELS	PÉRM	PERIMETER
CJ	CONTROL JOINT	FT	FOOT OR FEET	PERP	PERPENDICULAR
CL	CENTER LINE	FTG	FOOTING	PG	PAINT GRADE
CLG	CEILING	GA	GAUGE, GAGE	PL	PLATE, PROPERTY
CLO	CLOSET	GALV	GALVANIZED	PLAM	PLASTIC LAMINAT
CLR	CLEAR	GB	GRAB BAR	PLBG	PLUMBING
CMU	CONCRETE MASONRY UNIT	GC	GENERAL CONTRACTOR	PLYWD	PLYWOOD
CO	CLEAN OUT	GFCI	GROUND FAULT CIRCUIT INTERRUPTER	PNL	PANEL
COL	COLUMN	GWB	GYPSUM BOARD	PP	POWER POLE
CONC	CONCRETE	GYP	GYPSUM	PR	PAIR
CONST	CONSTRUCTION	HB	HOSE BIBB	PRTN	PARTITION
CONT	CONTINUOUS	HC	HOLLOW CORE	PSF	POUNDS PER SQU
CONTR	CONTRACTOR	HDWD	HARDWOOD	PSI	POUNDS PER SQU
CPT	CARPET	HDWR	HARDWARE	PSL	PARALLEL STRAN
CT	CERAMIC TILE	HGT HM	HEIGHT HOLLOW METAL	PT	PRESSURE TREAT
CTR	CENTER	HORIZ	HORIZONTAL	PTD	PAINTED
DBL	DOUBLE	HVAC	HEATING, VENTILATION, A/C	PV	PHOTO VOLTAIC
DF		ID	INSIDE DIAMETER	PVC	POLYVINYL CHLOP
DIA		lic	IMPACT INSULATION CLASS	PVMT	PAVEMENT QUANTITY
DIM DN	DIMENSION DOWN	IN	INCH	QTY R	RADIUS, RISER
DR	DOOR	INCAND	INCANDESCENT	RB	RUBBER BASE
DS	DOWN SPOUT	INSUL	INSULATION, INSULATED	RCP	REFLECTED CEILII
DTL	DETAIL	INT	INTERIOR	RD	ROOF DRAIN
DW	DISHWASHER	JC	JANITORS CLOSET	REF	REFRIGERATOR
DWG	DRAWING	JT	JOINT	REINF	REINFORCED
(E)	EXISTING	LAM	LAMINATE	REQD	REQUIRED
E	EAST	LAV	LAVATORY	RH	RIGHT HAND
EA	EACH	LBS	POUNDS	RM	ROOM
EJ	EXPANSION JOINT	LEED	LEADERSHIP IN ENERGY AND	RO	ROUGH OPENING
EL,	ELEVATION		ENVIRONMENTAL DESIGN	RTU	ROOF TOP UNIT (M
ELEV		LF		S	SOUTH
ELEC	ELECTRIC	LIN		SAFB	SOUND ATTENUAT
ENCL	ENCLOSURE	LINO		SAWP	SELF ADHEREING
EQ	EQUAL	LT(G)		SC	SCUPPER/SOLID C
EQUIP	EQUIPMENT			SCHED	SCHEDULE
EXH	EXHAUST	LVT		SEAL	SEALANT
EXP	EXPANSION	LW	LIGHTWEIGHT	SECT	SECTION

## FIRE HAZARD SEVERITY ZONES

DISCLAIMER: MAP IS FOR GENERAL REFERENCE ONLY. TO ACQUIRE ACCURATE INFORMATION FOR FIRE HAZARD SEVERITY IN SITE SPECIFIC LOCATION, REFER TO THE CALIFORNIA DEPARTMENT OF FORESTRY AND FIRE PROTECT



MTL N NIC NO NOM NTS O.P. OC OD OFF OH OPG OPP (P) PERM PERP PG	METAL NORTH NOT IN CONTRACT NUMBER NOMINAL NOT TO SCALE OVERFLOW PIPE ON CENTER OVERFLOW DRAIN OFFICE OPPOSITE HAND OPENING OPPOSITE PROPOSED PERIMETER PERPENDICULAR PAINT GRADE	STD STL STOR STRUCT SUSP SV SYM T T&G TEL TEMP TER THK THR TJI TO TOS	STANDARD STEEL STORAGE STRUCTURAL SUPSPENDED SHEET VINYL SYMMMETRICAL TREAD TONGUE & GROOVE TELEPHONE TEMPERED TERRAZZO THICK THRESHOLD TRUSS JOIST I-JOIST TOP OF TOP OF SLAB	LUIS PRC CAI NO ALT PER HAS CO CO CO IT IS DO FUR	OBISPO AS PART OF TH OGRAM AND ARE PUBLI NOT BE A CHARGE TO ALTERATIONS TO THESE ERATIONS MUST BE DOM MIT ONCE THE BUILDING BEEN ISSUED AND FINA MPLETED. IF YOU DO NG NSTRUCTION KNOWLED NTRUCT THESE PLANS W RECOMMENDED YOU THE CONSTRUCTION. TI	PROVIDE THESE PLANS. PLANS ARE ALLOWED. ALL VE UNDER A SEPARATE G PERMIT FOR THE ADU AL INSPECTION OT HAVE THE OGE AND EXPERIENCE TO 'ITHOUT FURTHER DETAILS, HIRE A CONTRACTOR TO HE CITY WILL NOT PROVIDE R DETAILS AND BUILDING	
PL PLAM PLBG PLYWD PNL PR PR PR PSF PSI PSI PSL PTD PVC PVC PVC PVC PVC PVC PVC R RCP RD REF REINF REQD RH REF REINF REQD RH RM RO RTU S SAFB SAWP	PLATE, PROPERTY LINE PLASTIC LAMINATE PLUMBING PLYWOOD PANEL POWER POLE PAIR PARTITION POUNDS PER SQUARE FOOT POUNDS PER SQUARE INCH PARALLEL STRAND LUMBER PRESSURE TREATED PAINTED PHOTO VOLTAIC POLYVINYL CHLORIDE PAVEMENT QUANTITY RADIUS, RISER RUBBER BASE REFLECTED CEILING PLAN ROOF DRAIN REFRIGERATOR REINFORCED REQUIRED RIGHT HAND ROOM ROUGH OPENING ROOF TOP UNIT (MECH) SOUND ATTENUATION FIBER BATT SELF ADHEREING WATERPROOFING	TOW TRANS TV TYP UFAS UG UNFIN UNO UV VCT VERT VIF VTR VWC W W/ W/D W/O W/O W/O W/O W/O W/O W/O W/O W/O W/O	TOP OF WALL TRANSFORMER TELEVISION TYPICAL UNIFORM FEDERAL ACCESSIBILITY STANDARDS UNDERGROUND UNFINISHED ULNESS NOTED OTHERWISE UTRAVIOLET VINYL COMPOSITION TILE VERTICAL VERIFY IN FIELD VENT TERMINATION PIPE VINYL WALL COVERING WEST WITH WASHER DRYER WITHOUT WATERCLOSET WOOD WINDOW WATER HEATER WROUGHT IRON WINDOW WATER PROOF(ING) WEATHER RESISTIVE WATER RESISTIVE BARRIER WAINSCOT WEIGHT				
SC SCHED SEAL SECT	SCUPPER/SOLID CORE SCHEDULE SEALANT SECTION		VIEW NUMBER VIEW TITLE W Name LEVEL DESIGNATION	Name 0' - 0"	INTY OF SAN LUIS OBISPO CESSORY DWELLING UNIT SAN LUIS OBISPO, CA	DEX, ABBREVIATIONS, & SYMBOLS	



SYMBOLS ACC 

DATE

SHEET

<u>@</u>	2022 Single-Family Residential Mandatory Re
§ 150.0(m)13:	<b>Space Conditioning System Airflow Rate and Fan Efficacy.</b> Space condition a hole for the placement of a static pressure probe, or a permanently installed be $\geq$ 350 CFM per ton of nominal cooling capacity, and an air-handling unit fan handlers and $\leq$ 0.58 watts per CFM for all others. Small duct high velocity syste cooling capacity, and an air-handling unit fan efficacy $\leq$ 0.62 watts per CFM. Find Reference Residential Appendix RA3.3. *
Ventilation and In	door Air Quality: Requirements for Ventilation and Indoor Air Quality. All dwelling units must
§ 150.0(o)1: § 150.0(o)1B:	Ventilation and Acceptable Indoor Air Quality in Residential Buildings subject to <b>Central Fan Integrated (CFI) Ventilation Systems.</b> Continuous operation of C dwelling unit ventilation airflow required per §150.0(o)1C. A motorized damper( prevents all airflow through the space conditioning duct system when the damp ventilation systems must have controls that track outdoor air ventilation run tim
	compliance with §150.0(o)1C. Whole-Dwelling Unit Mechanical Ventilation for Single-Family Detached a
§ 150.0(o)1C: § 150.0(o)1G:	and attached dwelling units not sharing ceilings or floors with other dwelling units spaces must have mechanical ventilation airflow specified in § 150.0(o)1Ci-iii. Local Mechanical Exhaust. Kitchens and bathrooms must have local mechanical
3 100.0(0)10.	controlled exhaust system meeting requirements of §150.0(o)1Giii,enclosed kit continuous exhaust meeting §150.0(o)1Giii-iv. Airflow must be measured by the §150.0(o)1Gvi. *
§ 150.0(o)1H&I:	Airflow Measurement and Sound Ratings of Whole-Dwelling Unit Ventilation be measured by using a flow hood, flow grid, or other airflow measuring device Residential Appendix RA3.7. Whole-Dwelling unit ventilation systems must be minimum airflow rate required by §150.0(o)1C.
§ 150.0(o)2:	<b>Field Verification and Diagnostic Testing.</b> Whole-Dwelling Unit ventilation air and HRV and ERV fan efficacy must be verified in accordance with Reference must be verified per Reference Residential Appendix RA3.7.4.3 to confirm if it is rates and sound requirements per §150.0(o)1G
	tems and Equipment: Certification by Manufacturers. Any pool or spa heating system or equipmen with the Appliance Efficiency Regulations and listing in MAEDAS: on on off aw
§ 110.4(a):	with the Appliance Efficiency Regulations and listing in MAEDbS; an on-off swi the heater without adjusting the thermostat setting; a permanent weatherproof use electric resistance heating. *
§ 110.4(b)1:	<b>Piping.</b> Any pool or spa heating system or equipment must be installed with at dedicated suction and return lines, or built-in or built-up connections to allow for
§ 110.4(b)2: § 110.4(b)3:	Covers. Outdoor pools or spas that have a heat pump or gas heater must have Directional Inlets and Time Switches for Pools. Pools must have directional switch that will allow all pumps to be set or programmed to run only during off-p
§ 110.5:	Pilot Light. Natural gas pool and spa heaters must not have a continuously bur Pool Systems and Equipment Installation. Residential pool systems or equip
§ 150.0(p): Lighting:	sizing, flow rate, piping, filters, and valves.*
§ 110.9:	<b>Lighting Controls and Components.</b> All lighting control devices and systems, requirements of § 110.9. *
§ 150.0(k)1A:	Luminaire Efficacy. All installed luminaires must meet the requirements in Tab range hoods, bath vanity mirrors, and garage door openers; navigation lighting less the second sec
§ 150.0(k)1B:	closets with an efficacy of at least 45 lumens per watt. Screw based luminaires. Screw based luminaires must contain lamps that cor
§ 150.0(k)1C:	Recessed Downlight Luminaires in Ceilings. Luminaires recessed into ceilin and must be sealed with a gasket or caulk. California Electrical Code § 410.116 Light Sources in Enclosed or Recessed Luminaires. Lamps and other sepa
§ 150.0(k)1D: § 150.0(k)1E:	elevated temperature requirements, including marking requirements, must not Blank Electrical Boxes. The number of electrical boxes that are more than five
	luminaire or other device shall be no more than the number of bedrooms. Thes control, low voltage wiring, or fan speed control. Lighting Integral to Exhaust Fans. Lighting integral to exhaust fans (except w
§ 150.0(k)1F: 5/6/22	hoods) must meet the applicable requirements of § 150.0(k).

Requirements Summary	

ditioning systems that use ducts to supply cooling must have led static pressure probe in the supply plenum. Airflow must fan efficacy $\leq 0.45$ watts per CFM for gas furnace air systems must provide an airflow $\geq 250$ CFM per ton of nominal <i>I</i> . Field verification testing is required in accordance with
nust meet the requirements of ASHRAE Standard 62.2, act to the amendments specified in § 150.0(o)1. *
of CFI air handlers is not allowed to provide the whole- per(s) must be installed on the ventilation duct(s) that amper(s) is closed andcontrolled per §150.0(o)1Biii&iv. CFI time, and either open or close the motorized damper(s) for
ed and townhouses . Single-family detached dwelling units, units, occupiable spaces, public garages, or commercial -iii.
hanical exhaust; nonenclosed kitchens must have demand-
d kitchens and bathrooms can use demand-controlled or y the installer per §150.0(o)1Gv, and rated for sound per
<b>ilation Systems.</b> The airflow required per § 150.0(o)1C must vice at the fan's inlet or outlet terminals/grilles per Reference be rated for sound per ASHRAE 62.2 §7.2 at no less than the
n airflow, vented range hood airflow and sound rating, nce Residential Appendix RA3.7. Vented range hoods if it is rated by HVI or AHAM to comply with the airflow
and a state of the later of the following compliance
nent must be certified to have all of the following: compliance switch mounted outside of the heater that allows shutting off oof plate or card with operating instructions; and must not
n at least 36 inches of pipe between the filter and the heater, or v for future solar heating.
nave a cover.
onal inlets that adequately mix the pool water, and a time off-peak electric demand periods.
/ burning pilot light.
equipment must meet the specified requirements for pump
the second burger in a second proof the explicitly
ems, ballasts, and luminaires must meet the applicable
Table 150.0-A, except lighting integral to exhaust fans, kitchen ess than 5 watts; and lighting internal to drawers, cabinets, and linen
t comply with Reference Joint Appendix JA8. *

eilings must not contain screw based sockets, must be airtight, 16 must also be met. eparable light sources that are not compliant with the JA8 not be installed in enclosed or recessed luminaires. five feet above the finished floor and do not contain a nese boxes must be served by a dimmer, vacancy sensor

t when installed by the manufacturer in kitchen exhaust

R

<u>@</u>	2022 Single-Family Residential Mandatory Requirements Summary	
§ 110.5:	Pilot Lights. Continuously burning pilot lights are prohibited for natural gas: fan-type central furnaces; household cooking appliances (except appliances without an electrical supply voltage connection with pilot lights that consume less than 150 Btu per hour ); and pool and spa heaters. *	<u>NOTE:</u> Single used. Review (04/2022)
	Building Cooling and Heating Loads. Heating and/or cooling loads are calculated in accordance with the ASHRAE Handbook,	Building Env
§ 150.0(h)1:	Equipment Volume, Applications Volume, and Fundamentals Volume; the SMACNA Residential Comfort System Installation Standards Manual; or the ACCA Manual J using design conditions specified in § 150.0(h)2.	§ 110.6(a)1:
§ 150.0(h)3A:	Clearances. Air conditioner and heat pump outdoor condensing units must have a clearance of at least five feet from the outlet of any dryer.	§ 110.6(a)5:
§ 150.0(h)3B:	Liquid Line Drier. Air conditioners and heat pump systems must be equipped with liquid line filter driers if required, as specified by the manufacturer's instructions.	§ 110.6(b):
§ 150.0(j)1:	Water Piping, Solar Water-heating System Piping, and Space Conditioning System Line Insulation. All domestic hot water piping must be insulated as specified in § 609.11 of the California Plumbing Code. *	§ 110.7:
	Insulation Protection. Piping insulation must be protected from damage, including that due to sunlight, moisture, equipment'	§ 110.8(a):
§ 150.0(j)2:	maintenance, and wind as required by §120.3(b). Insulation exposed to weather must be water retardant and protected from UV light (no adhesive tapes). Insulation covering chilled water piping and refrigerant suction piping located outside the conditioned space must	§ 110.8(g):
	include, or be protected by, a Class I or Class II vapor retarder. Pipe insulation buried below grade must be installed in a waterproof and non-crushable casing or sleeve.	§ 110.8(i):
§ 150.0(n)1:	Gas or Propane Water Heating Systems. Systems using gas or propane water heaters to serve individual dwelling units must designate a space at least 2.5' x 2.5' x 7' suitable for the future installation of a heat pump water heater, and meet electrical and plumbing requirements, based on the distance between this designated space and the water heater location; and a condensate drain no	§ 110.8(j):
§ 150.0(n)3:	more than 2" higher than the base of the water heater <b>Solar Water-heating Systems.</b> Solar water-heating systems and collectors must be certified and rated by the Solar Rating and Certification Corporation (SRCC), the International Association of Plumbing and Mechanical Officials, Research and Testing (IAPMO R&T), or by a listing agency that is approved by the executive director.	§ 150.0(a):
Ducts and Fans:		
§ 110.8(d)3:	<b>Ducts.</b> Insulation installed on an existing space-conditioning duct must comply with § 604.0 of the California Mechanical Code (CMC). If a contractor installs the insulation, the contractor must certify to the customer, in writing, that the insulation meets this requirement.	§ 150.0(b):
<u>3 110.0(d)</u> 3.	CMC Compliance. All air-distribution system ducts and plenums must meet CMC §§ 601.0-605.0 and ANSI/SMACNA-006-2006 HVAC Duct Construction Standards Metal and Flexible 3rd Edition. Portions of supply-air and return-air ducts and plenums must be insulated to	§ 150.0(c):
§ 150.0(m)1:	R-6.0 or higher; ducts located entirely in conditioned space as confirmed through field verification and diagnostic testing (RA3.1.4.3.8) do not require insulation. Connections of metal ducts and inner core of flexible ducts must be mechanically fastened. Openings must be sealed with mastic, tape, or other duct-closure system that meets the applicable UL requirements, or aerosol sealant that meets UL 723. The combination of mastic and either mesh or tape must be used to seal openings greater than ¼", If mastic or tape is used. Building cavities, air handler support platforms, and plenums designed or constructed with materials other than sealed sheet metal, duct board or flexible duct must not be used to convey conditioned air. Building cavities and support platforms may contain ducts; ducts installed in	§ 150.0(d): § 150.0(f): § 150.0(g)1:
	these spaces must not be compressed.*	3 100.0(g)1.
§ 150.0(m)2:	Factory-Fabricated Duct Systems. Factory-fabricated duct systems must comply with applicable requirements for duct construction, connections, and closures; joints and seams of duct systems and their components must not be sealed with cloth back rubber adhesive duct tapes unless such tape is used in combination with mastic and draw bands.	§ 150.0(g)2:
§ 150.0(m)3:	Field-Fabricated Duct Systems. Field-fabricated duct systems must comply with applicable requirements for: pressure-sensitive tapes, mastics, sealants, and other requirements specified for duct construction.	§ 150.0(q):
§ 150.0(m)7:	Backdraft Damper. Fan systems that exchange air between the conditioned space and outdoors must have backdraft or automatic dampers.	Fireplaces, D § 110.5(e)
§ 150.0(m)8:	Gravity Ventilation Dampers. Gravity ventilating systems serving conditioned space must have either automatic or readily accessible, manually operated dampers in all openings to the outside, except combustion inlet and outlet air openings and elevator shaft vents.	§ 150.0(e)1:
§ 150.0(m)9:	<b>Protection of Insulation.</b> Insulation must be protected from damage due tosunlight, moisture, equipment maintenance, and wind. Insulation exposed to weather must be suitable for outdoor service (e.g., protected by aluminum, sheet metal, painted canvas, or plastic cover). Cellular foam insulation must be protected as above or painted with a water retardant and solar radiation-resistant coating.	§ 150.0(e)2: § 150.0(e)3:
§ 150.0(m)10:	Porous Inner Core Flex Duct. Porous inner cores of flex ducts must have a non-porous layer or air barrier between the inner core and outer vapor barrier.	Space Condit
§ 150.0(m)11:	Duct System Sealing and Leakage Test. When space conditioning systems use forced air duct systems to supply conditioned air to an occupiable space, the ducts must be sealed and duct leakage tested, as confirmed through field verification and diagnostic testing, in accordance with Reference Residential Appendix RA3.1.	§ 110.0-§ 11 § 110.2(a):
§ 150.0(m)12:	Air Filtration. Space conditioning systems with ducts exceeding 10 feet and the supply side of ventilation systems must have MERV 13 or equivalent filters. Filters for space conditioning systems must have a two inch depth or can be one inch if sized per Equation 150.0-A. Clean-filter pressure drop and labeling must meet the requirements in §150.0(m)12. Filters must be accessible for regular service. Filter racks or grilles must use gaskets, sealing, or other means to close gaps around the inserted filters to and prevents air from bypassing the	§ 110.2(b):
	filter. *	§ 110.2(c):
		§ 110.3(c)3:

03	5/6/22	02	5/6/22
		2022 Single-Family Residential Mandatory Requirements Summary	
	§ 150.0(s)	Energy Storage System (ESS) Ready. All single-family residences must meet all of the following: Either ESS-ready interconnection equipment with backed up capacity of 60 amps or more and four or more ESS supplied branch circuits, or a dedicated raceway from the	§ 150.0(k)1G:
		main service to a subpanel that supplies the branch circuits in § 150.0(s); at least four branch circuits must be identified and have their source collocated at a single panelboard suitable to be supplied by the ESS, with one circuit supplying the refrigerator, one lighting circuit	§ 150.0(k)1H:
		near the primary exit, and one circuit supplying a sleeping room receptacle outlet; main panelboard must have a minimum busbar rating of 225 amps; sufficient space must be reserved to allow future installation of a system isolation equipment/transfer switch within 3' of the mair panelboard, with raceways installed between the panelboard and the switch location to allow the connection of backup power source.	§ 150.0(k)1I:
	§ 150.0(t)	Heat Pump Space Heater Ready. Systems using gas or propane furnaces to serve individual dwelling units must include: A dedicated unobstructed 240V branch circuit wiring installed within 3' of the furnace with circuit conductors rated at least 30 amps with the blank cover	§ 150.0(k)2A:
		identified as "240V ready;" and a reserved main electrical service panel space to allow for the installation of a double pole circuit breaker permanently marked as "For Future 240V use."	§ 150.0(k)2B:
	§ 150.0(u)	Electric Cooktop Ready. Systems using gas or propane cooktop to serve individual dwelling units must include: A dedicated unobstructed 240V branch circuit wiring installed within 3' of the cooktop with circuit conductors rated at least 50 amps with the blank cover identified as	§ 150.0(k)2A:
		"240V ready;" and a reserved main electrical service panel space to allow for the installation of a double pole circuit breaker permanently marked as "For Future 240V use."	§ 150.0(k)2B:
	§ 150.0(v)	Electric Clothes Dryer Ready. Clothes dryer locations with gas or propane plumbing to serve individual dwelling units must include: A	§ 150.0(k)2C:
	3 100.0(1)	dedicated unobstructed 240V branch circuit wiring installed within 3' of the dryer location with circuit conductors rated at least 30 amps with the blank cover identified as "240V ready;" and a reserved main electrical service panel space to allow for the installation of a double pole circuit breaker permanently marked as "For Future 240V use."	§ 150.0(k)2D:
	*Exceptions ma	ay apply.	§ 150.0(k)2E:
			§ 150.0(k)2F:
			0.450.0/12016


	§ 150.0(k)2F:
	§ 150.0(k)2K:
	§ 150.0(k)3A:
	§ 150.0(k)4:
	§ 150.0(k)5:
	Solar Readiness:
	§ 110.10(a)1:
	§110.10(b)1A:
	§ 110.10(b)2:
	§ 110.10(b)3A:
	§ 110.10(b)3B:
	§ 110.10(b)4:
	§ 110.10(c):
	§ 110.10(d):
	§ 110.10(e)1:
	§ 110.10(e)2:
'	Electric and Ene

05

§ 110.3(c)6:

#### 2022 Single-Family Residential Mandatory Requirements Summary

<u>TE:</u> Single-family residential buildings subject to the Energy Codes must comply with all applicable mandatory measures, regardless of the compliance approach d. Review the respective section for more information.



Screw based luminaires. Screw based luminaires must contain lamps that comply with Reference Joint Appendix JA8. Light Sources in Enclosed or Recessed Luminaires. Lamps and other separable light sources that are not compliant with the JA8 elevated temperature requirements, including marking requirements, must not be installed in enclosed or recessed luminaires.

Light Sources in Drawers, Cabinets, and Linen Closets. Light sources internal to drawers, cabinetry or linen closets are not required to comply with Table 150.0-A or be controlled by vacancy sensors provided that they are rated to consume no more than 5 watts of power, emit no more than 150 lumens, and are equipped with controls that automatically turn the lighting off when the drawer, cabinet or linen closet is closed.

Interior Switches and Controls. All forward phase cut dimmers used with LED light sources must comply with NEMA SSL 7A. Interior Switches and Controls. Exhaust fans must be controlled separately from lighting systems. Accessible Controls. Lighting must have readily accessible wall-mounted controls that allow the lighting to be manually turned

on and off. \* Multiple Controls. Controls must not bypass a dimmer, occupant sensor, or vacancy sensor function if the dimmer or sensor is installed

to comply with § 150.0(k). Mandatory Requirements. Lighting controls must comply with the applicable requirements of § 110.9.

Energy Management Control Systems. An energy management control system (EMCS) may be used to comply with dimming,

applicable requirements for nonresidential garages in §§ 110.9, 130.0, 130.1, 130.4, 140.6, and 141.0.

2D: occupancy, and control requirements if it provides the functionality of the specified control per § 110.9 and the physical controls specified in § 150.0(k)2A.

Automatic Shutoff Controls. In bathrooms, garages, laundry rooms, utility rooms and walk-in closets, at least one installed luminaire must be controlled by an occupancy or vacancy sensor providing automatic-off functionality. Lighting inside drawers and cabinets with opaque fronts or doors must have controls that turn the light off when the drawer or door is closed. Dimmers. Lighting in habitable spaces (e.g., living rooms, dining rooms, kitchens, and bedrooms) must have readily accessible wallmounted dimming controls that allow the lighting to be manually adjusted up and down. Forward phase cut dimmers controlling LED light

sources in these spaces must comply with NEMA SSL 7A. 150.0(k)2K: Independent controls. Integrated lighting of exhaust fans shall be controlled independently from the fans. Lighting under cabinets or shelves, lighting in display cabinets, and switched outlets must be controlled separately from ceiling-installed lighting.

Residential Outdoor Lighting. For single-family residential buildings, outdoor lighting permanently mounted to a residential building, or to § 150.0(k)3A: other buildings on the same lot, must have a manual on/off switch and either a photocell and motion sensor or automatic time switch control) or an astronomical time clock. An energy management control system that provides the specified control functionality and meets all applicable requirements may be used to meet these requirements. Internally illuminated address signs. Internally illuminated address signs must either comply with § 140.8 or consume no more than 5

watts of power Residential Garages for Eight or More Vehicles. Lighting for residential parking garages for eight or more vehicles must comply with the

Single-family Residences. Single-family residences located in subdivisions with 10 or more single-family residences and where the § 110.10(a)1: application for a tentative subdivision map for the residences has been deemed complete and approved by the enforcement agency, which do not have a photovoltaic system installed, must comply with the requirements of § 110.10(b)-(e). Minimum Solar Zone Area. The solar zone must have a minimum total area as described below. The solar zone must comply with access, pathway, smoke ventilation, and spacing requirements as specified in Title 24, Part 9 or other parts of Title 24 or in any requirements adopted by a local jurisdiction. The solar zone total area must be comprised of areas that have no dimension less than 5 feet and are no less than 80 square feet each for buildings with roof areas less than or equal to 10,000 square feet or no less than 160 §110.10(b)1A: square feet each for buildings with roof areas greater than 10,000 square feet. For single-family residences, the solar zone must be located on the roof or overhang of the building and have a total area no less than 250 square feet.

§ 110.10(b)2: **Azimuth.** All sections of the solar zone located on steep-sloped roofs must have an azimuth between 90-300° of true north. Shading. The solar zone must not contain any obstructions, including but not limited to: vents, chimneys, architectural features, and roof

§ 110.10(b)3A: mounted equipment. Shading. Any obstruction located on the roof or any other part of the building that projects above a solar zone must be located at least twice the § 110.10(b)3B: horizontal distance of the height difference between the highest point of the obstruction and the horizontal projection of the nearest point of the

solar zone, measured in the vertical plane.\* Structural Design Loads on Construction Documents. For areas of the roof designated as a solar zone, the structural design loads for roof dead load and roof live load must be clearly indicated on the construction documents.

Interconnection Pathways. The construction documents must indicate: a location reserved for inverters and metering equipment and a pathway reserved for routing of conduit from the solar zone to the point of interconnection with the electrical service; and for single-family residences and central water-heating systems, a pathway reserved for routing plumbing from the solar zone to the water-heating system. Documentation. A copy of the construction documents or a comparable document indicating the information from § 110.10(b)-(c) must be provided to the occupant.

Main Electrical Service Panel. The main electrical service panel must have a minimum busbar rating of 200 amps. Main Electrical Service Panel. The main electrical service panel must have a reserved space to allow for the installation of a double pole circuit breaker for a future solar electric installation. The reserved space must be permanently marked as "For Future Solar Electric." lectric and Energy Storage Ready:




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



DATE 09/28/2023

SHEET



## **2022 CALIFORNIA GREEN BUILDING STANDARDS CODE RESIDENTIAL MANDATORY MEASURES (SHEET 1)**

## **CHAPTER 1 - ADMINISTRATION**

#### **SECTION 101 GENERAL**

101.1 TITLE. THESE REGULATIONS SHALL BE KNOWN AS THE CALIFORNIA GREEN BUILDING STANDARDS CODE AND MAY BE CITED AS SUCH AND WILL BE REFERRED TO HEREIN AS "THIS CODE." IT IS INTENDED THAT IT SHALL ALSO BE KNOWN AS THE CALGREEN CODE. THE CALIFORNIA GREEN BUILDING

STANDARDS CODE IS PART 11 OF THIRTEEN PARTS OF THE OFFICIAL COMPILATION AND PUBLICATION OF THE ADOPTION, AMENDMENT AND REPEAL OF BUILDING REGULATIONS TO THE CALIFORNIA CODE OF REGULATIONS, TITLE 24, ALSO REFERRED TO AS THE CALIFORNIA BUILDING STANDARDS CODE.

#### 101.2 PURPOSE

THE PURPOSE OF THIS CODE IS TO IMPROVE PUBLIC HEALTH, SAFETY AND GENERAL WELFARE BY ENHANCING THE DESIGN AND CONSTRUCTION OF BUILDINGS THROUGH THE USE OF BUILDING CONCEPTS HAVING A REDUCED NEGATIVE IMPACT OR POSITIVE ENVIRONMENTAL IMPACT AND ENCOURAGING SUSTAINABLE CONSTRUCTION PRACTICES IN THE FOLLOWING CATEGORIES:

- . PLANNING AND DESIGN
- 2. ENERGY EFFICIENCY.
- 3. WATER EFFICIENCY AND CONSERVATION. 4. MATERIAL CONSERVATION AND RESOURCE EFFICIENCY. 5. ENVIRONMENTAL QUALITY.

#### 101.3 SCOPE.

THE PROVISIONS OF THIS CODE SHALL APPLY TO THE PLANNING, DESIGN, OPERATION. CONSTRUCTION. USE AND OCCUPANCY OF EVERY NEWLY CONSTRUCTED BUILDING OR STRUCTURE, UNLESS OTHERWISE INDICATED IN THIS CODE, THROUGHOUT THE STATE OF CALIFORNIA.

IT IS NOT THE INTENT THAT THIS CODE SUBSTITUTE OR BE IDENTIFIED AS MEETING THE CERTIFICATION REQUIREMENTS OF ANY GREEN BUILDING PROGRAM.

#### **SECTION 102 CONSTRUCTION DOCUMENTS AND INSTALLATION** VERIFICATION

#### **102.1 SUBMITTAL DOCUMENTS.**

CONSTRUCTION DOCUMENTS AND OTHER DATA SHALL BE SUBMITTED IN ONE OR MORE SETS WITH EACH APPLICATION FOR A PERMIT. WHERE SPECIAL CONDITIONS EXIST, THE ENFORCING AGENCY IS AUTHORIZED TO REQUIRE ADDITIONAL CONSTRUCTION DOCUMENTS TO BE PREPARED BY A LICENSED DESIGN PROFESSIONAL AND MAY BE SUBMITTED SEPARATELY.

**EXCEPTION:** THE ENFORCING AGENCY IS AUTHORIZED TO WAIVE THE SUBMISSION OF CONSTRUCTION DOCUMENTS AND OTHER DATA NOT REQUIRED TO BE PREPARED BY A LICENSED DESIGN PROFESSIONAL.

#### 102.2 INFORMATION ON CONSTRUCTION DOCUMENTS.

CONSTRUCTION DOCUMENTS SHALL BE OF SUFFICIENT CLARITY TO INDICATE THE LOCATION. NATURE AND SCOPE OF THE PROPOSED GREEN BUILDING FEATURE AND SHOW THAT IT WILL CONFORM TO THE PROVISIONS OF THIS CODE, THE CALIFORNIA BUILDING STANDARDS CODE AND OTHER RELEVANT LAWS, ORDINANCES, RULES AND REGULATIONS AS DETERMINED BY THE ENFORCING AGENCY.

#### 102.3 VERIFICATION.

DOCUMENTATION OF CONFORMANCE FOR APPLICABLE GREEN BUILDING MEASURES SHALL BE PROVIDED TO THE ENFORCING AGENCY. ALTERNATE METHODS OF DOCUMENTATION SHALL BE ACCEPTABLE WHEN THE ENFORCING AGENCY FINDS THAT THE PROPOSED ALTERNATE DOCUMENTATION IS SATISFACTORY TO DEMONSTRATE SUBSTANTIAL CONFORMANCE WITH THE INTENT OF THE PROPOSED GREEN BUILDING MEASURE.

### **CHAPTER 3 - GREEN BUILDING**

#### SECTION 301 GENERAL

#### 301.1 SCOPE.

BUILDINGS SHALL BE DESIGNED TO INCLUDE THE GREEN BUILDING MEASURES SPECIFIED AS MANDATORY IN THE APPLICATION CHECKLISTS CONTAINED IN THIS CODE. VOLUNTARY GREEN BUILDING MEASURES ARE ALSO INCLUDED IN THE APPLICATION CHECKLISTS AND MAY BE INCLUDED IN THE DESIGN AND CONSTRUCTION OF STRUCTURES COVERED BY THIS CODE, BUT ARE NOT REQUIRED UNLESS ADOPTED BY A CITY, COUNTY, OR CITY AND COUNTY AS SPECIFIED IN SECTION 101.7.

301.1.1 ADDITIONS AND ALTERATIONS. [HCD] THE MANDATORY PROVISIONS OF CHAPTER 4 SHALL BE APPLIED TO ADDITIONS OR ALTERATIONS OF EXISTING RESIDENTIAL BUILDINGS WHERE THE ADDITION OR ALTERATION INCREASES THE BUILDING'S CONDITIONED AREA, VOLUME, OR SIZE. THE REQUIREMENTS SHALL APPLY ONLY TO AND/OR WITHIN THE SPECIFIC AREA OF THE ADDITION OR ALTERATION.

THE MANDATORY PROVISIONS OF SECTION 4.106.4.2 MAY APPLY TO ADDITIONS OR ALTERATIONS OF EXISTING PARKING FACILITIES OR THE ADDITION OF NEW PARKING FACILITIES SERVING EXISTING MULTIFAMILY BUILDINGS. SEE SECTION 4.106.4.3 FOR APPLICATION.

NOTE: REPAIRS INCLUDING, BUT NOT LIMITED TO, RESURFACING, RESTRIPING, AND REPAIRING OR MAINTAINING EXISTING LIGHTING FIXTURES ARE NOT CONSIDERED ALTERATIONS FOR THE PURPOSE OF THIS SECTION.

#### 301.2 LOW-RISE AND HIGH-RISE RESIDENTIAL BUILDINGS [HCD]. THE PROVISIONS OF INDIVIDUAL SECTIONS OF CALGREEN MAY APPLY TO EITHER LOW-RISE RESIDENTIAL BUILDINGS, HIGH-RISE RESIDENTIAL

BUILDINGS, OR BOTH. INDIVIDUAL SECTIONS WILL BE DESIGNATED BY BANNERS TO INDICATE WHERE THE SECTION APPLIES SPECIFICALLY TO LOW-RISE ONLY (LR) OR HIGH-RISE ONLY (HR). WHEN THE SECTION APPLIES TO BOTH LOW-RISE AND HIGH-RISE BUILDINGS, NO BANNER WILL BE USED.

#### **SECTION 302 MIXED OCCUPANCY** BUILDINGS

302.1 MIXED OCCUPANCY BUILDINGS. IN MIXED OCCUPANCY BUILDINGS, EACH PORTION OF A BUILDING SHALL COMPLY WITH THE SPECIFIC GREEN BUILDING MEASURES APPLICABLE TO EACH SPECIFIC OCCUPANCY.

## **CHAPTER 4 - RESIDENTIAL** MANDATORY MEASURES

#### DIVISION 4.1 PLANNING AND DESIGN 4.106 SITE DEVELOPMENT

4.106.1 GENERAL.

PRESERVATION AND USE OF AVAILABLE NATURAL RESOURCES SHALL BE ACCOMPLISHED THROUGH EVALUATION AND CAREFUL PLANNING TO MINIMIZE NEGATIVE EFFECTS ON THE SITE AND ADJACENT AREAS. PRESERVATION OF SLOPES, MANAGEMENT OF STORM WATER DRAINAGE AND EROSION CONTROLS SHALL COMPLY WITH THIS SECTION.

- 4.106.2 STORM WATER DRAINAGE AND RETENTION DURING CONSTRUCTION PROJECTS WHICH DISTURB LESS THAN ONE ACRE OF SOIL AND ARE NOT PART OF A LARGER COMMON PLAN OF DEVELOPMENT WHICH IN TOTAL DISTURBS ONE ACRE OR MORE, SHALL MANAGE STORM WATER DRAINAGE DURING CONSTRUCTION. IN ORDER TO MANAGE STORM WATER DRAINAGE DURING CONSTRUCTION, ONE OR MORE OF THE FOLLOWING MEASURES SHALL BE IMPLEMENTED TO PREVENT FLOODING OF ADJACENT PROPERTY PREVENT EROSION AND RETAIN SOIL RUNOFF ON THE SITE. 1. RETENTION BASINS OF SUFFICIENT SIZE SHALL BE UTILIZED TO RETAIN
- STORM WATER ON THE SITE. 2. WHERE STORM WATER IS CONVEYED TO A PUBLIC DRAINAGE SYSTEM, COLLECTION POINT, GUTTER OR SIMILAR DISPOSAL METHOD, WATER SHALL BE FILTERED BY USE OF A BARRIER SYSTEM. WATTLE OR OTHER METHOD APPROVED BY THE ENFORCING AGENCY. 3. COMPLIANCE WITH A LAWFULLY ENACTED STORM WATER
- MANAGEMENT ORDINANCE.

#### 4.106.3 GRADING AND PAVING

CONSTRUCTION PLANS SHALL INDICATE HOW THE SITE GRADING OR DRAINAGE SYSTEM WILL MANAGE ALL SURFACE WATER FLOWS TO KEEP WATER FROM ENTERING BUILDINGS, EXAMPLES OF METHODS TO MANAGE SURFACE WATER INCLUDE, BUT ARE NOT LIMITED TO, THE FOLLOWING: 1. SWALES

- 2. WATER COLLECTION AND DISPOSAL SYSTEMS
- FRENCH DRAINS
- 4. WATER RETENTION GARDENS 5. OTHER WATER MEASURES WHICH KEEP SURFACE WATER AWAY FROM BUILDINGS AND AID IN GROUNDWATER RECHARGE. **EXCEPTIONS:** ADDITIONS AND ALTERATIONS NOT ALTERING THE DRAINAGE PATH.

#### 4.106.4 ELECTRIC VEHICLE (EV) CHARGING FOR NEW CONSTRUCTION NEW CONSTRUCTION SHALL COMPLY WITH SECTION 4.106.4.1, 4.106.4.2, OR 4.106.4.3, TO FACILITATE FUTURE INSTALLATION AND USE OF EV CHARGERS. ELECTRIC VEHICLE SUPPLY EQUIPMENT (EVSE) SHALL BE INSTALLED IN ACCORDANCE WITH THE CALIFORNIA ELECTRICAL CODE. ARTICLE 625.

#### **EXCEPTIONS:**

- 1. ON A CASE-BY-CASE BASIS, WHERE THE LOCAL ENFORCING AGENCY HAS DETERMINED EV CHARGING AND INFRASTRUCTURE ARE NOT FEASIBLE BASED UPON ONE OR MORE OF THE FOLLOWING CONDITIONS: 1.1. WHERE THERE IS NO LOCAL UTILITY POWER SUPPLY OR THE LOCAL UTILITY IS UNABLE TO SUPPLY ADEQUATE POWER. 1.2. WHERE THERE IS EVIDENCE SUITABLE TO THE LOCAL ENFORCING AGENCY SUBSTANTIATING THAT ADDITIONAL LOCAL UTILITY INFRASTRUCTURE DESIGN REQUIREMENTS, DIRECTLY RELATED TO THE IMPLEMENTATION OF SECTION 4.106.4, MAY ADVERSELY IMPACT THE CONSTRUCTION COST OF THE PROJECT.
- 2. ACCESSORY DWELLING UNITS (ADU) AND JUNIOR ACCESSORY DWELLING UNITS (JADU) WITHOUT ADDITIONAL PARKING FACILITIES.

#### 4.106.4.1 NEW ONE- AND TWO-FAMILY DWELLINGS AND TOWNHOUSES WITH ATTACHED PRIVATE GARAGES

FOR EACH DWELLING UNIT, INSTALL A LISTED RACEWAY TO ACCOMODATE A DEDICATED 208/240-VOLT BRANCH CIRCUIT. THE RACEWAY SHALL NOT BE LESS THAN TRADE SIZE 1 (NOMINAL 1-INCH INSIDE DIAMTER). THE RACEWAY SHALL ORIGINATE AT THE MAIN SERVICE OR SUBPANEL AND SHALL TERMINATE INTO A LISTED CABINET, BOX OR OTHER ENCLOSURE IN CLOSE PROXIMITY TO THE PROPOSED LOCATION OF AN EV CHARGER. RACEWAYS ARE REQUIRED TO BE CONTINUOUS AT ENCLOSED, INACCESSIBLE OR CONCEALED AREAS AND SPACES. THE SERVICE PANEL AND/OR SUBPANEL SHALL PROVIDE CAPACITY TO INSTALL A 40-AMPERE MINIMUM DEDICATED BRANCH CIRCUIT AND SPACE(S) RESERVED TO PERMIT INSTALLATION OF A BRANCH CIRCUIT OVERCURRENT PROTECTION DEVICE.

#### 4.106.4.1.1 IDENTIFICATION

THE SERVICE PANEL OR SUBPANEL CIRCUIT DIRECTORY SHALL IDENTIFY THE OVERCURRENT PROTECTIVE DEVICE SPACE(S) RESERVED FOR FUTURE EV CHARGING AS "EV CAPABLE". THE RACEWAY TERMINATION LOCATION SHALL BE PERMANENTLY AND VISIBLY MARKED AS "EV CAPABLE".

#### 4.106.4.2 NEW MULTIFAMILY DWELLINGS, HOTELS AND MOTELS AND NEW

RESIDENTIAL PARKING FACILITIES WHEN PARKING IS PROVIDED, PARKING SPACES FOR NEW MULTIFAMILY DWELLINGS, HOTELS AND MOTELS SHALL MEET THE REQUIREMENTS OF SECTIONS 4.106.4.2.1 AND 4.106.4.2.2. CALCULATIONS FOR SPACES SHALL BE ROUNDED UP TO THE NEAREST WHOLE NUMBER. A PARKING SPACE SERVED BY ELECTRIC VEHICLE SUPPLY EQUIPMENT OR DESIGNED AS A FUTURE EV CHARGING SPACE SHALL COUNT AS AT LEAST ONE STANDARD AUTOMOBILE PARKING SPACE ONLY FOR THE PURPOSE OF COMPLYING WITH ANY APPLICABLE MINIMUM PARKING SPACE REQUIREMENTS ESTABLISHED BY A LOCAL JURISDICTION. SEE VEHICLE CODE SECTION 22511.2 FOR FURTHER DETAILS.

#### 4.106.4.2.1 MULTIFAMILY DEVELOPMENT PROJECTS WITH LESS THAN 20 DWELLING UNITS; AND HOTELS AND MOTELS WITH LESS THAN 20 SLEEPING UNITS OR GUEST ROOMS

- THE NUMBER OF DWELLING UNITS, SLEEPING UNITS OR GUEST ROOMS SHALL BE BASED ON ALL BUILDINGS ON A PROJECT SITE SUBJECT TO THIS SECTION.
- EV CAPABLE. TEN (10) PERCENT OF THE TOTAL NUMBER OF PARKING SPACES ON A BUILDING SITE, PROVIDED FOR ALL TYPES OF PARKING FACILITIES, SHALL BE ELECTRIC VEHICLE CHARGING SPACES (EV SPACES) CAPABLE OF SUPPORTING FUTURE LEVEL 2 EVSE. ELECTRICAL LOAD CALCULATIONS SHALL DEMONSTRATE THAT THE ELECTRICAL PANEL SERVICE CAPACITY AND ELECTRICAL SYSTEM, INCLUDING ANY ON-SITE DISTRIBUTION TRANSFORMER(S), HAVE SUFFICIENT CAPACITY TO SIMULTANEOUSLY CHARGE ALL EVS AT ALL REQUIRED EV SPACES AT A MINIMUM OF 40 AMPERES.

#### THE SERVICE PANEL OR SUBPANEL CIRCUIT DIRECTORY SHALL IDENTIFY THE OVERCURRENT PROTECTIVE DEVICE SPACE(S) RESERVED FOR FUTURE EV CHARGING PURPOSES AS "EV CAPABLE" IN ACCORDANCE WITH THE CALIFORNIA ELECTRICAL CODE. **EXCEPTIONS:**

- 1. WHEN EV CHARGERS (LEVEL 2 EVSE) ARE INSTALLED IN A NUMBER EQUAL TO OR GREATER THAN THE REQUIRED NUMBER OF EV CAPABLE SPACES.
- 2. WHEN EV CHARGERS (LEVEL 2 EVSE) ARE INSTALLED IN A NUMBER LESS THAN THE REQUIRED NUMBER OF EV CAPABLE SPACES, THE NUMBER OF EV CAPABLE SPACES REQUIRED MAY BE REDUCED BY A NUMBER EQUAL TO THE NUMBER OF EV CHARGERS INSTALLED.
- NOTES: a. CONSTRUCTION DOCUMENTS ARE INTENDED TO DEMONSTRATE THE PROJECT'S CAPABILITY AND CAPACITY FOR FACILITATING FUTURE EV
- CHARGING. **b.** THERE IS NO REQUIREMENT FOR EV SPACES TO BE CONSTRUCTED OR AVAILABLE UNTIL RECEPTACLES FOR EV CHARGING OR EV CHARGERS ARE INSTALLED FOR USE.

2. EV READY. TWENTY-FIVE (25) PERCENT OF THE TOTAL NUMBER OF PARKING SPACES SHALL BE EQUIPPED WITH LOW POWER LEVEL 2 EV CHARGING RECEPTACLES. FOR MULTIFAMILY PARKING FACILITIES, NO MORE THAN ONE RECEPTACLE IS REQUIRED PER DWELLING UNIT WHEN MORE THAN ONE PARKING SPACE IS PROVIDED FOR USE BY A SINGLE DWELLING UNIT. **EXCEPTION:** AREAS OF PARKING FACILITIES SERVED BY PARKING LIFTS.

4.106.4.2.2 MULTIFAMILY DEVELOPMENT PROJECTS WITH 20 OR MORE DWELLING UNITS. HOTELS AND MOTELS WITH 20 OR MORE SLEEPING UNITS OR GUEST ROOMS

THE NUMBER OF DWELLING UNITS, SLEEPING UNITS OR GUEST ROOMS SHALL BE BASED ON ALL BUILDINGS ON A PROJECT SITE SUBJECT TO THIS SECTION. 1. EV CAPABLE. TEN (10) PERCENT OF THE TOTAL NUMBER OF PARKING

SPACES ON A BUILDING SITE, PROVIDED FOR ALL TYPES OF PARKING FACILITIES. SHALL BE ELECTRIC VEHICLE CHARGING SPACES (EV SPACES) CAPABLE OF SUPPORTING FUTURE LEVEL 2 EVSE. ELECTRICAL LOAD CALCULATIONS SHALL DEMONSTRATE THAT THE ELECTRICAL PANEL SERVICE CAPACITY AND ELECTRICAL SYSTEM, INCLUDING ANY ON-SITE DISTRIBUTION TRANSFORMER(S), HAVE SUFFICIENT CAPACITY TO SIMULTANEOUSLY CHARGE ALL EVS AT ALL REQUIRED EV SPACES AT A MINIMUM OF 40 AMPERES.

THE SERVICE PANEL OR SUBPANEL CIRCUIT DIRECTORY SHALL IDENTIFY THE OVERCURRENT PROTECTIVE DEVICE SPACE(S) RESERVED FOR FUTURE EV CHARGING PURPOSES AS "EV CAPABLE" IN ACCORDANCE WITH THE CALIFORNIA ELECTRICAL CODE.

EXCEPTION: WHEN EV CHARGERS (LEVEL 2 EVSE) ARE INSTALLED IN A NUMBER GREATER THAN FIVE (5) PERCENT OF PARKING SPACES REQUIRED BY SECTION 4.106.4.2.2, ITEM 3, THE NUMBER OF EV CAPABLE SPACES REQUIRED MAY BE REDUCED BY A NUMBER EQUAL TO THE NUMBER OF EV CHARGERS INSTALLED OVER THE FIVE (5) PERCENT REQUIRED.

NOTES:

CONSTRUCTION DOCUMENTS SHALL SHOW LOCATIONS OF FUTURE EV SPACES. THERE IS NO REQUIREMENT FOR EV SPACES TO BE CONSTRUCTED OR AVAILABLE UNTIL RECEPTACLES FOR EV CHARGING OR EV CHARGERS ARE INSTALLED FOR USE.

2. EV READY. TWENTY-FIVE (25) PERCENT OF THE TOTAL NUMBER OF PARKING SPACES SHALL BE EQUIPPED WITH LOW POWER LEVEL 2 EV CHARGING RECEPTACLES. FOR MULTIFAMILY PARKING FACILITIES, NO MORE THAN ONE RECEPTACLE IS REQUIRED PER DWELLING UNIT WHEN MORE THAN ONE PARKING SPACE IS PROVIDED FOR USE BY A SINGLE DWELLING UNIT.

EXCEPTION: AREAS OF PARKING FACILITIES SERVED BY PARKING LIFTS.

3. EV CHARGERS. FIVE (5) PERCENT OF THE TOTAL NUMBER OF PARKING SPACES SHALL BE EQUIPPED WITH LEVEL 2 EVSE. WHERE COMMON USE PARKING IS PROVIDED. AT LEAST ONE EV CHARGER SHALL BE LOCATED IN THE COMMON USE PARKING AREA AND SHALL BE AVAILABLE FOR USE BY ALL RESIDENTS OR GUESTS.

WHEN LOW POWER LEVEL 2 EV CHARGING RECEPTACLES OR LEVEL 2 EVSE ARE INSTALLED BEYOND THE MINIMUM REQUIRED, AN AUTOMATIC LOAD MANAGEMENT SYSTEM (ALMS) MAY BE USED TO REDUCE THE MAXIMUM REQUIRED ELECTRICAL CAPACITY TO EACH SPACE SERVED BY THE ALMS. THE ELECTRICAL SYSTEM AND ANY ON-SITE DISTRIBUTION TRANSFORMERS SHALL HAVE SUFFICIENT CAPACITY TO DELIVER AT LEAST 3.3 KW SIMULTANEOUSLY TO EACH EV CHARGING STATION (EVCS) SERVED BY THE ALMS. THE BRANCH CIRCUIT SHALL HAVE A MINIMUM CAPACITY OF 40 AMPERES, AND INSTALLED EVSE SHALL HAVE A CAPACITY OF NOT LESS THAN 30 AMPERES. ALMS SHALL NOT BE USED TO REDUCE THE MINIMUM REQUIRED ELECTRICAL CAPACITY TO THE REQUIRED EV CAPABLE SPACES.

4.106.4.2.2.1 ELECTRIC VEHICLE CHARGING STATIONS (EVCS) ELECTRIC VEHICLE CHARGING STATIONS REQUIRED BY SECTION 4.106.4.2.2, ITEM 3, SHALL COMPLY WITH SECTION 4.106.4.2.2.1.

**EXCEPTION:** ELECTRIC VEHICLE CHARGING STATIONS SERVING PUBLIC ACCOMMODATIONS, PUBLIC HOUSING, MOTELS AND HOTELS SHALL NOT BE REQUIRED TO COMPLY WITH THIS SECTION. SEE CALIFORNIA BUILDING CODE, CHAPTER 11B, FOR APPLICABLE REQUIREMENTS.

4.106.4.2.2.1.1 LOCATION EVCS SHALL COMPLY WITH AT LEAST ONE OF THE FOLLOWING OPTIONS: THE CHARGING SPACE SHALL BE LOCATED ADJACENT TO AN ACCESSIBLE PARKING SPACE MEETING THE REQUIREMENTS OF THE CALIFORNIA BUILDING CODE, CHAPTER 11A, TO ALLOW USE OF THE EV CHARGER FROM THE ACCESSIBLE PARKING SPACE.

THE CHARGING SPACE SHALL BE LOCATED ON AN ACCESSIBLE ROUTE, AS DEFINED IN THE CALIFORNIA BUILDING CODE, CHAPTER 2, TO THE BUILDING.

**EXCEPTION:** ELECTRIC VEHICLE CHARGING STATIONS DESIGNED AND CONSTRUCTED IN COMPLIANCE WITH THE CALIFORNIA BUILDING CODE. CHAPTER 11B, ARE NOT REQUIRED TO COMPLY WITH SECTION 4.106.4.2.2.1.1 AND SECTION 4.106.4.2.2.1.2, ITEM 3.

4.106.4.2.2.1.2 ELECTRIC VEHICLE CHARGING STATIONS (EVCS) DIMENSIONS THE CHARGING SPACES SHALL BE DESIGNED TO COMPLY WITH THE FOLLOWING:

- 1. THE MINIMUM LENGTH OF EACH EV SPACE SHALL BE 18 FEET. 2. THE MINIMUM WIDTH OF EACH EV SPACE SHALL BE 9 FEET. 3. ONE IN EVERY 25 CHARGING SPACES, BUT NOT LESS THAN ONE, SHALL ALSO HAVE AN 8-FOOT WIDE MINIMUM AISLE. A 5-FOOT WIDE MINIMUM AISLE SHALL BE PERMITTED PROVIDED THE MINIMUM WIDTH OF THE EV SPACE IS 12 FEET.
- a. SURFACE SLOPE FOR THIS EV SPACE AND THE AISLE SHALL NOT EXCEED 1 UNIT VERTICAL IN 48 UNITS HORIZONTAL (2.083 PERCENT SLOPE) IN ANY DIRECTION.

4.106.4.2.2.1.3 ACCESSIBLE EV SPACES

IN ADDITION TO THE REQUIREMENTS IN SECTIONS 4.106.4.2.2.1.1 AND 4.106.4.2.2.1.2, ALL EVSE, WHEN INSTALLED, SHALL COMPLY WITH THE ACCESSIBILITY PROVISIONS FOR EV CHARGERS IN THE CALIFORNIA BUILDING CODE, CHAPTER 11B. EV READY SPACES AND EVCS IN MULTIFAMILY DEVELOPMENTS SHALL COMPLY WITH CALIFORNIA BUILDING CODE, CHAPTER 11A, SECTION 1109A.

4.106.4.2.3 EV SPACE REQUIREMENTS

SINGLE EV SPACE REQUIRED. INSTALL A LISTED RACEWAY CAPABLE OF ACCOMMODATING A 208/240-VOLT DEDICATED BRANCH CIRCUIT. THE RACEWAY SHALL NOT BE LESS THAN TRADE SIZE 1 (NOMINAL 1-INCH INSIDE DIAMETER). THE RACEWAY SHALL ORIGINATE AT THE MAIN SERVICE OR SUBPANEL AND SHALL TERMINATE INTO A LISTED CABINET, BOX OR ENCLOSURE IN CLOSE PROXIMITY TO THE LOCATION OR THE PROPOSED LOCATION OF THE EV SPACE. CONSTRUCTION DOCUMENTS SHALL IDENTIFY THE RACEWAY TERMINATION POINT, RECEPTACLE OR CHARGER LOCATION, AS APPLICABLE. THE SERVICE PANEL AND/ OR SUBPANEL SHALL HAVE A 40-AMPERE MINIMUM DEDICATED BRANCH CIRCUIT, INCLUDING BRANCH CIRCUIT OVERCURRENT PROTECTIVE DEVICE INSTALLED, OR SPACE(S) RESERVED TO PERMIT INSTALLATION OF A BRANCH CIRCUIT OVERCURRENT PROTECTIVE DEVICE.

**EXCEPTION:** A RACEWAY IS NOT REQUIRED IF A MINIMUM 40-AMPERE 208/240-VOLT DEDICATED EV BRANCH CIRCUIT IS INSTALLED IN CLOSE PROXIMITY TO THE LOCATION OR THE PROPOSED LOCATION OF THE EV SPACE, AT THE TIME OF ORIGINAL CONSTRUCTION IN ACCORDANCE WITH THE CALIFORNIA ELECTRICAL CODE.

MULTIPLE EV SPACES REQUIRED. CONSTRUCTION DOCUMENTS S INDICATE THE RACEWAY TERMINATION POINT AND THE LOCATION INSTALLED OR FUTURE EV SPACES, RECEPTACLES OR EV CHARGE CONSTRUCTION DOCUMENTS SHALL ALSO PROVIDE INFORMATION AMPERAGE OF INSTALLED OR FUTURE RECEPTACLES OR EVSE, R METHOD(S), WIRING SCHEMATICS AND ELECTRICAL LOAD CALCUL PLAN DESIGN SHALL BE BASED UPON A 40-AMPERE MINIMUM BRAN CIRCUIT. REQUIRED RACEWAYS AND RELATED COMPONENTS THA PLANNED TO BE INSTALLED UNDERGROUND, ENCLOSED, INACCES IN CONCEALED AREAS AND SPACES SHALL BE INSTALLED AT THE ORIGINAL CONSTRUCTION.

**EXCEPTION:** A RACEWAY IS NOT REQUIRED IF A MINIMUM 40-AMPE 208/240-VOLT DEDICATED EV BRANCH CIRCUIT IS INSTALLED IN CLO PROXIMITY TO THE LOCATION OR THE PROPOSED LOCATION OF TH SPACE AT THE TIME OF ORIGINAL CONSTRUCTION IN ACCORDANC THE CALIFORNIA ELECTRICAL CODE.

#### 4.106.4.2.4 IDENTIFICATION

THE SERVICE PANEL OR SUBPANEL CIRCUIT DIRECTORY SHALL IDI THE OVERCURRENT PROTECTIVE DEVICE SPACE(S) RESERVED FC FUTURE EV CHARGING PURPOSES AS "EV CAPABLE" IN ACCORDAN THE CALIFORNIA ELECTRICAL CODE.

4.106.4.2.5 ELECTRIC VEHICLE READY SPACE SIGNAGE ELECTRIC VEHICLE READY SPACES SHALL BE IDENTIFIED BY SIGNA PAVEMENT MARKINGS, IN COMPLIANCE WITH CALTRANS TRAFFIC **OPERATIONS POLICY DIRECTIVE 13-01 (ZERO EMISSION VEHICLE S** PAVEMENT MARKINGS) OR ITS SUCCESSOR(S).

4.106.4.3 ELECTRIC VEHICLE CHARGING FOR ADDITIONS AND ALTERAT PARKING FACILITIES SERVING EXISTING MULTIFAMILY BUILDINGS

WHEN NEW PARKING FACILITIES ARE ADDED, OR ELECTRICAL SYS LIGHTING OF EXISTING PARKING FACILITIES ARE ADDED OR ALTER THE WORK REQUIRES A BUILDING PERMIT, TEN (10) PERCENT OF NUMBER OF PARKING SPACES ADDED OR ALTERED SHALL BE ELE VEHICLE CHARGING SPACES (EV SPACES) CAPABLE OF SUPPORT FUTURE LEVEL 2 EVSE.

NOTES:

- 1. CONSTRUCTION DOCUMENTS ARE INTENDED TO DEMONST THE PROJECT'S CAPABILITY AND CAPACITY FOR FACILITAT
- FUTURE EV CHARGING. 2. THERE IS NO REQUIREMENT FOR EV SPACES TO BE CONST

OR AVAILABLE UNTIL EV CHARGERS ARE INSTALLED FOR U

## **DIVISION 4.2 ENERGY EFFICIENCY**

4.201 GENERAL

4.201.1 SCOPE. FOR THE PURPOSES OF MANDATORY ENERGY EFFICIENCY STANDARD CODE, THE CALIFORNIA ENERGY COMMISSION WILL CONTINUE TO ADO MANDATORY STANDARDS.

#### **DIVISION 4.3 WATER EFFICIENCY A** CONSERVATION

#### 4.303 INDOOR WATER USE

4.303.1 WATER CONSERVING PLUMBING FIXTURES AND FITTINGS PLUMBING FIXTURES (WATER CLOSETS AND URINALS) AND FITTI (FAUCETS AND SHOWERHEADS) SHALL COMPLY WITH THE FOLLOW

4.303.1.1 WATER CLOSETS

THE EFFECTIVE FLUSH VOLUME OF ALL WATER CLOSETS SHAL EXCEED 1.28 GALLONS PER FLUSH. TANK-TYPE WATER CLOSE BE CERTIFIED TO THE PERFORMANCE CRITERIA OF THE U.S. EI WATERSENSE SPECIFICATION FOR TANK TYPE TOILET.

NOTE: THE EFFECTIVE FLUSH VOLUME OF DUAL FLUSH TOILET DEFINED AS THE COMPOSITE, AVERAGE FLUSH VOLUME OF TW REDUCED FLUSHES AND ONE FULL FLUSH.

4.303.1.2 URINALS

THE EFFECTIVE FLUSH VOLUME OF WALL-MOUNTED URINALS NOT EXCEED 0.125 GALLONS PER FLUSH. THE EFFECTIVE FLUS VOLUME OF ALL OTHER URINALS SHALL NOT EXCEED 0.5 GALL FLUSH

#### 4.303.1.3 SHOWERHEADS

4.303.1.3.1 SINGLE SHOWERHEAD SHOWERHEADS SHALL HAVE A MAXIMUM FLOW RATE OF N THAN 1.8 GALLONS PER MINUTE AT 80 PSI. SHOWERHEADS CERTIFIED TO THE PERFORMANCE CRITERIA OF THE U.S. E WATERSENSE SPECIFICATION FOR SHOWERHEADS.

4.303.1.3.2 MULTIPLE SHOWERHEADS SERVING ONE SHOWER WHEN A SHOWER IS SERVED BY MORE THAN ONE SHOWER THE COMBINED FLOW RATE OF ALL SHOWERHEADS AND/O SHOWER OUTLETS CONTROLLED BY A SINGLE VALVE SHAL EXCEED 1.8 GALLONS PER MINUTE AT 80 PSI. OR THE SHOW SHALL BE DESIGNED TO ALLOW ONLY ONE SHOWER OUTLE IN OPERATION AT A TIME.

**NOTE:** A HAND HELD SHOWER SHALL BE CONSIDERED A SHOWERHEAD.

#### 4.303.1.4 FAUCETS

4.303.1.4.1 RESIDENTIAL LAVATORY FAUCETS THE MAXIMUM FLOW RATE OF RESIDENTIAL LAVATORY FAU SHALL NOT EXCEED 1.2 GALLONS PER MINUTE AT 60 PSI. MINIMUM FLOW RATE OF RESIDENTIAL LAVATORY FAUCETS NOT BE LESS THAN 0.8 GALLONS PER MINUTE AT 20 PSI.

4.303.1.4.2 LAVATORY FAUCETS IN COMMON AND PUBLIC USE THE MAXIMUM FLOW RATE OF LAVATORY FAUCETS INSTAL COMMON AND PUBLIC USE AREAS (OUTSIDE OF DWELLING SLEEPING UNITS) IN RESIDENTIAL BUILDINGS SHALL NOT E 0.5 GALLONS PER MINUTE AT 60 PSI.

4.303.1.4.3 METERING FAUCETS METERING FAUCETS WHEN INSTALLED IN RESIDENTIAL BUI SHALL NOT DELIVER MORE THAN 0.2 GALLONS PER CYCLE.

4.303.1.4.4 KITCHEN FAUCETS THE MAXIMUM FLOW RATE OF KITCHEN FAUCETS SHALL NO EXCEED 1.8 GALLONS PER MINUTE AT 60 PSI. KITCHEN FAU

TEMPORARILY INCREASE THE FLOW ABOVE THE MAXIMUM BUT NOT TO EXCEED 2.2 GALLONS PER MINUTE AT 60 PSI, DEFAULT TO A MAXIMUM FLOW RATE OF 1.8 GALLONS PER AT 60 PSI.


NOTE: WHERE COMPLYING FAUCETS ARE UNAVAILABLE, AI OR OTHER MEANS MAY BE USED TO ACHIEVE REDUCTION.

4.303.2 SUBMETERS FOR MULTIFAMILY BUILDINGS AND DWELLING UN MIXED-USE RESIDENTIAL/COMMERCIAL BUILDINGS SUBMETERS SHALL BE INSTALLED TO MEASURE WATER USAGE OF INDIVIDUAL RENTAL DWELLING UNITS IN ACCORDANCE WITH THE CALIFORNIA PLUMBING CODE.


SHALL I OF ERS. N ON RACEWAY ATIONS.	4.303.2 SUBMETERS FOR MULTIFAMILY BUILDING MIXED-USE RESIDENTIAL/COMMERCIAL BUILDIN SUBMETERS SHALL BE INSTALLED TO MEASU INDIVIDUAL RENTAL DWELLING UNITS IN ACC CALIFORNIA PLUMBING CODE.	<b>GS</b> JRE WATER USAGE OF
NCH AT ARE SSIBLE OR TIME OF	<b>4.303.3 STANDARDS FOR PLUMBING FIXTURES A</b> PLUMBING FIXTURES AND FITTINGS SHALL B WITH THE CALIFORNIA PLUMBING CODE, AND STANDARDS REFERENCED IN TABLE 1701.1 ( CODE.	E INSTALLED IN ACCORDANCE D SHALL MEET THE APPLICABLE
ERE OSE 'HE EV CE WITH	NOTE: THIS TABLE COMPILES THE DATA IN SECTION CONVENIENCE FOR THE USER.	4.303.1 AND IS INCLUDED AS A
	TABLE - MAXIMUM FIXTURE WATER USE	
DENTIFY DR NCE WITH	FIXTURE TYPE SHOWER HEADS (RESIDENTIAL) LAVATORY FAUCETS	FLOW RATE 1.8 GMP @ 80 PSI MAX. 1.2 GPM @ 60 PSI
AGE OR SIGNS AND	(RESIDENTIAL) LAVATORY FAUCETS IN COMMON & PUBLIC USE AREAS KITCHEN FAUCETS	MIN. 0.8 GPM @ 20 PSI 0.5 GPM @ 60 PSI 1.8 GPM @ 60 PSI
TIONS OF	METERING FAUCETS WATER CLOSET URINALS	0.2 GAL/CYCLE 1.28 GAL/FLUSH 0.125 GAL/FLUSH
STEMS OR		
RED AND THE TOTAL CCTRIC ING	4.304 OUTDOOR WATER USE 4.304.1 OUTDOOR POTABLE WATER USE IN LANE RESIDENTIAL DEVELOPMENTS SHALL CO EFFICIENT LANDSCAPE ORDINANCE OR T DEPARTMENT OF WATER RESOURCES' M LANDSCAPE ORDINANCE (MWELO), WHIC NOTES:	MPLY WITH A LOCAL WATER THE CURRENT CALIFORNIA MODEL WATER EFFICIENT
TRATE TING	1. THE MODEL WATER EFFICIENT LAND LOCATED IN THE CALIFORNIA CODE (	
TRUCTED JSE.	CHAPTER 2.7, DIVISION 2. MWELO AND SUPPORTING DOCUMEN BUDGET CALCULATOR, ARE AVAILAB WWW.WATER.CA.GOV/	
DS IN THIS	DIVISION 4.4 MATERIAL AND RESOURCE EFFICIE 4.406 ENHANCED DURABILITY AND RE	NCY
OPT	4.406.1 RODENT PROOFING ANNULAR SPACES AROUND PIPES, ELECTRIC OPENINGS IN SOLE/BOTTOM PLATES AT EXT PROTECTED AGAINST THE PASSAGE OF ROD	ERIOR WALLS SHALL BE DENTS BY LCOSING SUCH
ND	OPENINGS WITH CEMENT MORTAR, CONCRE METHOD ACCEPTABLE TO THE ENFORCING A 4.408 CONSTRUCTION WASTE REDU RECYCLING	AGENCY.
GS	4.408.1 CONSTRUCTION WASTE MANAGEMENT	
WING: LL NOT ETS SHALL	RECYCLE AND/OR SALVAGE FOR REUSE A M NONHAZARDOUS CONSTRUCTION AND DEMO ACCORDANCE WITH EITHER SECTION 4.408.2 MORE STRINGENT LOCAL CONSTRUCTION A MANAGEMENT ORDINANCE.	OLITION WASTE IN 2, 4.408.3, OR 4.408.4, OR MEET A
PA	EXCEPTIONS: 1. EXCAVATED SOIL AND LAND-CLEARIN	
TS IS WO SHALL SH	<ol> <li>ALTERNATE WASTE REDUCTION MET WORKING WITH LOCAL AGENCIES IF FACILITIES CAPABLE OF COMPLIANCI OR ARE NOT LOCATED REASONABLY</li> <li>THE ENFORCING AGENCY MAY MAKE REQUIREMENTS OF THIS SECTION W LOCATED IN AREAS BEYOND THE HAI</li> </ol>	HODS DEVELOPED BY DIVERSION OR RECYCLE E WITH THIS ITEM DO NOT EXIST CLOSE TO THE JOBSITE. E ACCEPTIONS TO THE HEN ISOLATED JOBSITES ARE
ONS PER	DIVERSION FACILITY. 4.408.2 CONSTRUCTION WASTE MANAGEMENT P SUBMIT A CONSTRUCTION WASTE MANAGEM	IENT PLAN IN COMFORMANCE
NOT MORE S SHALL BE EPA	WITH ITEMS 1 THROUGH 5. THE CONSTRUCT SHALL BE UPDATED AS NECESSARY AND SH. CONSTRUCTION FOR EXAMINATION BY THE E 1. IDENTIFY THE CONSTRUCTION AND E TO BE DIVERTED FROM DISPOSAL BY PROJECT OR SALVAGE FOR FUTURE 2. SPECIFY IF CONSTRUCTION AND DEN WILL BE SORTED ON-SITE (SOURCE-S	ALL BE AVAILABLE DURING ENFORCING AGENCY. DEMOLITION WASTE MATERIALS ' RECYCLING, REUSE ON THE USE OR SALE. MOLITION WASTE MATERIALS
RHEAD, DR OTHER LL NOT WER .ET TO BE	<ul> <li>(SINGLE STREAM).</li> <li>3. IDENTIFY DIVERSION FACILITIES WHE DEMOLITION WASTE MATERIAL WILL</li> <li>4. IDENTIFY CONSTRUCTION METHODS AMOUNT OF CONSTRUCTION AND DE</li> <li>5. SPECIFY THAT THE AMOUNT OF CON</li> </ul>	ERE THE CONSTRUCTION AND BE TAKEN. EMPLOYED TO REDUCE THE EMOLITION WASTE GENERATED.
	WASTE MATERIAL DIVERTED SHALL E VOLUME, BUT NOT BY BOTH. 4.408.3 WASTE MANAGEMENT COMPANY. UTILIZE A WASTE MANAGEMENT COMPANY, A	BE CALCULATED BY WEIGHT OR
UCETS THE 'S SHALL	AGENCY, WHICH CAN PROVIDE VERIFIABLE D PERCENTAGE OF CONSTRUCTION AND DEMO DIVERTED FROM THE LANDFILL COMPLIES W <b>NOTE:</b> THE OWNER OR CONTRACTOR MA THE CONSTRUCTION AND DEMOLITION W DIVERTED BY A WASTE MANAGEMENT CO	OLITION WASTE MATERIAL /ITH SECTION 4.408.1. AY MAKE THE DETERMINATION IF VASTE MATERIALS WILL BE
AREAS LLED IN SS OR EXCEED	4.408.4 WASTE STREAM REDUCTION ALTERNATI PROJECTS THAT GENERATE A TOTAL COMBI CONSTRUCTION AND DEMOLITION WASTE DI WHICH DO NOT EXCEED 3.4 POUNDS PER SC AREA SHALL MEET THE MINIMUM 65 PERCEN	<b>VE [LR].</b> NED WEIGHT OF ISPOSED OF IN LANDFILLS, QUARE FOOT OF THE BUILDING IT CONSTRUCTION WASTE
IILDINGS	REDUCTION REQUIREMENT IN SECTION 4.408 4.408.4.1 WASTE STREAM REDUCTION ALTER PROJECTS THAT GENERATE A TOTAL CO CONSTRUCTION AND DEMOLITION WAST	RNATIVE. MBINED WEIGHT OF E DISPOSED OF IN LANDFILLS,
JCETS MAY 1 RATE, AND MUST 8 MINUTE	WHICH DO NOT EXCEED 2 POUNDS PER AREA, SHALL MEET THE MINIMUM 65-PER REDUCTION REQUIREMENT IN SECTION 4 4.408.5 DOCUMENTATION	CENT CONSTRUCTION WASTE 4.408.1.
ERATORS	DOCUMENTATION SHALL BE PROVIDED TO T DEMONSTRATES COMPLIANCE WITH SECTIO SECTION 4.408.3 OR SECTION 4.408.4 NOTES:	N 4.408.2, ITEMS 1 THOUGH 5,
IITS IN F	<ol> <li>SAMPLE FORMS FOUND IN "A GUIDE BUILDING STANDARDS CODE (RESIDE WWW.HCD.CA.GOV/CALGREEN.HTML DOCUMENTING COMPLIANCE WITH T</li> <li>MIXED CONSTRUCTION AND DEMOLIT PROCESSORS CAN BE LOCATED AT 1 OF RESOURCES RECYCLING AND RE</li> </ol>	ENTIAL)" LOCATED AT . MAY BE USED TO ASSIST IN HIS SECTION. TION DEBRIS (C&D) THE CALIFORNIA DEPARTMENT



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. AL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



## **2022 CALIFORNIA GREEN BUILDING STANDARDS CODE RESIDENTIAL MANDATORY MEASURES (SHEET 2)**



#### 4.504.2.3 AEROSOL PAINTS AND COATINGS

AEROSOL PAINTS AND COATINGS SHALL MEET THE PRODUCT-WEIGHTED MIR LIMITS FOR ROC IN SECTION 94522(A)(2) AND OTHER REQUIREMENTS, INCLUDING PROHIBITIONS ON USE OF CERTAIN TOXIC COMPOUNDS AND OZONE DEPLETING SUBSTANCES, IN SECTIONS 94522(E)(1) AND (F)(1) OF CALIFORNIA CODE OF REGULATIONS. TITLE 17. COMMENCING WITH SECTION 94520: AND IN AREAS UNDER THE JURISDICTION OF THE BAY AREA AIR QUALITY MANAGEMENT DISTRICT ADDITIONALLY COMPLY WITH THE PERCENT VOC BY WEIGHT OF PRODUCT LIMITS OF REGULATION 8, RULE 49.

#### 4.504.2.4 VERIFICATION

VERIFICATION OF COMPLIANCE WITH THIS SECTION SHALL BE PROVIDED AT THE REQUEST OF THE ENFORCING AGENCY. DOCUMENTATION MAY INCLUDE, BUT IS NOT LIMITED TO, THE FOLLOWING:

. MANUFACTURER'S PRODUCT SPECIFICATION. 2. FIELD VERIFICATION OF ON-SITE PRODUCT CONTAINERS.

#### 4.504.3 CARPET SYSTEMS

4.504.3.1 CARPET CUSHION

ALL CARPET CUSHION INSTALLED IN THE BUILDING INTERIOR SHALL MEET THE REQUIREMENTS OF THE CALIFORNIA DEPARTMENT OF PUBLIC HEALTH. "STANDARD METHOD FOR THE TESTING AND EVALUATION OF VOLATILE ORGANIC CHEMICAL EMISSIONS FROM INDOOR SOURCES USING ENVIRONMENTAL CHAMBERS," VERSION 1.2, JANUARY 2017 (EMISSION TESTING METHOD FOR CALIFORNIA SPECIFICATION 01350).

SEE CALIFORNIA DEPARTMENT OF PUBLIC HEALTH'S WEBSITE FOR CERTIFICATION PROGRAMS AND TESTING LABS.

HTTPS://WWW.CDPH.CA.GOV/PROGRAMS/CCDPHP/DEODC/EHLB/IAQ/PAG ES/VOC.ASPX

#### 4.504.3.2 CARPET ADHESIVE

ALL CARPET ADHESIVE SHALL MEET THE REQUIREMENTS OF TABLE 4 504 1

4.504.4 RESILIENT FLOORING SYSTEMS WHERE RESILIENT FLOORING IS INSTALLED, AT LEAST 80 PERCENT OF FLOOR AREA RECEIVING RESILIENT FLOORING SHALL MEET THE REQUIREMENTS OF THE CALIFORNIA DEPARTMENT OF PUBLIC HEALTH "STANDARD METHOD FOR THE TESTING AND EVALUATION OF VOLATILE ORGANIC CHEMICAL EMISSIONS FROM INDOOR SOURCES USING ENVIRONMENTAL CHAMBERS," VERSION 1.2, JANUARY 2017 (EMISSION TESTING METHOD FOR CALIFORNIA SPECIFICATION 01350).

> SEE CALIFORNIA DEPARTMENT OF PUBLIC HEALTH'S WEBSITE FOR CERTIFICATION PROGRAMS AND TESTING LABS.

HTTPS://WWW.CDPH.CA.GOV/PROGRAMS/CCDPHP/DEODC/EHLB/IAQ/PAG

#### 4.504.5 COMPOSITE WOOD PRODUCTS

ES/VOC.ASPX

HARDWOOD PLYWOOD, PARTICLEBOARD AND MEDIUM DENSITY FIBERBOARD COMPOSITE WOOD PRODUCTS USED ON THE INTERIOR OR EXTERIOR OF THE BUILDING SHALL MEET THE REQUIREMENTS FOR FORMALDEHYDE AS SPECIFIED IN ARB'S AIR TOXICS CONTROL MEASURE FOR COMPOSITE WOOD (17 CCR 93120 ET SEQ.) AS SHOWN IN TABLE 4.504.5.

4.504.5.1 DOCUMENTATION

- VERIFICATION OF COMPLIANCE WITH THIS SECTION SHALL BE PROVIDED AS REQUESTED BY THE ENFORCING AGENCY. DOCUMENTATION SHALL INCLUDE AT LEAST ONE OF THE FOLLOWING
- PRODUCT CERTIFICATIONS AND SPECIFICATIONS. CHAIN OF CUSTODY CERTIFICATIONS. PRODUCT LABELED AND INVOICED AS MEETING THE COMPOSITE WOOD PRODUCTS REGULATION (SEE CCR, TITLE 17, SECTION 93120, ET SEQ.).
- 4. EXTERIOR GRADE PRODUCTS MARKED AS MEETING THE PS-1 OR PS-2 STANDARDS OF THE ENGINEERED WOOD ASSOCIATION. THE AUSTRALIAN AS/NZS 2269, EUROPEAN 636 3S, AND CANADIAN CSA O121, CSA O151, CSA O153 AND CSA O325 STANDARDS.
- 5. OTHER METHODS ACCEPTABLE TO THE ENFORCING AGENCY.

#### TABLE 4.504.1 - ADHESIVE VOC LIMIT (LESS WATER AND LESS EXEMPT COMPOUNDS IN

CURREN
2
CURREN
Į
4
:
2
Ę
CURREN

1. IF AN ADHESIVE IS USED TO BOND DISSIMILAR SUBSTRATES TOGETHER, THE ADHESIVE WITH THE HIGHEST VOC CONTENT SHALL

BE ALLOWED. 2. FOR ADDITIONAL INFORMATION REGARDING METHODS TO MEASURE THE VOC CONTENT SPECIFIED IN THIS TABLE, SEE SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT RULE 1168.

IT VOC LIMIT 100 100 250 IT VOC LIMIT 325 250 550 250 140 T VOC LIMIT

TABLE 4.504.2 - SEALANT VOC LIMIT (LESS WATER AND LESS EXEMPT COMPOUNDS IN GRAMS PE	ER LITER)
<u>N</u>	,
SEALANTS	CURRENT VOC LIMIT
ARCHITECTURAL	250
MARINE DECK	760
NONMEMBRANE ROOF	300
ROADWAY	250
SINGLE-PLY ROOF MEMBRANE	450
OTHER	420
SEALANT PRIMERS	CURRENT VOC LIMIT
ARCHITECTURAL	
NONPOROUS	250
POROUS	250
MODIFIED BITUMINOUS	500
MARINE DECK	760
OTHER	750

#### TABLE 4.504.3 - VOC CONTENT LIMITS FOR ARCHITECTURAL COATINGS<sup>2, 3</sup> (GRAMS OF VOC PER LITER OF COATING, LESS WATER AND LESS EXEMPT COMPOUND

COATING CATEGORY	CURRENT VOC LIMIT
FLAT COATINGS	50
NONFLAT COATINGS	100
NONFLAT-HIGH GLOSS COATINGS	150
SPECIALTY COATINGS	CURRENT VOC LIMIT
ALUMINUM ROOF COATINGS	400
BASEMENT SPECIALTY COATINGS	400
BITUMINOUS ROOF COATINGS	50
BITUMINOUS ROOF PRIMERS	350
BOND BREAKERS	350
CONCRETE CURING COMPOUNDS	350
CONCRETE/MASONRY SEALERS	100
DRIVEWAY SEALERS	50
DRY FOG COATINGS	150
FAUX FINISHING COATINGS	350
FIRE RESISTIVE COATINGS	350
FLOOR COATINGS	100
FORM-RELEASE COMPOUNDS	250
GRAPHIC ARTS COATINGS (SIGN PAINTS)	500
HIGH TEMPERATURE COATINGS	420
IDUSTRIAL MAINTENANCE COATINGS	250
LOW SOLIDS COATINGS <sup>1</sup>	120
MAGNESITE CEMENT COATINGS	450
MASTIC TEXTURE COATINGS	100
METALLIC PIGMENTED COATINGS	500
MULTICOLOR COATINGS	250
PRETREATMENT WASH PRIMERS	420
PRIMERS, SEALERS, AND UNDERCOATERS	100
REACTIVE PENETRATING SEALERS	350
RECYCLED COATINGS	250
ROOF COATINGS	50
RUST PREVENTATIVE COATINGS	250
SHELLACS	200
CLEAR	730
OPAQUE	550
SPECIALTY PRIMERS, SEALERS AND	100
UNDERCOATERS	100
STAINS	250
STONE CONSOLIDANTS	450
SWIMMING POOL COATINGS	340
TRAFFIC MARKING COATINGS	100
TUB AND TILE REFINISH COATINGS	420
WATERPROOFING MEMBRANES	250
WOOD COATINGS	250
WOOD PRESERVATIVES	350
ZINC-RICH PRIMERS	340

1. GRAMS OF VOC PER LITER OF COATING, INCLUDING WATER AND

INCLUDING EXEMPT COMPOUNDS. 2. THE SPECIFIED LIMITS REMAIN IN EFFECT ENLESS REVISED LIMITS

ARE LISTED IN SUBSEQUENT COLUMNS IN THE TABLE 3. VALUES IN THIS TABLE ARE DERIVED FROM THOSE SPECIFIED BY THE CALIFORNIA AIR RESOURCES BOARD, ARCHITECTURAL COATINGS SUGGESTED CONTROL MEASURE, FEBUARY 1, 2008. MORE INFORMATION IS AVAILABLE FROM THE AIR RESOURCES BOARD.

TABLE 4.504.5 - FORMALDEHYDE LIMITS<sup>1</sup> MAXIMUM FORMALDEHYDE EMISSIONS IN PARTS PER MILLION

PRODUCT	CURRENT LIMIT
HARDWOOD PLYWOOD VENEER CORE	0.05
HARDWOOD PLYWOOD COMPOSITE CORE	0.05
PARTICLEBOARD	0.09
MEDIUM DENSITY FIBERBOARD	0.11
THIN MEDIUM DENSITY FIBERBOARD <sup>2</sup>	0.13

1. VALUES IN THIS TABLE ARE DERIVED FROM THOSE SPECIFIED BY THE CALIFORNIA AIR RESOURCES BOARD, AIR TOXICS CONTROL MEASURE FOR COMPOSITE WOOD AS TESTED IN ACCORDANCE WITH ASTM E1333. FOR ADDITIONAL INFORMATION, SEE CALIFORNIA CODE OF REGULATIONS, TITLE 17, SECTIONS 93120 THROUGH 93120.12.

2. THIN MEDIUM DENSITY FIBERBOARD HAS A MAXIMUM THICKNESS OF 5/16 INCH (8MM).

#### **DIVISION 4.5 ENVIORNMENTAL QUALITY** CONTINUED

**4.505 INTERIOR MOISTURE CONTROL** 

4.505.1 GENERAL BUILDINGS SHALL MEET OR EXCEED THE PROVISIONS OF THE CALIFORNIA BUILDING STANDARDS CODE.

**4.505.2 CONCRETE SLAB FOUNDATIONS** 

CONCRETE SLAB FOUNDATIONS REQUIRED TO HAVE A VAPOR RETARDER BY THE CALIFORNIA BUILDING CODE CHAPTER 19 OR CONCRETE SLAB-ON-GROUND FLOORS REQUIRED TO HAVE A VAPOR RETARDER BY THE CALIFORNIA RESIDENTIAL CODE, CHAPTER 5, SHALL ALSO COMPLY WITH THIS SECTION.

#### 4.505.2.1 CAPILLARY BREAK

- A CAPILLARY BREAK SHALL BE INSTALLED IN COMPLIANCE WITH AT LEAST ONE OF THE FOLLOWING: 1. A 4-INCH-THICK (101.6 MM) BASE OF 1/2 INCH (12.7 MM) OR LARGER CLEAN AGGREGATE SHALL BE PROVIDED WITH A VAPOR RETARDER IN DIRECT CONTACT WITH CONCRETE AND A
- CONCRETE MIX DESIGN, WHICH WILL ADDRESS BLEEDING, SHRINKAGE, AND CURLING, SHALL BE USED, FOR ADDITIONAL INFORMATION, SEE AMERICAN CONCRETE INSTITUTE, ACI 302.2R-06 2. OTHER EQUIVALENT METHODS APPROVED BY THE ENFORCING
- AGENCY 3. A SLAB DESIGN SPECIFIED BY A LICENSED DESIGN PROFESSIONAL

#### 4.505.3 MOISTURE CONTENT OF A BUILDING

BUILDING MATERIALS WITH VISIBLE SIGNS OF WATER DAMAGE SHALL NOT BE INSTALLED. WALL AND FLOOR FRAMING SHALL NOT BE ENCLOSED WHEN THE FRAMING MEMBERS EXCEED 19-PERCENT MOISTURE CONTENT. MOISTURE CONTENT SHALL BE VERIFIED IN COMPLIANCE WITH THE FOLLOWING:

- MOISTURE CONTENT SHALL BE DETERMINED WITH EITHER A PROBE TYPE OR CONTACT-TYPE MOISTURE METER. EQUIVALENT MOISTURE VERIFICATION METHODS MAY BE APPROVED BY THE ENFORCING AGENCY AND SHALL SATISFY REQUIREMENTS FOUND IN SECTION 101.8 OF THIS CODE.
- MOISTURE READINGS SHALL BE TAKEN AT A POINT 2 FEET (610 MM) TO 4 FEET (1219 MM) FROM THE GRADE STAMPED END OF EACH PIECE TO BE VERIFIED.
- AT LEAST THREE RANDOM MOISTURE READINGS SHALL BE PERFORMED ON WALL AND FLOOR FRAMING WITH DOCUMENTATION ACCEPTABLE TO THE ENFORCING AGENCY PROVIDED AT THE TIME OF APPROVAL TO ENCLOSE THE WALL AND FLOOR FRAMING.

INSULATION PRODUCTS WHICH ARE VISIBLY WET OR HAVE A HIGH MOISTURE CONTENT SHALL BE REPLACED OR ALLOWED TO DRY PRIOR TO ENCLOSURE IN WALL OR FLOOR CAVITIES. WET-APPLIED INSULATION PRODUCTS SHALL FOLLOW THE MANUFACTURERS' DRYING RECOMMENDATIONS PRIOR TO ENCLOSURE.

#### 4.506 INDOOR AIR QUALITY AND EXHAUST

4.506.1 BATHROOM EXHAUST FANS

- EACH BATHROOM SHALL BE MECHANICALLY VENTILATED AND SHALL COMPLY WITH THE FOLLOWING 1. FANS SHALL BE ENERGY STAR COMPLIANT AND BE DUCTED TO
- TERMINATE OUTSIDE THE BUILDING. 2. UNLESS FUNCTIONING AS A COMPONENT OF A WHOLE HOUSE VENTILATION SYSTEM, FANS MUST BE CONTROLLED BY A HUMIDITY
- CONTROL. a. HUMIDITY CONTROLS SHALL BE CAPABLE OF ADJUSTMENT BETWEEN A RELATIVE HUMIDITY RANGE OF ≤ 50 PERCENT TO A MAXIMUM OF 80 PERCENT, A HUMIDITY CONTROL MAY UTILIZE
- MANUAL OR AUTOMATIC MEANS OF ADJUSTMENT. b. A HUMIDITY CONTROL MAY BE A SEPARATE COMPONENT TO THE EXHAUST FAN AND IS NOT REQUIRED TO BE INTEGRAL (I.E., BUILT-IN). NOTES:
- 1. FOR THE PURPOSES OF THIS SECTION, A BATHROOM IS A ROOM WHICH CONTAINS A BATHTUB, SHOWER, OR TUB/ SHOWER COMBINATION.
- 2. LIGHTING INTEGRAL TO BATHROOM EXHAUST FANS SHALL COMPLY WITH THE CALIFORNIA ENERGY CODE.

#### 4.507 ENVIROMENTAL COMFORT

4.507.1 RESERVED

4.507.2 HEATING AND AIR-CONDITIONING SYSTEM DESIGN

- HEATING AND AIR-CONDITIONING SYSTEMS SHALL BE SIZED, DESIGNED AND HAVE THEIR EQUIPMENT SELECTED USING THE FOLLOWING METHODS: 1. THE HEAT LOSS AND HEAT GAIN IS ESTABLISHED ACCORDING TO ANSI/ACCA 2 MANUAL J-2016 (RESIDENTIAL LOAD CALCULATION), ASHRAE HANDBOOKS OR OTHER EQUIVALENT DESIGN SOFTWARE OR METHODS.
- 2. DUCT SYSTEMS ARE SIZED ACCORDING TO ANSI/ACCA 1 MANUAL D-2016 (RESIDENTIAL DUCT SYSTEMS), ASHRAE HANDBOOKS OR OTHER EQUIVALENT DESIGN SOFTWARE OR METHODS.
- 3. SELECT HEATING AND COOLING EQUIPMENT ACCORDING TO ANSI/ACCA 3 MANUAL S—2016 (RESIDENTIAL EQUIPMENT SELECTION) OR OTHER EQUIVALENT DESIGN SOFTWARE OR METHODS.

**EXCEPTION:** USE OF ALTERNATE DESIGN TEMPERATURES NECESSARY TO ENSURE THE SYSTEMS FUNCTION ARE ACCEPTABLE

## **CHAPTER 7 - INSTALLER &** SPECIAL INSPECTOR **QUALIFICATIONS**

#### **702 QUALIFICATIONS**

#### **702.1 INSTALLER TRAINING**

HVAC SYSTEM INSTALLERS SHALL BE TRAINED AND CERTIFIED IN THE PROPER INSTALLATION OF HVAC SYSTEMS INCLUDING DUCTS AND EQUIPMENT BY A NATIONALLY OR REGIONALLY RECOGNIZED TRAINING OR CERTIFICATION PROGRAM. UNCERTIFIED PERSONS MAY PERFORM HVAC INSTALLATIONS WHEN UNDER THE DIRECT SUPERVISION AND RESPONSIBILITY OF A PERSON TRAINED AND CERTIFIED TO INSTALL HVAC SYSTEMS OR CONTRACTOR LICENSED TO INSTALL HVAC SYSTEMS. EXAMPLES OF ACCEPTABLE HVAC TRAINING AND CERTIFICATION PROGRAMS INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING:

- STATE CERTIFIED APPRENTICESHIP PROGRAMS PUBLIC UTILITY TRAINING PROGRAMS.
- TRAINING PROGRAMS SPONSORED BY TRADE, LABOR OR STATEWIDE ENERGY CONSULTING OR VERIFICATION ORGANIZATIONS.
- 4. PROGRAMS SPONSORED BY MANUFACTURING ORGANIZATIONS. 5. OTHER PROGRAMS ACCEPTABLE TO THE ENFORCING AGENCY.

#### 702.2 SPECIAL INSPECTION [HCD]

WHEN REQUIRED BY THE ENFORCING AGENCY, THE OWNER OR THE RESPONSIBLE ENTITY ACTING AS THE OWNER'S AGENT SHALL EMPLOY ONE OR MORE SPECIAL INSPECTORS TO PROVIDE INSPECTION OR OTHER DUTIES NECESSARY TO SUBSTANTIATE COMPLIANCE WITH THIS CODE SPECIAL INSPECTORS SHALL DEMONSTRATE COMPETENCE TO THE SATISFACTION OF THE ENFORCING AGENCY FOR THE PARTICULAR TYPE OF INSPECTION OR TASK TO BE PERFORMED. IN ADDITION TO OTHER CERTIFICATIONS OR QUALIFICATIONS ACCEPTABLE TO THE ENFORCING AGENCY, THE FOLLOWING CERTIFICATIONS OR EDUCATION MAY BE CONSIDERED BY THE ENFORCING AGENCY WHEN EVALUATING THE QUALIFICATIONS OF A SPECIAL INSPECTOR:

- 1. CERTIFICATION BY A NATIONAL OR REGIONAL GREEN BUILDING PROGRAM OR STANDARD PUBLISHER. 2. CERTIFICATION BY A STATEWIDE ENERGY CONSULTING OR
- VERIFICATION ORGANIZATION, SUCH AS HERS RATERS, BUILDING PERFORMANCE CONTRACTORS, AND HOME ENERGY AUDITORS. 3. SUCCESSFUL COMPLETION OF A THIRD PARTY APPRENTICE TRAINING
- PROGRAM IN THE APPROPRIATE TRADE. 4. OTHER PROGRAMS ACCEPTABLE TO THE ENFORCING AGENCY

#### NOTES

- 1. SPECIAL INSPECTORS SHALL BE INDEPENDENT ENTITIES WITH NO FINANCIAL INTEREST IN THE MATERIALS OR THE PROJECT THEY ARE NSPECTING FOR COMPLIANCE WITH THIS CODE.
- 2. HERS RATERS ARE SPECIAL INSPECTORS CERTIFIED BY THE CALIFORNIA ENERGY COMMISSION (CEC) TO RATE HOMES IN CALIFORNIA ACCORDING TO THE HOME ENERGY RATING SYSTEM (HERS)

BSC] WHEN REQUIRED BY THE ENFORCING AGENCY, THE OWNER OR THE RESPONSIBLE ENTITY ACTING AS THE OWNER'S AGENT SHALL EMPLOY ONE OR MORE SPECIAL INSPECTORS TO PROVIDE INSPECTION OR OTHER DUTIES NECESSARY TO SUBSTANTIATE COMPLIANCE WITH THIS CODE SPECIAL INSPECTORS SHALL DEMONSTRATE COMPETENCE TO THE SATISFACTION OF THE ENFORCING AGENCY FOR THE PARTICULAR TYPE OF INSPECTION OR TASK TO BE PERFORMED. IN ADDITION, THE SPECIAL INSPECTOR SHALL HAVE A CERTIFICATION FROM A RECOGNIZED STATE, NATIONAL OR INTERNATIONAL ASSOCIATION, AS DETERMINED BY THE LOCAL AGENCY. THE AREA OF CERTIFICATION SHALL BE CLOSELY RELATED TO THE PRIMARY JOB FUNCTION, AS DETERMINED BY THE LOCAL AGENCY.

SPECIAL INSPECTORS SHALL BE INDEPENDENT ENTITIES WITH NO FINANCIAL INTEREST IN THE MATERIALS OR THE PROJECT THEY ARE INSPECTING FOR COMPLIANCE WITH THIS CODE

#### **703 VERIFICATIONS**

#### 703.1 DOCUMENTATION.

DOCUMENTATION USED TO SHOW COMPLIANCE WITH THIS CODE SHALL INCLUDE BUT IS NOT LIMITED TO, CONSTRUCTION DOCUMENTS, PLANS, SPECIFICATIONS, BUILDER OR INSTALLER CERTIFICATION, INSPECTION REPORTS, OR OTHER METHODS ACCEPTABLE TO THE ENFORCING AGENCY WHICH DEMONSTRATE SUBSTANTIAL CONFORMANCE. WHEN SPECIFIC DOCUMENTATION OR SPECIAL INSPECTION IS NECESSARY TO VERIFY COMPLIANCE, THAT METHOD OF COMPLIANCE WILL BE SPECIFIED IN THE APPROPRIATE SECTION OR IDENTIFIED APPLICABLE CHECKLIST.



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. AL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

SISPO 4 F U **LUIS ( FLIN** Ш SID| Σ Ш́ **Z S B** КШ UIR ' **`` ≻** ≌ **ה ה** ] ШQ  $\mathbf{O} \overline{\mathbf{O}} \overline{\mathbf{Z}}$  $\boldsymbol{\mathcal{C}}$ ш U U U U UNTY CESS ()δU Ū٩


BIS

Ō


DATE 09/28/2023 SHEET







## SITE PLAN LEGEND






	SITE	PLAN	GENERAL	NOTES
--	------	------	---------	-------

ALL EXISTING SWIMMING POOLS SHALL BE SHOWN ON THE SITE PLAN AND SHALL FLOOR OR GRADE BELOW (INCLUDING FLOORS, STAIRS, RAMPS, AND LANDINGS) ANYWHERE MEASURED LESS THAN 36 INCHES HORIZONTALLY TO THE EDGE OF PROPOSED ADU SHALL BE CONNECTED TO THE MAIN LATERAL AT THE PROPERTY REQUIRED CLEANOUTS, WATER LINE TO ADU, ELECTRIC TO ADU INCLUDING ANY TOTAL DEVELOPED LENGTH OF GAS SYSTEM FROM METER / REGULATOR SHOW MECHANICAL, PLUMBING, AND KITCHEN GAS APPLIANCE LOCATION



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



<b>GENERAL</b>	
GLINLINAL	NULS

		C	OOR	
NO.	TYPE	WIDTH	HEIGHT	REMARKS
101	A1	3' - 0"	6' - 8"	1, 2
102	A2	2' - 0"	6' - 8"	1, 3
103	D	6' - 0"	6' - 8"	
104	С	3' - 0"	6' - 8"	
105	С	3' - 0"	6' - 8"	
106	D	5' - 0"	6' - 8"	
107	E	6' - 0"	6' - 8"	3
108	С	3' - 0"	6' - 8"	
109	С	3' - 0"	6' - 8"	
110	D	4' - 0"	6' - 8"	
111	С	3' - 0"	6' - 8"	
112	С	3' - 0"	6' - 8"	
113	D	5' - 0"	6' - 8"	

## **FLOOR PLAN GENERAL NOTES**

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS. REFER TO STRUCTURAL PLANS FOR FURTHER INFORMATION. REFER TO ELECTRICAL PLANS FOR FURTHER INFORMATION IF PROVIDED.
- 4. REFER TO MECHANICAL PLANS, DRAWINGS OR REPORTS FOR FURTHER
- INFORMATION. 5. ALL FURNITURE AND EQUIPMENT IS BY OWNER AND IS SHOWN FOR
- COORDINATION PURPOSES ONLY. 6. DIMENSIONS ARE TO FACE OF FRAMING UNLESS SPECIFICALLY NOTED
- OTHERWISE. 7. PROVIDE ADEQUATE BLOCKING IN WALLS FOR CABINETS AND OTHER WALL MOUNTED ACCESSORIES INCLUDING BUT NOT LIMITED TO HANDRAILS,
- SHELVING AND BATHROOM FIXTURES. DOOR AND WINDOW DIMENSIONS ARE CENTERED AT OPENINGS. WHERE DOOR IS LOCATED WITHOUT DIMENSION AT THE CORNER OF A ROOM IT SHALL BE 4" FROM FACE OF FRAMING OF ADJACENT WALL TO ROUGH DOOR OPENING.
- 10. WHERE RECESSED FIXTURES OCCUR IN WALLS OR HORIZONTAL ASSEMBLIES, THE FIRE RATING OF THOSE ASSEMBLIES SHALL BE MAINTAINED.
- 11. AT ALL PENETRATIONS AND INTERSECTIONS OF FIRE-RATED PARTITIONS, PROVIDE FIRE SEALANT AND/OR FIRE STOPPING TO MAINTAIN CONTINUITY OF PARTITION RATING. 12. PER CRC R311.3 FLOORS OR LANDINGS AT EXTERIOR DOORS SHALL BE AT
- LEAST AS WIDE AS DOOR SERVED AND SHALL PROVIDE A LENGTH IN THE DIRECTION OF TRAVEL EQUAL TO 36 INCHES MINIMUM. SLOPE OF EXTERIOR LANDINGS SHALL NOT EXCEED 1/4" PER FOOT (2% SLOPE).
- 13. PER CRC 327.1.1 REINFORCEMENT FOR GRAB BARS SHALL BE PROVIDED IN AT LEAST ONE BATHROOM. 1. REINFORCEMENT SHALL BE SOLID LUMBER OR OTHER CONSTRUCTION MATERIALS APPROVED BY THE ENFORCING AGENCY. 2. REINFORCEMENT SHALL NOT BE LESS THAN 2X8 INCH NOMINAL LUMBER OR OTHER MATERIAL PROVIDING EQ. HT. AND CAPACITY. REINFORCEMENT ABOVE THE FINISHED FLOOR FLUSH WITH THE WALL FRAMING. 3. WATER CLOSET REINFORCEMENT SHALL BE INSTALLED ON BOTH SIDE WALLS OF THE FIXTURE. OR ONE SIDE WALL AND THE BACK WALL 4. SHOWER REINFORCEMENT SHALL BE CONTINUOUS WHERE WALL FRAMING IS PROVIDED. 5. BATHTUB AND COMBINATION BATHTUB/SHOWER REINFORCEMENT SHALL BE CONTINUOUS ON EACH END OF THE BATHTUB AND THE BACK WALL, ADDITIONALLY, BACK WALL REINFORCEMENT FOR A LOWER GRAB BAR SHALL BE PROVIDED WITH THE BOTTOM EDGE LOCATED NO MORE THAN 6 INCHES ABOVE THE BATHTUB RIM.

## **KEYNOTES**

-(1.A)

5

\A1-201/

–(1.B`

A01	30" WIDE FREE STANDING ELECTRIC RANGE OVEN. VENT TO EXTERIOR, STAINLESS STEEL.
405	REFRIGERATOR LOCATION. PROVIDE 42" SPACE WITH ROUGH PLUMBING FOR ICE MAKER (RECESS IN WALL).
407	CLOTHES DRYER LOCATION W/ RECESSED DRYER VENT BOX. PROVIDE DRYER VENT. VENT TO OUTSIDE AIR.
A15	WASHING MACHINE LOCATION. PROVIDE WASTE AND WATER IN RECESSED WALL BOX.
302	20" SINGLE COMPARTMENT UNDER-MOUNT KITCHEN SINK W/ GARBAGE DISPOSAL. REFER TO WATER EFFICIENCY REQUIREMENTS ON CALGREEN CODE NOTES SHEET.
304	LAVATORY SINK. REFER TO WATER EFFICIENCY REQUIREMENTS ON CALGREEN CODE NOTES SHEETS.
305	WATER CLOSET. REFER TO WATER EFFICIENCY REQUIREMENTS ON CALGREEN CODE NOTES SHEETS. REQ. AGING-IN-PLACE BLOCKING; SEE DETAIL 54/A-901.
306	32" x 60" x 72" TUB AND SHOWER COMBINATION. MODEL BY BUILDER. PROVIDE SHOWER ROD. REQ. AGING-IN-PLACE BLOCKING; SEE DETAIL 44/A-901.
318	ELECTRIC PANEL, 100AMP 240V.
338	MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION, 3" MIN. ABOVE GRADE.
347	40 GALLON HEAT PUMP WATER HEATER. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION.
C01	SINGLE WOOD SHELF AND POLE.
208	12" DEEP UPPER CABINET
C10	24" DEEP UPPER CABINET.
C13	30" HIGH BASE CABINET AND COUNTERTOP.
C14	TOWEL BAR. +54 INCHES ABOVE FLOOR, PROVIDE 2X6 BACKING AT BATHROOM WALL ATTACHMENTS
216	MIRROR. THE LENGTH OF THE VANITY OR PEDESTAL X 80" AFS. UNO. VERIFY WITH THE ELECTRICAL PLAN FOR LOCATION OF OUTLETS WHICH REQUIRE A CUT-OUT., PROVIDE 2X6 BACKING AT BATHROOM WALL ATTACHEMENTS
M02	DOWNSPOUT. CONNECT TO STORM DRAIN SYSTEM OR APPROVED DRAINAGE SYSTEM BY COUNTY.
X01	OPTIONAL CABINET
X27	OPTIONAL DISHWASHER

## **DOOR GENERAL NOTES**

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS REFER TO PLANS FOR LOCATION OF DOORS.
- 3. VERIFY ROUGH OPENING SIZE WITH DOOR MANUFACTURER SPECIFICATIONS PRIOR TO CONSTRUCTION. 4. CONTRACTOR TO VERIFY ACTUAL DOOR SIZE TO FIT FINISH OPENING PRIOR
- TO FABRICATION OF DOOR AND FINISH OPENING.
- INSTALL PER MANUFACTURERS WRITTEN INSTRUCTIONS. REFER TO DOOR TYPES LEGEND FOR GLAZING.
- REFER TO T24 REPORT FOR GLAZING ENERGY REQUIREMENTS. 8. GLAZING IN DOORS SHALL BE TEMPERED PER **SECTION R308.4.1**. PANES INDICATED IN DOOR LEGEND WITH (T).

## **DOOR REMARKS**

- EXTERIOR DOOR.
- 2. GLAZING PER DOOR TYPES. REFER TO GENERAL DOOR NOTE #8 3. PROVIDE 100 SQ INCHES OF VENTING IN DOOR OR BY OTHER APPROVED
- MEANS.
- 4. OPTIONAL DOOR.

## WALL LEGEND

·····

EXTERIOR - 5 1/2" WOOD STUD W/ SHEATHING AND EXTERIOR FINISH (REFER TO ELEVATIONS), ONE LAYER GYPSUM WALL BOARD INTERIOR.

**INTERIOR** - 3 1/2" WOOD STUD W/ONE LAYER GYPSUM WALL BOARD EACH SIDE.

**NOTE:** SEE MANUFACTURER'S PRODUCT LISTINGS FOR **IMPROVED SOUND AND/OR** MOISTURE/MOLD/MILDEW-RESISTANT PERFORMANCE. VISIT GYPSUM.ORG FOR MORE INFORMATION.



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU has been issued and final inspection COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO ACCESSORY DWELLING UNIT SAN LUIS OBISPO, CA

DATE

SHEET

09/28/2023

A1-101


AN

۵\_


 $\sim$ 

Ο

FLO




		FINISH SCHEDULE PLAN 1				
NAME	FLOOR	WALL	CEILING	N		
CL 2	CPT	GWB	GWB			
BED 1	CPT	GWB	GWB			
CL 1	CPT	GWB	GWB			
BED 3	CPT	GWB	GWB			
CL 3	CPT	GWB	GWB			
BED 4	CPT	GWB	GWB			
CL 4	CPT	GWB	GWB			
WH						



- EXTERNALLY MOUNTED HEATING/COOLING UNITS SHALL BE SCREENED IF
- 6. ALL SMOKE ALARMS TO BE HARD-WIRED WITH A BATTERY BACK-UP. AND ALL
- ALL CARBON MONOXIDE ALARMS TO BE HARD-WIRED WITH A BATTERY BACK-UP. AND ALL CARBON MONOXIDE ALARMS MUST BE INTERCONNECTED


## **FINISH PLAN GENERAL NOTES**

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
- 5. ALL HARD SURFACE FLOORING SHALL BE SLIP RESISTANT AND MEET THE ANSI A326.3 STANDARD FOR MEASURING THE DYNAMIC COEFFICIENT OF
- ALL WALL AND CEILING FINISHES SHALL COMPLY WITH CBC TABLE 803.13





THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



## **ROOF PLAN GENERAL NOTES**

2. REFER TO STRUCTURAL PLANS FOR ROOF FRAMING INFORMATION

3. REFERE TO MECHANCIAL/ELECTRICAL SHEETS FOR ROOF PENETRATION

4. PROVIDE A MINIMUM OF 1 INCH OF AIRSPACE BETWEEN THE INSULATION

WHERE THE ROOF PROFILE ALLOWS A SPACE BETWEEN THE ROOF COVERING AND DECKING, THE SPACES SHALL BE CONSTRUCTED TO

APPROVED MATERIALS OR HAVE ONE LAYER OF MINIMUM 72 POUND

MINERAL-SURFACED NONPERFORATED CAP SHEET OVER THE

6. ALL ROOFING MATERIALS TO BE INSTALLED PER MANUFACTURER'S

INCLUDING MEMBER SIZES AND CONNECTION HARDWARE.

REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS

PREVENT THE INTRUSION OF FLAMES AND EMBERS, BE FIRESTOPPED WITH

OVERHANG DIMENSIONS ARE FROM FACE OF EXTERIOR WALL FRAMING TO

ROOF COVERINGS AND UNDERLAYMENT SHALL BE APPLIED IN ACCORDANCE

MANUFACTURERS SPECIFICATIONS AND ADJUST TO ACCOMMODATE TRUSS

WITH (CRC R905), AND MANUFACTURER'S INSTALLATION INSTRUCTIONS

ROOF VENTS SHALL BE APPLIED PER MANUFACTURER'S SPECIFICATIONS

CEILINGS ARE APPLIED DIRECTLY TO THE UNDERSIDE OF ROOF RAFTERS

SNOW. VENTILATION OPENINGS SHALL HAVE A LEAST DIMENSION OF 1/16

MEMBERS SHALL CONFORM TO THE REQUIREMENTS OF SECTION R802.7.

INCH MINIMUM AND 1/4 INCH MAXIMUM. OPENINGS IN ROOF FRAMING

AIR AND SHALL BE PROTECTED TO PREVENT THE ENTRY OF BIRDS.

12. THE MINIMUM NET FREE VENTILATING AREA SHALL COMPLY WITH CRC

14. FOR VENTED ROOF ASSEMBLIES: PROVIDE A MINIMUM OF 1 INCH OF

15. FOR UN-VENTED ROOF ASSEMBLIES: ROOF ASSEMBLY TO MEET CODE

AIRSPACE BETWEEN THE INSULATION AND ROOF SHEATHING.

MINIMUM ROOF ASSEMBLY R-VALUE REQUIRED BY TITLE-24.

13. IN THE INSTANCE OF UPPER VENTS, VENTS SHALL BE LOCATED NO MORE

VENTILATING OPENINGS PROTECTED AGAINST THE ENTRANCE OF RAIN OR

REQUIRED VENTILATION OPENINGS SHALL OPEN DIRECTLY TO THE OUTSIDE

THAN 3 FT BELOW THE RIDGE OR HIGHEST POINT OF THE SPACE, MEASURED

REQUIREMENTS OF CRC R806.5. PROVIDE MINIMUM 2" HIGH DENSITY CLOSE

CELL INSULATION. PROVIDE ADDTIONAL INSULATION AS NEEDED TO MEET

16. ALL ROOFING TO BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS. 17. OVERHANG DIMENSIONS ARE FROM FACE OF EXTERIOR WALL FRAMING TO

10. FURNISHED DIMENSIONS FOR VENTS ARE GUIDES ONLY. INSTALL PER

11. ENCLOSED ATTICS AND ENCLOSED RAFTER SPACES FORMED WHERE

SHALL HAVE CROSS VENTILATION FOR EACH SEPARATE SPACE BY

LOCATIONS, PLUMBING VENTS, AND SOLAR COLLECTORS

RODENTS, SNAKES AND OTHER SIMILAR CREATURES.

EMENTS. FLOOR	
OTED. TS, &	

LOCATIONS.

AND ROOF SHEATHING.

COMBUSTIBLE DECKING.

SPECIFICATIONS.

ROOF EDGE

R806.2.

ROOF EDGE

VERTICALLY. CRC R806.2.

**ROOF VENTING CALCULATIONS** 

**UPPER & LOWER VENTS:** 

O'HAGIN TAPERED LOW PROFILE FIRE & ICE COMPOSITION SHINGLE FINISH TO MATCH ROOF 72.0 SQ.IN OF AIR MOVEMENT PER VENT = 72. SQ.IN. / 144 = 0.5 SF

"UPPER VENTS PROVIDED" = (TOTAL ATTIC AREA/300) \* (0.5) / (0.5 SF)

"LOWER VENTS PROVIDED" = (TOTAL ATTIC AREA/300) \* (0.5) / (0.5 SF)

NOTE: ROOF VENTING SHALL COMPLY WITH CRC R806 & CRC 337.

A) ENCLOSED ATTICS AND ENCLOSED RAFTER SPACES FORMED WHERE CEILINGS ARE APPLIED DIRECTLY TO THE UNDERSIDE OF ROOF RAFTERS SHALL HAVE CROSS VENTILATION FOR EACH SEPARATE SPACE BY VENTILATING OPENINGS PROTECTED AGAINST THE ENTRANCE OF RAIN OR SNOW. VENTILATION OPENINGS SHALL HAVE A LEAST DIMENSION OF 1/16 INCH MINIMUM AND 1/4 INCH MAXIMUM. OPENINGS IN ROOF FRAMING MEMBERS SHALL CONFORM TO THE REQUIREMENTS OF SECTION R802.7. REQUIRED VENTILATION OPENINGS SHALL OPEN DIRECTLY TO THE OUTSIDE AIR AND SHALL BE PROTECTED TO PREVENT THE ENTRY OF BIRDS, RODENTS, SNAKES AND OTHER SIMILAR CREATURES.

B) THE MINIMUM NET FREE VENTILATING AREA SHALL COMPLY WITH CRC R806.2. C) PER CRC R902.1.3 ROOFING REQUIREMENTS FOR STRUCTURES LOCATED IN A WILDLAND-URBAN INTERFACE (WUI) FIRE AREA SHALL COMPLY WITH SECTION

R337.5.

D) THE PRODUCT ABOVE CAN BE FOUND IN THE CAL-FIRE STATE FIRE MARSHAL LISTED WILDLAND URBAN INTERFACE (WUI) PRODUCT HANDBOOK.


ATTIC	AREA		RED ATTIC NG (NFA)	UPPER VEI REQUIRED			R VENTING
ATTIC 1 - PLAN 1	1127 SF	3.76 SF		1.88 SF		1.88 SF	
	VENT TYPE		COUNT	VENT LENGTH	ARE	FREE A PER ENT	PROVIDE NET FRE AREA
LOWER O'HAGIN SI (LOWER)	HINGLE ROOF	VENT	4	2' - 8"	0.50 S	F	2.00 SF
							2.00 SF
UPPER	HINGLE ROOF		4	2' - 8"	0.50 S		2.00 SF



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

_		
	COUNTY OF SAN LUIS OBISPO ACCESSORY DWELLING UNIT SAN LUIS OBISPO, CA	ROOF PLAN & REFLECTED CEILING PLAN
B) DE	DATE 09/28/2023 SHEET	

A1-121



2. 3.	REFER TO GENERAL NOTES SHEET G-102 FOR ADDITIONAL REQUIREMENTS SEE DETAILS FOR ADDITIONAL INFORMATION AND REQUIREMENTS. REFER TO ROOF PLAN FOR OVERHANGS. FASCIA PER DETAILS. PROVIDE ALUMINUM GUTTER. SEE ROOF PLAN FOR APPROXIMATE DOWNSPOUT LOCATIONS, U.N.O.
5.	REFER TO DOOR AND WINDOW SCHEDULES AND TYPES FOR DOOR AND WINDOW INFORMATION. THE NOMINAL THICKNESS AND ATTACHMENT OF EXTERIOR WALL COVERINGS SHALL BE IN ACCORDANCE WITH CRC TABLE R703.3(1). GYPSUM SHEATHING SHALL BE ATTACHED TO EXTERIOR WALLS IN ACCORDANCE WITH CRC TABLE R602.3.
	ECTIONS GENERAL NOTES
5	THE PURPOSE OF THESE DRAWINGS IS TO SHOW CONSTRUCTION MATERIALS/ASSEMBLIES. FOR SPECIFIC SIZES AND DETAILS REFER TO ARCHITECTURAL PLANS, ELEVATIONS, DETAILS, AND STRUCTURAL PLANS. *KEYNOTES ONLY APPLY IF REFERENCED ON PLANS. WALL ASSEMBLIES TO BE PER FLOOR PLAN.
- 3. 4. 5.	DOORS AND WINDOWS TO BE PER APPLICABLE SCHEDULE. REFER TO FLOOR PLANS FOR IDENTIFICATION. INSULATION: REFER TO TITLE 24 REPORT AND "INSULATION" NOTES ON SHEET FOR ADDITIONAL RATINGS, REQUIREMENTS, AND INFORMATION. FIREBLOCKING TO BE LOACATED AT THE FOLLOWING LOCATIONS PER <b>2022</b> <i>CRC SECTION R302.11</i> :
<u>r</u>	<ul> <li>A. SECTION R302.11 -</li> <li>1. FIREBLOCKING SHALL BE PROVIDED IN CONCEALED SPACES OF STUD WALLS AND PARTITIONS, INCLUDING FURRED SPACES AND PARALLEL ROWS OF STUDS OR STAGGERED STUDS, AS FOLLOWS:</li> <li>1. VERTICALLY AT CEILING AND FLOOR LEVELS</li> <li>2. HORIZONTALLY AT INTERVALS NOT EXCEEDING 10 FEET.</li> </ul>
	<ol> <li>AT INTERCONNECTIONS BETWEEN CONCEALED VERTICAL AND HORIZONTAL SPACES SUCH AS SOFFITS, DROP CEILINGS AND COVE CEILINGS.</li> <li>IN CONCEALED SPACES BETWEEN STAIR STRINGERS AT THE TOP AND BOTTOM OF THE RUN. ENCLOSED SPACES UNDER STAIRS SHALL COMPLY WITH SECTION R302.7.</li> <li>AT OPENINGS AROUND VENTS, PIPES, DUCTS, CABLES AND WIRES AT</li> </ol>
<u> </u>	<ul> <li>CEILINGS AND FLOOR LEVEL, WITH AN APPROVED MATERIAL TO RESIST THE FREE PASSAGE OF FLAME PRODUCTS OF COMBUSTION. THE MATERIAL FILLING THIS ANNULAR SPACE SHALL NOT BE REQUIRED TO MEET THE ASTM E136 REQUIREMENTS.</li> <li>5. FOR THE FIREBLOCKING OF CHIMNEYS AND FIREPLACES, SEE SECTION R1003.19.</li> <li>6. FIREBLOCKING OF CORNICES OF A TWO-FAMILY DWELLING IS</li> </ul>
	<ul> <li>A. SECTION R302.11.1 - FIREBLOCKING MATERIALS SHALL CONSIST OF FOLLOWING MATERIALS:</li> <li>1. TWO-INCH NOMINAL LUMBER</li> <li>2. TWO THICKNESSES OF ONE-INCH NOMINAL LUMBER WITH BROKEN LAP JOINTS</li> </ul>
	<ol> <li>THE THICKNESS OF 0.719-INCH WOOD STRUCTURAL PANELS WITH JOINTS BACKED BY 0.719-INCH WOOD STRUCTURAL PANELS</li> <li>THE THICKNESS OF 0.75-INCH PARTICLE BOARD WITH JOINTS BACKED BY 0.75-INCH PARTICLE BOARD</li> <li>ONE-HALF-INCH GYPSUM BOARD</li> <li>ONE-FOURTH-INCH CEMENT-BASED MILLBOARD</li> </ol>
	<ol> <li>BATTS OR BLANKETS OF MINERAL WOOL, MINERAL FIBER OR OTHER APPROVED MATERIAL INSTALLED IN SUCH A MANNER AS TO BE SECURELY RETAINED IN PLACE</li> <li>CELLULOSE INSULATION INSTALLED AS TESTED IN ACCORDANCE WITH ASTM E119 OR UL 263, FOR THE SPECIFIC APPLICATION.</li> <li>PER 2022 CRC SECION R317 SLEEPERS AND SILLS ON A CONCRETE OR MASONRY SLAB THAT IS IN DIRECT CONTACT WITH GROUND, UNLESS SEPARATED BY AN IMPERVIOUS MOISTURE BARRIER SHALL BE NATURALLY DURABLE OR PRESERVATIVE-TREATED WOOD IN ACCORDANCE WITH</li> </ol>
T )"	AWPA U1.
K	EYNOTES
B18 B38	ELECTRIC PANEL, 100AMP 240V. MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION, 3" MIN. ABOVE GRADE. ROOF EDGE/FASCIA. SEE DETAILS FOR FASCIA TYPE.
H05 H07 H12	BUILDING LINE BELOW. ATTIC VENT (LOW). PAINT OR FINISH TO MATCH ROOF COLOR, SEE VENTING CALCS."
H13 K05	ATTIC VENT (HIGH). PAINT OR FINISH TO MATCH ROOF COLOR, SEE VENTING CALCS." COMPOSITE ROOF SHINGLES, SEE MATERIALS LEGEND FOR MORE INFO.
<u>S.</u> L14 L20	LIGHT FIXTURE LOCATION, SEE DETAILS & ELECTRIC PLAN FOR MORE INFO. BUILDING SHALL HAVE ADDRESS NUMBERS PLACED IN A POSITION THAT IS PLAINLY LEGIBLE AND VISIBLE FROM STREET, MINIMUM OF
M01	4" HIGH WITH A MIN. STROKE OF 1/2" (EXACT LOCATION PER OWNER/APPLICANT). GUTTER. CONNECT TO DOWNSPOUT. PROVIDE MEANS TO
M02 S03 S04	DRAINAGE SYSTEM BY COUNTY.
T14 U11 U13	6x6 POST, REFER TO STRUCTURAL WOOD BEAM / HEADER, REFER TO STRUCTURAL.

-M01

-M02

-S04


COUNTY SAN LUIS OBISPO

HESE PLANS ARE PROVIDED BY THE COUNTY OF SAN UIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, T IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING NSPECTORS WILL NOT PROVIDE STEP BY STEP NSTRUCTIONS IN THE FIELD.


COUNTY OF SAN LUIS OBISPO ACCESSORY DWELLING UNIT SAN LUIS OBISPO, CA BUILDING NS ATIONS & I SECTION ELEV


DATE 09/28/2023 SHEET


A1-201




3 8:39:25 PM Vices/Decrimente/3272 04 SLO Cerimety ADH, CD, CENTBAL, 2022 (cess)








LNC - MODERN FROSTED BLACK PORCH OUTDER WALL SCONCE WITH MUSHROOM CLEAR SEEDED GLASS SHADE (VAFNYAHD13356V6) OR EQUAL
FRONT LIGHT OPTION A
LUTEC - BLACK SOLAR OUTDOOR BARN LIGHT SCONCE WITH DUSK TO DAWN (6940002012) OR EQUAL
FRONT SIDE
NOTE: ALL EXTERIOR LIGHTING MUST BE DARK SI
PER ZONING REGULATIONS SECTION 17.70.100.
41 TYP. LIGHT FIXTURES A911 SCALE: 1 1/2" = 1'-0"
FIBER CEMENT PAN FIBER CEMENT PAN FIBER CEMENT TRIN 0' - 3 1/2" DECO SHAP (WHE
42 DECORATIVE FAUX GABLE VE A1-201 A-911 SCALE: 3/4" = 1'-0"
SIDING PER ELEVATIONS PLYWOOD SHEATHING AND FRAMING PER STRUCTURAL TRIM WATER RESISTIVE BARRIER PER CRC 703, LAP FLASHING
FLASHING PER CRC R703
WOOD DOOR SYSTEM
WOOD DOOR PANEL
A911 A911 SCALE: 3" = 1'-0"
PLYWOOD SHEATHING AND FRAMING PER STRUCTURAL
TRIM
WATER RESISTIVE BARRIER PER CRC R703
SEALANT, BOTH SIDES OF
WOOD DOOR SYSTEM
WOOD DOOR PANEL
44 TYP. DOOR JAMB
A-911 A-911 SCALE: 3" = 1'-0"





#### SYMBOLS

<u>-</u> S-	DETAIL REFERENCE BUBBLE WITH LEADER	XX'-X"	INDICATES SHEAR WALL TYPE AND LENGTH, PER SHEAR WALL SCHEDULE
	DETAIL REFERENCE BUBBLE		INDICATES SPAN AND DIRECTION OF PREFABRICATED ROOF TRUSS (BY OTHERS)
<b>—</b>	FULL HEIGHT SECTION INDICATOR	XX	INDICATES SPAN AND DIRECTION OF ROOF RAFTER OR FLOOR JOIST WITH WEB STIFF
$\frown$		XX J	INDICATES SPAN AND DIRECTION OF ROOF RAFTER OR FLOOR JOIST
	ELEVATION OF WALL OR FRAME		INDICATES EXTENTS OF FRAMING OR OTHER STRUCTURAL ELEMENT
			INDICATES HEADER @ OPENING PER HEADER SCHEDULE
	NORTH ARROW		EARTH LAYER
			INDICATES SAND OR GROUT
BOT OF EL = (-X'-X'')	TOP/BOTTOM OF ELEVATIONS	ÓðÓð	INDICATES GRAVEL
$\longrightarrow$	SLOPE		STEEL IN CROSS SECTION
			INDICATES BEARING WALL
x x x	WELDED WIRE FABRIC (WWF LAYER)		SHADED AREA INDICATES CALIFORNIA FRAMING
	STEPPED SURFACE; FLOOR DEPRESSION		SHADED AREA INDICATES FOOTPRINT OF FLOOR ABOVE
			STEEL HSS TUBE COLUMN
	SLOPED SURFACE	$\bigcirc$	STEEL HSS OR PIPE COLUMN
v v	STEPPED FOOTING		WIDE FLANGE STEEL COLUMN
		$\square$	WOOD POST
8 8 8	BOTTOM STEPPED FOOTING		

A & B	ABOVE AND BELOW		
AB	ANCHOR BOLT	d	PENNY (NAIL OR BAR DIA)
ABV	ABOVE	DBL	DOUBLE
ACI	AMERICAN CONCRETE INSTITUTE	DEPT	DEPARTMENT
ADDL	ADDITIONAL	DET	DETAIL
ADJ	ADJACENT	DF	DOUGLAS FIR/LARCH
AESS	ARCHITECTURAL EXPOSED STRUCTURAL STEEL	DIA OR Ø	DIAMETER
AISC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION	DIAG	DIAGONAL
ALT	ALTERNATE	DIAPH	DIAPHRAGM
ALUM	ALUMINUM	DIM	DIMENSION
ANCH	ANCHOR	DN	DOWN
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE	DO	DO OVER
APA	ENGINEERED WOOD ASSOCIATION (FORMERLY THE	DWG	DRAWING
7.07.0	AMERICAN PLYWOOD ASSOCIATION)	DWL	DOWEL
APPVD	APPROVED	EA	EACH
APPROX	APPROXIMATE	EF	EACH FACE
ARCH	ARCHITECTURAL; ARCHITECT	EJ	EXPANSION JOINT
AWPA	AMERICAN WOOD PRESERVERS ASSOCIATION	EL	ELEVATION
AWS	AMERICAN WELDING SOCIETY	ELEC	ELECTRICAL
AITC	AMERICAN INSTITUTE OF TIMBER CONSTRUCTION	ELEV	ELEVATOR
ASTM	AMERICAN SOCIETY FOR TESTING MATERIALS	EMBED	EMBEDMENT
BLDG	BUILDING	ENIBLD	EDGE NAIL
BLK	BLOCK	ENGR	ENGINEER
BLKG	BLOCKING	ENGK	EQUAL OR EQUIVALENT
BM	BEAM	EQUIP	EQUIPMENT
BN	BOUNDARY NAIL	EQUIP	EACH SIDE
BOT OR I		ES	EACH WAY
BRC	BRACE		
BRG	BEARING	EXIST or (E)	EXISTING
BTWN	BETWEEN	EXT	
CANT	CANTILEVER	FDN FIN	Foundation Finish
CAM OR	C CAMBER	FJ	FLOOR JOIST
CC	CENTER TO CENTER	FLG	FLANGE
CG	CENTER OF GRAVITY	FLR	FLOOR
CIP	CAST-IN-PLACE	FN	FIELD NAIL
CJ	CONSTRUCTION JOINT; CONTROL JOINT	FOC	FACE OF CONCRETE
CL	CENTER LINE	FOM	FACE OF MASONARY
CLR	CLEARANCE; CLEAR	FOS	FACE OF STUD
CMU	CONCRETE MASONRY UNIT	FOW	FACE OF WALL
COL	COLUMN	FRMG	FRAMING
COMP	COMPRESSION	FT	FOOT; FEET
CONC	CONCRETE	FTA	FLOOR TIE ABOVE
CONN	CONNECTION; CONNECT	FTG	FOOTING
CONSTR	CONSTRUCTION	GA	GAUGE
CONT	CONTINUE; CONTINUOUS	GALV	GALVANIZED
		GB	GRADE BEAM
CONTR		GLB	GLUED LAMINATED BEAM
CJP	COMPLETE JOINT PENETRATION WELD	GR	GRADE
CTR	CENTER	GRND	GROUND
CTSK	COUNTERSINK; COUNTERSUNK	H or HORIZ	HORIZONTAL
CU FT	CUBIC FOOT		

#### WALL TYPES

	— (X)	INDICATES TOP PLATE SPLICE NAILING PER SCHEDU
5)		INDICATES SHEAR WALL STRAP / HOLDOWN TYPE
1	F1	INDICATES PAD FOOTING TYPE PER SCHEDULE
3 STIFFENER	Cl	INDICATES CONTINUOUS FOOTING TYPE PER SCHE
	↔	ANGLE BRACE
	(2L)	DOUBLE ANGLE BRACE
	•	DRAG STRUT CONNECTION
	<b>♦</b>	FULL HEIGHT STIFFENER CONNECTION
	•	MOMENT CONNECTION
	Ţ	MEMBER SPLICE
	(+3")	TOP OF STEEL ± ELEVATION
	[X]	NUMBER OF EVENLY SPACED SHEAR STUDS
	[X-Y-Z]	SPECIAL STUD SPACING SEE TYPICAL STEEL DETAILS
	<3/4>	BEAM CAMBER AT MID-SPAN

SPLICE NAILING PER SCHEDULE	
LL STRAP / HOLDOWN TYPE PER SCHEDULE	
ING TYPE PER SCHEDULE	ł
DUS FOOTING TYPE PER SCHEDULE	
	£=]
E	£
CTION	
RCONNECTION	
М	
TION	
PACED	₹ <i>∷</i> ∠ <i>∷</i> }
g see typical	
D-SPAN	
	A CONTRACTOR

<u> </u>	INDICATES PLYWOOD SIDE FOR SHEARWALL
ł	INDICATES BEARING WOOD WALL BELOW
ł	INDICATES BEARING WOOD WALL ABOVE
ł	INDICATES NON-BEARING WOOD WALL BELOW
ł	INDICATES NON-BEARING WOOD WALL ABOVE
ł	INDICATES EXISTING BEARING WOOD WALL
ł	INDICATES EXISTING NON-BEARING WOOD WALL
ł	INDICATES BEARING CMU WALL BELOW
}	INDICATES BEARING CMU WALL ABOVE
ŀ	INDICATES NON-BEARING CMU WALL BELOW
ł	INDICATES NON-BEARING CMU WALL ABOVE
$\left  \right\rangle$	INDICATES EXISTING BEARING CMU WALL
ł	INDICATES EXISTING NON-BEARING CMU WALL
ł	INDICATES BEARING CONCRETE WALL BELOW
}	INDICATES BEARING CONCRETE WALL ABOVE
	INDICATES NON-BEARING CONCRETE WALL BELOW
-	INDICATES NON-BEARING CONCRETE WALL ABOVE
-	INDICATES EXISTING BEARING CONCRETE WALL
	INDICATES EXISTING NON-BEARING CONCRETE WALL

#### ABBREVIATIONS

HDR	HEADER
HGR	HANGER
HP	HIGH POINT
HSH	HORIZONTALLY SLOTTED HOLES
HT	HEIGHT
ID	INSIDE DIAMETER
IF	INSIDE FACE
I-JST	1-JOILT
IN	INCH
INCL	INCLUDE
INFO	INFORMATION
INSP	INSPECTION
INT	INTERIOR
JST	JOIST
JT	JOINT
K	KIPS
KS	KING STUD
KP	KING POST
KSI	KIPS PER SQUARE INCH
LB(S) OR #	POUND(S)
LF	LINEAL FOOT
LIN	LINEAL; LINEAR
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
LP	LOW POINT
LSH	LONG SLOTTED HOLES
LSL	LAMINATED STRAND LUMBER
LT WT	LIGHTWEIGHT
LVL	LEVEL OR LAMINATED VENEER LUMBER
MAS	MASONRY
MATL	MATERIAL
MAX	MAXIMUM
MB	MACHINE BOLT
MECH	MECHANICAL
MFR	MANUFACTURER
MIN	MINIMUM; MINUTE
MISC	MISCELLANEOUS
(N)	NEW
Ν	NORTH
NO or #	NUMBER
NTS	NOT TO SCALE
OC	ON CENTER
OD	OUTSIDE DIAMETER
OF	OUTSIDE FACE
OH	OPPOSITE HAND
OPNG	OPENING
OPP	OPPOSITE
ORIG	ORIGINAL
OSB	ORIENTED STRAND BOARD

PA
PARA OR //
°C
PERP
 P
LOR PL.
201112
°LF
PLCS
203 21Y
PROP
Ϋ́
νW
рјр
PREFAB
PSF
PSI
PSL
PVMT
≠ v /v(1 #
* REF
REINF
REQD
REQU
R
Ø
SCHED
SECT
SEP
SHT
Shtg
SIM
SOG
SN
SPCG
SPECS
SQ
SS
SSL
STD
STGR
STIFF
STIRR
STL
STRUCT
SW
SYM

TB

POST ABOVE PARALLEL PRECAST; PIECE PERPENDICULAR PLYWOOD INDEX PLATE PROPERTY LINE PONDS PER LINEAL FOOT PLACES PLYWOOD PROPERTY PRESSURE TREATED PLATE WASHER PARTIAL JOINT PENETRATION WELD PREFABRICATED POUNDS PER SQUARE FOOT POUNDS PER SQUARE INCH PARALLEL STRAND LUMBER PAVEMENT POUND; NUMBER REFERENCE REINFORCE; REINFORCING REQUIRED ROOF **ROOF RAFTER** ROUND; DIAMETER SCHEDULE SECTION SEPARATION SHEET SHEATHING SIMILAR SLAB ON GRADE SHEAR NAIL SPACING SPECIFICATIONS SQUARE STAINLESS STEEL SHORT SLOTTED HOLES STANDARD STAGGER STIFFENERS STIRRUP STEEL STRUCTURAL SHEAR WALL Symmetrical TIE BEAM

#### SHEET INDEX

- S-101 SHEET INDEX, ABBREVIATIONS & SYMBOLS
  - GENERAL NOTES
  - GENERAL NOTES, SPECIAL INSPECTION & TESTS
  - FOUNDATION PLAN MID CENTURY MODERN ROOF FRAMING PLAN - MID CENTURY MODERN
- S-301 TYPICAL CONCRETE DETAILS S-311

S-102

S-103

S-201

S-202

S-401

S-402

S-403

S-404

S-421

S-422

- CONCRETE DETAILS S-312 CONCRETE DETAILS
  - TYPICAL WOOD DETAILS TYPICAL WOOD DETAILS TYPICAL WOOD DETAILS TYPICAL WOOD DETAILS
  - ROOF FRAMING DETAILS ROOF FRAMING DETAILS



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

Т&В	TOP AND BOTTOM
T & G	TONGUE & GROOVE
TO	TOP OF
TOC	TOP OF CURB; TOP OF CONCRETE
TOF	TOP OF FOOTING
TEMP	TEMPERATURE; TEMPORARY
THRU	THROUGH
THK	THICKNESS/THICK
THR	THREADED
TOP or T	TOP
TOS	TOP OF STEEL/TOP OF SLAB
TOW	TOP OF WALL
TS	TRIMMER STUD
TYP	TYPICAL
UNO	UNLESS NOTED OTHERWISE
UT	ULTRA-SONIC TEST
VERT	VERTICAL
VSH	VERTICAL SLOTTED HOLES
W/	WITH
W/O	WITHOUT
WO	WHERE OCCURS
WD	WOOD
WP	WORK POINT; WATERPROOF
WWF	WELDED WIRE FABRIC
STRUCTURAL STEEL S	HAPES
W	W SHAPE
С	AMERICAN STD CHANNEL SHAPE
MC	MISC CHANNEL SHAPE
L	ANGLE SHAPE
WT, ST, MT	STRUCT TEE SHAPE
PIPE	STANDARD PIPE SHAPE
PIPE-X	EXTRA STRONG PIPE SHAPE
PIPE-XX	DBL EXTRA STRONG PIPE SHAPE
HSS	HOLLOW STRUCTURAL SECTION

HSS

# SAN LUIS OBISPO DWELLING UNIT S OBISPO, CA COUNTY OF SA ACCESSORY E SAN LUIS O

SHEET INDEX, ABBREVIATIONS & SYMBOLS

DATE 09/28/2023 SHEET

S-101

	USE	SAWN LUMBER	SPECIES	GRADE			
	05E	2 X 4	D.F.	STANDARD OR BETTER	REFERENCE		
	MUDSILLS	2 X 6 AND LARGER	D.F.	PRESSURE TREATED	2022 CBC 2303.1.9		
		2 X	REDWOOD	PRESSURE TREATED			
		HORIZONTAL FRA	AMING LUMBE				
	ROOF JOISTS AND RAFTERS	2 x 2 X	D.F.	NO. 2 NO. 2			
	HEADERS AND BEAMS	4 X	D.F.	NO. 2	WCLIB &		
		4 X 4 AND SMALLER	D.F.	NO. 2	_WWPA		
	ANY OTHER HORIZONTAL	6 X 6 AND LARGER	D.F.	NO. 1			
		VERTICAL FRAM	1		1		
	TOP PLATES	2 X 2 X 4 & 3 X 4	D.F. D.F.	NO. 2 STUD	-		
	STUDS	2 X 6 & 2 X 8	D.F.	NO. 2	WCLIB & WWPA		
	POSTS	4 X 4 & 4 X 6 POSTS 6 X 6 & LARGER POSTS	D.F. D.F.	NO. 2 NO. 1			
		<u>ALL OTHER</u> FRA	MING LUMBEI	R			
	ALL OTHER FRAMING LUMBER, UNO	ALL SIZES	D.F.	STANDARD & BETTER	WCLIB & WWPA		
	ALL SOLE PLATES AND TOP PLAT MOISTURE CONTENT NOT EXCER STUD WALLS SHOWN ON PLANS <u>BELOW</u> THE FRAMING LEVEL, UN DRAWINGS, SEE PLANS AND AR MINIMUM FRAMING NAILING SH	EDING 15 PERCENT. S ARE NONBEARING PART NLESS NOTED OTHERWISE. CHITECTURAL DRAWINGS	TTIONS WALLS STUDS SHALL S. UNLESS OTH	S, BEARING WALLS OR SH BE SIZE AND SPACING A HERWISE NOTED.	iear walls S noted in the		
	NAILS. PREDRILL NAIL HOLES TO						
	UNLESS OTHERWISE NOTED, ALL WITH CONCRETE OR MASONRY W/ 0.229" X 3" X 3" PLATE WASH OF THE PLATES. THE BOLTS SHALL DRIVEN PINS AT 1/3 OF THE BOL BOLTS AT INTERIOR NON-SHEAR	' Shall be bolted to the ER (Galv) at 4'-0" o.c. L extend a minimum of T Spacing or 24" o.c. N	E CONCRETE BEGINNING A 7" INTO THE (	OR MASONRY WITH 5/8" AT 9" O.C. MAXIMUM FRC CONCRETE OR MASONR	Ø X 12" BOLTS DM EACH END Y. (POWDER		
	ALL LUMBER IN CONTACT WITH CONCRETE SHALL BE PRESSURE TREATED LUMBER WITH AWPA TREATMENT C2 USING EITHER ALKALINE QUAT (ACQ TYPE B AND D), COPPER AZOLE (CBA-A, CA-B), OR SODIUM BORATES (SBX). ANCHOR BOLTS, FASTENERS, AND METAL FRAMING CONNECTORS IN CONTACT WITH PRESSURE TREATED LUMBER SHALL BE HOT-DIPPED GALVANIZED TO A RATING OF G-185 PER ASTM A653.						
	PROVIDE 2 STUDS UNDER ALL 4 X 10 AND LARGER BEAMS OR HEADERS AT SPANS 6 FEET OR LONGER, UNLESS OTHERWISE NOTED. WHERE POSTS OR MULTIPLE STUDS UNDER BEAMS OR HEADERS ARE CALLED FOR ON DRAWINGS THOSE POSTS OR MULTIPLE STUDS SHALL BE CARRIED TO THE FOUNDATION/PODIUM LEVEL.						
	PROVIDE THE FOLLOWING BLOC 2" X FULL DEPTH SOLID BLOC 2" X FULL DEPTH SOLID BLOC	king between joists ov	/ER SUPPORT.				
•	Double Joists under Partitic Shown otherwise. Nail Doui				/ALL BELOW OR		
•	BRIDGING SHALL BE 2 X SOLID B ROOF JOISTS MORE THAN 10" FLOOR JOISTS MORE THAN 10	DEPTH, 8'-O" O.C. MAXIN	NUM, NOT MO				
•	JOIST HANGERS AND OTHER ME TYPE AS MANUFACTURED BY SIN OTHER MANUFACTURE WITH EQ	MPSON STRONG-TIE COM	IPANY, STOCI	KTON, CALIFORNIA. ACC			
•	FIRE STOPPING, BACKING FOR I FRAMING ARE NOT NECESSARIL				UCTURAL		
	HARDWARE AND C	CONNECTORS					
E	NERAL: ALL SPECIFIED FASTENERS AS SPEC		INDICATED O	N PLANS PROVIDE FASTE	NERS PER MFR'S		
	PROVED ICC-ESR REPORT OR PROI	duci liierature					
)L	<u>LDOWNS:</u> DO NOT OVER TIGHTEN NUTS O		ODS OR BOLT	s. tighten anchor ro	d nuts		
	ONE-THIRD TO ONE HALF TURN INSTALL ALL HOLDOWNS TIGHT BOLTS, EXTEND THE ANCHOR RC AND INSTALL THE HOLDOWN HI FOR HOLDOWNS THAT BOLT TO	TO END STUDS/POST, DO DD AT A 1:6 (HORIZ/VERT) GHER ON END STUD / PO	) USING A CC DST	OUPLER WITH EQUIVALEN	T ANCHOR ROD		
	THE SIDE OPPOSITE THE BRACKE						
	DOWN & COLLECTOR STRAPS: TIE DOWN AND COLLECTOR STI	RAPS SHALL BE INSTALLED	STRAIGHT AM	ND TRUE. DO NOT FOI D	BEND, KINK OR		
<u> </u>	OTHERWISE ALTER CONNECTOR INSTALL TIE DOWN STRAPS DIREC UNSHEATHED SIDE OF THE END S	R STRAPS CT TO POST IN LIEU OF ON					

#### CONCRETE

ALL CONCRETE CONSTRUCTION SHALL CONFORM WITH CHAPTER 19 OF THE CODE AND WITH THE PROVISIONS OF ACI 318-19.

CONCRETE MATERIALS SHALL BE IN ACCORDANCE WITH TH	e following standards:
MATERIAL	ASTM STAN
PORTLAND CEMENT (TYPE II) <sup>A</sup>	C150
CONCRETE AGGREGATES (HARDROCK)	C33
WATER <sup>8</sup>	C1602
COAL FLY ASH OR POZOLLAN (CLASS F)	C618
NATURAL OR MANUFACTURED SAND	C33
SLAG	C989

- A. FOR SOILS WITH HIGH CONCENTRATIONS OF SULFATES (EXPOSURES S2 OR S3 PER ACI 318-19 TABLE 19.3.2.1) PORTLAND CEMENT SHALL BE TYPE V. VERIFY WITH PROJECT GEOTECHNICAL REPORT.
- B. WATER SHOULD ONLY BE ADDED AT THE BATCH PLANT. IN NO CASE SHALL THE DESIGN WATER/ CEMENT RATIO BE EXCEEDED.

3. CONCRETE MIXES SHALL BE PROPORTIONED BASED ON SECTION 26.4.3 OF ACI 318-19, WHICH REFERENCES ACI 301-10 ARTICLE 4.2.3. MIX DESIGNS SHALL INCLUDE DOCUMENTATION OF MIX AVERAGE COMPRESSIVE STRENGTH THROUGH FIELD TEST DATA OR TRAIL MIXTURES IN ACCORDANCE WITH ACI 301-10 ARTICLE 4.2.3.4. SCHEDULE OF STRUCTURAL CONCRETE STRENGTHS AND LOCATIONS (UNO):

LOCATION IN STRUCTURE	MINIMUM STRENGTH (PSI)	DENSITY (PCF)	MAX SLUMP (IN±1)	MAX WATER/CEMENT RATIO	SLAG/ FLY ASH <sup>A</sup> (MAX)
CONCRETE FOUNDATIONS, GRADE BEAMS, TIE BEAMS	2,500	150	4	0.5	0.15
CONCRETE SLAB ON GRADE	2,500	150	4	0.45	0.15

A. AS MEASURED BY CEMENTITIOUS WEIGHT

- 4. DEPOSITING AND CONVEYING OF CONCRETE SHALL CONFORM TO SECTION 26.5 OF ACI 318-19 AND PROJECT SPECIFICATIONS.
- ALL CONCRETE SURFACES AGAINST WHICH NEW CONCRETE IS TO BE PLACED SHALL BE CLEANED AND ROUGHENED TO 1/4" AMPLITUDE.
- 6. ALL REINFORCING BARS, ANCHOR BOLTS AND OTHER CONCRETE INSERTS SHALL BE WELL SECURED IN POSITION PRIOR TO PLACING CONCRETE.
- 7. PROVIDE SLEEVES FOR PLUMBING AND ELECTRICAL OPENINGS IN CONCRETE BEFORE PLACING. DO NOT CUT ANY REINFORCING WHICH MAY CONFLICT. CORING IN CONCRETE IS NOT PERMITTED WITHOUT SEOR APPROVAL. NOTIFY THE SEOR IN ADVANCE OF CONDITIONS NOT SHOWN ON THE DRAWINGS. SEE THE DRAWINGS FOR ADDITIONAL RESTRICTIONS ON THE PLACEMENT OF OPENINGS IN SLABS AND WALLS.
- 8. PIPES EMBEDDED IN CONCRETE:
- A. CONCRETE a. PIPES LARGER THAN 1-1/2" DIAMETER SHALL NOTE BE EMBEDDED IN STRUCTURAL CONCRETE EXCEPT WHERE SPECIFICALLY APPROVED BY SEOR.
- b. NO CONDUITS SHALL BE PLACED IN CONCRETE FILL OVER METAL DECK.
- c. PIPES SHALL NOT DISPLACE OR INTERRUPT REINFORCING BARS. d. DO NOT STACK CONDUITS, SPACE EMBEDDED PIPES AND CONDUITS AT A MINIMUM OF 3
- DIAMETERS CLEAR FROM OTHER EMBEDDED PIPES/CONDUITS AND REBAR.

#### REINFORCING STEEL

- REINFORCING BARS SHALL CONFORM TO THE REQUIREMENTS OF CHAPTER 19 OF THE CODE AND WITH THE PROVISIONS OF ACI 318-19, ASTM A706, GRADE 60 UNO. ASTM A615 GR 60 STEEL MAY BE SUBSTITUTED FOR ASTM A706 GR60 STEEL PER ACI 318-19 SECTION 20.2.2.5 PROVIDED THE FOLLOWING CONDITIONS ARE MET:
- A. THE ACTUAL YIELD STRENGTH BASED ON MILL TESTS DOES NOT EXCEED THE SPECIFIED YIELD STRENGTH BY
- MORE THAN 18,000 PSI.
- B. THE RATIO OF THE ACTUAL ULTIMATE TENSILE STRESS TO THE ACTUAL YIELD STRENGTH IS NOT LESS THAN
- C. WHERE REINFORCEMENT COMPLYING WITH ASTM A615 IS TO BE WELDED, CHEMICAL TESTS SHALL BE PERFORMED TO DETERMINE WELDABILITY IN ACCORDANCE WITH SECTION 26.6.4 OF ACI 318-19.
- 2. BARS SHALL BE CLEAN OF RUST, GREASE, OR OTHER MATERIALS LIKELY TO IMPAIR BOND. ALL REINFORCING BAR BENDS SHALL BE MADE COLD.
- REINFORCING BAR LAP SPLICES SHALL BE MADE AS INDICATED ON THE DRAWINGS. LAP ALL HORIZONTAL BARS AT CORNERS AND INTERSECTIONS. STAGGER ALL SPLICES UNLESS NOTED OTHERWISE ON PLANS.
- A. MINIMUM LAP SPLICE LENGTH FOR REINFORCING STEEL BARS IN CONCRETE SHALL BE PER ACI 318-19 SECTION 25.5.2 AND THE REINFORCING SCHEDULE ON THE DRAWINGS.
- REINFORCING STEEL SHALL BE ACCURATELY PLACED AND ADEQUATELY SUPPORTED BEFORE THE CONCRETE IS PLACED AND SHALL BE SECURED AGAINST DISPLACEMENT DURING CONSTRUCTION WITHIN PERMITTED TOLERANCES. ADEQUATE SUPPORTS ARE ALSO NECESSARY TO KEEP THE REINFORCING STEEL AT THE PROPER DISTANCE FROM THE FORMS. USE WIRE BAR SUPPORTS, PRECAST CONCRETE SUPPORTS, SPACERS, BOLSTERS, REINFORCEMENT OR OTHER MEANS OF SUPPORT PER THE "CRSI MANUAL OF STANDARD PRACTICE", LATEST EDITION.
- ED ITEMS MAY BE CORRECTED PRIOR TO PLACEMENT OF OVERLYING GRIDS OR REINFORCING STEEL.
- CONCRETE PROTECTION FOR REINFORCEMENT

	FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR FORCEMENT IN CAST-IN-PLACE CONCRETE (NON-PRESTRESSED):	MINIMUM COVER, IN.
Α.	CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH	3
В.	CONCRETE EXPOSED TO EARTH OR WEATHER: NO.6 THROUGH NO. 18 BAR NO.5 BAR, W31 OR D31 WIRE & SMALLER	2 1 ½"
C.	CONCRETE NOT EXPOSED TO WEATHER OR IN CONTACT WITH GROUND: SLABS, WALLS, JOISTS: NO.14 AND NO.18 BARS NO.11 BAR & SMALLER BEAMS, COLUMNS: PRIMARY REINFORCEMENT TIES, STIRRUPS, SPIRALS	1 ½" 3⁄4" 1 ½"

#### WOOD (GENERAL)

- PRESERVATIVE TREATMENT:
- A. WOOD MEMBERS SHALL BE PRESERVATIVE TREATED IN ACCORDANCE WITH AITC 109-07, STANDARD FOR PRESERVATIVE TREATMENT, BASED ON THE SERVICE CONDITION PER THE USE CATEGORIES (UC#) SPECIFIED IN
- AWPA U1-06. a. UC1 - INTERIOR CONSTRUCTION, ABOVE GROUND, DRY - NO PRESERVATIVE TREATMENT REQUIRED
- b. UC2 INTERIOR CONSTRUCTION, ABOVE GROUND, WET PRESERVATIVE TREATMENT REQUIRED IF THE HUMIDITY OR MOISTURE CONDENSATION IS 20% OR GREATER.
- c. UC3 EXTERIOR CONSTRUCTION ABOVE GROUND PRESERVATIVE TREATMENT REQUIRED.
- FOR ALL TREATED WOOD MEMBERS, ALL CUTS, HOLES AND INJURIES SUCH AS ABRASIONS OR HOLES FROM REMOVAL OF NAILS AND SPIKES WHICH MAY PENETRATE THE TREATED ZONE SHALL BE FIELD TREATED IN ACCORDANCE WITH AWPA M4-06. THE FOLLOWING FIELD TREATMENTS SHALL BE USED: a. BORED HOLES: HOLES FOR CONNECTORS OR BOLTS MAY BE TREATED BY PUMPING COAL TAR ROOFING
- CEMENT MEETING ASTM D5643 INTO HOLES USING A GREASE GUN OR SIMILAR DEVICE b. EXTERIOR: COPPER NAPHTHENATE
- c. INTERIOR: INORGANIC BORON PRESERVATIVES LIMITED TO USE IN APPLICATIONS NOT IN CONTACT WITH GROUND AND CONTINUOUSLY PROTECTED FROM LIQUID WATER

#### FOUNDATION

2022 CBC TABLE 1806.2

5.	
STANDARD	
C150	
C33	
C1602	
C618	
C33	

2. SPREAD OR CONTINUOUS FOOTINGS: ALLOWABLE LATERAL RESISTANCE B ALLOWABLE BEARING PASSIVE RESISTANCE ELEMENT CAPACITY (PSF) A (PSF/FT BELOW COHESION (PSF) GRADE) <sup>E</sup> SHALLOW FOUNDATION 1,500 100 130

1. GEOTECHNICAL INFORMATION AND FOUNDATION DESIGN IS BASED ON THE FOLLOWING:

DESIGN LATERAL SOIL LOADS ARE IN ACCORDANCE WITH 2022 CBC TABLE 1610.1

ALLOWABLE FOUNDATION BEARING AND LATERAL PRESSURES ARE IN ACCORDANCE WITH

- NOTES A. THE ALLOWABLE CAPACITY MAY BE INCREASED BY ONE-THIRD WHEN CONSIDERING LOADS OF SHORT DURATION SUCH AS WIND OR SEISMIC FORCES.
- B. THE ALLOWABLE LATERAL RESISTANCE CAN BE TAKEN AS THE SUM OF THE FRICTIONAL RESISTANCE AND PASSIVE RESISTANCE.
- C. THE UPPER 0 FOOT OF SOIL NOT PROTECTED BY PAVEMENT SHALL BE NEGLECTED WHEN CALCULATING PASSIVE RESISTANCE.
- D. COMPACTED FILL SHOULD BE PREPARED AS FOLLOWS: A MIN OF 12" OF COMPACTED FILL SHALL BE PROVIDED, COMPACTED TO A MIN OF 90 PERCENT MODIFIED PROCTOR IN ACCORDANCE WITH ASTM D 1557 (2022 CBC 1804.6)
- 4. WHERE NOT SHOWN ON THE DRAWINGS, CONTRACTOR TO PROVIDE FOR DESIGN AND INSTALLATION OF ALL CRIBBING, SHEATHING AND SHORING REQUIRED AND SHALL BE SOLELY RESPONSIBLE FOR ALL EXCAVATION PROCEDURES INCLUDING LAGGING, SHORING, AND PROTECTION OF ADJACENT PROPERTY, STRUCTURES, STREETS, AND UTILITIES IN ACCORDANCE WITH ALL NATIONAL, STATE AND LOCAL SAFETY ORDINANCES.
- 5. CONTRACTOR TO PROVIDE FOR DE-WATERING OF EXCAVATIONS FROM SURFACE WATER, GROUND WATER AND/OR SEEPAGE.
- 6. EXCAVATION FOR FOOTINGS SHALL BE APPROVED BY THE INSPECTOR OR GEOTECHNICAL ENGINEER PRIOR TO PLACING CONCRETE AND REINFORCING.
- 7. ALL EXCAVATIONS SHALL BE PROPERLY BACKFILLED. DO NOT PLACE BACKFILL BEHIND RETAINING WALLS BEFORE CONCRETE OR GROUT HAS ATTAINED FULL DESIGN STRENGTH. CONTRACTOR SHALL PROVIDE FOR DESIGN, PERMITS AND INSTALLATION OF SUCH BRACING.
- 8. EXCAVATIONS SHALL BE CUT SQUARE AND SMOOTH, WITH LEVEL BOTTOMS.
- 9. FOOTING BACKFILL AND UTILITY TRENCH BACKFILL WITHIN BUILDING AREA SHALL BE MECHANICALLY COMPACTED IN LAYERS IN ACCORDANCE WITH THE GEOTECHNICAL INVESTIGATION REPORT AND APPROVED BY THE GEOTECHNICAL ENGINEER. FLOODING WILL NOT BE PERMITTED. ALL FILLS USED TO SUPPORT FOUNDATIONS SHALL BE INSPECTED BY THE GEOTECHNICAL ENGINEER REPRESENTATIVE PER SECTION 1705.6 OF THE CODE.
- 10. ALL ABANDONED FOOTINGS, UTILITIES, ETC. SHALL BE REMOVED. NEW FOOTINGS MUST EXTEND INTO UNDISTURBED SOILS.
- 11. THIS PLAN IS INTENDED FOR FLAT LOTS, WITHOUT HIGHLY EXPANSIVE OR LIQUEFIABLE SOILS. IF THE PROJECT SITE IS DETERMINED TO HAVE ANY OF THESE QUALITIES, AS DETERMINED BY THE BUILDING OFFICIAL, THESE PRE APPROVED ADU FOUNDATION PLANS AND DETAILS ARE NOT APPLICABLE.

EXISTING CONDITIONS

- ALL INFORMATION SHOWN ON THE PLANS RELATIVE TO EXISTING CONDITIONS IS GIVEN AS THE BEST PRESENT KNOWLEDGE FROM PLANS SUPPLIED BY THE OWNER, BUT WITHOUT GUARANTEE OF ACCURACY.
- WHERE ACTUAL CONDITIONS ARE NOT IN ACCORDANCE WITH THE INFORMATION PRESENTED, THE ARCHITECT AND/OR STRUCTURAL ENGINEER SHALL BE NOTIFIED IMMEDIATELY. NO MODIFICATIONS OF THE PLANS FOR NEW CONSTRUCTION SHALL BE MADE WITHOUT THE WRITTEN APPROVAL OF THE ARCHITECT.

EXISTING UNDERGROUND UTILITIES

- 1. THE ARCHITECT AND ENGINEERS ARE NOT RESPONSIBLE FOR THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES WHETHER OR NOT SHOWN ON THE DRAWINGS. DRAWINGS, IF ANY, IS APPROXIMATE. THE CONTRACTOR SHALL EXERCISE EXTREME CAUTION IN EXCAVATING AND TRENCHING ON THE SITE. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ARCHITECT AND/OR STRUCTURAL ENGINEER SHOULD ANY SUCH UNIDENTIFIED CONDITIONS BE DISCOVERED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES WHICH MAY RESULT FROM HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ALL EXISTING UNDERGROUND UTILITIES.
- 3. AN UNDERGROUND SERVICE ALERT INQUIRY IDENTIFICATION NUMBER MUST BE OBTAINED AT LEAST TWO WORKING DAYS BEFORE STARTING WORK WITH THIS PERMIT. A. FOR PROJECTS IN SOUTHERN CALIFORNIA TELEPHONE NO. 1-800-422-4133.

B. FOR PROJECTS IN NORTHERN CALIFORNIA TELEPHONE NO. 1-800-227-2600.

DEMOLITION

- ALL DEMOLITION SHALL BE CARRIED ON IN SUCH A WAY AS NOT TO DAMAGE EXISTING ELEMENTS, WHICH ARE TO REMAIN IN THE FINISHED STRUCTURE.
- 2. ALL ELEMENTS OF THE STRUCTURE, WHICH ARE TO REMAIN, AND WHICH ARE DAMAGED DURING DEMOLITION WORK SHALL BE REPLACED AT NO ADDITIONAL COST. EXISTING ELEMENTS SHALL BE PROTECTED TO THE FULLEST EXTENT POSSIBLE, IN ORDER TO MITIGATE DAMAGE.
- 3. CONTRACTOR IS REPONSIBLE FOR REMOVAL AND REPLACEMENT OF ALL EXISTING ELEMENTS THAT ARE NECESSARY FOR THE INSTALLATION OF ALL NEW WORK.
- 4. WHERE EXISTING PARTITION WALLS ARE TO BE DEMOLISHED, CONTRACTOR SHALL VERIFY WALLS ARE NON-BEARING PRIOR TO DEMOLITION. IF WALLS ARE FOUND TO BE BEARING, CONTRACTOR SHALL NOTIFY ARCHITECT IMMEDIATELY

DESIGN INFORMATION

FLOOR LIVE LOADS: (2022 CBC SECTION 1603.1.1)					
FLOOR	LIVE LO	ADS			
OCCUPANCY OR USE		UNIFORM (PSF)	CON (LBS		REFERENCE
RESIDENTIAL ONE- AND TWO- FAMILY DWELLINGS UNINHABITABLE ATTICS WITHOUT STORAGE UNINHABITABLE ATTICS WITH STORAGE HABITABLE ATTICS AND SLEEPING AREAS ALL OTHER AREAS		10 20 30 <b>40</b>			022 CBC TABLE 607.1
ROOF LIVE LOADS (2022 CBC SECTION 1603.1.2)				Ĩ	
ROOFL	IVE LOA	ADS .			
OCCUPANCY OR USE		UNIFORM (PSF)	CON (LBS		REFERENCE
ROOF ORDINARY FLAT, PITCHED AND CURVED ROOFS (THAT ARE NOT OCCUPIABLE)		20			022 CBC TABLE 607.1
ROOF SNOW LOADS (2022 CBC SECTION 1603.1.3):					
SNOW D	esign e	ATA			
PARAMETER		VALUE			REFERENCE
GROUND SNOW LOAD Pg = 0		PSF		ASCE 7-16 7.2	
WIND DESIGN DATA (2022 CBC SECTION 1603.1.4) :					
WIND DI	esign d	ATA			
PARAMETER		VALUE			REFERENCE
ULTIMATE DESIGN WIND SPEED (3-SEC GUST)	E DESIGN WIND SPEED (3-SEC GUST) V <sub>ULT</sub> = 92 MPH 2022 CBC FIG. 1609			CBC FIG. 1609.3	

COI	MPONENTS & C	CLADDING WIN	d pressures (psi	=)
		COMP	ONENT TRIBUTARY ARE	A (SQ FT)
LUCAIIC	LOCATION		100	500
	ZONE 1	-31.0	-16.0	-16.0
	ZONE 2e	-31.0	-16.0	-16.0
	ZONE 2n	-34.1	-21.6	-18.4
ROOF	ZONE 2r	-31.0	-16.0	-16.0
	ZONE 3e	-41.9	-26.3	-18.4
	ZONE 3r	-34.1	-21.6	-18.4
	ALL ZONES	16.9	16.0	16.0
	ZONE 1	-43.5	-27.8	-27.8
	ZONE 2e	-43.5	-27.8	-27.8
OVERHANG	ZONE 2n	-46.6	-34.1	-31.0
OVERHANG	ZONE 2r	-43.5	-27.8	-27.8
	ZONE 3e	-54.4	-38.8	-31.0
	ZONE 3r	-46.6	-34.1	-31.0
	ZONE 4	-20.0	-17.4	-16.0
WALL	ZONE 5	-24.7	-19.2	-16.0
	POSITIVE	18.4	16.0	16.0

ASD = 72 MPH

GCpi = ± 0.18

2022 CBC 1609.3.1

2022 CBC 1609.4.3

ASCE 7-16 TABLE 26.13-1

5. EARTHQUAKE DESIGN DATA (2022 CBC SECTION 1603.1.5):

NOMINAL DESIGN WIND SPEED (3-SEC GUST)

EXPOSURE CATEGORY

NTERNAL PRESSURE COEFFICIENT:

SITE AND OCCUPANCY PARAMETERS					
	VA	LUE			
PARAMETER	OPT 1	OPT 2	REFERENCE		
RISK CATEGORY	11	11	2022 CBC TABLE 1604.5		
SEISMIC IMPORTANCE FACTOR	I = 1.0	I = 1.0	ASCE 7-16 TABLE 1.5-2		
	Ss = 1.25g	Ss = 2.47 g			
MAPPED SPECTRAL RESPONSE ACCELERATIONS:	S 1 = 0.434 g	Sı = 1.05 g	2022 CBC 1613.2.1		
SITE CLASS	D (DF)	D (DF)	2022 CBC 1613.2.2		
SPECTRAL RESPONSE COEFFICIENTS:	S DS = 1.00 g	S DS = 1.97 g	2022 CBC 1613.2.4		
ISI LOTIAL KLSI ONGE COLITICIENTS.	S D1 = 0.54 g	S D1 = 1.19 g	2022 CDC 1013.2.4		

DII		TEDS		
BU	ILDING PARAME	IEK3		
PARAMFTER	VA	REFERENCE		
FARAMLIER	OPT 1 OPT 2			
SEISMIC DESIGN CATEGORY	SDC = D SDC = D 2		2022 CBC 1613.2.5	
BASIC SEISMIC FORCE RESISTING SYSTEM	light frame (wooi with wood struct for shear resistan			
RESPONSE MODIFICATION FACTOR	$R = 6 \frac{1}{2}$		ASCE 7-16 TABLE 12.2-1	
SYSTEM OVERSTRENGTH FACTOR	Ωo = 3			
DEFLECTION AMPLIFICATION FACTOR	Cd = 4			
DESIGN BASE SHEAR	V = 7.7 k V = 15.9 k		ASCE 7-16 12.8.1	
SEISMIC RESPONSE COEFFICIENTS	Cs = 0.154	Cs = 0.304	ASCE 7-16 12.8.1.1	
ANALYSIS PROCEDURE USED	EQUIVALENT LATERAL FORCE		ASCE 7-16 12.8	

6. GEOTECHNICAL INFORMATION (2022 CBC SECTION 1603.1.6): REFER TO FOUNDATION GENERAL NOTES

ARCHITECT

- 1. ALL WORK SHALL CONFORM TO THE MINIMUM STANDARDS OF THE FOLLOWING CODES AND STANDARDS:
- A. 2022 CALIFORNIA BUILDING CODE, PART 2, VOLUME 2 OF 2, AND TITLE 24 C.C.R. 2022 EDITION AND LATEST REVISIONS (INCLUDING SUPPLEMENTS AND ERRATA) HEREIN REFERRED TO AS "THE CODE". B. ANY OTHER REGULATING AGENCIES WHICH HAVE AUTHORITY OVER ANY PORTION OF THE WORK, INCLUDING THE STATE OF CALIFORNIA DIVISION OF OCCUPATIONAL SAFETY AND HEALTH (CAL/OSHA). C. CODES & STANDARDS REFERENCED IN THE CODE OR LISTED IN THESE NOTES AND SPECIFICATIONS. ALL DRAWINGS ARE CONSIDERED TO BE A PART OF THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REVIEW AND COORDINATION OF ALL DRAWINGS AND SPECIFICATIONS PRIOR TO THE START OF CONSTRUCTION. ANY DISCREPANCIES THAT OCCUR SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO START OF CONSTRUCTION SO THAT A CLARIFICATION CAN BE ISSUED. ANY WORK PERFORMED IN CONFLICT WITH THE CONTRACT DOCUMENTS OR ANY CODE REQUIREMENTS SHALL BE CORRECTED BY THE CONTRACTOR AT THEIR OWN EXPENSE AND AT NO EXPENSE TO THE OWNER OR
- NOTES AND DETAILS ON DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE GIVEN, CONSTRUCTION SHALL BE AS SHOWN FOR SIMILAR WORK.
- 4. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO STARTING CONSTRUCTION. THE ARCHITECT SHALL BE NOTIFIED OF ANY DISCREPANCIES OR INCONSISTENCIES. IN NO INSTANCE SHALL DIMENSIONS BE SCALED FROM THE DRAWINGS.
- 5. SEE ARCHITECTURAL DRAWINGS FOR THE FOLLOWING:
- A. SIZE AND LOCATION OF ALL DOOR AND WINDOW OPENINGS, EXCEPT AS NOTED
- B. SIZE AND LOCATION OF ALL INTERIOR AND EXTERIOR NON-BEARING PARTITIONS UNLESS NOTED AND/OR DETAILED ON THE STRUCTURAL DRAWINGS
- C. SIZE AND LOCATION OF ALL CONCRETE CURBS, EQUIPMENT PADS, PITS, FLOOR DRAINS, SLOPES, DEPRESSED AREAS, CHANGE IN LEVEL, CHAMFERS, GROOVES, INSERTS, ETC
- D. SIZE AND LOCATION OF ALL FLOOR AND ROOF OPENINGS EXCEPT AS SHOWN
- E. FLOOR AND ROOF FINISHES
- F. MISCELLANEOUS DRAINAGE AND WATERPROOFING
- G. ALL FIREPROOFING REQUIREMENTS INCLUDING FIREPROOFING OF STRUCTURAL STEEL
- H. DIMENSIONS NOT SHOWN ON STRUCTURAL DRAWINGS
- 6. SEE MECHANICAL, PLUMBING AND ELECTRICAL DRAWINGS FOR THE FOLLOWING:
- A. PIPE RUNS, SLEEVES, HANGERS, TRENCHES, WALL AND SLAB OPENINGS, ETC., EXCEPT AS SHOWN OR NOTED.
- B. ELECTRICAL CONDUIT RUNS, BOXES, OUTLETS IN WALLS AND SLABS.
- C. CONCRETE INSERTS FOR ELECTRICAL, MECHANICAL OR PLUMBING FIXTURES.
- D. SIZE AND LOCATION OF MACHINE OR EQUIPMENT BASES, ANCHOR BOLTS FOR MOTOR MOUNTS.
- SEE CIVIL DRAWINGS FOR THE FOLLOWING: A. HEIGHT AND/OR ELEVATION OF:
  - a. FINISHED SURFACE
  - b. TOP OF WALL
  - c. TOP OF GRADE
  - d. FINISHED GRADE
  - e. SLOPE
- B. SITE CONCRETE WALKWAYS, CURBS & PAVING
- 8. THE CONTRACT STRUCTURAL DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE STRUCTURE DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE. BU NOT BE LIMITED TO, BRACING, SHORING FOR LOADS DUE TO CONSTRUCTION EQUIPMENT ETC. THE CONTRACTOR IS RESPONSIBLE FOR PROVISION OF TEMPORARY SHORING AND OTHER CONSTRUCTION AIDS, INCLUDING ALL ENGINEERING OF SUCH SYSTEMS, FOR TEMPORARY SUPPORT OF NEW AND/OR EXISTING STRUCTURAL ELEMENTS AS REQUIRED FOR ERECTION AND OTHER CONTRACTOR'S MEANS AND METHODS OF CONSTRUCTION (UNO). OBSERVATION VISITS TO THE SITE BY THE STRUCTURAL ENGINEER SHALL NOT INCLUDE INSPECTION OF THE ABOVE ITEMS OR CONCERN CONSTRUCTION MEANS AND METHODS OR CONSTRUCTION SAFFTY.
- 9. BACKFILL SHALL NOT BE PLACED BEHIND EXTERIOR AND INTERIOR RETAINING WALLS UNTIL THE CONCRETE / CMU HAS ACHIEVED FULL DESIGN STRENGTH. FOR BRACED WALLS SUPPORTED BY STRUCTURAL DIAPHRAGMS. BACKFILL SHALL NOT BE PLACED BEHIND THE WALL UNTIL THE DIAPHRAGM HAS BEEN INSTALLED , AND FOR CONCRETE DIAPHRAGMS, HAS ACHIEVED FULL DESIGN STRENGTH.
- 10. THE CONTRACT STRUCTURAL DRAWINGS SHOW THE BUILDING IN ITS FINAL INTENDED POSITION. CONTRACTOR SHALL MAKE PROVISIONS IN THE LAYOUT OF THE BUILDING TO TAKE INTO ACCOUNTS SHRINKAGE, CREEP, SHORTENING, ETC..
- 11. OPENINGS, POCKETS, ETC., LARGER THAN 6" SHALL NOT BE PLACED IN CONCRETE SLABS, DECKS, WALLS, UNLESS SPECIALLY DETAILED ON THE STRUCTURAL DRAWINGS. NOTIFY THE STRUCTURAL ENGINEER WHEN DRAWINGS BY OTHERS SHOW OPENINGS, POCKETS, ETC., LARGER THAN 6" NOT SHOWN ON THE STRUCTURAL DRAWINGS, BUT WHICH ARE LOCATED IN STRUCTURAL MEMBERS.
- 12. ASTM SPECIFICATIONS ON THE DRAWINGS SHALL BE THE VERSION REFERENCED IN CHAPTER 35 OF THE CODE OR AS REFERENCED IN THE APPLICABLE DESIGN STANDARD.
- 13. CONTRACTOR SHALL INVESTIGATE SITE DURING CLEARING AND EARTHWORK OPERATIONS FOR FILLED EXCAVATIONS OR BURIED STRUCTURES, SUCH AS CESSPOOLS, CISTERNS, FOUNDATIONS, ETC. IF ANY SUCH STRUCTURES ARE FOUND, THE STRUCTURAL ENGINEER AND GEOTECHNICAL ENGINEER SHALL BE NOTIFIED IMMEDIATELY.
- 14. CONSTRUCTION MATERIAL SHALL BE SPREAD OUT IF PLACED ON FRAMED ROOF OR FLOOR. LOAD SHALL NOT EXCEED THE DESIGN LIVE LOAD PER SQUARE FOOT. THE CONTRACTOR TO DESIGN AND PROVIDE ADEQUATE SHORING AND/OR BRACING WHERE STRUCTURE HAS NOT ATTAINED DESIGN STRENGTH.
- 15. CONTRACTOR SHALL COORDINATE SHORING WITH DRAWINGS OF RECORD TO INSURE PROVISIONS FOR POCKETS, BLOCKOUTS, OFFSETS, STEPPED FOOTINGS AND ANY OTHER ITEMS AFFECTED BY THE SHORING
- 16. AN UNDERGROUND SERVICE ALERT INQUIRY IDENTIFICATION NUMBER MUST BE OBTAINED AT LEAST TWO WORKING DAYS BEFORE STARTING WORK WITH THIS PERMIT. A. FOR PROJECTS IN SOUTHERN CALIFORNIA TELEPHONE NO. 1-800-422-4133.
- B. FOR PROJECTS IN NORTHERN CALIFORNIA TELEPHONE NO. 1-800-227-2600. 17. EDGE OF SLAB DIMENSIONS TO BE COORDINATED AND VERIFIED BY THE GENERAL CONTRACTOR PRIOR TO

#### DIMENSIONS

FABRICATION.

- 1. DIMENSIONS SHALL BE DEFINED TO INCLUDE BOTH HORIZONTAL DIMENSIONS AND VERTICAL DIMENSIONS (ELEVATIONS).
- 2. WRITTEN DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALED DRAWINGS.
- 3. SEE ARCHITECTURAL DRAWINGS FOR DIMENSION NOT NOTED ON STRUCTURAL DRAWINGS.
- 4. SEE ARCHITECTURAL AND/OR CIVIL DRAWINGS FOR FINISH FLOOR ELEVATIONS.
- 5. SEE ARCHITECTURAL DRAWINGS FOR ALL TOP OF SHEATHING AND/OR ROOF ELEVATIONS.
- 6. THE CONTRACTOR SHALL REVIEW AND VERIFY ALL DIMENSIONS PRIOR TO STARTING CONSTRUCTION. THE ARCHITECT SHALL BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCIES OR INCONSISTENCIES.



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU has been issued and final inspection COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

> $\overline{O}$ ELLIN PO, CA ≺ <sub>S</sub> RY LUIS 0 Ō Ζ

⊽∢

Ш

0 Z

R

Ш

ZШ

( )

DATE 09/28/2023 SHEET

#### REQUIRED VERIFICATION AND INSPECTIONS

CBC REFERENCE

1705.5.1

2306.2

1705.13.2

1705.13.2

1705.13.2

1705.5.2

CBC REFERENCE

WC CODE CHAPTER 17 AND REFERENC	OD ED 2018	NDS AI	VD AWC	C SDPV	NS-201	5
SPECIAL INSPECTION OR TEST				CONTINUOUS	PERIODIC	
1. HIGH LOAD DIAPHRAGM WOOD STRUCTURAL PANELS FOLLOWING: - GRADE - THICKNESS - NOMINAL SIZE OF FRAMING MEMBERS AT ADJOINING - NAIL OR STAPLE DIAMETER AND LENGTH - NUMBER OF FASTENER LINES - SPACING BETWEEN FASTENERS IN EACH LINE - SPACING BETWEEN FASTENERS AT EDGE MARGINS					x	
2. FIELD GLUING OPERATIONS OF ELEMENTS OF THE SEISM SYSTEM.	IC FORCI	e resist	ING	x		
3. WOOD LATERAL FORCE-RESISTING SYSTEM WITH FASTEN SHEATHING LESS THAN OR EQUAL TO 4" OC. - WOOD SHEAR WALLS - WOOD DIPHRAGMS - DRAG STRUTS - SHEAR PANELS - HOLD-DOWNS	IER SPAC	ING OI	THE		x	
<ul> <li>4. WOOD LATERAL FORCE-RESISTING SYSTEM WITH FASTEN SHEATHING GREATER THAN 4" OC (NOT REQUIRED)</li> <li>WOOD SHEAR WALLS</li> <li>WOOD DIAPHRAGMS</li> <li>DRAG STRUTS</li> <li>SHEAR PANELS</li> <li>HOLD-DOWNS</li> </ul>	ier spac	ING OI	F THE			
<ol> <li>METAL PLATE CONNECTED WOOD TRUSSES SPANNING         <ul> <li>TEMPORARY INSTALLATION RESTRAINT/BRACING</li> <li>PERMANENT INDIVIDUAL TRUSS MEMBER RESTRAINT/BF IN ACCORDANCE WITH APPROVED TRUSS SUBMITTAL</li> </ul> </li> </ol>	ACING		ATER		х	
<b>SO</b> CODE TAI	<b>ILS</b> BLE 1705.	.6				
SPECIAL INSPECTION C	OR TEST					
1. VERIFY MATERIALS BELOW SHALLOW FOUNDATIONS AR BEARING CAPACITY	E ADEQU	ATE TO	ACHIE	VE THE	DESIG	N
2. VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPT MATERIAL.				PROPI	ER	
<ol> <li>PERFORM CLASSIFICATION AND TESTING OF COMPACT</li> <li>VERIFY USE OF PROPER MATERIALS, DENSITIES, AND LIFT AND COMPACTION OF COMPACTED FILL.</li> <li>PRIOR TO PLACEMENT OF COMPACTED FILL, INSPECT S BEEN PREPARED PROPERLY.</li> </ol>	THICKNE	SSES DI	JRING F			
		-	ON			
CODE TAI	SILE 1705.	PERIODIC		FEREN( TANDA	-	
	<u> </u>				0.	+

	0		
3. INSPECT ANCHORS CAST IN CONCRETE		Х	ACI 318: 26.7
<ul> <li>4. INSPECT ANCHORS POST-INSTALLED IN HARDENED CONCRETE MEMBERS <sup>(b)</sup></li> <li>(a) ADHESIVE ANCHORS INSTALLED IN HORIZONTALLY OR UPWARDLY INCLINED ORIENTATIONS TO RESIST SUSTAINED TENSION LOADS</li> <li>(b) MECHANICAL ANCHORS AND ADHESIVE ANCHORS NOT DEFINED IN 4.a.</li> </ul>	Х	Х	ACI 318: 26.7.1 ACI 318: 26.7.1

STATEN	MENT OF SPECIAL INSPECTIONS
THIS SECTI	MENT OF SPECIAL INSPECTIONS HAS BEEN PREPARED PURSUANT TO SECTION 1704.3 OF THE CODE ON DETAILS BOTH REQUIRED SPECIAL INSPECTIONS AND TESTS INCLUDING TESTING PER SECTION HE CODE. THE FOLLOWING SHALL BE OBSERVED DURING THEIR IMPLEMENTATION:
A. GEN	IERAL: a. STRUCTURAL VERIFICATIONS, INSPECTIONS AND TESTS SHALL BE PERFORMED IN ACCORDANC WITH CHAPTER 17 OF THE CODE AND/OR THE APPLICABLE REFERENCE STANDARD.
	NER REQUIREMENTS: a. THE OWNER OR OWNER'S AGENT SHALL EMPLOY ONE OR MORE APPROVED AGENCIES TO PERFORM INSPECTIONS DURING CONSTRUCTION ON THE TYPES OF WORK LISTED IN SECTION 1705 OF THE CODE AND IN THIS STATEMENT OF INSPECTIONS.
	CIAL INSPECTOR QUALIFICATIONS: a. THE SPECIAL INSPECTIONS SHALL PROVIDE WRITTEN DOCUMENTATION TO THE BUILDING OFFICIAL DEMONSTRATING HIS OR HER COMPETENCE AND RELEVANT EXPERIENCE OR TRAINING. THE EXPERIENCE OR TRAINING SHALL BE CONSIDERED RELEVANT WHEN THE DOCUMENTED EXPERIENCE OR TRAINING IS RELATED IN COMPLEXITY TO THE SAME TYPE OF SPECIAL INSPECTION ACTIVITIES FOR PROJECTS OF SIMILAR COMPLEXITY AND MATERIAL QUANTITIES.
	NTRACTOR REQUIREMENTS: a. SPECIAL INSPECTION IS IN ADDITION TO THE CONTRACTOR'S QUALITY CONTROL INSPECTIONS AND TESTING. THE CONTRACTOR'S QUALITY CONTROL INSPECTIONS AND TESTING SHALL OCCUR PRIOR TO SPECIAL INPECTION AND REPORTS SHALL BE AVAILABLE TO THE SPECIAL INSPECTOR.
	b. THE CONTRACTOR SHALL ENSURE THAT THE WORK FOR WHICH SPECIAL INSPECTION IS REQUIR REMAINS ACCESSIBLE AND EXPOSED FOR SPECIAL INSPECTION PURPOSES UNTIL COMPLETION OF THE REQUIRED SPECIAL INSPECTION.
	C. ANY CONTRACTOR RESPONSIBLE FOR THE CONSTRUCTION OF THE MAIN WIND OR SEISMIC FORCE RESISTING SYSTEM SHALL SUBMIT A WRITTEN STATEMENT OF RESPONSIBILITY TO THE BUILDING OFFICIAL AND OWNER PRIOR TO COMMENCEMENT OF WORK ON THE SYSTEM OR COMPONENT. THE STATEMENT OF RESPONSBILITY SHALL CONTAIN ACKNOWLEDGEMENT OF AWARENESS OF THE SPECIAL INSPECTION REQUIREMENTS CONTAINED IN THE STATEMENT OF SPECIAL INSPECTIONS.
	CIAL INSPECTOR REPORT REQUIREMENTS: a. THE SPECIAL INSPECTOR SHALL KEEP RECORD OF INSPECTIONS
	<ul> <li>THE SPECIAL INPSECTOR SHALL FURNISH INSPECTION REPORTS TO THE BUILDING OFFICIAL AND TO THE ARCHITECT AND STRUCTURAL ENGINEER OF RECORD.</li> </ul>
	C. REPORTS SHALL INDICATE THAT WORK INSPECTED WAS OR WAS NOT COMPLETED IN CONFORMANCE TO APPROVED CONSTRUCTION DOCUMENTS.
	d. DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION.
	e. IF NOT CORRECTED DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE BUILDING OFFICIAL AND THE ARCHITECT AND STRUCTURAL ENGINEER OF RECORD PRIOR TO THE COMPLETION OF THAT PHASE OF WORK.
	f. A FINAL REPORT DOCUMENTING SPECIAL INSPECTIONS AND CORRECTION OF ANY DISCREPANCIES NOTED SHALL BE SUBMITTED TO THE BUILDING OFFICIAL.
SHOP	
1. SHOP FAB EXCEPTIO FABRICAT SECTION A. STEE	RICATION REQUIRES SPECIAL INSPECTION IN ACCORDANCE WITH CODE SECTION 1704.2.5. N: SHOP SPECIAL INSPECTIONS ARE NOT REQUIRED WHEN WORK IS DONE ON THE PREMISES OF OR REGISTERED AND APPROVED TO PERFORM SUCH WORK IN ACCORDANCE WITH CODE 1704.2.5.1. THE FOLLOWING ACCREDITATIONS MEET THE REQUIREMENTS OF THIS EXCEPTION: EL BUILDINGS (OR STEEL ELEMENTS IN OTHER BUILDINGS) a. FOR GENERAL STEEL BUILDINGS OR ELEMENTS THE FABRICATOR SHALL BE AN AISC CERTIFIED FABRICATOR IN ACCORDANCE WITH THE AISC CERTIFICATION PROGRAM FOR STRUCTURAL STEEL FABRICATORS (AISC 201-06).
	b. OTHER ACCREDITATION DEEMED ACCEPTABLE BY THE AUTHORITY HAVING JURISDICTION.
	c. IF FABRICATION IS PERFORMED BY AN APPROVED FABRICATOR A CERTIFICATE OF COMPLIAN MUST BE PROVIDED TO THE BUILDING INSPECTOR THAT THE MATERIALS SUPPLIED AND WORK PERFORMED BY THE FABRICATOR ARE IN CONFORMANCE WITH THE CONSTRUCTION DOCUMENTS

DOCUMENTS. d. IF FABRICATION IS NOT PERFORMED BY AN APPROVED FABRICATOR WELDING INSPECTION REPORTS MUST BE SUBMITTED TO THE BUILDING OFFICIAL BY AN APPROVED TESTING AGENCY. e.a. NONDESTRUCTIVE TESTING (NDT) MAY BE PERFORMED BY THE FABRICATOR, HOWEVER

#### B. WOOD BUILDINGS

a. WOOD STRUCTURAL PANELS (SHEATHING) SHALL BE IDENTIFIED BY THE APA TRADEMARK.

THE QA AGENCY SHALL REVIEW THE FABRICATOR'S NDT REPORTS.

	PRE-FAB	RICATED WOOD TRUSS NOTES
1.		OF METAL PLATE CONNECTED WOOD TRUSSES SHALL BE IN ACCORDANCE WITH THE FOLLOWING S AND STANDARDS:
		THE GOVERNING CODE LISTED IN THE PROJECT GENERAL NOTES
	b.	MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES (ASCE 7-16)
	C.	NATIONAL DESIGN STANDARD FOR WOOD CONSTRUCTION AND SUPPLEMENT (ANSI/AWC NDS-2018)
	d.	SPECIAL DESIGN PROVISIONS FOR WIND & SEISMIC (AWC SDPWS-2015)
	e.	THE NATIONAL DESIGN STANDARD FOR METAL PLATE CONNECTED WOOD TRUSS
		CONSTRUCTION (ANSI/TPI 1-2014)
	B. DESIGN	
	a.	TRUSSES SHALL BE DESIGNED FOR THE FOLLOWING MINIMUM VERTICAL LOADS AND OTHER LOADS INDICATED ON THE CONSTRUCTION DOCUMENTS (ATTIC MECHANICAL UNITS, ETC.)
		ROOF TRUSS LOADING:
		ASPHALT SHINGLE W/ GYP CEILING: TOP-CHORD DEAD LOAD: 13.0 PSF * (11.9 PSF SUPERIMPOSED)
		BOT CHORD DEAD LOAD: 8.3 PSF (6.7 PSF SUPERIMPOSED)
		ROOF - LIVE LOAD: 20 PSF ASPHALT SHINGLE W/ STUCCO CEILING:
		TOP-CHORD DEAD LOAD: 13.0 PSF * (11.9 PSF SUPERIMPOSED)
		BOT CHORD DEAD LOAD: 12.7 PSF (11.1 PSF SUPERIMPOSED)
		ROOF - LIVE LOAD: 20 PSF
		DEFLECTION CRITERIA: DEAD + LIVE LOAD L/240
		LIVE LOAD ONLY L/360
		*INCLUDES 4 PSF ALLOWANCE FOR PV PANELS
	b.	( ) INDICATES HORIZONTAL SEISMIC/WIND LOAD ON COLLECTOR TRUSSES. THE TRUSS DESIGNER SHALL DESIGN FOR THE TRUSSES FOR THE INDICATED HORIZONTAL LOAD ACTING IN BOTH THE TOP AND BOTTOM TRUSS CHORDS AND FOR THE TRANSFER OF THE FORCE TO THE CHORDS THROUGH THE WEB.
2.		DR REQUIREMENTS: DNTRACTOR SHALL MEET ALL THE REQUIREMENTS LISTED IN SECTION 2.3.4 OF ANSI/TPI 1-2014
		DIN RACTOR SHALL MEET ALL THE REQUIREMENTS LISTED IN SECTION 2.3.4 OF ANSI/TPT 1-2014 DING THE FOLLOWING:
	а.	MEANS AND METHODS: THE CONTRACTOR IS RESPONSIBLE FOR ALL MEANS AND METHODS,
		TECHNIQUES, SEQUENCES, PROCEDURES, PROGRAMS AND SAFETY IN CONNECTION WITH THE RECEIPT, STORAGE, HANDLING, INSTALLATION, RESTRAINING, AND BRACING OF THE TRUSSES.
		REFER TO THE GUIDE TO GOOD PRACTICE FOR HANDLING, INSTALLING, RESTRAINING &
		BRACING OF METAL PLATE CONNECTED WOOD TRUSSES (BCSI-B1)
	b.	TRUSS INSTALLATION SHALL COMPLY WITH INSTALLATION TOLERANCES SHOWN IN BCSI-B1
	С.	TEMPORARY INSTALLATION RESTRAINT/BRACING FOR THE TRUSS SYSTEM AND THE PERMANENT TRUSS SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH BCSI-B2.
	d	CONSTRUCTION LOADING ON TRUSSES SHALL BE DONE IN ACCORDANCE WITH BCSI-B4.
		TRUSS DAMAGE, JOBSITE MODIFICATIONS & INSTALLATION ERRORS SHALL BE BROUGHT TO THE
	6.	IMMEDIATE ATTENTION OF THE EOR AND THE TRUSS DESIGNER, REFERENCE BCSI-B5.
	r.	SUBMIT THE DRAWINGS FROM THE TRUSS DESIGNER/MANUFACTURER TO THE BUILDING DEPARTMENT PRIOR TO FABRICATION FOR APPROVAL. A COPY OF THIS SUBMITTAL SHALL BE PROVIDED TO TEH ENGINEER OF RECORD FOR REVIEW OF GENERAL CONFORMANCE TO THE DESIGN INTENT. THE CONTRACTOR SHALL INCORPORATE THE TIME REQUIRED FOR THE SUBMITTAL TO BE REVIEWED, STAMPED AND APPROVED BY ALL PARTIES AND SHALL HAVE THE APPROVED TRUSS DLANS ON THE FOR SITE OPIOD TO FOUNDATION INSPECTION.
3.	TRUSS DESIGI	TRUSS PLANS ON THE JOB SITE PRIOR TO FOUNDATION INSPECTION. NER REQUIREMENTS:
0.	A. THE TRU	USS DESIGNER SHALL MEET ALL THE REQUIREMENTS LISTED IN SECTION 2.3.5 OF ANSI/TPI 1-2014 DING THE FOLLOWING:
	a.	TRUSS DESIGNER SHALL SUPERVISE THE PREPARATION OF THE TRUSS DESIGN DRAWINGS WHICH SHALL CONTAIN THE INFORMATION LISTED IN SECTION 2.3.5.5 OF ANSI/TPI 1-2014. THIS INCLUDES ALL TRUSS TO TRUSS CONNECTIONS, AND DETAILS FOR THE "CALIFORNIA FILL" AREAS.
	b.	TRUSS DESIGNER SHALL COMPLY WITH THE REFERENCED CODE AND DESIGN CRITERIA ABOVE.
	С.	TRUSS DESIGNER SHALL SHOW ALL HANGERS, BRACING AND RESTRAINTS AS WELL AS METHOD OF RESTRAINT/BRACING ON THE TRUSS PLANS TO MEET ANY SEISMIC AND WIND REQUIREMENTS OF THE CODE.
	d.	SUBMIT TRUSS DESIGN DRAWINGS INCLUDING ALL RELEVANT DETAILS FOR THE FABRICATION OF
		THE TRUSSES AND PREPARE CALCULATIONS. ALL PLANS, DETAILS AND CALCULATIONS FOR THE TRUSSES SHALL BE STAMPED AND SIGNED BY A LICENSED PROFESSIONAL ENGINEER (CIVIL OR STRUCTURAL), LICENSED TO PRACTICE IN THE STATE OF CALIFORNIA.

#### WOOD STRUCTURAL PANELS (SHEATHING)

1. WOOD STRUCTURAL PANELS SHALL MEET THE FOLLOWING MINIMUM STANDARDS EXCEPT WHERE OTHERWISE

NOTED: WOOD STRUCTURAL PANEL PROPERTIES SHEATHING PERFORMANCE SPAN RATING RATING<sup>B</sup> REFERENCE BOND USE GRADE RATING CLASSIFICATION C ROOF EXPOSURE 1 APA 2022 CBC REFER TO TYPICAL DIAPHRAGM SCHEDULE 2303.1.5 APA (DOC PS 1-09 FLOOR EXPOSURE 1 OR PS 2-10) REFER TO TYPICAL SHEAR WALL SCHEDULE EXPOSURE 1 WALL APA

TABLE NOTES:

- A. WOOD STRUCTURAL PANELS SHALL CONFORM TO THE REQUIREMENTS FOR THEIR TYPE IN ACCORDANCE WITH THE FOLLOWING VOLUNTARY STANDARDS BY THE ENGINEERED WOOD ASSOCIATION (APA):
- a. VOLUNTARY PRODUCT STANDARD, STRUCTURAL PLYWOOD, PS 1-09
- b. VOLUNTARY PRODUCT STANDARD, PERFORMANCE STANDARD FOR WOOD-BASED STRUCTURAL-USE PANELS, PS 2-10
- B. WOOD STRUCTURAL PANELS SHALL BE IDENTIFIED BY THE APA TRADEMARK INDICATING CONFORMANCE TO THE APPLICABLE VOLUNTARY STANDARD
- C. WHERE PANELS ARE EXPOSED TO REPEATED WETTING AND REDRYING, LONG-TERM EXPOSURE TO WEATHER, OR CONDTIONS OF SIMILAR SEVERITY, "EXTERIOR" APA RATED PLYWOOD SHEATHING SHALL BE USED. C-D "EXPOSURE 1" APA RATED PLYWOOD SHEATHING (CDX) <u>SHALL NOT</u> BE USED FOR CONDITIONS INVOLVING LONG-TERM EXPOSURE TO WEATHER.
- a. EXCEPTION: WOOD STRUCTURAL PANEL ROOF SHEATHING EXPOSED TO THE OUTDOORS ON THE UNDERSIDE IS PERMITTED TO BE "EXPOSURE 1" TYPE.
- b. WOOD STRUCTURAL PANELS TO BE USED AS SIDING SHALL COMPLY WITH ANSI/APA PRP-210.
- D. ORIENTED STRAND BOARD (OSB) WITH EQUIVALENT CLASSIFICATION AND RATINGS MAY BE USED IN LIEU OF PLYWOOD FOR WOOD STRUCTURAL PANEL WALL SHEATHING.

2. TRANSPORTATION, STORAGE, AND HANDLING:

A. TRANSPORTATION

- a. IN TRANSPORTING PANELS ON OPEN TRUCK BEDS, COVER THE BUNDLES WITH A TARP.
- b. Storage a. ALWAYS STORE THE PANELS UNDER COVER WHENEVER POSSIBLE
  - b. WHEN STORING PANELS OUTSIDE STACK THEM ON A LEVEL SURFACE ON TOP OF STRINGERS OR OTHER BLOCKING, THREE STRINGERS MINIMUM.
  - c. NEVER LEAVE PANELS IN CONTACT WITH THE GROUND
  - d. COVER THE STACK WITH A PLASTIC TARP, ENSURING THAT THE BUNDLE IS WELL VENTILATED TO PREVENT MILDEW.
  - e. IF MOISTURE ABSORPTION IS EXPECTED, CUT THE STEEL BAND TO PREVENT DAMAGE
  - f. KEEP SANDED OR OTHER APPEARANCE GRADE PANELS AWAY FROM HIGH TRAFFIC AREAS

#### C. HANDLING

- a. ALWAYS PROTECT ENDS AND EDGES, ESPECIALLY TONGUE AND GROOVE PRODUCTS, FROM PHYSICAL DAMAGE.
- b. ACCLIMATIZE THE PANELS FOR 24 HOURS MINIMUM BEFORE INSTALLATION BY STANDING THE PANELS ON EDGE WITH A GAP BETWEEN EACH TO ALLOW FOR AIR CIRCULATION OR PER MANUFACTURER'S RECOMMENDATIONS.

#### 3. PLYWOOD ORIENTATION

- A. ROOF AND FLOOR SHEATHING SHALL BE LAID WITH THE GRAIN OF THE OUTER PILES PERPENDICULAR TO THE FRAMING MEMBERS, SHALL BE CONTINUOUS OVER 2 JOIST BAYS MINIMUM AND END JOINTS SHALL BE JOINED OVER FRAMING AND STAGGERED. LEAVE A  $angle_8^{\prime\prime}$  GAP BETWEEN PANELS TO ALLOW FOR PANEL EXPANSION UNLESS RECOMMENDED OTHERWISE BY THE PANEL MANUF. REFER TO SPECIFIC DETAILS IN THE DRAWINGS FOR FURTHER PARAMETERS.
- B. PLYWOOD OR OSB WALL SHEATHING MAY BE APPLIED VERTICALLY OR HORIZONTALLY. ALL END JOINTS BE JOINED OVER FRAMING AND STAGGERED.
- 4. BLOCKING:
- A. ROOF: ALL ROOF SHEATHING SHALL BE BLOCKED UNLESS SPECIFICALLY ALLOWED ON PLANS. WHERE PERMITTED TO BE UNBLOCKED, ALL UNBLOCKED EDGES SHALL BE TONGUE AND GROOVE.
- B. ALL FLOOR SHEATHING SHALL BE BLOCKED UNLESS SPECIFICALLY ALLOWED ON PLANS. WHERE PERMITTED TO BE UNBLOCKED, ALL UNBLOCKED EDGES SHALL BE TONGUE AND GROOVE.
- C. WALLS: ALL SHEAR WALLS SHALL BE FULLY BLOCKED AT PLYWOOD EDGES.

5. FASTENERS

- A. USE SHEATHING NAILS SAME GAUGE AS COMMON WIRE NAILS WITH LENGTHS AT LEAST EQUAL TO SHEATHING THICKNESS PLUS REQUIRED PENETRATION PER AWS SDPWS TABLE 4.2A OR 4.3A (AS REQUIRED).
- B. EQUIVALENT PNEUMATIC DRIVE NAILS OR STAPLES MAY BE USED IF FASTENER MANUFACTURER HAS RECEIVED ICC OR IAPMO APPROVAL FOR THE INTENDED US. FASTENERS TO BE SUBSTITUTED SHALL BE EQUIVALENT IN LATERAL AND WITHDRAWAL STRENGTH TO THE SIZE OF COMMON NAIL SPECIFIED.
- C. USE OF MACHINE NAILING IS SUBJECT TO A SATISFACTORY JOB SITE DEMONSTRATION FOR EACH PROJECT AND THE APPROVAL BY THE PROJECT ARCHITECT OR STRUCTURAL ENGINEER. THE APPROVAL IS SUBJECT TO CONTINUED SATISFACTORY PERFORMANCE. MACHINE NAILING WILL NOT BE APPROVED IN 5/16" PLYWOOD OR OSB SHEATHING. IF NAIL HEADS PENETRATE THE OUTER PLY MORE T HAN WOULD BE NORMAL FOR A HAND HAMMER OR IF MINIMUM ALLOWABLE EDGE DISTANCES ARE NOT MAINTAINED, THE PERFORMANCE WILL BE DEEMED UNSATISFACTORY.
- D. TYPICAL NAILING SHALL BE 10D AT 6" O.C. AT ALL SUPPORTED EDGES AND OVER SHEAR WALLS, AND 10D AT 12" O.C. AT ALL INTERMEDIATE SUPPORTS, UNLESS OTHERWISE NOTED, SEE PLANS AND REFER TO SHEAR WALL SCHEDULE.

## COUNTY **SAN LUIS** OBISPO

THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU has been issued and final inspection COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

> SAN LUIS OBISPO DWELLING UNIT S OBISPO, CA COUNTY OF SA ACCESSORY E SAN LUIS C

DATE 09/28/2023 SHEET


S-103

 $\overline{\triangleleft}$ 

SPECI, TESTS

GENERAL NOTES, S INSPECTION & 1

ک∢



#### FOUNDATION PLAN NOTES

REFER TO THE FOLLOWING SHEETS FOR TYPICAL DETAILS:

DESCRIPTION	SHEET (S)
SYMBOLS AND ABBREVIATIONS	S-101
STRUCTURAL GENERAL NOTES	S-102 - S-103
TESTING AND INSPECTION	S-103
TYPICAL CONCRETE DETAILS	S-301
TYPICAL WOOD DETAILS	S-401 - S-405

- 2. SEE ARCHITECTURAL DRAWINGS FOR FINISHED FLOOR ELEVATIONS. REFERENCE FINISHED FLOOR ELEVATION = 0'-0" CORRESPONDS TO FINISHED FLOOR ELEVATION.
- 3. ALL DIMENSIONS SHOWN ARE FROM FACE OF CONCRETE/MASONRY, FACE OF SHEATHING, OR CENTERLINE OF COLUMN. ALL COLUMNS ARE CENTERED IN STUD WALLS, UNO.
- 4. FOR ANY DIMENSIONAL INFORMATION NOT SHOWN, SEE ARCHITECTURAL DRAWINGS.
- 5. SEE ARCHITECTURAL DRAWINGS FOR ANY EMBEDDED ITEMS AND ALL EXTERIOR CONCRETE PAVING.
- 6. SEE PLANS AND ARCHITECTURAL DRAWINGS FOR DEPRESSIONS AND/OR SLOPES IN CONCRETE SLABS.
- SEE ARCHIECTURAL DRAWINGS FOR SIZE AND LOCATION OF ALL DOOR AND WINDOW OPENINGS IN BEARING AND NON-BEARING WALLS.
- 8. SEE ARCHITECTURAL DRAWINGS FOR LOCATION OF INTERIOR NON-BEARING PARTITIONS.
- SEE ARCHITECTURAL, PLUMBING, MECHANICAL AND ELECTRICAL DRAWINGS FOR ADDITIONAL EMBEDDED ITEMS AND SLAB PENETRATIONS.
- 10. FOR TYPICAL SLAB-ON-GRADE REQUIREMENTS, INCLUDING SLAB JOINTS, SEE DETAIL 31/S-301.
- 11. ALL POSTS IN 4" WALLS SHALL BE 4x4, UNLESS NOTED OTHERWISE ALL POSTS IN 6" WALLS SHALL BE 6x6, UNLESS NOTED OTHERWISE
- 12. PLATE WASHERS ARE REQUIRED FOR ALL SILL PLATE ANCHOR BOLTS. REFER TO 34/S-402 FOR PLATE WASHER REQUIREMENTS AT SHEAR WALLS.
- 13. ALL HOLDOWN ANCHOR NUTS SHALL BE TIGHTENED JUST PRIOR TO COVERING.
- 14. ALL BOLT HOLES IN WOOD MEMBERS, SHALL BE DRILLED A MAXIMUM OF  $\frac{1}{16}$  "OVERSIZED. INSPECTOR TO VERIFY.
- 15. THE BUILDING PAD SHALL BE PREPARED AS OUTLINED IN DETAIL 53/S-301. THE BUILDING OFFICIAL SHALL REQUIRE PAD CERTIFICATION BY A GEOTECHNICAL ENGINEER AT THEIR DISCRETION.
- 16. BOTTOM OF FOOTING SHALL BE, UNLESS DEEPER FOUNDATIONS ARE REQUIRED BY THE BUILDING OFFICIAL: A. 21" BELOW PAD OR ADJACENT GRADE AT PERIMETER, WHICHEVER IS DEEPER, UNO.
- B. 21" BELOW PAD OR ADJACENT GRADE AT INTERIOR GRADE BEAMS, WHICHEVER IS DEEPER, UNO. NOTE: FOOTING MUST BE DEEPENED LOCALLY PER DETAIL 32/S-301 TO ACCOMMODATE ANCHOR BOLT HOLDOWN EMBED DEPTHS.
- 17. ALL THIS PLAN IS INTENDED FOR FLAT LOTS, WITHOUT HIGHLY EXPANSIVE OR LIQUEFIABLE SOILS. IF THE PROJECT SITE IS DETERMINED TO HAVE ANY OF THESE QUALITIES, AS DETERMINED BY THE BUILDING OFFICIAL, THESE PRE APPROVED ADU FOUNDATION PLANS AND DETAILS ARE NOT APPLICABLE.

#### SYMBOL LEGEND



6X

INDICATES SHEAR WALL TYPE AND LENGTH, SEE SCHEDULE ON 13/S-402



 SPECIFIES HOLDOWN/
 INDICATES HOLDOWN/

 STRAP DETAIL
 STRAP TYPE

 INDICATES SIMPSON SSTB HOLDOWN TO:
 CONC FOUNDATION:

 DETAIL 12/S-311

		CONTINUOUS F	OOTING SCHEDUI	E	
MARK	WIDTH	MIN EMBED BELOW LOWEST PAD GRADE	LONG REINF	TRANS REINF	DETAIL
C1.25	1'-3"	SEE NOTE 16	(2) #5 T&B	#3 @ 12" OC, BOT	31/\$-311

	GRADE BEAM SCHEDULE					
TYPE	WIDTH	THICKNESS	MIN EMBED BELOW LOWEST PAD GRADE	LONG REINF	TRANS REINF	DETAIL
(GB1)	1'-0"	1'-0''	SEE NOTE 16	(2) #4 @ TOP (2) #4 @ BOT	#3 @ 24" OC	13/S-312

	PAD FOOTING SCHEDULE							
TYPE	WIDTH	LENGTH	THICKNESS	MIN EMBED BELOW LOWEST PAD GRADE	TOP REINF	BOT REINF	DETAIL	
F2	2'-0"	2'-0''	1'-6"	SEE NOTE 16	(3) #5, EW	(3) #5 @, EW	11/S-312	
NOTE: FOOTING MUST BE DEEPENED LOCALLY PER DETAIL 32/S-301 TO ACCOMMODATE AB								

HOLDOWN EMBED DEPTHS

# COUNTY উSAN LUIS OBISPO


THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.




PLAN - MID ODERN

FOUNDATION I CENTURY M

DATE 09/28/2023 SHEET





#### ROOF FRAMING NOTES

1. SEE ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS AND ELEVATIONS INCLUDING, BUT NOT LIMITED TO THE FOLLOWING, ALL DIMENSIONS TO BE VERIFIED PRIOR TO CONSTRUCTION:

- A. GRID DIMENSIONS AND HORIZONTAL CONTROL
- B. ALL DIMENSIONS, ELEVATIONS, FINISH SURFACE, SLOPES, DRAINS, SLAB DEPRESSIONS, ETC C. LOCATION AND EXTENT OF EXTERIOR WALL ASSEMBLIES AND OPENINGS
- D. ALL NON STRUCTURAL WALLS
- 2. REFER TO THE FOLLOWING SHEETS FOR TYPICAL DETAILS:

DESCRIPTION	SHEET (S)
SYMBOLS AND ABBREVIATIONS	S-101
STRUCTURAL GENERAL NOTES	S-102 - S-103
TESTING AND INSPECTION	S-103
TYPICAL CONCRETE DETAILS	S-301
TYPICAL WOOD DETAILS	S-401 - S-405

- 3. SEE ARCHITECTURAL DRAWINGS FOR ALL TOP OF SHEATHING AND TOP OF WALL ELEVATIONS.
- 4. SEE ARCHITECTURAL, PLUMBING, MECHANICAL AND ELECTRICAL DRAWINGS FOR SIZE AND LOCATION OF PIPES, DUCTS AND OTHER ROOF PENETRATIONS. FOR ROOF PENETRATIONS NOT SHOWN ON ROOF FRAMING PLAN, SEE DETAIL 23/S-403 FOR TYPICAL OPENINGS, UNO.
- ALL POSTS IN 6" WALLS SHALL BE 6x6, UNLESS NOTED OTHERWISE.

TYPICAL WALL FRAMING SHALL BE:

- 2x6 @ 16" OC @ ALL EXTERIOR WALLS, UNO 2x4 @ 16" OC @ ALL INTERIOR BEARING WALLS, UNO
- 2x4 @ 16" @ ALL INTERIOR NON-BEARING WALLS, UNO
- 6. ALL INTERIOR WALLS NOT SHOWN ON THE STRUCTURAL FRAMING PLANS BUT SHOWN ON THE ARCHITECTURAL DRAWINGS SHALL BE CONSTRUCTED PER NON-BEARING PORTION WALL DETAIL 43/S-401, UNO.
- 7. DIAPHRAGM TYPES:
- ALL ROOF DIAPHRAGMS SHALL BE TYPE A, UNO REFER TO 12/S-403
- 8. ALL LINES AND/OR MEMBERS INDICATED AS "STRUT" SHALL RECEIVE (2) ROWS OF BOUNDARY NAILING (BN), STGR.
- 9. TRUSS MEMBERS AND COMPONENTS SHALL NOT BE CUT, NOTCHED, DRILLED OR OTHERWISE ALTERED IN ANY WAY WITHOUT WRITTEN CONCURRENCE AND APPROVAL OF A REGISTERED DESIGN PROFESSIONAL.
- 10. ALTERATIONS RESULTING IN THE ADDITION OF LOADS TO ANY MEMBER (E.G. HVAC EQUIPMENT, WATER HEATER) SHALL NOT BE PERMITTED WITHOUT VERIFICATION THAT THE TRUSS IS CAPABLE OF SUPPORTING SUCH ADDITIONAL LOADING.

SYMBOL LEGEND

XX'-X'' \ x /

INDICATES SHEAR WALL TYPE AND LENGTH, SEE SCHEDULE ON 13/S-402

 $\overline{\ast}$ 

\_\_\_\_

INDICATES BLOCKING & STRAPPING ABOVE & BELOW WINDOW OPENINGS PER DETAIL 44/S-402

- INDICATES HEADER @ OPENING. REFER TO 32/S-401 FOR HEADER SIZE, UNO ON PLANS
- \_\_\_\_\_(X)

INDICATES TOP PLATE SPLICE NAILING PER 33/S-403 NOTE THAT NAILING APPLIES TO ENTIRE LENGTH OF TOP

INDICATES STRAP PER 34/S-405, UNO

PLATE. PROVIDE TYPE (C) SPLICE, UNO

HOLDOWN SCHEDULE DETAIL INDICATES SIMPSON SSTB HOLDOWN TO: 6X> CONC FOUNDATION: 22/S-311

SCHEDULES

	ROOF BEAM SCHEDULE	
MARK	SIZE	REMARKS
B1	4x6 SELECT STRUCTURAL	
B2	4x10	
B3	6x10	

	ROOF RAFTER SCHEDULE	
MARK	SIZE	REMARKS
R1	2x8 @ 16" OC	
	HEADER SCHEDULE	
MARK	SIZE	REMARKS
H1	6x8	
H2	4x10	

PREFABRICATED ROOF TRUSS


1. FOR PREFABRICATED ROOF TRUSS NOTES SEE NOTES ON SHEET S-103

	ROOF TRUSS SCHEDU	LE
MARK	DESCRIPTION	REMARKS
RT	ROOF TRUSS (COMMON)	24" OC MAX
SGT	STRUCTURAL GABLE TRUSS	
MT	MONO PITCH TRUSS	24" OC MAX
JT	JACK TRUSS	24" OC MAX
VJT	VALLEY JACK TRUSS	24" OC MAX
CJT	CORNER JACK TRUSS	
GT	GIRDER TRUSS	
MGT	MONO PITCH GIRDER TRUSS	
DT (#*)	DRAG TRUSS	
CGT	CALIFORNIA GIRDER TRUSS	
HR	HIP RAFTER / JACK RAFTER	
CHT	CALIFORNIA HIP TRUSS	24" OC MAX
SCT	SCISSOR TRUSS	24" OC MAX, CEILING SLOPE PER ARCH

(#\*) - EQUALS DRAG FORCE IN LBS, DRAG FORCE IS AT A FACTORED LEVEL (0.7E) DRAG FORCES CALCULATED IN ACCORDANCE WITH ASCE 7-16 12.10.1.1. IN STRUCTURES ENTIRELY BRACED BY LIGHT FRAME SHEAR WALLS, OR PORTIONS THEREOF, DRAG MEMBERS SHALL BE DESIGNED TO RESIST FORCES USING THE LOAD COMBINATIONS OF ASCE 7-16 SECTION 12.4.2.3 IN ALL OTHER STRUCTURES DRAGS SHALL INCLUDE THE EFFECT OF OVER STRENGTH PER ASCE 7-16 12.4.3.2




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



MID ROOF FRAMING PLAN -CENTURY MODERN

DATE 09/28/2023 SHEET







COUNTY **SAN LUIS** OBISPO

THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

> AILS DET. Ш **—** Ш И U Z Ο AL TYPIC,

 $\sim$ 







# COUNTY SAN LUIS OBISPO

THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

CONCRETE DETAILS CONCRETE DETAILS SAN LUIS OBISPO SAN LUIS OBISPO COUNTY OF SAN LUIS OBISPO SAN LUIS OBISPO COUNTY OF SAN LUIS OBISPO SAN LUIS OBISPO COUNTY OF SAN LUIS OBISPO SAN LUIS






TYPICAL WOOD STUD INTERSECTIONS 2727-01-CU22 - \$401

#### FASTENING SCHEDULE PER 2022 CBC 2304.10.1

	FASTENING	LOCATION
ER FRAMING BELOW	3-8d COMMON	EACH END, TOENAIL
	2-8d COMMON	EACH END, TOENAIL
ter or truss	2-16d COMMON	END NAIL
	16d COMMON @ 6" OC	FACE NAIL
	3-8d COMMON	EACH JOIST, TOENAIL
	3-16d COMMON	FACE NAIL
	3-16d COMMON	FACE NAIL
	3-10d COMMON	FACE NAIL
	3-10d COMMON	TOENAIL <sup>b</sup>
GE BEAM	2-16d COMMON	END NAIL
	3-10d COMMON	TOENAIL
	16d COMMON	16" OC FACE NAIL
	16d COMMON	16" OC EACH EDGE, FACE NAIL
	4-10d COMMON	TOENAIL
	16d COMMON	16" OC FACE NAIL
8	8-16d COMMON	EACH SIDE OF END JOINT, FACE NAIL (MINIMUM 24" LAP SPLICE LENGTH EACH SID OF END JOINT)
	2-16d COMMON	16" OC FACE NAIL
	4-8d COMMON	TOENAIL
	2-16d COMMON	END NAIL
	2-16d COMMON	FACE NAIL
	3-8d COMMON	TOENAIL
BELOW	8d COMMON	6" OC, TOENAIL
	2-8d COMMON	FACE NAIL
	2-16d COMMON	FACE NAIL
	20d COMMON (4" x 0.192")	32" OC FACE NAIL AT TOP AND BOTTOM STAGGERED ON APPOSITE SIDE
	3-16d COMMON	EACH JOIST OR RAFTER, FACE NAIL
	3-16d COMMON	END NAIL
	2-8d COMMON	EACH END, TOENAIL

THIS NAILING SCHEDULE SHALL ONLY BE USED IF CONDITION IS NOT OTHERWISE DETAILED OR SPECIFIED ON THE CONSTRUCTION DOCUMENTS. COMMON NAILS SHALL BE USED EXCEPT WHERE WHERE A RAFTER IS FASTENED TO AN ADJACENT PARALLEL CEILING JOIST IN ACCORDANCE WITH THIS SCHEDULE AND THE CEILING JOIST IS FASTENED TO THE TOP PLATE IN ACCORDANCE WITH THIS



# COUNTY **SAN LUIS** OBISPO

THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

> ETAILS  $\Box$ MOOD AL TYPIC,

OBISPO IG UNIT

ELLING

LUIS

S

щ́к


ΟŌ


**COUNTY ACCESS(** 

DATE 09/28/2023 SHEET

S-401


NTS 24






				SHEA	R WALL SHEATHING	/ NAILING SCHEDULE				
WALL	1,12	6 EDAMINIC		NAILING	2,3,4	SILL NAILIN	NG 7		10, 11	CAPACITY PER
SYMBOL	STRUCT SHEATHING	FRAMING	(2) 2x STUD	EDGE	INTERMEDIATE SUPPORTS	8 NAILS /LAG SCREWS	SDS SCREWS <sup>14</sup> OPTION	A35s	ANCHOR BOLTING	2015 AWC SDPW
	15/32" STRUCT 1 PLYWOOD	2x	10d @ 9" OC	8d @ 6" OC	8d @ 12" OC	16d @ 6" OC	12" OC	24" OC	5/8" DIA @ 48" OC	280 PLF
B	15/32" STRUCT 1 PLYWOOD	2x	10d @ 8" OC	10d @ 6" OC	10d @ 12" OC	5/8"Ø LAG SCREWS @ 16" OC	12" OC	16" OC	5/8" DIA @ 48" OC	340 PLF
Â	15/32" STRUCT 1 PLYWOOD	2x	10d @ 5" OC	10d @ 4" OC	10d @ 12" OC	5/8"Ø LAG SCREWS @ 16" OC	8" OC	12" OC	5/8" DIA @ 32" OC	510 PLF
	15/32" STRUCT 1 PLYWOOD	2x	10d @ 4" OC	10d @ 3" OC	10d @ 12" OC	5/8"Ø LAG SCREWS @ 16" OC	6" OC	8" OC	5/8" DIA @ 32" OC	665 PLF
Ē	15/32" STRUCT 1 PLYWOOD	2x	10d @ 3" OC	10d @ 2" OC	10d @ 12" OC	5/8"Ø LAG SCREWS @ 8" OC	4" OC	8" OC	5/8" DIA @ 24" OC	860 PLF
Ē	15/32" STRUCT 1 PLYWOOD (EACH FACE OF WALL)	Зx	(2) 10d @ 5" OC	10d @ 4" OC	10d @ 12" OC	5/8"Ø LAG SCREWS @ 8" OC	(2) @ 8" OC *	6" OC	5/8" DIA @ 16" OC	1020 PLF
Â	15/32" STRUCT 1 PLYWOOD (EACH FACE OF WALL)	3x	(2) 10d @ 4" OC	10d @ 3" OC	10d @ 8" OC	5/8"Ø LAG SCREWS @ 8" OC	(2) @ 6" OC *	A34 @ 4" OC	5/8" DIA @ 16" OC	1330 PLF
	15/32" STRUCT 1 PLYWOOD (EACH FACE OF WALL)	3x	(2) 10d @ 3" OC	10d @ 2" OC	10d @ 6" OC	5/8"Ø LAG SCREWS @ 6" OC	(2) @ 4" OC *	LTP4 @ <sup>15</sup> 4" OC	5/8" DIA @ 8" OC	1740 PLF





NAILS	BOUNDARY NAILING (BN)	EDGE NAILING AT CONT. PANEL EDGES (EN)	EDGE NAILING AT OTHER PANEL EDGES (EN)	FIELD NAILING (FN)	PANEL EDGE SUPPORT OR NOMINAL MEMBER WIDTH AT PANEL EDGES	LINES OF FASTENERS
10d	6	-	6	12	H-CLIPS	1
10d	6	-	6	12	T&G	1
10d	2 ½	2 ½	4	12	2x4 FLAT	1







THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU has been issued and final inspection COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO COUNTY OF SAN LUIS OBISPO ACCESSORY DWELLING UNIT SAN LUIS OBISPO, CA SAN LUIS OBISPO, CA TYPICAL WOOD DETAILS

SHEET

S-404






	on: Title 24 Analy	sis		Input File	e Name: 4 E	3edrm Plan -	1a CZ 4.ribd2	2x		
ENERGY USE SUMMARY	Standard De		Standard Design TDV Ene				d Design TDV E		liance	Compliance Margin (EDR2
Space Heating	Energy (EDR1)		(EDR2) (kTDV/ft <sup>2</sup> -yr) 12.53	Energy (EDR1)		r) CEDF	<b>2) (kTDV/ft<sup>2</sup> -y</b> 13.58	-	06	-1.05
Space Cooling	0.4		19.69	0.2		/	15.92		13	3.77
IAQ Ventilation	0.4	17	5.02	0.4	17		5.02		0	0
Water Heating	2.4	16	25.98	1.7	'2		20.17	0.	74	5.81
Self Utilization/Flexibility Credit							0			o
North Facing Efficiency Compliance Total	6.1	16	63.22	4.2	23		54.69	1.	93	8.53
Space Heating	2.8	31	12.53	1.6	69		12.71	1.	12	-0.18
Space Cooling	0.4	12	19.69	0.3	9		17.8	0.	03	1.89
IAQ Ventilation	0.4	17	5.02	0.4	7		5.02		0	0
Water Heating	2.4	16	25.98	1.7	/1		20.08	0.	75	5.9
Self Utilization/Flexibility Credit			CO.				0			0
East Facing Efficiency Compliance Total	6.1	6	63.22	4.2	26		55.61	1	.9	7.61
				I				I		1
CERTIFICATE OF COMI Project Name: 4 Bedri Calculation Descriptic REQUIRED PV SYSTEMS	m Plan on: Title 24 Analy		MANCE COMPLIANCE	Calculati	on Date/Tii	<b>me:</b> 2023-09	-27T14:43:28 la CZ 4.ribd2:			CF1R-PRF-0 (Page 6 of 1
01	02	03	04	05	06	07	08 09	10	11	
DC System Size (kWdc)	Exception	Module Type	e Array Type	Power Electronics	CELL		ilt Array Ar put (deg	-	Inverte (%	
2.6	NA	Standard (14-1	7%) Fixed	none	true 1	.50-270 r	ı/a n/a	<=7:12	96	
REQUIRED SPECIAL FEAT		-			6					
		stalled as condition	on for meeting the modeled	d energy performance	for this comp	outer analysis.				
detail is provided in the	building tables bel		ld-verified by a certified HE F2Rs and CF3Rs are require				energy perfori	nance for this cor	mputer an	alysis. Additional
<ul> <li>detail is provided in the</li> <li>Quality insulation</li> <li>Indoor air quality</li> <li>Kitchen range hoo</li> <li>Verified EER/EER2</li> <li>Verified SEER/SEE</li> <li>Verified Refrigera</li> <li>Airflow in habitab</li> </ul>	nary of the features building tables bel n installation (QII) ventilation od 2 R2	ow. Registered Cl					energy perfori	nance for this cor	nputer an	alysis. Additional
detail is provided in the Quality insulation Indoor air quality Kitchen range hoo Verified EER/EER2 Verified Refrigera Airflow in habitab Verified HSPF2 Verified heat purr Wall-mounted the	hary of the features building tables bel n installation (QII) ventilation od 2 ER2 ont Charge ble rooms (SC3.1.4. mp rated heating ca ermostat in zones g	ow. Registered Cl 1.7) pacity greater than 150	F2Rs and CF3Rs are require				energy perforr	nance for this cor	nputer an	alysis. Additional
detail is provided in the Quality insulation Indoor air quality Kitchen range hoo Verified EER/EER2 Verified SEER/SEE Verified Refrigera Airflow in habitab Verified HSPF2 Verified heat pur Wall-mounted the Ductless indoor u BUILDING - FEATURES IN	nary of the features building tables bel n installation (QII) ventilation od 2 R2 int Charge ole rooms (SC3.1.4. np rated heating ca ermostat in zones g inits located entirel	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8)	ed to be completed in t		istry	energy perfor		mputer an	
detail is provided in the Quality insulation Indoor air quality Kitchen range hod Verified EER/EER Verified Refrigera Airflow in habitab Verified HSPF2 Verified heat pur Wall-mounted the Ductless indoor u	ary of the features building tables bel n installation (QII) ventilation od 2 R2 int Charge ole rooms (SC3.1.4. np rated heating ca ermostat in zones g inits located entirel NFORMATION	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 	ed to be completed in t	he HERS Reg			06 ber of Ventilatior		07 lumber of Water
detail is provided in the Quality insulation Indoor air quality Kitchen range hoo Verified EER/EER/ Verified Refrigera Airflow in habitab Verified HSPF2 Verified heat purr Wall-mounted the Ductless indoor u BUILDING - FEATURES IN 01	ary of the features building tables bel n installation (QII) ventilation od 2 R2 int Charge ole rooms (SC3.1.4. np rated heating ca ermostat in zones g inits located entirel NFORMATION	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned	ft2 (SC3.4.5) space (SC3.1.4.1.8)	ed to be completed in t	he HERS Reg	05		06		07
detail is provided in the Quality insulation Indoor air quality Kitchen range hoo Verified EER/EER/ Verified Refrigera Airflow in habitab Verified HSPF2 Verified heat purr Wall-mounted tha Ductless indoor u BUILDING - FEATURES II 01 Project Name	ary of the features building tables bel n installation (QII) ventilation od 2 R2 int Charge ole rooms (SC3.1.4. np rated heating ca ermostat in zones g inits located entirel NFORMATION	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 it <sup>2</sup> ) Number of Dwelling Units	ed to be completed in t	he HERS Reg	05 umber of Zone		06 ber of Ventilatior poling Systems		07 lumber of Water leating Systems
detail is provided in the Quality insulation Indoor air quality Kitchen range hoo Verified EER/EER/ Verified Refrigera Airflow in habitab Verified HSPF2 Verified heat purr Wall-mounted tha Ductless indoor u BUILDING - FEATURES II 01 Project Name	ary of the features building tables bel n installation (QII) ventilation od 2 R2 int Charge ole rooms (SC3.1.4. np rated heating ca ermostat in zones g inits located entirel NFORMATION Conditio	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 t <sup>2</sup> ) Number of Dwelling Units 1	d to be completed in t 04 g Number of Bedro 4 Registration Date/ Report Version: 20	oms Nu Fime: 22.0.000	05 umber of Zone	s Num Ca	06 ber of Ventilatior poling Systems		07 Jumber of Water Jeating Systems 1 CZ-4
detail is provided in the Quality insulation Indoor air quality Kitchen range hoo Verified EER/EER2 Verified Refrigera Airflow in habitab Verified HSPF2 Verified HSPF2 Verified heat pum Wall-mounted the Ductless indoor u BUILDING - FEATURES II O1 Project Name A Bedrm Plan Registration Number: CA Building Energy Effice CERTIFICATE OF COMI	hary of the features building tables belowing installation (QII) ventilation od 2 R2 Int Charge ble rooms (SC3.1.4. hp rated heating ca ermostat in zones g inits located entirel NFORMATION Conditio	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200 2022 Residential ENTIAL PERFOR	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 t <sup>2</sup> ) Number of Dwelling Units 1	ed to be completed in t 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: re METHOD Calculati	oms Nu Fime: 22.0.000 vv 20220901	05 umber of Zone 1 me: 2023-09	s Num Ca	06 ber of Ventilation poling Systems 0 HERS Provider: Report Generated		07 Jumber of Water Jeating Systems 1 CZ-4 -27 14:44:01 CF1R-PRF-0
detail is provided in the Quality insulation Indoor air quality Kitchen range hoo Verified EER/EER2 Verified Refrigera Airflow in habitab Verified HSPF2 Verified HSPF2 Verified heat pum Wall-mounted the Ductless indoor u BUILDING - FEATURES II O1 Project Name A Bedrm Plan Registration Number: CA Building Energy Effice CERTIFICATE OF COMI	A part of the features building tables below installation (QII) eventilation od 2 and the set of th	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200 2022 Residential ENTIAL PERFOR sis N 02	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 it <sup>2</sup> ) Number of Dwelling Units 1 Compliance Complianc	ed to be completed in t 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: re METHOD Calculati	oms Nu Fime: 22.0.000 v 20220901	05 umber of Zono 1 1 me: 2023-09 Bedrm Plan -	-27T14:43:28	06 ber of Ventilation poling Systems 0 HERS Provider: Report Generated	1: 2023-09	07 Jumber of Water Jeating Systems 1 CZ-4 -27 14:44:01 CF1R-PRF-0
detail is provided in the Quality insulation Indoor air quality Kitchen range hoo Verified EER/EER2 Verified KER/SEE Verified Refrigera Airflow in habitab Verified HSPF2 Verified HSPF2 Verified heat purr Wall-mounted the Ductless indoor u BUILDING - FEATURES IN 01 Project Name 4 Bedrm Plan Registration Number: CA Building Energy Effic CERTIFICATE OF COMI Project Name: 4 Bedrn Calculation Descriptic BUILDING ENVELOPE - H 01 Quality Insulation Inst: Required	Analy of the features building tables below installation (QII) ventilation od 2 R2 Int Charge ole rooms (SC3.1.4. Inp rated heating ca ermostat in zones g inits located entirel <b>NFORMATION</b> Conditio Conditio	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 it <sup>2</sup> ) Number of Dwelling Units 1 Compliance Complianc	ed to be completed in t 9 9 10 10 10 10 10 10 10 10 10 10 10 10 10	oms Nu Fime: 22.0.000 v 20220901	05 umber of Zono 1 1 me: 2023-09 Bedrm Plan -	27T14:43:28 La CZ 4.ribd2: 04	06 ber of Ventilation poling Systems 0 HERS Provider: Report Generated	1: 2023-09	07 Jumber of Water Jeating Systems 1 CZ2 -27 14:44:01 CF1R-PRF-0 (Page 9 of 1 (Page 9 of 1
detail is provided in the Quality insulation Indoor air quality Kitchen range hoo Verified EER/EER/ Verified SEER/SEE Verified Refrigera Airflow in habitab Verified HSPF2 Verified heat purr Vall-mounted the Ductless indoor u BUILDING - FEATURES II O1 Project Name 4 Bedrm Plan Registration Number: CA Building Energy Effic CERTIFICATE OF COMI Project Name: 4 Bedr Calculation Descriptic BUILDING ENVELOPE - H O1 Quality Insulation Inst	Analy of the features building tables below installation (QII) ventilation od 2 R2 Int Charge ole rooms (SC3.1.4. Inp rated heating ca ermostat in zones g inits located entirel <b>NFORMATION</b> Conditio Conditio	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 it <sup>2</sup> ) Number of Dwelling Units 1 Compliance Complianc	ed to be completed in t 9 9 10 10 10 10 10 10 10 10 10 10 10 10 10	oms Nu Fime: 22.0.000 v 20220901	05 umber of Zono 1 1 me: 2023-09 Bedrm Plan -	27T14:43:28 La CZ 4.ribd2: 04	06 ber of Ventilation poling Systems 0 HERS Provider: Report Generated	1: 2023-09	07 Jumber of Water Jeating Systems 1 CZ2 -27 14:44:01 CF1R-PRF-0 (Page 9 of 1 (Page 9 of 1
detail is provided in the Quality insulation Indoor air quality Kitchen range hoo Verified EER/EER/ Verified Refrigera Airflow in habitab Verified HSPF2 Verified HSPF2 Verified heat pur Vall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name A Bedrm Plan Registration Number: CA Building Energy Effici CERTIFICATE OF COMI Project Name: 4 Bedri Calculation Descriptic BUILDING ENVELOPE - H 01 Quality Insulation Inst: Required	Analy of the features building tables below installation (QII) eventilation od 2 ER2 and Charge ble rooms (SC3.1.4. hp rated heating ca ermostat in zones g units located entirel <b>NFORMATION</b> Conditio Conditio	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray Not Rec	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 tc <sup>2</sup> ) Number of Dwelling Units 1 Compliance	ed to be completed in t 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: re METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 05	oms Nu oms Nu Fime: 22.0.000 ev 20220901 on Date/Tin e Name: 4 E kage 6 6 6 6 6 8 8 9 9 9 9 9 9 9 9 9 9 9 9 9	05 umber of Zone 1 1 Bedrm Plan -	-27TT14:43:28 La CZ 4.ribd2: 04	06 ber of Ventilation poling Systems 0 HERS Provider: Report Generated -07:00 2x	1: 2023-09	07 Jumber of Water Heating Systems 1 CZ-4 -27 14:44:01 CF1R-PRF-0 (Page 9 of 1 05 M50 1/a 09 Water Heater
detail is provided in the Quality insulation Indoor air quality Kitchen range hoo Verified EER/EER2 Verified KER/SEE Verified Refrigera Airflow in habitab Verified HSPF2 Verified HSPF2 Verified heat purr Wall-mounted the Ductless indoor u Mall-mounted the Ductless indoor u Mall-mounted the Ductless indoor u Mall-mounted the Ductless indoor u Cerrified heat purr Calculation Number: CA Building Energy Effic CERTIFICATE OF COMI Project Name: 4 Bedrr Calculation Descriptic BUILDING ENVELOPE - H 01 Quality Insulation Inst Required WATER HEATING SYSTEF 01	ary of the features building tables bel n installation (QII) ventilation od 2 ER2 int Charge ble rooms (SC3.1.4. np rated heating ca ermostat in zones g inits located entirel NFORMATION Conditio Conditio Conditio Conditio Conditio Conditio HERS VERIFICATION HERS VERIFICATION Control (QII) His callation (QII) His System Type Domestic Hot	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray Not Rec 03	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 tc <sup>2</sup> ) Number of Dwelling Units 1 Compliance	ed to be completed in t 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: re METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 05	oms Nu oms Nu Fime: 22.0.000 ev 20220901 on Date/Tin e Name: 4 E kage	05 umber of Zono 1 1 3 Bedrm Plan -	es Num Co Co Co P27T14:43:28 La CZ 4.ribd2: 04 EFM50 n/a 07 Compact	06 ber of Ventilation poling Systems 0 HERS Provider: Report Generated -07:00 2x 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	1: 2023-09	07 Jumber of Water Jeating Systems 1 CZ-4 -27 14:44:01 CF1R-PRF-0 (Page 9 of 1 05 M50 1/a 09
detail is provided in the Quality insulation Kitchen range hoo Verified EER/EER/ Verified SEER/SEE Verified Refrigera Airflow in habitab Verified HSPF2 Verified heat purr Vall-mounted the Ductless indoor u BUILDING - FEATURES II A Bedrm Plan Registration Number: CA Building Energy Efficient Calculation Description BUILDING ENVELOPE - H 01 Quality Insulation Inst Required WATER HEATING SYSTEF 01 Name A Data Same Calculation Description Calculation Description Calculat	Analy of the features building tables below in installation (QII) inventilation od 2 R2 Int Charge ole rooms (SC3.1.4. Anp rated heating ca ermostat in zones g inits located entirely <b>NFORMATION</b> Condition	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray Not Rec 03 Distribution T	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 it <sup>2</sup> ) Number of Dwelling Units 1 Compliance Compliance Foam Insulation Bui quired 04 ype Water Heater Name	ed to be completed in t 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: re METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 05	oms Nu oms Nu Fime: 22.0.000 vv 20220901 on Date/Tiu e Name: 4 E kage kage 6 06 Solar Hu Syste	05 umber of Zono 1 1 3 Bedrm Plan -	27T14:43:28 -27T14:43:28 1a CZ 4.ribd2: 04 CZ 4.ribd2: CZ	06 ber of Ventilation poling Systems 0 HERS Provider: Report Generated 2x -07:00 2x 0 0 HERS Verifit	1: 2023-09	07 lumber of Water leating Systems 1 CZ2 -27 14:44:01 CF1R-PRF-0 (Page 9 of 1 (Page 9 of 1 05 M50 /a 09 Water Heater Name (#)
detail is provided in the Quality insulation Kitchen range hoo Verified EER/EER2 Verified Refrigera Airflow in habitab Verified NSPF2 Verified HSPF2 Verified heat purr Vall-mounted the Ductless indoor u Mall-mounted the Ductless indoor u Mall-mounted the Ductless indoor u Mall-mounted the Certified heat purr A Bedrm Plan Registration Number: CA Building Energy Efficient Calculation Description BUILDING ENVELOPE - H O1 Quality Insulation Insta Required WATER HEATING SYSTEF O1 Name DHW Sys 1 MATER HEATERS - NEEA	A principal de la company of the features building tables bel principal de la company of the features building tables bel principal de la company de la comp	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray Not Rec 03 Distribution T Standard	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 Number of Dwelling Units 1 Compliance SMANCE COMPLIANCE N SMANCE COMPLIANCE N Poam Insulation Buil quired 04 ype Water Heater Name DHW Heater 1	ed to be completed in t 04 9 Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: re METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 05 e Number of Units 1	oms Nu oms Nu fime: 22.0.000 ev 20220901 ev 20220901 kage 6 kage 6 Solar He Syste n/a	05 umber of Zone 1 1 Bedrm Plan -	es Num Co Co Co Co Co Co Co Co Co Co Co Co Co	06 ber of Ventilation poling Systems 0 HERS Provider: Report Generated -07:00 2x -07:00 2x -07:00 2x -07:00 2x -07:00 2x -07:00 2x -07:00 2x -07:00 2x	1: 2023-09	07 Jumber of Water Heating Systems 1 CZ2-2 -27 14:44:01 CF1R-PRF-0 (Page 9 of 1 05 M50 1/a 09 Water Heater Name (#) DHW Heater 1 (1
detail is provided in the   • Quality insulation   • Indoor air quality   • Kitchen range hoo   • Verified EER/EER/ER/ER/ER/ER/ER/ER/ER/ER/ER/ER/ER	A principal de la compara de l	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray Not Rec 03 Distribution T Standard	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 t <sup>2</sup> ) Number of Dwelling Units 1 Compliance	ed to be completed in t 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: re METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 05 e Number of Units 1	oms Nu oms Nu Fime: 22.0.000 vv 20220901 on Date/Tiu e Name: 4 E kage kage 6 06 Solar Hu Syste	05 umber of Zono 1 1 Bedrm Plan -	277114:43:28 -277114:43:28 1a CZ 4.ribd2: 04 2FM50 n/a 07 Compact Distribution Basic 6	06 ber of Ventilation boling Systems 0 HERS Provider: Report Generated 2 -07:00 2x 0 HERS Verifit 0 0 8 HERS Verifit	1: 2023-09	07 Jumber of Water Heating Systems 1 CZ-4 -27 14:44:01 CF1R-PRF-0 (Page 9 of 1 05 M50 1/a 09 Water Heater Name (#) DHW Heater 1 (1 08
detail is provided in the  Quality insulation  Kitchen range hoo Verified EER/EER/SEE Verified Refrigera Airflow in habitab Verified HSPF2 Verified HSPF2 Verified heat pur Vall-mounted the Ductless indoor u  BUILDING - FEATURES II  A Bedrm Plan  Registration Number: CA Building Energy Effic  BUILDING ENVELOPE - H 01  Quality Insulation Inst: Required  WATER HEATING SYSTEF  O1 Name  UXATER HEATERS - NEEA  O1 Name	A principal and the features building tables below installation (QII) eventilation od 22 and Charge one set of the features of	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (f 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray Not Rec 03 Distribution T Standard Tank	F2Rs and CF3Rs are require         ft2 (SC3.4.5)         space (SC3.1.4.1.8)         03         units         1         Compliance         RMANCE COMPLIANCE N         Proam Insulation         Building         quired         04         ype         Water Heater Name         DHW Heater 1         03         Vol. (gal)	ed to be completed in t d 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: ro METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 05 e Number of Units 1 1 NA NA	oms Nu oms Nu Fime: 22.0.000 vv 20220901 vv 20200 vv 20200 vv 20200 vv 20200 vv 20200 vv 20200 vv 20200 vv 2000 vv 200	05 umber of Zono 1 1 3 a bedrm Plan -	27T14:43:28         -27T14:43:28         1a CZ 4.ribd2:         04         :FM50         n/a         07         Compact         Distribution         Basic         6         ocation	06 ber of Ventilation poling Systems 0 HERS Provider: Report Generated 2x -07:00 2x 0 HERS Verifie 08 HERS Verifie n/a 07 Duct Inlet Air Sou	1: 2023-09	07 Jumber of Water Heating Systems 1 CZ4 -27 14:44:01 CF1R-PRF-0 (Page 9 of 1 05 M50 /a 09 Water Heater Name (#) DHW Heater 1 (1 08 ct Outlet Air Sour
detail is provided in the   • Quality insulation   • Indoor air quality   • Kitchen range hoo   • Verified EER/EER/ER/ER/ER/ER/ER/ER/ER/ER/ER/ER/ER	A principal de la compara de l	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (f 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray Not Rec 03 Distribution T Standard Tank	F2Rs and CF3Rs are require         ft2 (SC3.4.5)         space (SC3.1.4.1.8)         03         units         1         Compliance         RMANCE COMPLIANCE N         RMANCE COMPLIANCE N         Poam Insulation         Building         quired         04         ype         Water Heater Name         DHW Heater 1         03         Vol. (gal)	ed to be completed in t d 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: ro METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 05 e Number of Units 1 1 NA NA	oms Nu oms Nu Fime: 22.0.000 v 20220901 on Date/Til e Name: 4 E kage kage of Solar He Syste n/a 05 Heat Pump	05 umber of Zono 1 1 3 a bedrm Plan -	277114:43:28 -277114:43:28 1a CZ 4.ribd2: 04 2FM50 n/a 07 Compact Distribution Basic 6	06 ber of Ventilation boling Systems 0 HERS Provider: Report Generated 2 -07:00 2x 0 4 HERS Verifit n/a 0 0 8	1: 2023-09	07 Jumber of Water Heating Systems 1 CZ-4 -27 14:44:01 CF1R-PRF-0 (Page 9 of 1 05 M50 1/a 09 Water Heater Name (#) DHW Heater 1 (1 08
detail is provided in the Quality insulation Kitchen range hoo Verified EER/EER/ Verified SEER/SEE Verified Refrigera Airflow in habitab Verified heat purr Vall-mounted the Ductless indoor u BUILDING - FEATURES II A Bedrm Plan Registration Number: CA Building Energy Effic BUILDING ENVELOPE - H O1 Project Name: 4 Bedr Calculation Descriptic BUILDING ENVELOPE - H O1 Quality Insulation Inst Required WATER HEATING SYSTEF O1 Name DHW Sys 1 DHW Sys 1 CARA ANA ANA ANA ANA ANA ANA ANA ANA ANA	ary of the features building tables belows installation (QII) ventilation od 2 R2 int Charge ble rooms (SC3.1.4. mp rated heating ca ermostat in zones guints located entirel <b>NFORMATION</b> Conditio Condi	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray Not Rec 03 Distribution T Standard Tank	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 tc <sup>2</sup> ) Number of Dwelling Units 1 Compliance Compliance Foam Insulation Bui quired 04 ype Water Heater Name DHW Heater 1 03 0 Vol. (gal) NEEA He Bra 50 Gen	ed to be completed in t d 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: re METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 03 ilding Envelope Air Lea N/A 03 ilding Envelope Air Lea N/A 03 ilding Envelope Air Lea N/A 03 ilding Envelope Air Lea N/A	oms Nu oms Nu Fime: 22.0.000 vv 20220901 vv 20200 vv 20200 vv 20200 vv 20200 vv 20200 vv 20200 vv 20200 vv 2000 vv 200	05 umber of Zono 1 1 3 Bedrm Plan - 3 Bedrm Plan - 6 Beating em a 0 5 C C Tank L	27T14:43:28         -27T14:43:28         1a CZ 4.ribd2:         04         :FM50         n/a         07         Compact         Distribution         Basic         6         ocation	06 ber of Ventilation poling Systems 0 HERS Provider: Report Generated 2 2x -07:00 0 2x -07:00 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	1: 2023-09	07 Jumber of Water Heating Systems 1 CCF1R-PRF-0 (Page 9 of 1 CF1R-PRF-0 (Page 9 of 1 09 Water Heater Name (#) DHW Heater 1 (1 08 ct Outlet Air Sour Zone 1
detail is provided in the Quality insulation Kitchen range hoo Verified EER/EER2 Verified SEER/SEE Verified Refrigera Airflow in habitab Verified HSPF2 Verified heat purr Vall-mounted the Ductless indoor u Mall-mounted the Ductless indoor u Mall-mounted the Ductless indoor u Mall-mounted the Ductless indoor u Mall-mounted the CERTIFICATE OF COMI Project Name: 4 Bedrr Calculation Descriptic BUILDING ENVELOPE - H O1 Quality Insulation Insta Required WATER HEATING SYSTE O1 Name DHW Sys 1 DHW Heater 1 DHW Heater 1	Analy of the features building tables belows installation (QII) eventilation od 2 R2 and Charge ole rooms (SC3.1.4. Anp rated heating ca ermostat in zones g inits located entirely <b>NFORMATION</b> Conditio	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray Not Rec 03 Distribution T Standard N N 1 Standard N 1 N 1 1 1 1 1 1 1 1 1 1 1 1 1	F2Rs and CF3Rs are require ft2 (SC3.4.5) space (SC3.1.4.1.8) 03 tc <sup>2</sup> ) Number of Dwelling Units 1 Compliance Complianc	ed to be completed in t d 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: ro METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 05 e Number of Units 1 1 NA NA	oms Nu oms Nu Fime: 22.0.000 v 20220901 on Date/Til e Name: 4 E kage kage of Solar He Syste n/a Go of Solar He Syste n/a Go of Solar He Syste n/a Go of Solar He Syste n/a Go of Solar He Syste n/a	05 umber of Zono 1 1 3 a bedrm Plan -	-27T14:43:28 La CZ 4.ribd2: 04 CFM50 n/a 07 Compact Distribution Basic 6 cation Zone initial	06 ber of Ventilation poling Systems 0 HERS Provider: Report Generated 2x -07:00 2x 0 HERS Verifie 08 HERS Verifie n/a 07 Duct Inlet Air Sou	1: 2023-09	07 Jumber of Water Heating Systems 1 CZ4 -27 14:44:01 CF1R-PRF-0 (Page 9 of 1 05 M50 /a 09 Water Heater Name (#) DHW Heater 1 (1 08 ct Outlet Air Sour
detail is provided in the Quality insulation Kitchen range hoo Verified EER/EER/ Verified SER/SEE Verified Refrigera Airflow in habitab Verified HSPF2 Verified heat purr Vall-mounted the Ductless indoor u Ductless indoor u Project Name CA Building Energy Effic Registration Number: CA Building Energy Effic BUILDING ENVELOPE - F Calculation Descriptic BUILDING ENVELOPE - F O1 Quality Insulation Inst Required Name DHW Sys 1 DHW Sys 1 DHW Sys 1 DHW Heater 1 DHW Heater 1 DHW Heater 1 DHW Heater 1 DHW Heater 1 DHW Insulation Inst Calculation Descriptic Calculation Con Calculation Con	ary of the features building tables bel n installation (QII) ventilation od 2 ER2 int Charge ble rooms (SC3.1.4. np rated heating ca ermostat in zones g inits located entirel NFORMATION Conditio Condit	ow. Registered Cl 1.7) pacity greater than 150 ly in conditioned 02 ned Floor Area (1 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray Not Rec 03 Distribution T Standard N N 1 Standard N 1 N 1 1 1 1 1 1 1 1 1 1 1 1 1	F2Rs and CF3Rs are required         ft2 (SC3.4.5)         space (SC3.1.4.1.8)         Image: SC3.1.4.1.8)         Image: SC3.1.4.1.8) </td <td>ed to be completed in t d 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: re METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 05 e Number of Units 1 1 NA Pand N NA NA NA</td> <td>oms Nu oms Nu Fime: 22.0.000 v 20220901 on Date/Til e Name: 4 E kage Name: 4 E kage n/a Solar He Syste n/a G G G G G G G G G G G G G G G G G G G</td> <td>05 umber of Zono 1 1 1 3 a b control c</td> <td>-27T14:43:28 La CZ 4.ribd2: 04 CFM50 n/a 07 Compact Distribution Basic 6 cation Zone initial</td> <td>06 ber of Ventilation boling Systems 0 HERS Provider: Report Generated 2 -07:00 2x -07:00 2x -07:00 2x -07 0 2x -07 0 7 Duct Inlet Air Sou Zone 1 -07 -07</td> <td>1: 2023-09</td> <td>07 Jumber of Water Heating Systems 1 CCF1R-PRF-0 (Page 9 of 1 05 M50 /a 09 Water Heater Name (#) DHW Heater 1 (1 08 ct Outlet Air Sour Zone 1 07 SRS Verification</td>	ed to be completed in t d 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: re METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 05 e Number of Units 1 1 NA Pand N NA NA NA	oms Nu oms Nu Fime: 22.0.000 v 20220901 on Date/Til e Name: 4 E kage Name: 4 E kage n/a Solar He Syste n/a G G G G G G G G G G G G G G G G G G G	05 umber of Zono 1 1 1 3 a b control c	-27T14:43:28 La CZ 4.ribd2: 04 CFM50 n/a 07 Compact Distribution Basic 6 cation Zone initial	06 ber of Ventilation boling Systems 0 HERS Provider: Report Generated 2 -07:00 2x -07:00 2x -07:00 2x -07 0 2x -07 0 7 Duct Inlet Air Sou Zone 1 -07 -07	1: 2023-09	07 Jumber of Water Heating Systems 1 CCF1R-PRF-0 (Page 9 of 1 05 M50 /a 09 Water Heater Name (#) DHW Heater 1 (1 08 ct Outlet Air Sour Zone 1 07 SRS Verification
detail is provided in the Quality insulation Kitchen range hoo Verified EER/EER/SEE Verified SEER/SEE Verified Refrigera Airflow in habitab Verified HSPF2 Verified heat purr Vall-mounted the Ductless indoor u BUILDING - FEATURES IN Registration Number: CA Building Energy Effic BUILDING ENVELOPE - H Calculation Descriptic BUILDING ENVELOPE - H Calculation Inst: Required MATER HEATING SYSTEF O1 Name DHW Sys 1 DHW Sys 1 CA BUILDING ENVELOPE - H CO1 CARCENTER HEATING SYSTEF O1 CARCENTER HEATING SYSTEF CARCENTER SYSTEF CARC	ary of the features building tables bel n installation (QII) ventilation od 2 ER2 int Charge ble rooms (SC3.1.4. np rated heating ca ermostat in zones g inits located entirel NFORMATION Conditio Condit	ow. Registered Cl 1.7) pacity greater than 150 y in conditioned 02 ned Floor Area (f 1200 2022 Residential ENTIAL PERFOR sis N 02 gh R-value Spray Not Rec 03 Distribution T Standard 03 Distribution T Standard Not Rec 03 03 04 04 04 04 04 04 04 04 04 04	F2Rs and CF3Rs are required         ft2 (SC3.4.5)         space (SC3.1.4.1.8)         Image: SC3.1.4.1.8)         Image: SC3.1.4.1.8) </td <td>ed to be completed in t d 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: re METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 05 e Number of Units 1 1 NA Pand N NA NA NA</td> <td>oms Nu oms Nu Fime: 22.0.000 v 20220901 on Date/Til 22.0.000 v 20220901 on Date/Til e Name: 4 E kage 0 06 Solar He Syste 06 Solar He Solar He Syste 06 Solar He Syste 06 Solar He Syste 06 Solar He Syste 06 Solar He Syste 06 Solar He Syste 06 Solar He Syste 06 Solar He Solar He</td> <td>05 umber of Zone 1 1 3 3 a b a a b a c c c c c c c c c c c c c c</td> <td>-27TT14:43:28 La CZ 4.ribd2: 04 CFM50 n/a 07 Compact Distribution Basic 6 Cocation Con</td> <td>06 ber of Ventilation boling Systems 0 HERS Provider: Report Generated 2 -07:00 2x -07:00 2x -07:00 2x -07 0 2x -07 0 7 Duct Inlet Air Sou Zone 1 -07 -07</td> <td>2023-09</td> <td>07 Jumber of Water Heating Systems 1 CCF1R-PRF-0 (Page 9 of 1 05 M50 /a 09 Water Heater Name (#) DHW Heater 1 (1 08 ct Outlet Air Sour Zone 1 07 SRS Verification</td>	ed to be completed in t d 04 g Number of Bedro 4 Registration Date/ Report Version: 20 Schema Version: re METHOD Calculati Input File 03 ilding Envelope Air Lea N/A 05 e Number of Units 1 1 NA Pand N NA NA NA	oms Nu oms Nu Fime: 22.0.000 v 20220901 on Date/Til 22.0.000 v 20220901 on Date/Til e Name: 4 E kage 0 06 Solar He Syste 06 Solar He Solar He Syste 06 Solar He Syste 06 Solar He Syste 06 Solar He Syste 06 Solar He Syste 06 Solar He Syste 06 Solar He Syste 06 Solar He Solar He	05 umber of Zone 1 1 3 3 a b a a b a c c c c c c c c c c c c c c	-27TT14:43:28 La CZ 4.ribd2: 04 CFM50 n/a 07 Compact Distribution Basic 6 Cocation Con	06 ber of Ventilation boling Systems 0 HERS Provider: Report Generated 2 -07:00 2x -07:00 2x -07:00 2x -07 0 2x -07 0 7 Duct Inlet Air Sou Zone 1 -07 -07	2023-09	07 Jumber of Water Heating Systems 1 CCF1R-PRF-0 (Page 9 of 1 05 M50 /a 09 Water Heater Name (#) DHW Heater 1 (1 08 ct Outlet Air Sour Zone 1 07 SRS Verification

14:43

<text><text><text><text><text></text></text></text></text></text>	<text><text><text></text></text></text>
CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD CF1R-PRF-01E	CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD CF1R-PRF-01E
Project Name: 4 Bedrm Plan       Calculation Date/Time: 2023-09-27T14:43:28-07:00       (Page 5 of 12)         Calculation Description: Title 24 Analysis       Input File Name: 4 Bedrm Plan -1a CZ 4.ribd22x	Project Name: 4 Bedrm PlanCalculation Date/Time: 2023-09-27T14:43:28-07:00(Page 4 of 12)Calculation Description: Title 24 AnalysisInput File Name: 4 Bedrm Plan -1a CZ 4.ribd22xENERGY USE SUMMARY
ENERGY USE INTENSITY           Standard Design (kBtu/ft <sup>2</sup> - yr )         Proposed Design (kBtu/ft <sup>2</sup> - yr )         Compliance Margin (kBtu/ft <sup>2</sup> - yr )         Margin Percentage	Energy UseStandard Design Source Energy (EDR1) (kBtu/ft²-yr)Standard Design TDV Energy (EDR2) (kTDV/ft²-yr)Proposed Design Source Energy (EDR1) (kBtu/ft²-yr)Compliance Margin (EDR2)Compliance Margin (EDR2)
North Facing         21.3         18.75         2.55         11.97	Space Heating         2.81         12.53         1.31         9.99         1.5         2.54           Space Cooling         0.42         19.69         0.34         16.56         0.08         3.13
Net EUl <sup>2</sup> 9.59         7.04         2.55         26.59	IAQ Ventilation         0.47         5.02         0.47         5.02         0         0           Water Heating         2.46         25.98         1.71         20.06         0.75         5.92
East Facing         21.3         18.86         2.44         11.46	Water Heating         2.46         25.98         1.71         20.06         0.75         5.92           Self Utilization/Flexibility         Vertical of the second
Net EUl <sup>2</sup> 9.59         7.15         2.44         25.44	Credit     South Facing
South Facing         Gross EUI <sup>1</sup> 21.3         18.42         2.88         13.52	Efficiency Compliance Total         6.16         63.22         3.83         51.63         2.33         11.59
Net EUI <sup>2</sup> 9.59         6.71         2.88         30.03           West Facing         6.71         6.71         2.88         30.03	Space Heating         2.81         12.53         1.58         12.21         1.23         0.32           Space Cooling         0.42         19.69         0.56         24.14         -0.14         -4.45
Gross EUI <sup>1</sup> 21.3         18.99         2.31         10.85	IAQ Ventilation         0.47         5.02         0.47         5.02         0         0           Water Heating         2.46         25.98         1.71         20.04         0.75         5.94
Net EUI <sup>2</sup> 9.59         7.28         2.31         24.09           Notes	Self Utilization/Flexibility Credit 0 0 0
1. Gross EUI is Energy Use Total (not including PV) / Total Building Area. 2. Net EUI is Energy Use Total (including PV) / Total Building Area.	West Facing Efficiency Compliance Total6.1663.224.3261.411.841.81
Cet	George
Registration Number: Registration Date/Time: HERS Provider: CZ-4-05	Registration Number: HERS Provider: CZ-4-04
CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000 Report Generated: 2023-09-27 14:44:01 Schema Version: rev 20220901	CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000 Report Generated: 2023-09-27 14:44:01 Schema Version: rev 20220901
CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD       CF1R-PRF-01E         Project Name: 4 Bedrm Plan       Calculation Date/Time: 2023-09-27T14:43:28-07:00       (Page 8 of 12)         Calculation Description: Title 24 Analysis       Input File Name: 4 Bedrm Plan -1a CZ 4.ribd22x         FENESTRATION / GLAZING       FENESTRATION / GLAZING       CF1R-PRF-01E	CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHODCF1R-PRF-01EProject Name: 4 Bedrm PlanCalculation Date/Time: 2023-09-27T14:43:28-07:00(Page 7 of 12)Calculation Description: Title 24 AnalysisInput File Name: 4 Bedrm Plan -1a CZ 4.ribd22x(Page 7 of 12)
01     02     03     04     05     06     07     08     09     10     11     12     13     14	ZONE INFORMATION         01       02       03       04       05       06       07         Zone Name       Zone Type       HVAC System Name       Zone Floor Area (ft <sup>2</sup> )       Avg. Ceiling Height       Water Heating System 1       Status
NameTypeSurfaceOrientationAzimuthWithin (ft)Height (ft)Mult.Height (ft2)U-factorOrientationSHGCSHGC SourceExterior ShadingWindow 3WindowRear WallBack1801250.3NFRC0.35NFRCBug Screen	Zone NameZone TypeHVAC System NameZone Floor Area (ft²)Avg. Ceiling HeightWater Heating System 1StatusZone 1ConditionedHVAC System112008DHW Sys 1New
Window 4     Window     Right Wall     Right     270     1     25     0.3     NFRC     0.35     NFRC     Bug Screen	OPAQUE SURFACES         01         02         03         04         05         06         07         08
SLAB FLOORS         01         02         03         04         05         06         07         08	NameZoneConstructionAzimuthOrientationGross Area (ft²)Window and Door Area (ft2)Tilt (deg)Front WallZone 1R-19 Wall0Front40011090
Name     Zone     Area (ft <sup>2</sup> )     Perimeter (ft)     Edge Insul. R-value and Depth     Edge Insul. R-value and Depth     Edge Insul. R-value and Depth     Edge Insul. R-value and Depth     Carpeted Fraction     Heated       Slab     Zone 1     1200     148     none     0     80%     No	Left Wall         Zone 1         R-19 Wall         90         Left         192         25         90           Rear Wall         Zone 1         R-19 Wall         180         Back         400         25         90
OPAQUE SURFACE CONSTRUCTIONS	Right Wall         Zone 1         R-19 Wall         270         Right         192         25         90           Roof         Zone 1         R-38 Roof Attic         n/a         n/a         600         n/a         n/a           Roof 2         Zone 1         R-38 Roof Attic         n/a         n/a         600         n/a         n/a
01     02     03     04     05     06     07     08       Construction Name     Surface Type     Construction Type     Framing     Total Cavity R-value     Interior / Exterior Continuous     U-factor     Assembly Layers	ATTIC
R-19 Wall     Exterior Walls     Wood Framed Wall     2x6 @ 16 in. O. C.     R-19     None / None     0.074     Inside Finish: Gypsum Board Cavity / Frame: R-19 in 5-1/2 in. (R-18) / 2x6	0102030405060708NameConstructionTypeRoof Rise (x in 12)Roof ReflectanceRoof EmittanceRadiant BarrierCool RoofAttic Zone 1Attic RoofZone 1Ventilated40.10.85YesNo
Attic RoofZone 1       Attic Roofs       Wood Framed Ceiling       2x4 @ 24 in. O. C.       R-0       None / 0       0.644       Roofing: Light Roof (Asphalt Shingle) Roof Deck: Wood Siding/sheathing/decking Cavity / Frame: no insul. / 2x4	FENESTRATION / GLAZING         01       02       03       04       05       06       07       08       09       10       11       12       13       14         Name       Type       Surface       Orientation       Azimuth       Width (ft)       Height (ft)       Mult.       Area (ft <sup>2</sup> )       U-factor       SHGC       SHGC Source       Exterior Shading
R-38 Roof Attic       Ceilings (below attic)       Wood Framed Ceiling       2x4 @ 24 in. O. C.       R-38       None / None       0.025       Over Ceiling Joists: R-28.9 insul. Cavity / Frame: R-9.1 / 2x4 Inside Finish: Gypsum Board	WindowWindowFront WallFront01900.3NFRC0.35NFRCBug ScreenFrench DoorWindowFront WallFront01200.3NFRC0.35NFRCBug ScreenWindow 2WindowLeft WallLeft901250.3NFRC0.35NFRCBug Screen
Registration Number: HERS Provider: CZ-4-08	Registration Number:     Registration Date/Time:     HERS Provider:     CZ-4-07
CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000 Report Generated: 2023-09-27 14:44:01 Schema Version: rev 20220901	CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000 Report Generated: 2023-09-27 14:44:01 Schema Version: rev 20220901

ciency Standards - 2022 Residential Compliance	Report Version: 2022.0.000	
	Schema Version: rev 20220901	





THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU has been issued and final inspection COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

> $\triangleleft$ \_\_\_\_

COUNTY OF SAN LUIS OBISPO ACCESSORY DWELLING UNIT SAN LUIS OBISPO, CA	ENERGY COMPLIANCE - PLAN 1
DATE 09/28/2023 SHEET T24 -	101

	INDOOR AIR QUALITY (I	IAQ) FANS		
	Dwelling Unit	02 03 Airflow (CFM) Fan Efficacy	04 05 Includes IAQ Fan Type Heat/Energy	06 07 IAQ Recovery Includes Fault
f applicable):	SFam IAQVentRpt	Citical (W/CFM)           73         0.35	Exhaust No	Effectiveness - SRE     Indicator Display?       n/a / n/a     No
			C <sup>O</sup>	
ate of Compliance. of Title 24, Part 1 and Part 6 of the California Code of Regulations. ided on other applicable compliance documents, worksheets,			o ar	
			Com	
			e e e e e e e e e e e e e e e e e e e	
		O L	COL	
		Lins		
HERS Provider: CZ-4-] Report Generated: 2023-09-27 14:44:01		ciency Standards - 2022 Residential Com	Registration Date/ pliance Report Version: 20 Schema Version: ru	022.0.000 Report Ge
	Title 24, Part 1 and Part 6 of the California Code of Regulations.         ed on other applicable compliance documents, worksheets,	HERS Provider: CZ-4-12 Registration Number: CA Building Energy Effi	HERS Provider:   CZ-4-12   Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Comp	HERS Provider: CZ-4-12 Report Generated: 2023-09-27 14:44:01 Report Generated: 2023-09-27 14:44:01

	I						I						1		
CERTIFICATE OF CC Project Name: 4 Be Calculation Descrip	edrm Plan	E <b>NTIAL PERFORMAN</b> sis	NCE COMPLIANCE N	Calculati	ion Date/Time: 2023 e Name: 4 Bedrm Pl			CF1R-PRF-01E (Page 11 of 12)	CERTIFICATE OF CC Project Name: 4 Be Calculation Descrip	edrm Plan		RFORMAN	CE COMPLIANCE	Cal	culation Date/ ut File Name:
INDOOR AIR QUALIT	Y (IAQ) FANS					5			SPACE CONDITIONIN	IG SYSTEMS					
01	02	03	04	05	06	07	08	09	01	02	0	3	04	05	
Dwelling Unit	Airflow (CFM)	Fan Efficacy (W/CFM)	IAQ Fan Type	Includes Heat/Energy Recovery?	IAQ Recovery Effectiveness - SRE	Includes Fault Indicator Display?	HERS Verification	Status	Name	System Type			Heating Equipmen Count		
SFam IAQVentRpt	73	0.35	Exhaust	No	n/a / n/a	No	Yes		HVAC System1	Heat pump heating coolin	Heat Pum Ig 1	p system	5	Heat Pump Sy 1	stem
				4	2				HVAC - HEAT PUMPS						-2
				Q					01	02	03	04	05	06 07	08
				moliance					Name	System Type	Number o Units	f Efficie Type		Cap 47 Cap 17	Efficiency Type
				ra <sup>8</sup>					Heat Pump System 1	VCHP-ductless	5 5	HSPF		10900 10200	EER2SEER2
			, G						HVAC HEAT PUMPS -	HERS VERIFICATI	ON		G		
			Ö						01	02	0	3	04	05	
			.0						Name	Verified Airflo	w Airflow	Target	Verified EER/EER2	2 Verified SEER/SEEF	Verified
			Cate						Heat Pump System 1-hers-htpump	Not Required			Required	Required	
									VARIABLE CAPACITY	HEAT PUMP CON	IPLIANCE OPTIO	N - HERS V	ERIFICATION		
									01		02	03	04	05	06
		Ger							Name		Certified Low-Static /CHP System	Airflow t Habitabl Rooms	le in Condition		
		is is							Heat Pump Sy	stem 1	Not required	Require	d Required	Required	Not requ
											~				
Registration Numbe	r:			Registration Date/	Time:	HE	RS Provider:	CZ-4-11	Registration Numbe	r:				Registration	Date/Time:
CA Building Energy I	Efficiency Standards - 2	2022 Residential Comp	liance	Report Version: 20 Schema Version: re		Rep	port Generated: 2023-		CA Building Energy E	Efficiency Standard	ds - 2022 Reside	ntial Compl	liance		on: 2022.0.000 ion: rev 202209
							5 P								

CF1R-PRF-01E (Page 10 of 12)

Calculation Date/Time: 2023-09-27T14:43:28-07:0	)(
Input File Name: 4 Bedrm Plan -1a CZ 4.ribd22x	


06 05 07 08 09 Cooling Equipment Count Required **Distribution Name** ooling Unit Name Fan Name Thermostat Type eat Pump System 05 n/a n/a Setback 1 07 08 09 10 11 12 13 Cooling Efficiency SEER / EER / Type SEER2 CEER Zonally Compressor Controlled Type Cap 17 **HERS** Verification Multi-speed Heat Pump System 12.4 Not Zonal 10200 EER2SEER2 16 1-hers-htpump 05 06 07 08 09 Verified Verified Verified Refrigerant Verified Heating Verified Heating SEER/SEER2 Charge HSPF/HSPF2 Cap 47 Cap 17 Required Yes Yes Yes Yes 05 06 07 08 09 10 Wall Mount Thermostat Minimum Certified Indoor Fan not Airflow per Running Continuously non-continuous RA3.3 and Drop Rating Fan SC3.3.3.4.1 Space Required Not required Not required Not required Not required Not required 

HERS Provider: CZ-4-10

Report Generated: 2023-09-27 14:44:01




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



CERTIFICATE OF COM Project Name: Plan 1 Calculation Descriptio	4 Bedrm Plan			Calculation	•	:: 2023-09-26T irm Plan -1a CZ		:00		(Page 3 of
ENERGY USE SUMMARY				1						
Energy Use	Standard Desig Energy (EDR1) (k		tandard Design TDV Energy (EDR2) (kTDV/ft <sup>2</sup> -yr)	Proposed Desig Energy (EDR1) (k		Proposed Des (EDR2) (k	ign TDV Ener; FDV/ft <sup>2</sup> -yr)	gy Complia Margin (I		Complianc Margin (EDF
Space Heating	2.84		12.76	2.13		17	/.34	0.71	L	-4.58
Space Cooling	0		0.3	0	0		0	0		0.3
IAQ Ventilation	0.47		5.05	0.47	6	5	.05	0		0
Water Heating	2.87		33.23	1.92		24	.26	0.95	;	8.97
Self Utilization/Flexibility Credit							0			0
North Facing Efficiency Compliance	6.18		51.34	4.52		46	5.65	1.66	5	4.69
Total										
Space Heating	2.84		12.76	1.99			5.56	0.85	5	-2.8
Space Cooling	0		0.3	0			0	0		0.3
IAQ Ventilation	0.47		5.05	0.47			.05	0		0
Water Heating Self	2.87		33.23	1.91		24	1.12	0.96	)	9.11
Utilization/Flexibility Credit							0			0
East Facing Efficiency Compliance Total	6.18	0	51.34	4.37		44	l.73	1.81	L	6.61
CA Building Energy Effic CERTIFICATE OF COM Project Name: Plan 1 Calculation Descriptio	<b>PLIANCE - RESIDEN</b> 4 Bedrm Plan	TIAL PERFORM	IANCE COMPLIANCE MET	Calculation	20220901 • Date/Time	:: 2023-09-26T drm Plan -1a CZ	20:49:25-07	ort Generated: 2		CZ 20:49:49 CF1R-PRI (Page 6 c
REQUIRED PV SYSTEMS						<u> </u>				
01	02	03	04	05		7 08	09	10	11	12 . Annu
DC System Size (kWdc)	Exception	Module Type	Array Type Po	wer Electronics	CFI Azin	eg) Input	Array Angle (deg)	Tilt: (x in 12)	Inverter Ef (%)	f. Solar Ad
2.38	NA St	tandard (14-17%	5) Fixed	none t	rue 150-	-270 n/a	n/a	<=7:12	96	98
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER	RY hary of the features the building tables below n installation (QII) ventilation od 2	at must be field-	pump water heater; specifi verified by a certified HERS Rs and CF3Rs are required to	Rater as a condition fo	or meeting th	e modeled ener	gy performan	ce for this comp	outer analys	is. Additior
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range hou Verified EER/EER Verified SEER/SEE Verified Refrigera Airflow in habitat Verified HSPF2 Verified heat pun Wall-mounted the	RY hary of the features the building tables below n installation (QII) r ventilation od 2 ER2 ant Charge ble rooms (SC3.1.4.1.7 mp rated heating capac ermostat in zones grea	at must be field- . Registered CF2 ') city ater than 150 ft2	verified by a certified HERS Rs and CF3Rs are required to Compare the second se	Rater as a condition fo	or meeting th	e modeled ener	gy performan	ce for this comp	outer analys	is. Addition
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER Verified SEER/SEE Verified Refrigera Airflow in habitat Verified HSPF2 Verified heat pun Wall-mounted th Ductless indoor u	RY hary of the features the building tables below in installation (QII) ventilation od 2 ER2 ont Charge ole rooms (SC3.1.4.1.7 np rated heating capace ermostat in zones green units located entirely in	at must be field- . Registered CF2 ') city ater than 150 ft2	verified by a certified HERS Rs and CF3Rs are required to Compare the second se	Rater as a condition fo	or meeting th	e modeled ener	gy performan	ce for this comp	outer analys	is. Additior
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER Verified Refrigera Airflow in habitat Verified HSPF2 Verified heat pun Wall-mounted the Ductless indoor u BUILDING - FEATURES II	RY hary of the features the building tables below in installation (QII) ventilation od 2 ER2 int Charge ble rooms (SC3.1.4.1.7 np rated heating capac ermostat in zones great inits located entirely in NFORMATION	at must be field- . Registered CF2 () city ater than 150 ft n conditioned sp 02	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03	Rater as a condition fo be completed in the	or meeting th HERS Registr	e modeled ener y 05		06		07
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER Verified Refrigera Airflow in habitat Verified HSPF2 Verified heat pun Wall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name	RY hary of the features the building tables below in installation (QII) ventilation od 2 ER2 int Charge ole rooms (SC3.1.4.1.7 np rated heating capar ermostat in zones great inits located entirely in NFORMATION	at must be field. Registered CF2 () city ater than 150 ft n conditioned sp 02 02 d Floor Area (ft <sup>2</sup>	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units	Rater as a condition for b be completed in the b be completed in the 04 Number of Bedroon	or meeting th HERS Registr	e modeled ener γ 05 ber of Zones	Number	06 of Ventilation ng Systems	Numl	07 ber of Wate
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER Verified Refrigera Airflow in habitat Verified HSPF2 Verified heat pun Wall-mounted the Ductless indoor u BUILDING - FEATURES II	RY hary of the features the building tables below in installation (QII) ventilation od 2 ER2 int Charge ole rooms (SC3.1.4.1.7 np rated heating capar ermostat in zones great inits located entirely in NFORMATION	at must be field. Registered CF2 () city ater than 150 ft n conditioned sp 02	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling	Rater as a condition fo be completed in the	or meeting th HERS Registr	e modeled ener y 05	Number	06 of Ventilation	Numl	07 ber of Wate
detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER/ Verified SEER/SEE Verified Refrigera Airflow in habitab Verified HSPF2 Verified heat pun Wall-mounted th Ductless indoor u BUILDING - FEATURES II 01 Project Name	RY hary of the features the building tables below in installation (QII) ventilation od 2 ER2 ont Charge ole rooms (SC3.1.4.1.7 np rated heating capace ermostat in zones gree inits located entirely in NFORMATION Conditioned an	at must be field. Registered CF2 () city ater than 150 ft n conditioned sp 02 d Floor Area (ft <sup>2</sup> 1200	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 ) Number of Dwelling Units 1	Rater as a condition for b be completed in the b be completed in the 04 Number of Bedroon	ns Num	e modeled ener γ 05 ber of Zones	Number Coolir HER:	06 of Ventilation ng Systems	Numl Heat	07 ber of Wate ing System 1 CZ-
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified HSPF2 Verified heat pun Wall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effor	RY  Anary of the features the building tables below an installation (QII) a ventilation an Charge ant Charge ant Charge ble rooms (SC3.1.4.1.7 anp rated heating capaae ermostat in zones greater inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDENT 4 Bedrm Plan an: Title 24 Analysis HERS VERIFICATION  Callation (QII) High	at must be field. Registered CF2 ) city ater than 150 ft n conditioned sp 02 d Floor Area (ft <sup>2</sup> 1200 22 Residential Co TIAL PERFORIV	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 Number of Dwelling Units 1 MANCE COMPLIANCE MET	Rater as a condition for o be completed in the o be completed in the o d4 Number of Bedroon 4 Registration Date/Tin Report Version: 2022 Schema Version: rev FHOD Calculation	ns Num ne: .0.000 20220901	e modeled ener γ 05 ber of Zones	Number Coolir HER: Repo	06 of Ventilation ng Systems 0 S Provider: ort Generated: 2	Numl Heat	07 ber of Wate ing Systems 1 CZ- 20:49:49 CF1R-PRF- (Page 9 of
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified heat purn Wall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effice CERTIFICATE OF COM Project Name: Plan 1 Calculation Descriptice BUILDING ENVELOPE - I 01 Quality Insulation Inst Required	RY  hary of the features the building tables below in installation (QII) reentilation od 2 ER2 Int Charge ole rooms (SC3.1.4.1.7 hp rated heating capade ermostat in zones greate inits located entirely in NFORMATION Conditioned an Ciency Standards - 202 PLIANCE - RESIDEN 4 Bedrm Plan on: Title 24 Analysis HERS VERIFICATION Callation (QII) High MS	at must be field. Registered CF2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 Mumber of Dwelling Units 1 MANCE COMPLIANCE MET	Rater as a condition for b be completed in the o be completed in the o d4 Number of Bedroon 4 Registration Date/Tin Report Version: 2022 Schema Version: 202	ns Num ne: .0.000 20220901	e modeled ener γ 05 ber of Zones 1 :: 2023-09-26T drm Plan -1a Cz 04 CFM5	Number Coolir HER: Repo 20:49:25-07: 25.ribd22x	06 of Ventilation ng Systems 0 S Provider: cort Generated: 2	Numl Heat 2023-09-26	07 ber of Wate ing System 1 CZ- 20:49:49 CF1R-PRF (Page 9 or
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified HSPF2 Verified heat pur Wall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effor CERTIFICATE OF COM Project Name: Plan 1 Calculation Description BUILDING ENVELOPE - F 01 Quality Insulation Inst Required WATER HEATING SYSTEI 01	RY  hary of the features the building tables below in installation (QII) rventilation od 2 ER2 int Charge ole rooms (SC3.1.4.1.7 hp rated heating capade ermostat in zones greate inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDEN  4 Bedrm Plan on: Title 24 Analysis HERS VERIFICATION  allation (QII) High MS  02	at must be field. Registered CF2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 Mumber of Dwelling Units 1 MANCE COMPLIANCE MET Dam Insulation Buildir ired	Rater as a condition for b be completed in the o be completed in the o be completed in the o d o d Number of Bedroon 4 Registration Date/Tin Report Version: 2022 Schema Version:	ns Num ne: .0.000 20220901	e modeled ener y 05 ber of Zones 1 :: 2023-09-26T drm Plan -1a Cz 04 CFM5 n/a	Number Coolir HER: Repo	06 of Ventilation ng Systems 0 S Provider: cort Generated: 2 cool cool cool cool cool cool cool coo	05 CFM50 n/a	07 ber of Wate ing System 1 CF1R-PRF- (Page 9 of (Page 9 of 09
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified heat purn Wall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effice CERTIFICATE OF COM Project Name: Plan 1 Calculation Descriptice BUILDING ENVELOPE - I 01 Quality Insulation Inst Required	RY  hary of the features the building tables below in installation (QII) ventilation od 2 ER2 int Charge ble rooms (SC3.1.4.1.7 inp rated heating capade ermostat in zones great inits located entirely in  NFORMATION  Conditioned an  Condit	at must be field. Registered CF2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 Mumber of Dwelling Units 1 MANCE COMPLIANCE MET Dam Insulation Buildir ired	Rater as a condition for b be completed in the o be completed in the o d4 Number of Bedroon 4 Registration Date/Tin Report Version: 2022 Schema Version: 202	or meeting th HERS Registr	e modeled ener y 05 ber of Zones 1 .: 2023-09-26T irm Plan -1a Cz 04 CFM5 n/a ing Co	Number Coolir HER Repo 20:49:25-07: 25.ribd22x	06 of Ventilation ng Systems 0 S Provider: cort Generated: 2	05 CFM50 n/a	07 ber of Wate ing Systems 1 CCZ- 20:49:49 CF1R-PRF- (Page 9 of (Page 9 of
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified HSPF2 Verified HSPF2 Verified HSPF2 Verified HSPF2 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effor CERTIFICATE OF COM Project Name: Plan 1 Calculation Description BUILDING ENVELOPE - F 01 Quality Insulation Inst Required WATER HEATING SYSTEI 01	RY  hary of the features the building tables below in installation (QII) rventilation od 2 ER2 int Charge ole rooms (SC3.1.4.1.7 hp rated heating capade ermostat in zones greate inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDEN  4 Bedrm Plan on: Title 24 Analysis HERS VERIFICATION  allation (QII) High MS  02	at must be field. Registered CF2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 Mumber of Dwelling Units 1 MANCE COMPLIANCE MET Dam Insulation Buildir ired	Rater as a condition for b be completed in the o be completed in the o be completed in the o d o d Number of Bedroon 4 Registration Date/Tin Report Version: 2022 Schema Version:	or meeting th HERS Registr	e modeled ener γ 05 ber of Zones 1 1 :: 2023-09-26T drm Plan -1a CZ 04 CFM5 n/a ing Co Dist	Number Coolir HER Repo 20:49:25-07: 5.ribd22x 5.ribd22x 0	06 of Ventilation ng Systems 0 S Provider: cort Generated: 2 cool cool cool cool cool cool cool coo	05 CFM50 n/a	07 ber of Wate ing Systems 1 CF1R-PRF- (Page 9 of (Page 9 of 09 Vater Heate Name (#)
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range hod Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified heat purn Vall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effice CERTIFICATE OF COM Project Name: Plan 1 Calculation Descriptice BUILDING ENVELOPE - H 01 Quality Insulation Inst Required WATER HEATING SYSTER 01 Name DHW Sys 1	RY  aary of the features the building tables below in installation (QII) reentilation od 2 ER2 int Charge ole rooms (SC3.1.4.1.7 inp rated heating capade ermostat in zones greater inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDEN  4 Bedrm Plan on: Title 24 Analysis HERS VERIFICATION  Callation (QII) High Co2  System Type Domestic Hot Water (DHW)	at must be field. Registered CF2 () city ater than 150 ft2 () city ater than 150 ft2 () city () ci city () city () city () city () city () ci city () city () city c	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 1 MANCE COMPLIANCE MET ANCE COMPLIANCE MET 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Rater as a condition for b be completed in the o be completed in the o be completed in the o d o d Number of Bedroor d a Registration Date/Tin Report Version: 2022 Schema Versio	or meeting th HERS Registr	e modeled ener γ 05 ber of Zones 1 1 :: 2023-09-26T drm Plan -1a CZ 04 CFM5 n/a ing Co Dist	Number Coolir HER: Repo 20:49:25-07: 20:40:25-07: 20:40:25-07: 20:40:25-07: 20:40:25-07: 20:40:25-07: 20:40:25-07: 20:40:25-07: 20:40:25-07: 20:40:40:40:40:40:40:40:40:40:40:40:40:40	06 of Ventilation ng Systems 0 S Provider: ort Generated: 2 00 00 00 00 00 00 00 00 00 00	05 CFM50 n/a	07 ber of Wate ing System 1 CF1R-PRF- (Page 9 of (Page 9 of 09 Vater Heate Name (#)
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER Verified SEER/SEE Verified Refrigera Airflow in habitat Verified HSPF2 Verified heat pum Verified heat pum Vall-mounted the Ductless indoor un BUILDING - FEATURES II 01 Project Name Plan 1 4 Bedrm Plan Registration Number: CA Building Energy Effice CERTIFICATE OF COM Project Name: Plan 1 Calculation Description BUILDING ENVELOPE - H 01 Quality Insulation Inst Required WATER HEATING SYSTEN DHW Sys 1 WATER HEATERS - NEEA	RY  Anary of the features the building tables below an installation (QII) a ventilation an Charge ant Charge ble rooms (SC3.1.4.1.7 anp rated heating capade ermostat in zones green inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDEN  A Bedrm Plan on: Title 24 Analysis  HERS VERIFICATION  Callation (QII)  High  MS  02  System Type  Domestic Hot Water (DHW)  A HEAT PUMP	at must be field- Registered CF2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 Mumber of Dwelling Units 1 MANCE COMPLIANCE MET Coam Insulation Buildir ired 04 buildir ired buildir buildir buildir ired buildir ired buildir bu	Rater as a condition for b be completed in the o be completed in the o be completed in the o d o d Number of Bedroom 4 Registration Date/Tin Report Version: 2022 Schema Version:	or meeting th HERS Registr	e modeled ener γ 05 ber of Zones 1 1 :: 2023-09-26T drm Plan -1a Cz 04 CFM5 n/a ing Co Dist	Number Coolir HER: Repo 20:49:25-07: 20:40:25-07: 20:40:25-07: 20:40:25-07: 20:40:25-07: 20:40:25-07: 20:40:25-07: 20:40:25-07: 20:40:40:40; 20:40:40; 20:40:40; 20:40:40; 20:40:40; 20:40:40; 2	06 of Ventilation ng Systems 0 S Provider: ort Generated: 2 c00 	05 CFM50 n/a tion W	07 ber of Wate ing System 1 CCZ- 20:49:49 CF1R-PRF (Page 9 or 09 Vater Heate Name (#) W Heater 1 08
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range hod Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified heat purn Vall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effice BUILDING ENVELOPE - H 01 Quality Insulation Inst Required WATER HEATING SYSTER 01 Name DHW Sys 1 WATER HEATERS - NEEA 01 Name	RY  aary of the features the building tables below in installation (QII) reentilation od 2 ER2 ant Charge ole rooms (SC3.1.4.1.7 ap rated heating capade ermostat in zones greater inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDEN  A Bedrm Plan on: Title 24 Analysis HERS VERIFICATION  Callation (QII) High Co2  System Type Domestic Hot Water (DHW)  A HEAT PUMP  02	at must be field. Registered CF2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 ) Number of Dwelling Units 1 0 mpliance 04 04 04 04 04 04 04 04 04 04 04 04 04	Rater as a condition for b be completed in the o be completed in the o be completed in the o d o d Number of Bedroor 4 Registration Date/Tin Report Version: 2022 Schema Version:	or meeting th HERS Registr	e modeled ener γ 05 ber of Zones 1 1 2 2023-09-26T drm Plan -1a CZ 04 CFM5 n/a ing Co Dist ing Co Dist	Number Coolir HER: Repo 20:49:25-07: 20:40:40 20:40:40 20:40:40 20:40	06 of Ventilation ng Systems 0 S Provider: ort Generated: 2 s00 s00 s00 s00 s00 s00 s00 s00 s00 s0	05 CFM50 n/a tion W	07 ber of Wate ing System 1 CF1R-PRF (Page 9 o (Page 9 o 0 0 Vater Heate Name (#) W Heater 1 08 utlet Air So
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range hod Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified heat pur Vall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effice CERTIFICATE OF COM Project Name: Plan 1 Calculation Descriptice BUILDING ENVELOPE - H 01 Quality Insulation Inst Required WATER HEATING SYSTEN 01 Name DHW Sys 1 WATER HEATERS - NEEA 01	RY  aary of the features the building tables below in installation (QII) ventilation od 2 ER2 ant Charge ole rooms (SC3.1.4.1.7 apprated heating capade ermostat in zones greater inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDEN  A Bedrm Plan on: Title 24 Analysis  HERS VERIFICATION  Callation (QII) High  MS  02  System Type  Domestic Hot Water (DHW)  A HEAT PUMP  02	at must be field- Registered CF2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 ) Number of Dwelling Units 1 0 mpliance 04 04 04 04 04 04 04 04 04 04 04 04 04	Rater as a condition for b be completed in the o be completed in the o be completed in the o d o d Number of Bedroor d d Registration Date/Tin Report Version: 2022 Schema Versio	or meeting th HERS Registr	e modeled ener y 05 ber of Zones 1 :: 2023-09-26T drm Plan -1a CZ 04 CFM5 n/a ing Co Dist 6	Number Coolir HER: Repo 20:49:25-07: 20:40:40 20:40:40 20:40:40 20:40	06 of Ventilation ng Systems 0 S Provider: ort Generated: 2 cot Generated: 2 cot Generated: 2 dot Generated: 2 cot Generated:	05 CFM50 n/a tion W	07 ber of Wate ing System 1 CCZ. 20:49:49 CF1R-PRF (Page 9 o (Page 9 o 0 0 Vater Heate Name (#) W Heater 1 08
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range hod Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified heat purn Vall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effice BUILDING ENVELOPE - H 01 Quality Insulation Inst Required WATER HEATING SYSTET 01 Name DHW Sys 1 DHW Sys 1 WATER HEATERS - NEEA 01 Name DHW Heater 1 WATER HEATING - COM	RY  ary of the features the building tables below in installation (QII) reentilation od 2 ER2 int Charge ole rooms (SC3.1.4.1.7 inp rated heating capade ermostat in zones greater inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDEN  A Bedrm Plan on: Title 24 Analysis HERS VERIFICATION  Callation (QII) High Co2  System Type Domestic Hot Water (DHW)  A HEAT PUMP  02  # of Units 1  PACT DISTRIBUTION	at must be field. Registered CF2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 MANCE COMPLIANCE MET MANCE COMPLIANCE MET MANCE COMPLIANCE MET 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Rater as a condition for b be completed in the o be completed in the o be completed in the o d o d Number of Bedroor d a Registration Date/Tin Report Version: 2022 Schema Versio	or meeting th HERS Registr	e modeled ener y  05 ber of Zones 1  1  2023-09-26T  trm Plan -1a C2  04  CFM5 n/a  ing Co Dist ing 06  Tank Location TankZone	Number Coolir HER: Repo 20:49:25-07: 25.ribd22x 20:49:25-07: 25.ribd22x	06 of Ventilation ng Systems 0 S Provider: ort Generated: 2 soft Generated: 3 soft G	05 CFM50 n/a tion W	07 ber of Wate ing System 1 CF1R-PRF (Page 9 o 0 09 Vater Heate Name (#) W Heater 1 08 utlet Air So Zone 1
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified HSPF2 Verified HSPF2 Verified HSPF2 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effice BUILDING ENVELOPE - H 01 Quality Insulation Inst Required BUILDING ENVELOPE - H 01 Quality Insulation Inst Required MATER HEATING SYSTER 01 Name DHW Sys 1 DHW Sys 1 DHW Heater 1 DHW Heater 1	RY arry of the features the building tables below in installation (QII) reentilation od 2 ER2 ant Charge ole rooms (SC3.1.4.1.7 apprated heating capade ermostat in zones greater inits located entirely in NFORMATION Conditioned an C	at must be field. Registered CF2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 MNOME OF Dwelling Units 1 MANCE COMPLIANCE MET Deam Insulation Buildir ired 04 04 e Water Heater Name DHW Heater 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Rater as a condition for b be completed in the o be completed in the o be completed in the o d o d Number of Bedroor d d Registration Date/Tin Report Version: 2022 Schema Versio	or meeting th HERS Registr	e modeled ener γ 05 ber of Zones 1 1 2 2023-09-26T drm Plan -1a CZ 04 CFM5 n/a ing Co Dist ing Co Dist	Number Coolir HER: Repo 20:49:25-07: 25.ribd22x 20:49:25-07: 25.ribd22x	06 of Ventilation ng Systems 0 S Provider: ort Generated: 2 s00 s00 s00 s00 s00 s00 s00 s00 s00 s0	05 CFM50 n/a tion W	07 ber of Wate ing System 1 CF1R-PRF (Page 9 o (Page 9 o 0 0 Vater Heate Name (#) W Heater 1 08 utlet Air So
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range hod Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified heat purn Wall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effice BUILDING ENVELOPE - H 01 Quality Insulation Inst Required WATER HEATING SYSTER 01 Name DHW Sys 1 DHW Sys 1 WATER HEATERS - NEEA 01 Name DHW Heater 1 WATER HEATING - COM	RY  ary of the features the building tables below in installation (QII) reentilation od 2 ER2 int Charge ole rooms (SC3.1.4.1.7 inp rated heating capade ermostat in zones greater inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDEN  A Bedrm Plan on: Title 24 Analysis HERS VERIFICATION  Callation (QII) High Co2  System Type Domestic Hot Water (DHW)  A HEAT PUMP  02  # of Units 1  PACT DISTRIBUTION	at must be field. Registered CF2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 Number of Dwelling Units 1 ANCE COMPLIANCE MET oam Insulation Buildir ired 04 04 e Water Heater Name DHW Heater 1 0 3 04 M. (gal) NEEA Heat F Brand DHW Heater 1 8 3 04 M. (gal) NEEA Heat F Brand DHW Heater 1	Rater as a condition for b be completed in the o be completed in the o be completed in the o d o d Number of Bedroom 4 Registration Date/Tin Report Version: 2022 Schema Version:	or meeting th HERS Registr	e modeled ener y  05 ber of Zones 1  1  2023-09-26T  ing 04 CFM5 n/a  ing 06 Tank Locatia TankZone 05	Number Coolir HER: Repo 20:49:25-07: 25.ribd22x 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	06 of Ventilation ng Systems 0 S Provider: ort Generated: 2 soft Generated: 3 soft G	05 CFM50 n/a tion M e Duct O	07 ber of Water ing System 1 CCZ 20:49:49 CF1R-PRF (Page 9 or 09 Vater Heater Name (#) W Heater 1 08 utlet Air So Zone 1
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range hod Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified HSPF2 Verified HSPF2 Verified HSPF2 Verified HSPF2 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effor BUILDING ENVELOPE - H 01 Calculation Description BUILDING ENVELOPE - H 01 Quality Insulation Inst Required WATER HEATING SYSTEI 01 Name DHW Sys 1 DHW Sys 1 WATER HEATERS - NEEA 01 Name DHW Heater 1 WATER HEATING - COM 01	RY  arry of the features the building tables below in installation (QII) reentilation od 2 ER2 ant Charge ole rooms (SC3.1.4.1.7 apprated heating capade ermostat in zones greater inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDENT 4 Bedrm Plan on: Title 24 Analysis HERS VERIFICATION  HERS VERIFICATION  Colomestic Hot Water (DHW)  NEALEAT PUMP  O2  Water Heating 1  PACT DISTRIBUTION  O2  Water Heating	at must be field- Registered CF2 () (ity ater than 150 ft2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 Number of Dwelling Units 1 ANCE COMPLIANCE MET oam Insulation Buildir ired 04 04 e Water Heater Name DHW Heater 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Rater as a condition for b be completed in the o d Number of Bedroom 4 Registration Date/Tin Report Version: 2022 Schema Version: 2	or meeting th HERS Registr	e modeled ener y  05 ber of Zones 1  1  2023-09-26T: drm Plan -1a CZ  04  CFM5  n/a  ing Co Dist ing Co Dist ing Co Dist	Number Coolir HER Repo 20:49:25-07: 5.ribd22x 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	06 of Ventilation ng Systems 0 S Provider: ort Generated: 2 con 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Numi Heat     Numi Heat     D	07 ber of Water ing System 1 CCZ 20:49:49 CF1R-PRF (Page 9 or 09 Vater Heater Name (#) W Heater 1 08 utlet Air So Zone 1
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range hod Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified heat purn Wall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effice BUILDING ENVELOPE - H 01 Quality Insulation Inst Required UATER HEATING SYSTER 01 Name DHW Sys 1 DHW Sys 1 DHW Sys 1 DHW Heater 1 WATER HEATING - COM 01 DWelling Unit type Dwelling	RY  ary of the features the building tables below in installation (QII) reentilation od 2 ER2 ant Charge ole rooms (SC3.1.4.1.7 ap rated heating capade ermostat in zones greater inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDEN  A Bedrm Plan on: Title 24 Analysis  HERS VERIFICATION  Callation (QII) High Co2  System Type Domestic Hot Water (DHW)  Domestic Hot Water (DHW)  A HEAT PUMP  02  A HEAT PUMP  02  Water Heating DHW Sys  DHW Sys  DHW Sys	at must be field- Registered CF2 () (ity ater than 150 ft2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 1 Mumber of Dwelling Units 1 1 Mumber of Dwelling Units 1 Mumber of Dwelling Mumber of Dwel	Rater as a condition for b be completed in the o be completed in the o be completed in the o d o Number of Bedroom 4 Registration Date/Tin Report Version: 2022 Schema Version: 2	or meeting th HERS Registr	e modeled ener y 05 ber of Zones 1 1 2 2023-09-26T drm Plan -1a C2 04 CFM5 n/a ing Co Dist ing Co Dist ing Co Dist ing Co Dist	Number Coolir HER Repo 20:49:25-07: 5.ribd22x 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	06 of Ventilation ng Systems 0 S Provider: ort Generated: 2 cot Generated:	Numi Heat     Numi Heat     D	07 ber of Wate ing System 1 CF1R-PRF (Page 9 o 09 Vater Heate Name (#) W Heater 1 08 utlet Air So Zone 1 07 Verification
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified PSF2 Verified HSPF2 Verified H	RY  ary of the features the building tables below in installation (QII) reentilation od 2 ER2 ant Charge ole rooms (SC3.1.4.1.7 ap rated heating capade ermostat in zones greater inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDEN  A Bedrm Plan on: Title 24 Analysis  HERS VERIFICATION  Callation (QII) High Co2  System Type Domestic Hot Water (DHW)  Domestic Hot Water (DHW)  A HEAT PUMP  02  A HEAT PUMP  02  Water Heating DHW Sys  DHW Sys  DHW Sys	at must be field- Registered CF2 () (ity ater than 150 ft2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 1 Mumber of Dwelling Units 1 1 Mumber of Dwelling Units 1 Mumber of Dwelling Mumber of Dwel	Rater as a condition for b be completed in the o be completed in the o be completed in the o d o Number of Bedroom 4 Registration Date/Tin Report Version: 2022 Schema Version: 2	or meeting th HERS Registr	e modeled ener y  05 ber of Zones 1  1  2023-09-26T  ing 04 CFM5 n/a  ing 06 Tank Locatie TankZone 05 Third furthest Water Heater (ft) n/a  05	Number Coolir HER Repo 20:49:25-07: 25.ribd22x 5.ribd22x 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	06 of Ventilation ng Systems 0 S Provider: ort Generated: 2 cot Generated:	Numi Heat     Numi Heat     D	07 ber of Wate ing System 1 CF1R-PRF (Page 9 o 09 Vater Heate Name (#) W Heater 1 08 utlet Air So Zone 1 07 Verification
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range how Verified EER/EER/ Verified SEER/SEE Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified heat pur Wall-mounted the Ductless indoor u BUILDING - FEATURES II 01 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effor BUILDING ENVELOPE - F 01 Calculation Description BUILDING ENVELOPE - F 01 Quality Insulation Inst Required DHW Sys 1 DHW Sys 1 DHW Sys 1 DHW Heater 1	RY  aary of the features the building tables below in installation (QII) is ventilation od 2 ER2 ant Charge ole rooms (SC3.1.4.1.7 apprated heating capade ermostat in zones greated inits located entirely in  NFORMATION  Conditioned an  Co	at must be field. Registered CF2 () (ity ater than 150 ft n conditioned sp () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to 2 (SC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 Mumber of Dwelling Units 1 MANCE COMPLIANCE MET ANCE COMPLIANCE MET Dimpliance 04 04 04 04 04 04 04 04 04 04 04 04 04	Rater as a condition for b be completed in the o d o d Number of Bedroor 4 Registration Date/Tin Report Version: 2022 Schema Versio	or meeting th HERS Registr	e modeled ener y  05 ber of Zones 1  1  2023-09-26T  ing 04 CFM5 n/a  ing 06 Tank Locatia TankZone 05 Third furthest Water Heater (ft) n/a	Number Coolir HER: Repo 20:49:25-07: 20:40:100:100:100:100:100:100:100:100:100	06 of Ventilation ng Systems 0 S Provider: ort Generated: 2 cot Generated:	Numi Heat     Numi Heat     D	07 ber of Wate ing Systems 1 CF1R-PRF- (Page 9 of 09 Vater Heate Name (#) W Heater 1 08 utlet Air So Zone 1 07 Verification n/a 07
The following is a summ detail is provided in the Quality insulation Indoor air quality Kitchen range hod Verified EER/EER/ Verified EER/EER/ Verified Refrigera Airflow in habitat Verified HSPF2 Verified HSPF2 Verified HSPF2 Verified HSPF2 Verified HSPF2 Uerified HSPF2 Project Name Plan 1 4 Bedrm Pla Registration Number: CA Building Energy Effor BUILDING ENVELOPE - H 01 Calculation Description BUILDING ENVELOPE - H 01 Quality Insulation Inst Required WATER HEATING SYSTEI 01 Name DHW Sys 1 DHW Sys 1 DHW Sys 1 WATER HEATING - NEEA 01 Name DHW Heater 1 WATER HEATING - COM 01 Name DHW Heater 1 WATER HEATING - HERS 01	RY  ary of the features the building tables below in installation (QII) is ventilation od 2 ER2 ant Charge ole rooms (SC3.1.4.1.7  apprated heating capade ermostat in zones greated inits located entirely in  NFORMATION  Conditioned an  Ciency Standards - 202  PLIANCE - RESIDEN  A Bedrm Plan on: Title 24 Analysis  HERS VERIFICATION  Callation (QII) High Co2  System Type Domestic Hot Water (DHW)  Domestic Hot Water (DHW)  A HEAT PUMP  Co2  # of Units  A HEAT PUMP  Co2  Water Heating DHW Sys  CO2  A Water Heating Co2  A HEAT PUMP  A HEAT	at must be field. Registered CF2 () () () () () () () () () () () () ()	verified by a certified HERS Rs and CF3Rs are required to (CSC3.4.5) ace (SC3.1.4.1.8) 03 Number of Dwelling Units 1 Number of Dwelling Units 1 MANCE COMPLIANCE MET Coam Insulation Buildin ired 04 04 e Water Heater Name DHW Heater 1 0 3 0 4 0 4 0 4 9 0 1 0 1 0 1 0 1 0 1 0 1 0 1 0 1 0 1 0	Rater as a condition for b be completed in the b be completed in the oble completed in the oble completed in the oble completed in the of of Number of Bedroom 4 Registration Date/Tin Report Version: 2022 Schema Version:	or meeting th HERS Registr	e modeled ener y  05 ber of Zones 1  05  1  2023-09-26T  drm Plan -1a CZ  04  CFM5  n/a  ing Co Dist Ing Co Dig Co Dist Ing Co Dig Co Dig Co Dist Ing Co Dist Ing	Number Coolir HER: Repo 20:49:25-07: 20:40:100:100: 20:40:100:100:100:100:100:100:100:100:100	06 of Ventilation by Systems 0 S Provider: ort Generated: 2 con con d d d d d d d d d d d d d		07 ber of Wate ing Systems 1 CCZ- 20:49:49 CF1R-PRF- (Page 9 of 09 Vater Heate Name (#) W Heater 1 09 Vater Heate Name (#) W Heater 1 08 utlet Air Sou Zone 1 07 verification n/a 07

	1									
CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD         Project Name: Plan 14 Bedrm Plan         Project Name: Plan 14 Bedrm Plan         Calculation Date/Time: 2023-09-26T20:49:25-07:00         (Page 2 of 12)         Calculation Date/Time: 2023-09-26T20:49:25-07:00         Calculation Date/Time: 2023-09-26T20:49:25-07:00         (Page 2 of 12)         Calculation Date/Time: 2023-09-26T20:49:25-07:00         Celse 2 of 12         Calculation Date/Time: 2023-09-26T20:49:25-07:00         Celse 2 of 12         Celse 2 of 12       Celse	Standard Design         35.1         50.3         43.7            Andard Design         35.1         50.3         43.7             North Facing         30.8         45.7         41.6         4.3         4.6         2.1           Proposed Design         30.5         43.8         40.9         4.6         2.1         3.1           Vorth Facing         30.5         43.8         40.9         4.6         5.8         2.1           Vorth Facing         30.5         43.3         39.4         5.8         10         4.3           Vest Facing         30.2         43.1         40.6         4.9         7.2         3.1 <sup>1</sup> Efficiency EDR includes improvements like a better building envelope and more efficient equipment         7.2         3.1         3.1	Teulding complex when source energy. efficiency and total compliance margins, are greater than or equal to zero and unmet load hour limits are not exceeded <ul> <li>Standard Design PV Capacity. 238 KWdc) East (2.38 KWdc) West (2.38 KWdc) West</li></ul>	CZ-5-02	IFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD ect Name: Plan 1 4 Bedrm Plan ulation Description: Title 24 Analysis :RAL INFORMATION Project Name Plan 1 4 Bedrm Plan Run Title 24 Analysis Project Location	04         City         City         05         Standards Version         2022           06         Zip code         07         Software Version         EnergyPro 9.2           08         Limate Zone         5         09         Front Orientation         EnergyPro 9.2           10         Building Type         5ingle family         11         Number of EnergyPro 9.2         1           12         Project Scope         Newly Constructed         13         Number of Energy Outils         1           14         Addition Cond. Floor Area (ft <sup>2</sup> )         0         13         Number of Stories         1           15         Number of Stories         1         Number of Stories         1         1           16         Existing Cond. Floor Area (ft <sup>2</sup> )         0         15         Number of Stories         1           16         Existing Cond. Floor Area (ft <sup>2</sup> )         0         15         Stories U-factor         0.3           17         Fenestration Average U-factor         0.3         1.5         1.5         1.5           18         Total Cond. Floor Area (ft <sup>2</sup> )         10         0.3         1.5         1.5         1.5	Fuel Type     All electric       PLIANCE RESULTS     PLIANCE RESULTS       01     Building Complies with Computer Performance       02     This building incorporates features that require field testing and/or verificatio       03     This building incorporates one or more Special Features shown below	Registration Number:	Communicating cincency standards - 2022 Mesterinal Compliance Report Version: EV 20220901 Schema Version: EV 20220901	CZ-	5-01
CERTIFICATE OF COMPL Project Name: Plan 1 4 Calculation Description:		COMPLIANCE METHOD Calculation Date/Time: 2023-09 Input File Name: 4 Bedrm Plan		CERTIFICATE OF COMP Project Name: Plan 1 4 Calculation Description ENERGY USE SUMMARY		RMANCE COMPLIANCE METH	Calculation Date/Tim	<b>e:</b> 2023-09-26T20:49:25-07:00 drm Plan -1a CZ 5.ribd22x		CF1R-PRF-01E (Page 4 of 12)
ENERGY USE INTENSITY	Standard Design (kBtu/ft <sup>2</sup>	- yr ) Proposed Design (kBtu/ft <sup>2</sup> - yr ) Compliance N	1argin (kBtu/ft <sup>2</sup> - yr ) Margin Percentage	Energy Use	Standard Design Source	Standard Design TDV Energy	Proposed Design Source	Proposed Design TDV Energy	Compliance Margin (EDR1)	Compliance Margin (EDR2)
North Facing	Standard Design (kBtu/Tt*	- yr ) Proposed Design (KBtu/rt - yr ) Compliance N		Space Heating	Energy (EDR1) (kBtu/ft <sup>2</sup> -yr) 2.84	(EDR2) (kTDV/ft <sup>2</sup> -yr) 12.76	Energy (EDR1) (kBtu/ft <sup>2</sup> -yr)	(EDR2) (kTDV/ft <sup>2</sup> -yr) 11.92	1.34	0.84
Gross EUI <sup>1</sup>	21.24	19	2.24 10.55	Space Cooling	0	0.3	0	0.13	0	0.17
Net EUI <sup>2</sup>	10.06	7.81	2.25 22.37	IAQ Ventilation	0.47	5.05	0.47	5.05	0	0
East Facing				Water Heating	2.87	33.23	1.9	24.07	0.97	9.16
Gross EUI <sup>1</sup>	21.24	18.72	2.52 11.86	Self Utilization/Flexibility			<i>S</i>	0		0
Net EUI <sup>2</sup>	10.06	7.54	2.52 25.05	Credit						
South Facing				South Facing Efficiency Compliance	6.18	51.34	3.87	41.17	2.31	10.17
Gross EUI <sup>1</sup>	21.24	18.39	2.85 13.42	Total			8			
Net EUI <sup>2</sup>	10.06	7.21	2.85 28.33	Space Heating	2.84	12.76	1.88	14.87	0.96	-2.11
West Facing			I	Space Cooling	0	0.3	0	0.1	0	0.2
Gross EUI <sup>1</sup>	21.24	18.69	2.55 12.01	IAQ Ventilation	0.47	5.05	0.47	24.03	0.97	0
Net EUI <sup>2</sup>	10.06	7.51	2.55 25.35	Water Heating Self	2.87	33.23	1.9	24.03	0.97	9.2
Notes				Utilization/Flexibility Credit				0		0
1. Gross EUI is Energy U 2. Net EUI is Energy Use	Use Total (not including PV) / Total Building A e Total (including PV) / Total Building Area.	Area.		West Facing Efficiency			4.25	44.95	1.02	7.20
				Compliance Total	6.18	51.34	4.25	44.05	1.93	7.29
	G				Ge					
	.9				105					
					L.C.					
Registration Number:	*	Registration Date/Time:	HERS Provider: CZ-5-05	Registration Number:	~	R	egistration Date/Time:	HERS Pr	ovider: $C7$ -	5-04
CA Building Energy Efficie	ency Standards - 2022 Residential Complianc		Report Generated: 2023-09-26 20:49:49	CA Building Energy Effici	ency Standards - 2022 Residentia		eport Version: 2022.0.000	Report	Generated: 2023-09-2	
		Schema Version: rev 20220901				S	chema Version: rev 20220901			
Project Name: Plan 1 4		Calculation Date/Time: 2023-09		Project Name: Plan 1 4		RMANCE COMPLIANCE METH	Calculation Date/Tim	e: 2023-09-26T20:49:25-07:00		CF1R-PRF-01E (Page 7 of 12)
Calculation Description		Input File Name: 4 Bedrm Plan			II THE 24 ANAIYSIS		input File Name: 4 Be	drm Plan -1a CZ 5.ribd22x		1
01 02	2 03 04	05 06 07 08 09 10	11 12 13 14	ZONE INFORMATION 01	02	03	04	05 06		07
Name Typ	pe Surface Orientation A	7 Mult   Istactor	U-factor SHGC SHGC Source Exterior Shading	Zone Name	Zone Type	HVAC System Name Zor	e Floor Area (ft <sup>2</sup> ) Avg. C	eiling Height Water Heating	System 1	Status
Window 3 Wind	dow Rear Wall Back	180     1     25     0.3	NFRC 0.35 NFRC Bug Screen	Zone 1	Conditioned	HVAC System1	1200	8 DHW Sy	s 1	New
Window 4 Wind	dow Right Wall Right	270 1 25 0.3	NFRC 0.35 NFRC Bug Screen	OPAQUE SURFACES			4			
SLAB FLOORS	<b>_ I</b>	· · · · · · · · · · · · · · · · · · ·	i	01	02	03 04		Window	07 w and Door	08
01	02 03	04 05	06 07 08	Name	Zone	Construction Azim	0	Gross Area (ft <sup>2</sup> ) Are	ea (ft2)	Tilt (deg)
Name	Zone Area (ft <sup>2</sup> )		ul. R-value Depth Carpeted Fraction Heated	Front Wall Left Wall	Zone 1 Zone 1	R-19 Wall         0           R-19 Wall         90			110 25	90 90
Slab	Zone 1 1200		0 80% No	Rear Wall	Zone 1		0 Back 0 Right		25	90 90
OPAQUE SURFACE CONSTI				Right Wall Roof	Zone 1 Zone 1	R-38 Roof Attic n/	a n/a		25 n/a	90 n/a
01	02 03	04 05 06		Roof 2	Zone 1	R-38 Roof Attic	a n/a	600	n/a	n/a
Construction Name	Surface Type Construction Ty	pe Framing Total Cavity Interior / E R-value R-value	ous U-factor Assembly Layers	ATTIC 01	02	03	4 05		07	08
<u> </u>		K-valu	Inside Finish: Gypsum Board	01 Name	02 Construction	03 04 Type Roof Rise	4 05 (x in 12) Roof Reflectance			08 Cool Roof
R-19 Wall	Exterior Walls Wood Framed W	/all 2x6 @ 16 in. O. C. R-19 None / N	one 0.074 Cavity / Frame: R-19 in 5-1/2 in. (R-18) / 2x6	Attic Zone 1	Attic RoofZone 1	Ventilated 4	0.1	0.85	Yes	No
	G		Exterior Finish: 3 Coat Stucco	FENESTRATION / GLAZIN		6				
Attic RoofZone 1	Attic Roofs Wood Framed	2x4 @ 24 in. O. C. R-0 None /	0     0.644     Roofing: Light Roof (Asphalt Shingle)       Roof Deck: Wood     Siding/sheathing/decking	01 0	2 03 0	4 05 06		10 11 12	13	14
	Centing		Cavity / Frame: no insul. / 2x4	Name Ty	pe Surface Orien	tation Azimuth Width (ft)	leight (ft) Mult. Area (ft <sup>2</sup> ) U-f	actor U-factor SHGC	SHGC Source	Exterior Shading
R-38 Roof Attic	Ceilings (below attic) Ceiling	2x4 @ 24 in. O. C. R-38 None / N	Over Ceiling Joists: R-28.9 insul.one0.025Cavity / Frame: R-9.1 / 2x4	Window Wind	dow Front Wall	ont O	1 90	0.3 NFRC 0.35	NFRC	Bug Screen
			Inside Finish: Gypsum Board	French Door Win				D.3 NFRC 0.35	NFRC	Bug Screen
				Window 2 Window	dow Left Wall Le	ft 90	1 25	0.3 NFRC 0.35	NFRC	Bug Screen
Registration Number:		Registration Date/Time:	HERS Provider: CZ-5-08	Registration Number:		R	egistration Date/Time:	HERS Pr	ovider: CZ-	5-07
CA Building Energy Efficie	ency Standards - 2022 Residential Complianc	ce Report Version: 2022.0.000 Schema Version: rev 20220901	Report Generated: 2023-09-26 20:49:49	CA Building Energy Effici	ency Standards - 2022 Residentia		eport Version: 2022.0.000 chema Version: rev 20220901	Report	Generated: 2023-09-2	26 20:49:49
				•						





LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU has been issued and final inspection COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

> $\triangleleft$ \_\_\_\_

COUNTY OF SAN LUIS OBISPO ACCESSORY DWELLING UNIT SAN LUIS OBISPO, CA PLAN I ENERGY COMPLIANCE \_\_\_\_ **DATE** 09/28/2023

SHEET


T24 - 103

<ol> <li>I certify that the energy features and performance specifications identified</li> <li>The building design features or system design features identified on this C calculations, plans and specifications submitted to the enforcement agence</li> <li>Responsible Designer Name:</li> <li>Company:</li> </ol>	Calculation Date/Time: 2023-09-26120:49:25-07:00 (Page 12 of 1 Input File Name: 4 Bedrm Plan -1a CZ 5.ribd22x  complete.  Documentation Author Signature:  Signature Date: 9/26/2023  CEA/ HERS Certification Identification (If applicable): Phone: Phone: a: pt responsibility for the building design identified on this Certificate of Compliance. I on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations. ertificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, y for approval with this building permit application.  Responsible Designer Signature: Date Signed:	Project Name: Plan 1 4 Bedrm Plan         Calculation Description: Title 24 Analysis         INDOOR AIR QUALITY (IAQ) FANS         01       02       03	Calculation Date/Time: 2023-09 Input File Name: 4 Bedrm Plan 04 05 06	1a CZ 5.ribd22x 07 08 09 Includes Fault	CERTIFICATE OF COMPLIANCE - RES Project Name: Plan 1 4 Bedrm Plan Calculation Description: Title 24 AnSPACE CONDITIONING SYSTEMS0102NameSystem TypeHVAC System1Heat pump heating coolingHVAC - HEAT PUMPS010102NameSystem Type0102Heat Pump System 1VCHP-ductlessHVAC HEAT PUMPS - HERS VERIFICATION010102
Address: City/State/Zip: , Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance	License: Phone: Registration Date/Time: HERS Provider: CZ-5 Report Version: 2022.0.000 Schema Version: rev 20220901	-12 Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Complian	Registration Date/Time: nce Report Version: 2022.0.000 Schema Version: rev 20220901	HERS Provider: CZ-5-11 Report Generated: 2023-09-26 20:49:49	Name       Verified Airflor         Heat Pump System       Not Required         1-hers-htpump       Not Required         VARIABLE CAPACITY HEAT PUMP COM       01         01       01         Name       V         Heat Pump System 1       N         Registration Number:       CA Building Energy Efficiency Standard

Project Name: Pla			NCE COMPLIANCE M	Calculat	ion Date/Time: 2023 le Name: 4 Bedrm Pl			CF1R-PRF-01E (Page 11 of 12)	CERTIFICATE OF CO Project Name: Pla Calculation Descri	n 1 4 Bedrm Plan	<b>PENTIAL PERFORMA</b> ysis	NCE COMPLIANCE I	Calcula	tion Date/Time: 2 ile Name: 4 Bedrr				CF1R-PRF-01E (Page 10 of 12)
INDOOR AIR QUALI	ry (IAQ) fans					5			SPACE CONDITIONIN	IG SYSTEMS					.5			
01	02	03	04	05	06	07	08	09	01	02	03	04	05	06	07		08	09
Dwelling Unit	Airflow (CFM)	Fan Efficacy (W/CFM)	IAQ Fan Type	Includes Heat/Energy Recovery?	IAQ Recovery Effectiveness - SRE	Includes Fault Indicator Display?	HERS Verification	Status	Name	System Type	Heating Unit Name	Heating Equipment Count	Cooling Unit Nam	e Cooling Equipm Count	ent Fan Nan	ne Distrib	ution Name T	Required Thermostat Type
SFam IAQVentRpt	73	0.35	Exhaust	No	n/a / n/a	No	Yes		HVAC System1	Heat pump heating cooling	Heat Pump System 1	5	Heat Pump Systen 1	n <b>0</b> 5	n/a		n/a	Setback
				4	9				HVAC - HEAT PUMPS	6				<u>.</u>				
				Q					01	02	03 0	4 05	06 07	08 09	10	11 12	2	13
				liano					Name	System Type	Number of Units Effici Ty			Cooling Efficiency SEER / Type SEER2		nally Compr trolled Typ		S Verification
			ć	nolit.					Heat Pump System 1	VCHP-ductless	5 HS			ER2SEER2 16	12.4 No	Zonal Mu		: Pump System ners-htpump
			G						HVAC HEAT PUMPS	HERS VERIFICATION								
			ő						01	02	03	04	05	06	07		08	09
									Name	Verified Airflow	Airflow Target	Verified EER/EER2	Verified SEER/SEER2	Verified Refriger Charge	rant Verifie HSPF/HS		ed Heating \ Cap 47	Verified Heating Cap 17
			C C C						Heat Pump System 1-hers-htpump	Not Required	0	Required	Required	Yes	Yes		Yes	Yes
									VARIABLE CAPACITY	HEAT PUMP COMPL	IANCE OPTION - HERS							
		L.							01		02 03	04	05	06	07	08	09	10
		Cer							Name	Lov	ertified Airflov w-Static Habita P System Roon	ble in Condition		Air Filter Sizing & Pressure Drop Rating	Low Leakage Ducts in Conditioned Space	Minimum Airflow per RA3.3 and SC3.3.3.4.1	Certified non-continuous Fan	Indoor Fan not Running Continuously
		15							Heat Pump Sy	vstem 1 Not	required Requir	ed Required	Required	Not required	Not required	Not required	Not required	Not required
	er:			Registration Date/	/Time:	HE	RS Provider:	CZ-5-11	Registration Numbe	er:			Registration Date	e/Time:		HERS Provid	er: CZ-	5-10
Registration Numb								0-0-1										



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU has been issued and final inspection COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



8/2023 8:39:34 PM Users\icox\Documents\2727-01 SLO County ADU\_CD\_CENTRAL\_2022\_icox9EWTU

[	New Home Single Family Version 8.0		New Home Single Family Version 8.0		
	G2. Install Water-Efficient Fixtures           Yes         G2.1 WaterSense Showerheads 1.8 gpm with Matching Compensation Valve	2 2	Yes         C13. Reduced Light Pollution           No         C14. Large Stature Tree(s)	1     1       0     1	InterPointRATED SINGLE FAMIL
	Yes         G2.2 WaterSense Bathroom Faucets 1.0 gpm           ≤1.28 gpf         G2.3 WaterSense Toilets with a Maximum Performance (MaP) Threshold of No Less Than 500 Grams 1.28 gpf OR 1.1 gpf		No         C15. Third Party Landscape Program Certification           No         C16. Maintenance Contract with Certified Professional	0         1           0         1	The GreenPoint Rated checklist tracks green features incorporated into the hom non-profit whose mission is to promote healthy, energy and resource efficient bu The minimum requirements of GreenPoint Rated are: verification of 50 or more p
	No         G3. Pre-Plumbing for Graywater System           No         G4. Operational Graywater System		D. STRUCTURAL FRAME AND BUILDING ENVELOPE D1. Optimal Value Engineering		Community (2) Energy (25), Indoor Air Quality/Health (6), Resources (6), and V Mandatory, E5.2 , H6.1, J5.1, O1, O7. Directions for Use: Column A is a dropdown menu with the options of "Yes", "Ne
	© G5. Thermostatic Shower Valve or Auto-Diversion Tub Spout		No         D1.1 Joists, Rafters, and Studs at 24 Inches on Center           No         D1.2 Non-Load Bearing Door and Window Headers Sized for Load	0 1 2	Select the appropriate dropdown and the appropriate points will appear in the blu The criteria for the green building practices listed below are described in the Green information please visit www.builditgreen.org/greenpointrated
	H. HEATING, VENTILATION, AND AIR CONDITIONING H1. Sealed Combustion Units		No D1.3 Advanced Framing Measures	0         1           0         2	Build It Green is not a code enforcement agency.           A home is only GreenPoint Rated if all features are verified by a Certified Green New Home Single Family Version 8.0
	No         H1.1 Sealed Combustion Furnace           No         H1.2 Sealed Combustion or Heat Pump Water Heater	0         1         -           0         2         -	No         D2. Construction Material Efficiencies           D3. Engineered Lumber	0   1	Project Name: SLO County ADU Plan 1 Project City:San Lus Obispo
	№         H2. High Performing Zoned Hydronic Radiant Heating System           H3. Effective Ductwork	0 1 1 .	No         D3.1 Engineered Beams and Headers           No         D3.2 Wood I-Joists or Web Trusses for Floors	0         1           0         1	MEASURES
	No         H3.1 Duct Mastic on Duct Joints and Seams           No         H3.2 Pressure Balance the Ductwork System		Yes         D3.3 OSB for Subfloor           Yes         D3.4 OSB for Wall and Roof Sheathing	0.5         0.5           0.5         0.5	CALGreen Yes CALGreen Res (REQUIRED)
	H4. ENERGY STAR® Bathroom Fans Per HVI Standards with Air Flow Verified	$\begin{array}{c c c c c c c c c c c c c c c c c c c $	D4. Insulated Headers D5. FSC-Certified Wood		A SITE No A1. Construction Footprint
	H5. Advanced Practices for Cooling H5.1 ENERGY STAR® Ceiling Fans in Living Areas and Bedrooms	0         1	No D5.1 Dimensional Lumber, Studs, and Timber	0         6	A2. Job Site Construction Waste Diversio A2.1 70% C&D Waste Diversion (Including A
	Yes         H6.1 Meet ASHRAE 62.2-2016 Ventilation Residential Standards	ity <u>Y</u> R R R R R	No         D5.2 Panel Products           D6. Solid Wall Systems	0 3 3 	A2.2 Recycling Rates from Third-Party Verifie Yes A3. Recycled Content Base Material
	No         H6.2 Advanced Ventilation Standards           No         H6.3 Outdoor Air is Filtered and Tempered	0         2           0         1	No         D6.1 At Least 90% of Floors           No         D6.2 At Least 90% of Exterior Walls	0         1           0         1	A4. Heat Island Effect Reduction (Non-Ro     No A5. Construction Environmental Quality I
	H7. Effective Range Hood Design and Installation No H7.1 Effective Range Hood Ducting and Design		No         D6.3 At Least 90% of Roofs           No         D7. Energy Heels on Roof Trusses		A6. Stormwater Control: Prescriptive Path
	No         H7.2 Automatic Range Hood Control           No         H8. High Efficiency HVAC Filter (MERV 16+)		16 inches         D8. Overhangs and Gutters           D9. Reduced Pollution Entering the Home from the Garage		No         A6.1 Permeable Paving Material           No         A6.2 Filtration and/or Bio-Retention Features
	No H9. Advanced Refrigerants	0         1           0         1	No D9.1 Detached Garage	0 2 V	Yes A6.3 Non-Leaching Roofing Materials A6.4 Smart Stormwater Street Design
	Yes         H10. No Fireplace or Sealed Gas Fireplace           No         H11. Humidity Control Systems	1         1           0         1           0         1   Only applies to climate zones 1, 3, 5, 6, and 7.	No         D9.2 Mitigation Strategies for Attached Garage           D10. Structural Pest and Rot Controls		No A7. Stormwater Control: Performance Pat
1	No H12. Register Design Per ACCA Manual T		Yes         D10.1 All Wood Located At Least 12 Inches Above the Soil           No         D10.2 Wood Framing Treated With Borates or Factory-Impregnated, or Wall Materials Other Than Wood	1         1           0         1	Yes B1. Fly Ash and/or Slag in Concrete B2. Radon-Resistant Construction
	100%         I1. Onsite Renewable Generation (Solar PV, Solar Thermal, and Wind)           I2. Low Carbon Homes	25 25 25 I	Yes D11. Moisture-Resistant Materials in Wet Areas (such as Kitchen, Bathrooms, Utility Rooms. and Basements)		No B3. Foundation Drainage System
	Yes         I2.1 Near Zero Energy Home           No         I2.2 Low Carbon Home		No         E1. Environmentally Preferable Decking           No         E2. Flashing Installation Third-Party Verified		No         B4. Moisture Controlled Crawlspace           B5. Structural Pest Controls
	No I3. Energy Storage	0     4       0     1	No E3. Rain Screen Wall System	0     2       0     2	No         B5.1 Termite Shields and Separated Exterior           No         B5.2 Plant Trunks, Bases, or Stems at Least 3
	No 14. Solar Hot Water Systems to Preheat Domestic Hot Water J. BUILDING PERFORMANCE AND TESTING		Yes       E4. Durable and Non-Combustible Cladding Materials         E5. Durable Roofing Materials		C. LANDSCAPE
	No         J1. Third-Party Verification of Quality of Insulation Installation           No         J2. Supply and Return Air Flow Testing	0         1           0         1	Yes         E5.1 Durable and Fire Resistant Roofing Materials or Assembly           No         E6. Vegetated Roof	1     1       0     2       2     2	No         C1. Plants Grouped by Water Needs (Hyd           No         C2. Three Inches of Mulch in Planting Ber
	No         J3. Mechanical Ventilation Testing           No         J4. All Electric or Combustion Appliance Safety Testing		F. INSULATION F1. Insulation with 30% Post-Consumer or 60% Post-Industrial Recycled Conte	ent l	C3. Resource Efficient Landscapes
		Option 1: Mixed Fuel - Minimum Delta EDR ranges from 6-10 based on climate zone. P wiring requirements: Dryer - conductor rated for 40 amp, Range - conductor rated for		0         0.5           0         0.5	Yes         C3.1 No Invasive Species Listed by Cal-IPC           No         C3.2 Plants Chosen and Located to Grow to N           C3.3 Drought Tolerant, California Native, Med
	Mixed Fuel Compliance Energy Design Rating J5. Building Performance Exceeds Title 24 Part 6	amp. PV and storage credit allowed. <b>Option 2: All Electric Compliance</b> - Meet Efficiency EDR based on climate zone (0-5). P and Storage credit allowed.	F2. Insulation that Meets the CDPH Standard Method—Residential for		Appropriate Species C4. Minimal Turf in Landscape
		Option 3: Annual Energy Use - Minimum 20% compliance based on annual energy use credit not allowed	PV No F2.2 Ceilings	0 0.5 0 0.5	Yes         C4.1 No Turf on Slopes Exceeding 10% and Nareas Less Than Eight Feet Wide           No         C4.2 Turf on a Small Percentage of Landscap
	5         Select Project Climate Zone           2         J5.1 Home Outperforms Title 24 Part 6	0 25+ C	F3. Low GWP Insulation That Does Not Contain Fire Retardants F3.1 Cavity Walls and Floors	0 1	No         C5. Trees to Moderate Building Temperat           No         C6. High-Efficiency Irrigation System
	Yes         J6. Title 24 Prepared and Signed by a CABEC Certified Energy Analyst           No         J7. Participation in Utility Program with Third-Party Plan Review	1     1	No         F3.2 Ceilings           No         F3.3 Interior and Exterior		No         C7. One Inch of Compost in the Top Six to           No         C8. Rainwater Harvesting System
	№         J8. ENERGY STAR® for Homes           №         J9. EPA Indoor airPlus Certification	0         1           0         2	G. PLUMBING G1. Efficient Distribution of Domestic Hot Water		C9. Recycled Wastewater Irrigation Syste
	No J10. Blower Door Testing K. FINISHES		Yes         G1.1 Insulated Hot Water Pipes           No         G1.2 WaterSense Volume Limit for Hot Water Distribution		C11. Landscape Meets Water Budget
	K1. Entryways Designed to Reduce Tracked-In Contaminants		No G1.3 Increased Efficiency in Hot Water Distribution	0 2	No     C12.1 Environmentally Preferable Materials for     Elements and Fencing
		03			02
	© Build It Green Gre	enPoint Rated New Home Single Family Checklist Version 7.0	© Build It Green Green New Home Single Family Version 8.0	eenPoint Rated New Home Single Family Checklist Version 7.0	© Build It Green New Home Single Family Version 8.0
			Yes         N5.1 Residence Entries with Views to Callers           No         N5.2 Entrances Visible from Street and/or Other Front Doors		Yes K1.1 Individual Entryways Yes K2. Zero-VOC Interior Wall and Ceiling Pa
			No N5.3 Porches Oriented to Street and Public Space N6. Passive Solar Design	0 1	Yes K3. Low-VOC Caulks and Adhesives K4. Environmentally Preferable Materials
			No         N6.1 Heating Load           No         N6.2 Cooling Load		No K4.1 Cabinets K4.2 Interior Trim
			N7. Adaptable Building           No         N7.1 Universal Design Principles in Units		No         K4.3 Shelving           No         K4.4 Doors
			No N7.2 Full-Function Independent Rental Unit N8. Resiliency		K4.5 Countertops K5. Formaldehyde Emissions in Interior F
			No         N8.1 Assessment           No         N8.2 Strategies to Address Assessment Findings	0 1 1 1 1	No         K5.1 Doors           No         K5.2 Cabinets and Countertops
			N9. Social Equity in Community	0     1     1     1       1	No K5.3 Interior Trim and Shelving
			No         N9.1 Diverse Workforce           No         N9.2 Community Location	0         1         1           0         1         1	No         K6. Products That Comply With the Healt           No         K7. Indoor Air Formaldehyde Level Less
			O. OTHER Yes O1. GreenPoint Rated Checklist in Blueprints	Y R R R R R	No K8. Comprehensive Inclusion of Low Emi
			Yes         O2. Pre-Construction Kickoff Meeting with Rater and Subcontractors           No         O3. Orientation and Training to Occupants—Conduct Educational Walkthroug	2         0.5         1         0.5           0         0.5         0.5         0.5         0.5	No         L1. Environmentally Preferable Flooring           ≥25%         L2. Low-Emitting Flooring Meets CDPH 20
			No         O4. Builder's or Developer's Management Staff are Certified Green Building Professionals           O5. Home System Monitors	0 0.5 0.5 0.5 0.5	Yes         L3. Durable Flooring           Yes         L4. Thermal Mass Flooring
			No         O5.1 Energy Home System Monitors           No         O5.2. Water Home System Monitors	0 1 .	M. APPLIANCES AND LIGHTING Yes M1. ENERGY STAR® Dishwasher
			O6. Green Building Education		M2. Efficient Laundry Appliances CEE Tier 2 M2.1 CEE-Rated Clothes Washer
			Yes         O6.1 Marketing Green Building           No         O6.2 Green Building Signage	2     2	Yes M2.2 ENERGY STAR® Dryer
			Yes         O7. Green Appraisal Addendum           No         O8. Detailed Durability Plan and Third-Party Verification of Plan Implementation	Y         R         R         R         R           0         0         1         1         1	No         M2.3 Solar Dryer/ Laundry Lines           <20 cubic feet
_			Summary		Yes         M4.1 Built-In Recycling Center
			Total Available Points in Specific Categorian Control Available Points in Specific Categorian Control		Mo M4.2 Built-In Composting Center
WTU.rvt			Total Points Achieved	78.0 6.0 38.5 8.0 15.0 10.5	Yes         M5.1 High-Efficacy Lighting           No         M5.2 Lighting System Designed to IESNA For Lighting Consultant
X 6 X 6					N. COMMUNITY N1. Smart Development
22					No N1.1 Infill Site N1.2 Designated Brownfield Site
AL_20					No N1.3 Conserve Resources by Increasing Dens
ENTR.					No N1.4 Cluster Homes for Land Preservation N1.5 Home Size Efficiency
					Enter the area of the home, in square feet Enter the number of bedrooms
					No         N2. Home(s)/Development Located Near 1           No         N2.1 Within 1 Mile of a Major Transit Store
county					No N 2.2. Within 1/ 2 mile of a Major Transit N3. Pedestrian and Bicycle Access
SLOC					N3.1 Pedestrian Access to Services Within 1/2 Enter the number of Tier 1 services
27-01 5					Enter the number of Tier 2 services           TBD         N3.2 Connection to Pedestrian Pathways
nts\27.					TBD N3.3 Traffic Calming Strategies N4. Outdoor Gathering Places
ocume					Yes N4.1 Public or Semi-Public Outdoor Gathering N4.2 Public Outdoor Gathering Places with Di
					N5. Social Interaction
Users					05
<del>.</del>	I		© Build It Green Gree	enPoint Rated New Home Single Family Checklist Version 7.0	© Build It Green

1								
TING SYSTEM, VERSION 8.0								
FAMILY CHECKLIST o the home. GreenPoint Rated is administered by Build It Green, a			Targeted	: vel Target	ted:	78 Certifie	d	
fficient buildings in California. or more points; Earn the following minimum points per category: 6), and Water (6); and meet the prerequisites CALGreen				hway Tar			Fuel Compliance Energy Design Rating	
"Yes", "No", or "TBD" or a range of percentages to allocate points. in the blue "points achieved" column.		POII	NTS RE	QUIRED		nimum Point hieved Point		
in the GreenPoint Rated New Home Rating Manual. For more			38.5					
fied GreenPoint Rater and certified by Build It Green.	-	2 6.0		6 8.0	6	6 10.5		
	Points Achieved	Community	nergy	AQ/Health	sources	ter		
	Poi Act	Co	<u> </u>	ossible Po	Ľ Ř	Water	NOTES	
	4		1	1	1	1		
	4							
Diversion	0				1			
cluding Alternative Daily Cover) ty Verified Mixed-Use Waste Facility	2				2			
ial	1				1			THESE PLA
Non-Roof) Quality Management Plan Including Flush-Out	0		1	1				LUIS OBISP PROGRAM
ive Path (section capped at 3 points)	0					1		CANNOT E NO ALTER
Features	0					1		ALTERATIC PERMIT ON
s	1	1				1		HAS BEEN COMPLETE
nce Path	0					3		CONSTRUC
te	1				1			DO THE CO
	0			2	2			FURTHER IN
ice	0			1				INSTRUCTIO
Exterior Wood-to-Concrete Connections	0				1			
at Least 36 Inches from the Foundation	0				1			
pped at 6 for less than 15%. ds (Hydrozoning)	0					1		
ting Beds	0					1		
is Cal-IPC	1				1			
Grow to Natural Size tive, Mediterranean Species, or Other	0				1	3		
0% and No Overhead Sprinklers Installed in								
andscaped Area	2					2		
emperature tem	0		1	1		1		
op Six to Twelve Inches of Soil	0					2		
n System	0					3		
r for Landscape Irrigation get	0					2		
<b>Materials for Site</b> aterials for 70% of Non-Plant Landscape								
	0				1			
Guardia	Dete d No		Ciacle Fe	wile Char		i 70	01	
GreenPoin	1			1				-
iling Paints res	2			2				
aterials for Interior Finish	1			1				
	0				2			S
	0				2			OBISP
	0				1			
nterior Finish Exceed CARB	0			1				ruis
	0			2				
ne Health Product Declaration Open Standard	0			2				
el Less Than 27 Parts Per Billion .ow Emitting Finishes	0			2				SAN
ooring	0				3			
CDPH 2010 Standard Method—Residential	1			3				C
	1		1		1			≿
	1					1		
ər	2		1			2		COUNTY
	2		1					
s ® Refrigerator	0		0.5 2					
Reduction Strategies	1				1			_
	0				1			
	2		2					
ESNA Footcandle Standards or Designed by	0		2					
	0	1			1			
sing Density vation	0	1	2		2			
uare feet					9			
<b>d Near Transit</b> ransit Stop	0	1						
r Transit Stop <b>s</b>	0	2						
s Within 1/2 Mile of Community Services		2						
es es			_					
ways		1						D
		2	1					0
Gathering Places for Residents es with Direct Access to Tier 1 Community	1	1						SH
								<sup>эг</sup>

ç	OUNTY 5 SAN LUIS OBISPO	5
	OBISPO	

THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, T IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING NSPECTORS WILL NOT PROVIDE STEP BY STEP NSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO ACCESSORY DWELLING UNIT SAN LUIS OBISPO, CA	ENERGY COMPLIANCE - PLAN 1
<mark>DATE</mark> 09/28/2023 SHEET T24	- 113