



MODERN  
**ACCESSORY DWELLING UNIT - PLAN 4B**  
 SAN LUIS OBISPO COUNTY, CA

**USER LICENSE AGREEMENT**

BY USING THESE PERMIT READY ACCESSORY DWELLING UNIT CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE, HOLD HARMLESS, AND INDEMNIFY THE COUNTY OF SAN LUIS OBISPO, ITS ELECTED OFFICIALS AND EMPLOYEES, RRM DESIGN GROUP, AND THE ARCHITECT OR ENGINEER WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.

THE PLANS ATTACHED HERE ARE APPROVED FOR ONLY USE IN SAN LUIS OBISPO COUNTY, NO DEVIATIONS, ALTERATIONS, OR OPTIONS BEYOND THOSE SPECIFICALLY INDICATED IN THE PLANS ARE ALLOWED WITHOUT PRIOR APPROVAL BY THE ISSUING JURISDICTION AND CHIEF BUILDING OFFICIAL. ANY UNAPPROVED PLAN MODIFICATIONS MAY BE DEVELOPED THROUGH RRM DESIGN GROUP AND THE APPROVING JURISDICTION IF REQUIRED.



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_

**SHEET INDEX**

G-042	TITLE SHEET - PLAN 4B
G-101	GENERAL NOTES
G-102	INDEX, ABBREVIATIONS, & SYMBOLS
G-103	2022 SINGLE-FAMILY RESIDENTIAL MANDATORY REQUIREMENTS
G-201	CAL GREEN RESIDENTIAL REQUIREMENTS
G-202	CAL GREEN RESIDENTIAL REQUIREMENTS
AS-104	ARCHITECTURAL SITE PLAN (EXAMPLE & INSTRUCTIONS)
A4-102	FLOOR PLAN
A4-111	FINISH, MECHANICAL, & ELECTRICAL PLANS
A4-122	ROOF PLAN & REFLECTED CEILING PLAN
A4-202	ELEVATIONS & BUILDING SECTIONS
A-904	ARCHITECTURAL DETAILS - LOFT
A-905	ARCHITECTURAL DETAILS - LOFT
A-906	ARCHITECTURAL DETAILS - LOFT
A-921	ARCHITECTURAL DETAILS - LOFT
A-923	ARCHITECTURAL DETAILS - LOFT
A-941	METAL ROOF DETAIL REFERENCES
S-101	SHEET INDEX, ABBREVIATIONS & SYMBOLS
S-102	GENERAL NOTES
S-103	GENERAL NOTES, SPECIAL INSPECTION & TESTS
S-201	MODERN PLANS
S-301	TYPICAL CONCRETE DETAILS
S-311	CONCRETE DETAILS
S-312	CONCRETE DETAILS
S-401	TYPICAL WOOD DETAILS
S-402	TYPICAL WOOD DETAILS
S-403	TYPICAL WOOD DETAILS
S-404	TYPICAL WOOD DETAILS
S-411	FLOOR FRAMING DETAILS
S-421	ROOF FRAMING DETAILS
T24 - 405	ENERGY COMPLIANCE - PLAN 4B
T24 - 406	ENERGY COMPLIANCE - PLAN 4B
T24 - 407	ENERGY COMPLIANCE - PLAN 4B
T24 - 408	ENERGY COMPLIANCE - PLAN 4B
T24 - 413	ENERGY COMPLIANCE - PLAN 4
Grand total: 35	

**PROJECT GENERAL NOTES**

THESE NOTES APPLY TO ALL PORTIONS, PHASES AND SUBCONTRACTORS OF THIS PROJECT.  
 APPLICABLE CODES AND STANDARDS:  
 • 2022 CALIFORNIA BUILDING CODE AND ITS APPENDICES AND STANDARDS.  
 • 2022 CALIFORNIA PLUMBING CODE AND ITS APPENDICES AND STANDARDS.  
 • 2022 CALIFORNIA MECHANICAL CODE AND ITS APPENDICES AND STANDARDS.  
 • 2022 CALIFORNIA FIRE CODE AND ITS APPENDICES AND STANDARDS.  
 • 2022 CALIFORNIA ELECTRICAL CODE AND ITS APPENDICES AND STANDARDS.  
 • 2022 CALIFORNIA BUILDING ENERGY EFFICIENCY STANDARDS.  
 • 2022 CALIFORNIA GREEN BUILDING STANDARDS CODE AND ITS APPENDICES AND STANDARDS.

CURRENT COUNTY OF SAN LUIS OBISPO MUNICIPAL CODE.

**PROJECT DIRECTORY**

\*FOR PLANNING STAFF ONLY  
 INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS: \_\_\_\_\_

**APPLICANT (TO BE PROVIDED BY OWNER/APPLICANT)**

ADDRESS: \_\_\_\_\_ PROJECT ADDRESS: \_\_\_\_\_  
 CONTACT: \_\_\_\_\_  
 EMAIL: \_\_\_\_\_  
 PHONE: \_\_\_\_\_

**ARCHITECT**

ADDRESS: 3765 S HIGUERA ST, SUITE 102  
 SAN LUIS OBISPO, CA 93401  
 CONTACT: RANDY RUSSOM  
 EMAIL: RWRUSSOM@RRMDESIGN.COM  
 PHONE: P:(805) 543-1794

**SUPPORTING DOCUMENTS**

\*FOR PLANNING STAFF ONLY  
 INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS: \_\_\_\_\_

UTILITY, GRADING, AND DRAINAGE PLAN TO BE PROVIDED BY OTHERS.

**PV SYSTEM:** NOT REQUIRED. SYSTEM EXEMPTION < 1.80KWDC. SEE TITLE 24

PLEASE PROVIDE THE WASTE RECYCLE FORM FILLED OUT AND SIGNED PRIOR TO ISSUANCE. THE OWNER/APPLICANT/CONTRACTOR/PERSON DOING THE WORK IS REQUIRED TO RECYCLE 75% OF ALL PROJECT CONSTRUCTION AND DEMOLITION DEBRIS.

**ENERGY COMPLIANCE**

PREPARED BY: \_\_\_\_\_ IN BALANCE GREEN CONSULTING  
 DATE PREPARED: \_\_\_\_\_ SEPTEMBER 27, 2023  
 JOB NUMBER: \_\_\_\_\_ CF1R-PRF-01E

**HERS QII:** HERS RATER WILL VERIFY THAT THE HOME'S INSULATION WAS INSTALLED PER THE MANUFACTURER'S INSTRUCTIONS AND PER QUALITY INSULATION INSTALLATION (QII) PROTOCOL.

**HERS VCHP:** HERS RATER WILL NEED TO FOLLOW THE VERIFICATION AND TESTING PROTOCOL FOR THE VARIABLE CAPACITY HEAT PUMP CREDIT REQUIREMENTS, INCLUDING BUT NOT LIMITED TO, VERIFIED REFRIGERANT CHARGE, VERIFIED MINIMUM HSPF AND EER/SEER, AND CAPACITY, DUCTLESS INDOOR UNITS AND THE COMPONENTS ARE WITHIN THE CONDITIONED ENVELOPE, AND AIRFLOW PROVIDED TO ALL HABITABLE SPACES (BDMS AND LIVING SPACE).

**SOILS & FOUNDATIONS**

\*FOR PLANNING STAFF ONLY  
 INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS: \_\_\_\_\_

**NOTE:** THESE PRE-APPROVED PLANS ARE INTENDED FOR FLAT LOTS, WITHOUT THE PRESENCE OF EXPANSIVE OR LIQUEFIABLE SOILS. THE BUILDING OFFICIAL SHALL MAKE THIS DETERMINATION PRIOR TO ISSUING THE PERMIT. A NOTE HAS BEEN ADDED TO THE FOUNDATION PLAN AND FOUNDATION NOTES TO CLEARLY OUTLINE THIS REQUIREMENT. PLEASE REFER TO GENERAL FOUNDATION NOTE 11 ON S4-102 AND FOUNDATION PLAN NOTE 17 ON S4-201.

**PROJECT INFORMATION**

\*FOR PLANNING STAFF ONLY  
 INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS: \_\_\_\_\_

**PROJECT SCOPE:**

- CONSTRUCTION OF A NEW DETACHED ONE STORY 399 SF ACCESSORY DWELLING UNIT WITH 1 BEDROOM AND 1 BATH.
- ALL SITE WORK WITHIN THE PROPERTY LINE.
- ALL THE WORK SHOWN IN THE DRAWINGS AND SPECIFICATIONS.

**SITE INFORMATION (TO BE PROVIDED BY COUNTY OF SAN LUIS OBISPO):**

STREET ADDRESS: \_\_\_\_\_

APN: \_\_\_\_\_  
 ZONING: \_\_\_\_\_  
 LOT SIZE: \_\_\_\_\_  
 LAND USE: \_\_\_\_\_  
 EXISTING USE: \_\_\_\_\_  
 PROPOSED USE: \_\_\_\_\_

**FLOOR AREA RATIO (TO BE PROVIDED BY COUNTY OF SAN LUIS OBISPO)**

MAXIMUM FAR: \_\_\_\_\_  
 PROPOSED FAR: \_\_\_\_\_

**LOT COVERAGE (TO BE PROVIDED BY OWNER / APPLICANT)**

BUILDING: \_\_\_\_\_  
 HARDSCAPE/PAVING: \_\_\_\_\_  
 LANDSCAPE: \_\_\_\_\_

**SETBACKS (TO BE PROVIDED BY COUNTY OF SAN LUIS OBISPO)**

	REQUIRED	PROPOSED
FRONT:		
REAR:	4' - 0" (A.B. NO. 86)	
SIDES:	4' - 0" (A.B. NO. 86)	

**BUILDING INFORMATION:**

NUMBER OF STORIES: 1  
 OCCUPANCY GROUP: R-3 1 & 2 FAMILY DWELLINGS  
 CONSTRUCTION TYPE: VB  
 SPRINKLERED: SEE FIRE SPRINKLER SECTION ON SHEET  
IF YES, A SEPARATE REVIEW/PERMIT IS REQUIRED FOR AUTO SPRINKLER SYSTEM DESIGN (CRC R313.3)  
 MAX. HEIGHT ALLOWED: (PER CBC TABLE 504.3) 16' - 0"  
 MAX. HEIGHT ALLOWED: (PER CALIFORNIA ASSEMBLY BILL NO. 86) 16' - 0"  
 MAX. HEIGHT PROPOSED: \_\_\_\_\_  
 ROOF RATING: REFER TO 'WILDLAND-URBAN INTERFACE FIRE AREA' AND 'FIRE HAZARD SEVERITY ZONE LEVEL'  
 HIGH FIRE ZONE: \_\_\_\_\_

**UTILITIES**

**WATER AND SEWER SERVICE** COUNTY OF SAN LUIS OBISPO UTILITIES  
**ELECTRICAL SERVICE** PACIFIC GAS & ELECTRIC  
**GAS SERVICE** PACIFIC GAS & ELECTRIC  
**TELEPHONE SERVICE** \_\_\_\_\_  
**GARBAGE SERVICE** \_\_\_\_\_  
**CABLE SERVICE** \_\_\_\_\_

**BUILDING AREAS**

GROUND FLOOR PLAN DWELLING AREA	399 SF
LOFT SLEEPING AREA	93 SF
(OPTIONAL) COVERED PORCH	70 SF

**PROJECT CHECKLIST**

\*FOR PLANNING STAFF ONLY  
 INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS: \_\_\_\_\_

**WASTE WATER**  SEWER  SEPTIC - \*A SEPARATE REVIEW & PERMIT IS REQUIRED FOR SEPTIC.

**FIRE SPRINKLERS**

DOES THE PRIMARY RESIDENCE HAVE NFPA 13D SPRINKLERS?  
 NO  YES \*IF YES, A SEPARATE REVIEW & PERMIT IS REQUIRED FOR AUTOMATIC SPRINKLER SYSTEM DESIGN (CRC R313.3)

REQUIRED AT PROPOSED ADU: COUNTY OF SAN LUIS OBISPO FIRE SPRINKLERS SYSTEM REQUIREMENTS FOR ADU BLD-3044

NO (NOT REQUIRED IF THE PRIMARY RESIDENCE IS UNSPRINKLERED)  
 YES (REQUIRED IF THE PRIMARY RESIDENCE IS SPRINKLERED)

**FIRE SPRINKLERS NOTES**

- IF FIRE SPRINKLERS ARE REQUIRED AT PROPOSED ADU THEN THE FOLLOWING NOTES APPLY.
- AUTOMATIC FIRE SPRINKLER SYSTEM - AN AUTOMATIC FIRE SPRINKLER SYSTEM SHALL BE INSTALLED AS PER NFPA 13D THE MOST CURRENT EDITION. DETAILED SPRINKLER PLANS SHALL BE SUBMITTED TO THE FIRE PREVENTION BUREAU AND APPROVED PRIOR TO INSTALLATION. PLANS AND INSTALLATION MUST BE BY A C16 LICENSED SPRINKLER CONTRACTOR.
- SECTION 903.2.1 GROUP R** AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 903.3 SHALL BE PROVIDED THROUGHOUT ALL BUILDINGS WITH A GROUP R FIRE AREA. THIS INCLUDES SINGLE FAMILY DWELLINGS, MULTI-FAMILY DWELLINGS AND ALL RESIDENTIAL CARE FACILITIES REGARDLESS OF OCCUPANT LOAD.
- SECTION 903.2.1.1** ADDITIONS AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH 903.3 MAY BE REQUIRED TO BE INSTALLED THROUGHOUT STRUCTURES WHEN THE ADDITION IS MORE THAN 50% OF THE EXISTING BUILDING OR WHEN THE ALTERED BUILDING WILL EXCEED A FIRE FLOW OF 1,500 GALLONS PER MINUTE AS CALCULATED PER SECTION 907.3. THE FIRE CODE OFFICIAL MAY REQUIRE AN AUTOMATIC SPRINKLER SYSTEM BE INSTALLED IN BUILDINGS WHERE NO WATER MAIN EXISTS TO PROVIDE THE REQUIRED FIRE FLOW OR WHERE A SPECIAL HAZARD EXISTS SUCH AS: POOR ACCESS ROADS, GRADE, BLUFFS AND CANYON RIMS, HAZARDOUS BRUSH AND RESPONSE TIMES GREATER THAN 5 MINUTES BY A FIRE DEPARTMENT.
- SECTION 903.2.1.2** REMODELS OR RECONSTRUCTION AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 903.3 MAY BE REQUIRED IF THE SCOPE OF WORK INCLUDES SIGNIFICANT MODIFICATION TO THE INTERIOR AND/OR ROOF OF THE BUILDING, AND THE COST OF THE INSTALLATION DOES NOT EXCEED 15 PERCENT OF THE CONSTRUCTION COSTS OF THE REMODEL.
- LOCATION AND SIZE OF WATER SERVICE UNDERGROUND SHALL BE INSTALLED AS SHOWN ON APPROVED FIRE SPRINKLER PLANS. A MINIMUM 1 INCH WATER SHALL BE INSTALLED.
- A FIRE UNDERGROUND FLUSH CERTIFICATION SHALL BE REQUIRED AT FINAL INSPECTION.
- A HYDRO INSPECTION OF THE FIRE SPRINKLER SYSTEM IS REQUIRED PRIOR TO FRAME INSPECTION. ONLY THE NEW PIPING SHALL BE TESTED.

**ONSITE PARKING REQUIRED**

- NONE, EXCEPTION USED:
- THE ADU IS LOCATED WITHIN 1/2 MILE OF PUBLIC TRANSIT.
  - OFF STREET PARKING PERMITS ARE REQUIRED BUT NOT OFFERED TO THE OCCUPANT OF THE ADU.
  - WHEN THERE IS A CAR SHARE VEHICLE LOCATED WITHIN ONE BLOCK OF THE ADU.
- ONE PARKING SPACE (STUDIO OR 1-BEDROOM ADU)  
 TWO PARKING SPACES (2-BEDROOM ADU)

**WILDLAND-URBAN INTERFACE FIRE AREA**

- PORTIONS OF THE COUNTY OF SAN LUIS OBISPO COUNTY ARE LOCATED IN WITHIN THE WILDLAND-URBAN INTERFACE FIRE AREA (AS DEFINED BY CRC R337.2).  
 a. AREA DEFINED BY STATE AS A "FIRE HAZARD SEVERITY ZONE" (FHSZ).  
 b. AREA DESIGNATED BY ENFORCING AGENCY TO BE AT A SIGNIFICANT RISK FROM WILDFIRES.
- MORE INFORMATION ABOUT FIRE HAZARD SEVERITY ZONES, INCLUDING AN INTERACTIVE MAP, BUILDING MATERIALS LISTINGS, AND WUI REQUIREMENTS CAN BE FOUND ON THE OFFICE OF THE STATE FIRE MARSHAL WEBSITE (HTTPS://OSFM.FIRE.CA.GOV).
- AN ADU WITHIN THE WILDLAND-URBAN INTERFACE FIRE AREA SHALL COMPLY WITH THE CRC SECTION R337.
- THIS PROTOTYPE PLAN PROVIDES DESIGNS THAT COMPLY WITH THE PROVISIONS REQUIRED BY THE CRC SECTION R337.

**FIRE HAZARD SEVERITY ZONE LEVEL**

- NONE  MODERATE  HIGH  VERY HIGH
- IN ACCORDANCE WITH THE CFC SECTION 4904, STRUCTURES LOCATED IN THE VERY HIGH FIRE HAZARD SEVERITY ZONE SHALL PROVIDE & MAINTAIN A FUEL MODIFICATION ZONE. FUEL MODIFICATION ZONES: THE APPLICANT SHALL PROVIDE & MAINTAIN FIRE/FUEL BREAKS TO THE SATISFACTION OF THE LOCAL FIRE DEPARTMENT. FIRE/FUEL BREAKS SHALL BE SHOWN ON THE GRADING, MAP, AND BUILDING PLANS.

**OPTIONS SELECTIONS**

\*OWNER OR APPLICANT ADDITIONALLY TO PROVIDE SELECTIONS FOR EACH OF THE FOLLOWING CATEGORIES. ADDITIONALLY, OWNER/APPLICANT TO PROVIDE MANUFACTURER, COLOR/FINISH SPECIFICATIONS, & W.U.I. PRODUCT LISTING (WHEN APPLICABLE) IN THE MATERIALS LEGEND.  
**NOTE:** OWNER/APPLICANT TO STRIKE THROUGH UNSELECTED OPTIONS THROUGHOUT THE PLAN SET WHEN APPLICABLE FOR CLARITY.

**FRONT PORCH** (SELECT ONE)  A) FRONT (COVERED) PORCH  B) NO FRONT PORCH

**RAKE & EAVE DETAILS** (SELECT ONE)  A) ENCLOSED  B) OPEN EXPOSED

**EXTERIOR RAKES, EAVES, & PORCH/OVERHANG SOFFIT MATERIALS** (MARK ALL THAT APPLY)

- A) 2X TOUNGE & GROOVED (SOLID SAWN LUMBER)  
 B) FIBER CEMENT SOFFIT PANELS  
 C) HARDBOARD SOFFIT PANELS  
 D) EXT. GRADE FIRE RETARDANT TREATED SHEATHING

**WALL COVERINGS** (MARK ALL THAT APPLY)  
**NOTE:** WALL COVERINGS TO MEET ALL REQUIREMENTS OF CRC R703.3. SEE CRC TABLE R703.3(1) FOR MIN. ATTACHMENT AND MIN. THICKNESS REQUIREMENTS.

- E) FIBER CEMENT HORIZONTAL LAP SIDING  
 F) EXT. GRADE WOOD HORIZONTAL LAP SIDING  
 G) EXT. GRADE WOOD PANEL SIDING

**EXTERIOR TRIM ELEMENTS** (SELECT ONE)  A) FIBER CEMENT  B) EXT. GRADE WOOD

**BASE TRIM 24/A-904** (SELECT ONE)  A) YES  B) NO

**EXTERIOR LIGHT** (SELECT ONE)  A) HAMPTON BAY  B) ROBERT STEVENSON

**ATTIC VENTING METHOD** (SELECT ONE)  
 A) RIDGE & SOFFIT ATTIC VENTING; SEE: 43/A-923 42/A-923 54/A-923  
 B) DORMER VENTS; SEE: 41/A-923 24/A-923

**DOOR MATERIAL** (SELECT ONE)  
 A) VINYL  B) FIBERGLASS  C) WOOD  D) ALUMINUM CLAD WOOD

**WINDOW MATERIAL** (SELECT ONE)  
 A) VINYL  B) FIBERGLASS  C) WOOD  D) ALUMINUM CLAD WOOD

**SPECIAL INSPECTIONS REQUIRED**

OWNER/APPLICANT HAS COMPLETED SPECIAL INSPECTION FORM

OWNER/APPLICANT SIGNATURE: \_\_\_\_\_  
 SEE SHEET S-103 FOR REQUIRED SPECIAL INSPECTIONS

A REGISTERED DESIGN PROFESSIONAL SHALL COMPLETE THE COUNTY OF SAN LUIS OBISPO STATEMENT OF REQUIRED SPECIAL INSPECTIONS CERTIFICATE (FORM BLD-1032) PRIOR TO PERMIT ISSUANCE. IDENTIFY THE TYPE OF WORK REQUIRING SPECIAL INSPECTIONS IN THE PLANS AND THE INDIVIDUALS OR FIRMS RESPONSIBLE FOR THE SPECIAL INSPECTION ELEMENT(S). FURTHER INSTRUCTIONS ARE IDENTIFIED IN THE STATEMENT OF SPECIAL INSPECTION AGREEMENT (FORM BLD-1031).

**VICINITY MAP**

\*FOR PLANNING STAFF ONLY  
 INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS: \_\_\_\_\_

(TO BE PROVIDED BY OWNER/APPLICANT)

COUNTY OF SAN LUIS OBISPO  
 ACCESSORY DWELLING UNIT  
 SAN LUIS OBISPO, CA

TITLE SHEET - PLAN 4B

DATE  
 11/28/2023

SHEET  
 G-042






FIGURE 100.1-A—CALIFORNIA CLIMATE ZONES  
Climate Zones for Residential and Nonresidential Occupancies

SECTION 100.1 – DEFINITIONS AND RULES OF CONSTRUCTION

ABBREVIATIONS


A/C AIR CONDITIONING	EXT EXTERIOR	MAX MAXIMUM	SF SQUARE FOOT
ABV ABOVE	FAACP FIRE ALARM CONTROL PANEL	MDF MEDIUM DENSITY FIBERBOARD	SHT SHEET
ACOUS ACOUSTICAL	FAU FORCED AIR UNIT	MECH MECHANICAL	SHTHG SHEATHING
ACT ACOUSTICAL CEILING TILE	FAWP FLUID APPLIED WATERPROOFING	MEMB MEMBRANE	SIM SIMILAR
ADA AMERICANS WITH DISABILITIES ACT	FD FLOOR DRAIN	MEP MECHANICAL, ELECTRICAL, PLUMBING	SM SHEET METAL
AFCI ARC FAULT CIRCUIT INTERRUPTER	FDC FIRE DEPARTMENT CONNECTION	MFR MANUFACTURER	SPEC SPECIFICATION
AFF ABOVE FINISH FLOOR	FE FIRE EXTINGUISHER	MIN MINIMUM	SQ SQUARE
AL ALUMINUM	FEC FIRE EXTINGUISHER CABINET	MISC MISCELLANEOUS	SS SOLID SURFACE
ALT ALTERNATE	FF FINISHED FLOOR ELEVATION	MO MASONRY OPENING	SSTL STAINLESS STEEL
ARCH ARCHITECT(URAL)	FG FINISHED GRADE	MTD MOUNTED	STC SOUND TRANSMISSION CLASS
BD BOARD	FH FIRE HYDRANT	MTL METAL	STD STANDARD
BDRM BEDROOM	FHC FIRE HOSE CABINET	N NORTH	STL STEEL
BET BETWEEN	FIN FINISH	NIC NOT IN CONTRACT	STOR STORAGE
BIT BITUMINOUS	FIXT FIXTURE	NO NUMBER	STRUCT STRUCTURAL
BLDG BUILDING	FLR FLOOR	NOM NOMINAL	SUSP SUSPENDED
BLKG BLOCKING	FLUOR FLOURESCENT	NTS NOT TO SCALE	SV SHEET VINYL
BLW BELOW	FND FOUNDATION	O.P. OVERFLOW PIPE	SYM SYMMETRICAL
BM BEAM	FO FACE OF	OC ON CENTER	T TREAD
BOT BOTTOM	FOC FACE OF CONCRETE	OD OVERFLOW DRAIN	T&G TONGUE & GROOVE
BUR BUILT UP ROOF	FOF FACE OF FINISH	OFF OFFICE	TEL TELEPHONE
CB CATCH BASIN	FOIC FURNISHED BY OWNER INSTALLED BY CONTRACTOR	OH OPPOSITE HAND	TEMP TEMPERED
CB CALIFORNIA BUILDING CODE	FOM FACE OF MASONRY	OPG OPENING	TER TERRAZZO
CEM CEMENT	FOS FACE OF STUD	OPP OPPOSITE	THK THICK
CFM CUBIC FEET PER MINUTE	FRP FIBERGLASS REINFORCED PANELS	(P) PROPOSED	THR THRESHOLD
CIP CAST IN PLACE	FT FOOT OR FEET	PERM PERIMETER	TJI TRUSS JOIST I-JOIST
CJ CONTROL JOINT	FTG FOOTING	PERP PERPENDICULAR	TO TOP OF
CL CENTER LINE	GA GAUGE, GAGE	PG PAINT GRADE	TOS TOP OF SLAB
CLG CEILING	GALV GALVANIZED	PL PLATE, PROPERTY LINE	TOW TOP OF WALL
CLO CLOSET	GB GRAB BAR	PLAM PLASTIC LAMINATE	TRANS TRANSFORMER
CLR CLEAR	GC GENERAL CONTRACTOR	PLBG PLUMBING	TV TELEVISION
CMU CONCRETE MASONRY UNIT	GFCI GROUND FAULT CIRCUIT INTERRUPTER	PLYWD PLYWOOD	TYP TYPICAL
CO CLEAN OUT	GWB GYPSUM BOARD	PNL PANEL	UFAS UNIFORM FEDERAL ACCESSIBILITY STANDARDS
COL COLUMN	GYP GYPSUM	PP POWER POLE	UG UNDERGROUND
CONC CONCRETE	HB HOSE BIBB	PR PAIR	UNFIN UNFINISHED
CONST CONSTRUCTION	HC HOLLOW CORE	PRTN PARTITION	UNO UNLSS NOTED OTHERWISE
CONT CONTINUOUS	HDWD HARDWOOD	PSF POUNDS PER SQUARE FOOT	UV ULTRAVIOLET
CONTR CONTRACTOR	HDWR HARDWARE	PSI POUNDS PER SQUARE INCH	VCT VINYL COMPOSITION TILE
CPT CARPET	HGT HEIGHT	PSL PARALLEL STRAND LUMBER	VERT VERTICAL
CT CERAMIC TILE	HM HOLLOW METAL	PT PRESSURE TREATED	VIF VERIFY IN FIELD
CTR CENTER	HORIZ HORIZONTAL	PTD PAINTED	VTR VENT TERMINATION PIPE
DBL DOUBLE	HVAC HEATING, VENTILATION, A/C	PV PHOTO VOLTAIC	VWC VINYL WALL COVERING
DF DRINKING FOUNTAIN	ID INSIDE DIAMETER	PVC POLYVINYL CHLORIDE	W WEST
DIA DIAMETER, DIAPHRAGM	IIC IMPACT INSULATION CLASS	PVMT PLYWOOD	W/ WITH
DIM DIMENSION	IN INCH	QTY QUANTITY	WD WASHER DRYER
DN DOWN	INCAND INCANDESCENT	R RADIUS, RISER	WO WITHOUT
DR DOOR	INSUL INSULATION, INSULATED	RB RUBBER BASE	WC WATERCLOSET
DS DOWN SPOUT	INT INTERIOR	RCP REFLECTED CEILING PLAN	WD WOOD
DTL DETAIL	JC JANITORS CLOSET	RD ROOF DRAIN	WDW WINDOW
DW DISHWASHER	JT JOINT	REF REFRIGERATOR	WH WATER HEATER
DWG DRAWING	LAM LAMINATE	REINFORC REINFORCED	WI WROUGHT IRON
(E) EXISTING	LAV LAVATORY	REQD REQUIRED	WIN WINDOW
E EAST	LBS POUNDS	RH RIGHT HAND	WP WATERPROOF(ING)
EA EACH	LEED LEADERSHIP IN ENERGY AND ENVIRONMENTAL DESIGN	RM ROOM	WR WEATHER RESISTIVE
EJ EXPANSION JOINT	LF LINEAR FEET	RO ROUGH OPENING	WRB WATER RESISTIVE BARRIER
EL ELEVATION	LIN LINEN CLOSET	RTU ROOF TOP UNIT (MECH)	WSCT WAINSCOT
ELEV ELEVATION	LINO LINOLEUM	S SOUTH	WT WEIGHT
ELEC ELECTRIC	LT(G) LIGHT(ING)	SAFB SOUND ATTENUATION FIBER BATT	WWF WELDED WIRE FABRIC
ENCL ENCLOSURE	LVL LAMINATED VENEER LUMBER	SC SCUPPER/SOLID CORE	YD YARD
EQ EQUAL	LVT LUXURY VINYL TILE	SCHED SCHEDULE	
EQUIP EQUIPMENT	LW LIGHTWEIGHT	SEAL SEALANT	
EXH EXHAUST		SECT SECTION	
EXP EXPANSION			




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

FIRE HAZARD SEVERITY ZONES

DISCLAIMER: MAP IS FOR GENERAL REFERENCE ONLY. TO ACQUIRE ACCURATE INFORMATION FOR FIRE HAZARD SEVERITY IN SITE SPECIFIC LOCATION, REFER TO THE CALIFORNIA DEPARTMENT OF FORESTRY AND FIRE PROTECTION.



SYMBOLS



COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA

INDEX, ABBREVIATIONS, &  
SYMBOLS

DATE  
11/28/2023  
SHEET

G-102



2022 Single-Family Residential Mandatory Requirements Summary

§ 150.0(m)13: Space Conditioning System Airflow Rate and Fan Efficacy. Space conditioning systems that use ducts to supply cooling must have a hole for the placement of a static pressure probe...

Ventilation and Indoor Air Quality:

- § 150.0(o)1: Requirements for Ventilation and Indoor Air Quality. All dwelling units must meet the requirements of ASHRAE Standard 62.2, Ventilation and Acceptable Indoor Air Quality in Residential Buildings...
§ 150.0(o)1B: Central Fan Integrated (CFI) Ventilation Systems. Continuous operation of CFI air handlers is not allowed to provide the whole-dwelling unit ventilation airflow required per § 150.0(o)1C...

Pool and Spa Systems and Equipment:

- § 110.4(a): Certification by Manufacturers. Any pool or spa heating system or equipment must be certified to have all of the following: compliance with the Appliance Efficiency Regulations and listing in MAEDDS...
§ 110.4(b)1: Piping. Any pool or spa heating system or equipment must be installed with at least 36 inches of pipe between the filter and the heater...
§ 110.4(b)2: Covers. Outdoor pools or spas that have a heat pump or gas heater must have a cover...

5/6/22

03



2022 Single-Family Residential Mandatory Requirements Summary

- § 110.5: Pilot Lights. Continuously burning pilot lights are prohibited for natural gas, fan-type central furnaces, household cooking appliances (except appliances without an electrical supply voltage connection with pilot lights that consume less than 150 Btu per hour)...
§ 150.0(h)1: Building Cooling and Heating Loads. Heating and/or cooling loads are calculated in accordance with the ASHRAE Handbook, Equipment Volume, Applications Volume, and Fundamentals Volume...
§ 150.0(h)3A: Clearances. Air conditioner and heat pump outdoor condensing units must have a clearance of at least five feet from the outlet of any dryer...

Ducts and Fans:

- § 110.8(d)3: Ducts. Insulation installed on an existing space-conditioning duct must comply with § 604.0 of the California Mechanical Code (CMC)...
§ 150.0(m)1: CMC Compliance. All air-distribution system ducts and plenums must meet CMC §§ 601.0-605.0 and ANSIS/MACNA-006-2006 HVAC Duct Construction Standards Metal and Flexible 3rd Edition...
§ 150.0(m)2: Field-Fabricated Duct Systems. Field-fabricated duct systems must comply with applicable requirements for: pressure-sensitive tapes, mastics, sealants, and other requirements specified for duct construction...

5/6/22

02



2022 Single-Family Residential Mandatory Requirements Summary

NOTE: Single-family residential buildings subject to the Energy Codes must comply with all applicable mandatory measures, regardless of the compliance approach used. Review the respective section for more information.

Building Envelope:

- § 110.6(a)1: Air Leakage. Manufactured fenestration, exterior doors, and exterior pet doors must limit air leakage to 0.3 CFM per square foot or less when tested per NFRC-400, ASTM E283, or AAMA WDMA/CSA 1011 S.2/A440-2011...
§ 110.6(a)5: Labeling. Fenestration products and exterior doors must have a label meeting the requirements of § 10-111(a)...
§ 110.6(b): Field fabricated exterior doors and fenestration products must use U-factors and solar heat gain coefficient (SHGC) values from Tables 110.6-A, 110.6-B, or JA4.5 for exterior doors...
§ 110.7: Air Leakage. Gaskets, penetrations, and other openings in the building envelope that are potential sources of air leakage must be caulked, gasketed, or weather-stripped...

Fireplaces, Decorative Gas Appliances, and Gas Log:

- § 110.5(e): Pilot Light. Continuously burning pilot lights are not allowed for indoor and outdoor fireplaces...
§ 150.0(e)1: Closable Doors. Masonry or factory-built fireplaces must have a closable metal or glass door covering the entire opening of the firebox...
§ 150.0(e)2: Combustion Intake. Masonry or factory-built fireplaces must have a combustion outside air intake, which is at least six square inches in area and is equipped with a readily accessible, operable, and tight-fitting damper or combustion-air control device...
§ 150.0(e)3: Flue Damper. Masonry or factory-built fireplaces must have a flue damper with a readily accessible control device...

5/6/22

01



2022 Single-Family Residential Mandatory Requirements Summary

- § 150.0(s): Energy Storage System (ESS) Ready. All single-family residences must meet all of the following: Either ESS-ready interconnection equipment with backed up capacity of 60 amps or more and four or more ESS supplied branch circuits, or a dedicated raceway from the main service to a subpanel that supplies the branch circuits in § 150.0(s)...
§ 150.0(t): Heat Pump Space Heater Ready. Systems using gas or propane furnaces to serve individual dwelling units must include: A dedicated unobstructed 240V branch circuit wiring installed within 3' of the furnace with circuit conductors rated at least 30 amps with the blank cover identified as "240V ready"...
§ 150.0(u): Electric Cooktop Ready. Systems using gas or propane cooktop to serve individual dwelling units must include: A dedicated unobstructed 240V branch circuit wiring installed within 3' of the cooktop with circuit conductors rated at least 50 amps with the blank cover identified as "240V ready"...
§ 150.0(v): Electric Clothes Dryer Ready. Clothes dryer locations with gas or propane plumbing to serve individual dwelling units must include: A dedicated unobstructed 240V branch circuit wiring installed within 3' of the dryer location with circuit conductors rated at least 30 amps with the blank cover identified as "240V ready"...

\*Exceptions may apply.

5/6/22

05



2022 Single-Family Residential Mandatory Requirements Summary

- § 150.0(k)1G: Screw based luminaires. Screw based luminaires must contain lamps that comply with Reference Joint Appendix JA8...
§ 150.0(k)1H: Light Sources in Enclosed or Recessed Luminaires. Lamps and other separable light sources that are not compliant with the JA8 elevated temperature requirements, including marking requirements, must not be installed in enclosed or recessed luminaires...
§ 150.0(k)1I: Light Sources in Drawers, Cabinets, and Linen Closets. Light sources internal to drawers, cabinetry or linen closets are not required to comply with Table 150.0-A or be controlled by vacancy sensors provided that they are rated to consume no more than 5 watts of power...
§ 150.0(k)2A: Interior Switches and Controls. All forward phase cut dimmers used with LED light sources must comply with NEMA SSL 7A...
§ 150.0(k)2B: Interior Switches and Controls. Exhaust fans must be controlled separately from lighting systems...
§ 150.0(k)2C: Accessible Controls. Lighting must have readily accessible wall-mounted controls that allow the lighting to be manually turned on and off...
§ 150.0(k)2D: Multiple Controls. Controls must not bypass a dimmer, occupant sensor, or vacancy sensor function if the dimmer or sensor is installed to comply with § 150.0(k)...
§ 150.0(k)2E: Energy Management Control Systems. An energy management control system (EMCS) may be used to comply with dimming, occupancy, and control requirements if it provides the functionality of the specified control per § 110.9 and the physical controls specified in § 150.0(k)2A...
§ 150.0(k)2F: Automatic Shut-off Controls. In bathrooms, garages, laundry rooms, utility rooms and walk-in closets, at least one installed luminaire must be controlled by an occupancy or vacancy sensor providing automatic off functionality...
§ 150.0(k)2G: Dimmers. Lighting in habitable spaces (e.g., living rooms, dining rooms, kitchens, and bedrooms) must have readily accessible wall-mounted dimming controls that allow the lighting to be manually adjusted up and down...
§ 150.0(k)2H: Independent controls. Integrated lighting of exhaust fans shall be controlled independently from the fans...
§ 150.0(k)3A: Residential Outdoor Lighting. For single-family residential buildings, outdoor lighting permanently mounted to a residential building, or to other buildings on the same lot, must have a manual on/off switch and either a photocell and motion sensor or automatic time switch control...
§ 150.0(k)4: Internally illuminated address signs. Internally illuminated address signs must either comply with § 140.8 or consume no more than 5 watts of power...
§ 150.0(k)5: Residential Garages for Eight or More Vehicles. Lighting for residential parking garages for eight or more vehicles must comply with the applicable requirements for nonresidential garages in §§ 110.9, 130.0, 130.1, 130.4, 140.6, and 141.0...

Solar Readiness:

- § 110.10(a)1: Single-family Residences. Single-family residences located in subdivisions with 10 or more single-family residences and where the application for a tentative subdivision map for the residences has been deemed complete and approved by the enforcement agency, which do not have a photovoltaic system installed, must comply with the requirements of § 110.10(b)-(e)...
§ 110.10(b)1A: Minimum Solar Zone Area. The solar zone must have a minimum total area as described below. The solar zone must comply with access, pathway, smoke ventilation, and spacing requirements as specified in Title 24, Part 9 or other parts of Title 24 or in any requirements adopted by a local jurisdiction...
§ 110.10(b)2: Azimuth. All sections of the solar zone located on steep-sloped roofs must have an azimuth between 90-300° of true north...
§ 110.10(b)3A: Shading. The solar zone must not contain any obstructions, including but not limited to: vents, chimneys, architectural features, and roof mounted equipment...
§ 110.10(b)3B: Shading. Any obstruction located on the roof or any other part of the building that projects above a solar zone must be located at least twice the horizontal distance of the height difference between the highest point of the obstruction and the horizontal projection of the nearest point of the solar zone, measured in the vertical plane...
§ 110.10(b)4: Structural Design Loads on Construction Documents. For areas of the roof designated as a solar zone, the structural design loads for roof dead load and roof live load must be clearly indicated on the construction documents...
§ 110.10(c): Interconnection Pathways. The construction documents must indicate a location reserved for inverters and metering equipment and a pathway reserved for routing of conduit from the solar zone to the point of interconnection with the electrical service...
§ 110.10(d): Documentation. A copy of the construction documents or a comparable document indicating the information from § 110.10(b)-(c) must be provided to the occupant...
§ 110.10(e)1: Main Electrical Service Panel. The main electrical service panel must have a minimum busbar rating of 200 amps...
§ 110.10(e)2: Main Electrical Service Panel. The main electrical service panel must have a reserved space to allow for the installation of a double pole circuit breaker for a future solar electric installation. The reserved space must be permanently marked as "For Future Solar Electric."

Electric and Energy Storage Ready:

5/6/22

04



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRACT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO ACCESSORY DWELLING UNIT SAN LUIS OBISPO, CA

2022 SINGLE-FAMILY RESIDENTIAL MANDATORY REQUIREMENTS

DATE 11/28/2023

SHEET


G-103





# SITE PLAN TO BE PROVIDED BY APPLICANT

## SITE PLAN LEGEND



## SITE PLAN GENERAL NOTES


- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS
- REFER TO STRUCTURAL PLANS FOR FURTHER INFORMATION.

## SITE PLAN CHECKLIST

- ELECTRICAL PANEL:**
- OPTION 1 -** NEW ELECTRICAL MAIN PANEL WITH 225 AMP MINIMUM BUSBAR RATING
  - OPTION 2 -** A NEW ELECTRICAL SUBPANEL CONNECTS TO THE ELECTRICAL MAIN PANEL OF THE PRIMARY HOME WITH A 225 AMP MINIMUM BUSBAR RATING. A SEPARATE ELECTRICAL PERMIT SHALL BE PULLED FOR THE ELECTRICAL MAIN PANEL OF THE PRIMARY HOME. ELECTRICAL LOAD CALCULATIONS IS REQUIRED.
- IS THE NEW ADU IS 5' - 0" OR LESS TO ANY PROPERTY LINE AND/OR ADU IS 10' - 0" OR LESS FROM ANY ADJACENT BUILDING OR STRUCTURE?**
- NO**     **YES;** IF YES, 1-HR FIRE RATED WALL, 1-HR RATED ROOF, AND 1-HR RATED FIRE PROJECTS REQUIRED. **SEE DETAILS: 21/A-903 & 24/A-903**
- NOTE:** WHERE 1-HR FIRE-RESISTANCE RATED PROJECTIONS REQUIRED (NON-SPRINKLERED & FIRE SEPARATION DISTANCE ≥2'-0" <5'-0")
- TABLE 302.1(1)**  
 A. THE FIRE-RESISTANCE RATING SHALL BE PERMITTED TO BE REDUCED TO 0 HOURS ON THE UNDERSIDE OF THE EAVE OVERHANG IF FIREBLOCKING IS PROVIDED FROM THE WALL TOP PLATE TO THE UNDERSIDE OF THE ROOF SHEATING
- NOTE:**
- A SEPARATE PERMIT FOR ONSITE WASTEWATER SYSTEM WILL BE REQ'D.**
  - SOILS REPORT TO BE PROVIDED BY OTHERS.**
  - UTILITY, GRADING, AND DRAINAGE PLAN TO BE PROVIDED BY OTHERS.**
  - PROVIDE WASTE RECYCLE FORM FILLED OUT AND SIGNED PRIOR TO ISSUANCE. THE OWNER/APPLICANT/CONTRACTOR/PERSON DOING THE WORK IS REQUIRED TO RECYCLE 75% OF ALL PROJECT CONSTRUCTION AND DEMOLITION DEBRIS.**
  - FOOTPRINT OF ALL EXISTING AND PROPOSED BUILDINGS**  
PLOT THE PROPOSED ADU BUILDING FOOTPRINT ALONG WITH ANY OTHER EXISTING BUILDINGS ONSITE. THIS INCLUDES ALL STRUCTURES / PORCHES / GAZEBOS. IF AN OPTIONAL COVERED PATIO IS SELECTED, PLEASE PLOT THAT AS WELL.
  - AREA OF EXISTING BUILDING**  
INDICATE THE SQUARE FOOTAGE OF THE EXISTING HOUSE.
  - FOOTPRINT OF PROPOSED ADU**  
REFER TO LEGEND FOR FOOTPRINT AT 10'=1" SCALE
  - DRAWING SCALE**  
SITE PLAN SHOULD BE DRAWN TO A MEASURABLE SCALE.
  - PROPERTY LINES**  
SHOW OUTLINE OF PROPERTY USING DASHED LINE IN LEGEND. INDICATE THE BEARING AND DISTANCE OF THE PROPERTY LINE.
  - LABEL YARDS**  
LABEL FRONT, REAR, SIDE YARDS, AS WELL AS DRIVEWAYS, PATHWAYS AND ANY OTHER HARDSCAPE.
  - SETBACKS**  
DIMENSION THE DISTANCE BETWEEN BUILDINGS AND PROPOERTY LINES, AS WELL AS BUILDINGS TO OTHER STRUCTURES. SETBACKS TO SIDE AND REAR PROPERTY SIDE SHALL BE A MINIMUM OF (4' - 0"). PROPOSED ADU SHALL BE LOCATED A MINIMUM OF (10' - 0") FROM EXISTING STRUCTURES.
  - EASEMENTS**  
REFER TO LEGEND. MUST INCLUDE ALL APPLICABLE EASEMENTS. SETBACK PROPOSED STRUCTURE HSALL COMPLY WITH EASEMENT REQUIREMENTS.
  - LOCATION OF RAIN WATER LEADERS**  
THE ROOF DRAINS SHOULD DRAIN AWAY FROM THE PROPERTY LINES AND INTO THE LANDSCAPE AREA.
  - LABEL STREETS & SIDEWALKS**
  - LABEL ADU AND ADDRESS LOCATION**  
ADU SHALL HAVE THE SAME ADDRESS AS THE PRIMARY RESIDENCE. THE ADDRESS IDENTIFICATION SHALL BE LEGIBLE AND PLACED IN A POSITION THAT IS VISIBLE FROM THE STREET OR ROAD FRONTING THE PROPERTY. ADDRESS IDENTIFICATION CHARACTERS SHALL CONTRAST WITH THEIR BACKGROUND. ADDRESS SHALL COMPLY WITH **CRC SECTION R319**.
  - DIMENSION BUILDING SEPARATION**  
DIMENSION THE DISTANCE BETWEEN THE PROPOSED ADU AND ANY EXISTING STRUCTURES
  - ALL EXISTING/PROPOSED PLANTINGS AND HARDSCAPE SHOWN**
  - LOT COVERAGE CALCULATION**  
TOTAL FOOTPRINT AREA FOR STRUCTURES ON SITE / LOT AREA
  - SWIMMING POOLS**  
ALL EXISTING SWIMMING POOLS SHALL BE SHOWN ON THE SITE PLAN AND SHALL HAVE 10' - 0" MINIMUM SETBACK TO THE NEW ADU STRUCTURE.
  - PORCHES**  
THERE SHALL BE NO MORE THAN 30 INCHES MEASURED VERTICALLY TO THE FLOOR OR GRADE BELOW (INCLUDING FLOORS, STAIRS, RAMPS, AND LANDINGS) ANYWHERE MEASURED LESS THAN 36 INCHES HORIZONTALLY TO THE EDGE OF THE PORCH/SLAB/SURFACE OF THE RAIL. INSECT SCREENING SHALL NOT BE CONSIDERED AS A GUARD.
  - LOCATION OF EXISTING UTILITIES**  
UTILITIES, POLES, SEWER, DRAINS, ELECTRICAL, GAS METERS AND LINES AND ANY PHOTOVOLTAIC.
  - LOCATION OF PROPOSED UTILITIES**  
SANITARY SEWER FROM ADU TO EXISTING SEWER. SEWER LINE TO THE PROPOSED ADU SHALL BE CONNECTED TO THE MAIN LATERAL AT THE PROPERTY LINE OR BEHIND THE SIDEWALK. LATERAL POINT OF CONNECTION INCLUDING REQUIRED CLEANOUTS, WATER LINE TO ADU, ELECTRIC TO ADU INCLUDING ANY NEW METERS OR SUBPANELS, GAS LINE TO ADU.
    - A.** TOTAL DEVELOPED LENGTH OF GAS SYSTEM FROM METER / REGULATOR TO MOST REMOTE GAS OUTLET.
    - B.** TOTAL DEVELOPED LENGTH FOR EACH GAS BRANCH AND ITS CORRESPONDING DEMAND.
    - C.** SHOW MECHANICAL, PLUMBING, AND KITCHEN GAS APPLIANCE LOCATION AND ITS DEMAND FACTORS.
    - D.** SHOW THE LOCATION AND AMPACITY OF THE ELECTRICAL PANEL SERVING THE ADU. VERIFY COMPLIANCE WITH ALL APPLICABLE REQUIREMENTS OF THE 2022 CEC.



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRACT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



**1 SITE PLAN EXAMPLE**  
SCALE: 1" = 20'-0"

**COUNTY OF SAN LUIS OBISPO**  
**ACCESSORY DWELLING UNIT**  
 SAN LUIS OBISPO, CA  
**ARCHITECTURAL SITE PLAN**  
 (EXAMPLE & INSTRUCTIONS)

**DATE**  
11/28/2023  
**SHEET**  
AS-104

**SITE PLAN**

SCALE:





THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRACT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

### FLOOR PLAN GENERAL NOTES

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
- REFER TO STRUCTURAL PLANS FOR FURTHER INFORMATION.
- REFER TO ELECTRICAL PLANS FOR FURTHER INFORMATION IF PROVIDED.
- REFER TO MECHANICAL PLANS, DRAWINGS OR REPORTS FOR FURTHER INFORMATION.
- ALL FURNITURE AND EQUIPMENT IS BY OWNER AND IS SHOWN FOR COORDINATION PURPOSES ONLY.
- DIMENSIONS ARE TO FACE OF FRAMING UNLESS SPECIFICALLY NOTED OTHERWISE.
- PROVIDE ADEQUATE BLOCKING IN WALLS FOR CABINETS AND OTHER WALL MOUNTED ACCESSORIES INCLUDING BUT NOT LIMITED TO HANDRAILS, SHELVING AND BATHROOM FIXTURES.
- DOOR AND WINDOW DIMENSIONS ARE CENTERED AT OPENINGS.
- WHERE DOOR IS LOCATED WITHOUT DIMENSION AT THE CORNER OF A ROOM IT SHALL BE 4" FROM FACE OF FRAMING OF ADJACENT WALL TO ROUGH DOOR OPENING.
- WHERE RECESSED FIXTURES OCCUR IN WALLS OR HORIZONTAL ASSEMBLIES, THE FIRE RATING OF THOSE ASSEMBLIES SHALL BE MAINTAINED.
- AT ALL PENETRATIONS AND INTERSECTIONS OF FIRE-RATED PARTITIONS, PROVIDE FIRE SEALANT AND/OR FIRE STOPPING TO MAINTAIN CONTINUITY OF PARTITION RATING.
- PER CRC R311.3 FLOORS OR LANDINGS AT EXTERIOR DOORS SHALL BE AT LEAST AS WIDE AS DOOR SERVED AND SHALL PROVIDE A LENGTH IN THE DIRECTION OF TRAVEL EQUAL TO 36 INCHES MINIMUM. SLOPE OF EXTERIOR LANDINGS SHALL NOT EXCEED 1/4" PER FOOT (2% SLOPE).
- PER CRC 327.1.1 REINFORCEMENT FOR GRAB BARS SHALL BE PROVIDED IN AT LEAST ONE BATHROOM. 1. REINFORCEMENT SHALL BE SOLID LUMBER OR OTHER CONSTRUCTION MATERIALS APPROVED BY THE ENFORCING AGENCY. 2. REINFORCEMENT SHALL NOT BE LESS THAN 2X8 INCH NOMINAL LUMBER OR OTHER MATERIAL PROVIDING EQ. HT. AND CAPACITY. REINFORCEMENT ABOVE THE FINISHED FLOOR FLUSH WITH THE WALL FRAMING. 3. WATER CLOSET REINFORCEMENT SHALL BE INSTALLED ON BOTH SIDE WALLS OF THE FIXTURE, OR ONE SIDE WALL AND THE BACK WALL. 4. SHOWER REINFORCEMENT SHALL BE CONTINUOUS WHERE WALL FRAMING IS PROVIDED. 5. BATH TUB AND COMBINATION BATH TUB/SHOWER REINFORCEMENT SHALL BE CONTINUOUS ON EACH END OF THE BATH TUB AND THE BACK WALL. ADDITIONALLY, BACK WALL REINFORCEMENT FOR A LOWER GRAB BAR SHALL BE PROVIDED WITH THE BOTTOM EDGE LOCATED NO MORE THAN 6 INCHES ABOVE THE BATH TUB RIM.

### WALL LEGEND



- EXTERIOR - 5 1/2" WOOD STUD W/ SHEATHING AND EXTERIOR FINISH (REFER TO ELEVATIONS), ONE LAYER GYPSUM WALL BOARD INTERIOR.
- EXTERIOR - DOUBLE 5 1/2" WOOD STUD W/ SHEATHING AND EXTERIOR FINISH (REFER TO ELEVATIONS)
- INTERIOR - 3 1/2" WOOD STUD W/ ONE LAYER GYPSUM WALL BOARD EACH SIDE.

NOTE: SEE MANUFACTURER'S PRODUCT LISTINGS FOR IMPROVED SOUND AND/OR MOISTURE/MOLD/MILDEW-RESISTANT PERFORMANCE. VISIT GYPSUM.ORG FOR MORE INFORMATION.


### KEYNOTES

- A01 30" WIDE FREE STANDING ELECTRIC RANGE OVEN. VENT TO EXTERIOR, STAINLESS STEEL.
- A05 REFRIGERATOR LOCATION. PROVIDE 42" SPACE WITH ROUGH PLUMBING FOR ICE MAKER (RECESS IN WALL).
- A06 STACKED WASHER/DRYER MACHINE LOCATION. PROVIDE WASTE AND WATER IN RECESSED WALL BOX. PROVIDE DRYER VENT. VENT TO OUTSIDE AIR.
- B02 20" SINGLE COMPARTMENT UNDER-MOUNT KITCHEN SINK W/ GARBAGE DISPOSAL. REFER TO WATER EFFICIENCY REQUIREMENTS ON CALGREEN CODE NOTES SHEET.
- B04 LAVATORY SINK. REFER TO WATER EFFICIENCY REQUIREMENTS ON CALGREEN CODE NOTES SHEETS.
- B05 WATER CLOSET. REFER TO WATER EFFICIENCY REQUIREMENTS ON CALGREEN CODE NOTES SHEETS. REQ. AGING-IN-PLACE BLOCKING; SEE DETAIL SHEETS FOR MORE INFO.
- B06 32" x 60" x 72" TUB AND SHOWER COMBINATION. MODEL BY BUILDER. PROVIDE SHOWER ROD. REQ. AGING-IN-PLACE BLOCKING; SEE DETAIL SHEETS FOR MORE INFO.
- B38 MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION, 3" MIN. ABOVE GRADE.
- B47 40 GALLON HEAT PUMP WATER HEATER. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION.
- C01 SINGLE WOOD SHELF AND POLE.
- C08 12" DEEP UPPER CABINET.
- C16 MIRROR. THE LENGTH OF THE VANITY OR PEDESTAL X 80" AFS. UNQ. VERIFY WITH THE ELECTRICAL PLAN FOR LOCATION OF OUTLETS WHICH REQUIRE A CUT-OUT. PROVIDE 2X6 BACKING AT BATHROOM WALL ATTACHEMENTS.
- M01 GUTTER. CONNECT TO DOWNSPOUT. PROVIDE MEANS TO PREVENT ACCUMULATION OF LEAVES AND DEBRIS IN GUTTER PER CRC R337.5.4
- M02 DOWNSPOUT. CONNECT TO STORM DRAIN SYSTEM OR APPROVED DRAINAGE SYSTEM BY COUNTY.
- X27 OPTIONAL DISHWASHER.
- X29 OPTIONAL MEDICINE CABINET.

### DOOR LEGEND



**2 C2 - MODERN - LOFT PLAN**  
SCALE: 1/4" = 1'-0"



**4 LOFT PLAN - NO FRONT PORCH OPTION**  
SCALE: 1/4" = 1'-0"


### WINDOW GENERAL NOTES

- REFER TO GENERAL NOTES ON SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
- REFER TO FLOOR PLANS FOR WINDOW LOCATIONS.
- CONTRACTOR TO VERIFY EXACT ROUGH OPENING SIZES PRIOR TO FABRICATION OF ROUGH OPENINGS.
- INSTALL PER MANUFACTURERS WRITTEN INSTRUCTIONS.
- REFER TO ENERGY COMPLIANCE REPORTS FOR U-FACTOR, SHGC AND ADDITIONAL WINDOW REQUIREMENTS.
- ALL GLAZING IS DOUBLE PANE WITH A MINIMUM OF ONE TEMPERED PANE UNLESS OTHERWISE NOTED.
- EGRESS WINDOWS SHALL HAVE A CLEAR OPENING WITH A MAX. SILL HEIGHT OF 44" AFF. MIN NET CLEAR OPENING FOR EMERGENCY ESCAPE SHALL BE 5.7 S.F. EXCEPTION: MIN 5.5 S.F. AT GROUND FLOOR. MINIMUM NET CLEAR OPENING DIMENSIONS: HEIGHT: 24". WIDTH: 20".
- GLAZING IN WALLS ADJACENT TO BATH TUB / SHOWER WHERE THE BOTTOM EXPOSED EDGE OF THE GLAZING IS LESS THAN 60" MEASURED VERTICALLY ABOVE ANY STANDING OR WALKING SURFACE SHALL BE SAFETY GLAZING. [CRC SEC. R308.4.5]


### WINDOW SCHEDULE

NO.	TYPE	WIDTH	HEIGHT	HEAD HEIGHT	REMARKS
101	B	6'-0"	5'-0"	6'-8"	
102	B	6'-0"	5'-0"	6'-8"	
103	B	5'-0"	5'-0"	6'-8"	1
104	B	3'-0"	2'-0"	6'-8"	2
105	B	3'-0"	3'-0"	6'-8"	
211	B	3'-0"	3'-0"	4'-8"	1
212	C	3'-0"	3'-0"	3'-6"	

NOTE: PLEASE CROSS THROUGH THE CLIMATE ZONE THAT IS NOT APPLICABLE.  
CLIMATE ZONE 4 (C24) U-4.36 AND SHGC 0.23  
CLIMATE ZONE 5 (C25) U-4.36 AND SHGC 0.35



**1 GROUND FLOOR PLAN**  
SCALE: 1/4" = 1'-0"




**3 GROUND FLOOR PLAN - NO FRONT PORCH OPTION**  
SCALE: 1/4" = 1'-0"


### WINDOW REMARKS

- REQUIRED EGRESS WINDOW. REFER TO GENERAL NOTE #7 FOR ADDITIONAL INFORMATION.
- HAZARDOUS LOCATION. WINDOW INCLUDES BOTH PANES TEMPERED GLAZING.
- MULLED WINDOW ASSEMBLY.
- OPTIONAL WINDOW.
- OBSCURE OPTIONAL. VERIFY WITH OWNER/APPLICANT.

### WINDOW LEGEND



### LOFT LEGEND



### DOOR GENERAL NOTES

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
- REFER TO PLANS FOR LOCATION OF DOORS.
- VERIFY ROUGH OPENING SIZE WITH DOOR MANUFACTURER SPECIFICATIONS PRIOR TO CONSTRUCTION.
- CONTRACTOR TO VERIFY ACTUAL DOOR SIZE TO FIT FINISH OPENING PRIOR TO FABRICATION OF DOOR AND FINISH OPENING.
- INSTALL PER MANUFACTURERS WRITTEN INSTRUCTIONS.
- REFER TO DOOR TYPES LEGEND FOR GLAZING.
- REFER TO T24 REPORT FOR GLAZING ENERGY REQUIREMENTS.
- GLAZING IN DOORS SHALL BE TEMPERED PER SECTION R308.4.1. PANES INDICATED IN DOOR LEGEND WITH (T).

### DOOR REMARKS

- EXTERIOR DOOR.
- GLAZING PER DOOR TYPES. REFER TO GENERAL DOOR NOTE #8
- PROVIDE 100 SQ INCHES OF VENTING IN DOOR OR BY OTHER APPROVED MEANS.
- OPTIONAL DOOR.

### DOOR SCHEDULE

NO.	TYPE	WIDTH	HEIGHT	REMARKS
101	A	3'-0"	6'-8"	1, 2
102	D	4'-6"	6'-8"	1
103	C	2'-6"	6'-8"	
104	C	2'-6"	6'-8"	
105	E	2'-6"	6'-8"	3
106	C	2'-6"	6'-8"	

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA

FLOOR PLAN

DATE  
11/28/2023  
SHEET

A4-102





THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

### GENERAL MEP NOTES

1. REFER TO ELECTRICAL NOTES ON SHEET G-101.
2. REFER TO MECHANICAL NOTES ON SHEET G-101.
3. REFER TO PLUMBING NOTES ON SHEET G-101.
4. REFER TO TITLE 24 COMPLIANCE NOTES ON SHEET G-101.
5. EXTERNALLY MOUNTED HEATING/COOLING UNITS SHALL BE SCREENED IF THEY ARE VISIBLE FROM A PUBLIC STREET.
6. ALL SMOKE ALARMS TO BE HARD-WIRED WITH A BATTERY BACK-UP, AND ALL SMOKE ALARMS MUST BE INTERCONNECTED AND SOUND AN ALARM CLEARLY AUDIBLE IN ALL BEDROOMS.
7. ALL CARBON MONOXIDE ALARMS TO BE HARD-WIRED WITH A BATTERY BACK-UP, AND ALL CARBON MONOXIDE ALARMS MUST BE INTERCONNECTED AND SOUND AN ALARM CLEARLY AUDIBLE IN ALL BEDROOMS.

### KEYNOTES

- A01 30" WIDE FREE STANDING ELECTRIC RANGE OVEN. VENT TO EXTERIOR, STAINLESS STEEL.
- A05 REFRIGERATOR LOCATION. PROVIDE 42" SPACE WITH ROUGH PLUMBING FOR ICE MAKER (RECESS IN WALL).
- A06 STACKED WASHER/DRYER MACHINE LOCATION. PROVIDE WASTE AND WATER IN RECESSED WALL BOX. PROVIDE DRYER VENT. VENT TO OUTSIDE AIR.
- B18 ELECTRIC PANEL, 100AMP 240V.
- B38 MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION, 3" MIN. ABOVE GRADE.
- B47 40 GALLON HEAT PUMP WATER HEATER. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION.
- B48 FAN COIL. REFER TO PLANS FOR LOCATION OF OUTDOOR CONDENSING UNIT. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE OUTLET.


### LEGEND

NOTE: ALL OUTDOOR OUTLETS SHALL HAVE GFCI PROTECTION AND WEATHERPROOF COVERS.


⊕ ELECTRICAL SWITCH	⊙ SMOKE DETECTOR/ALARM	⊕ ARC-FAULT CIRCUIT INTERRUPTER
⊕ ELECTRICAL SWITCH-THREE WAY	⊙ COMBINATION SMOKE/CARBON MONOXIDE ALARM	⊕ DUPLEX OUTLET 240 VOLTS
⊕ ELECTRICAL SWITCH-VACANCY SENSOR	⊕ COMPUTER DATA LOCATION	⊕ DUPLEX OUTLET GROUND FAULT INTERRUPTER
⊕ ELECTRICAL SWITCH-MOTION SENSOR	⊕ TELEPHONE LOCATION	⊕ DUPLEX OUTLET WATERPROOF GROUND FAULT INTERRUPTER
⊕ ELECTRICAL SWITCH-DIMMER	⊕ CABLE TELEVISION LOCATION	⊕ DUPLEX OUTLET AFCI-HALF HOT
⊕ ELECTRICAL SWITCH-FAN	⊕ ELECTRICAL JUNCTION BOX	⊕ DUPLEX OUTLET DISH WASHER
⊕ ASTRONOMICAL TIME SWITCH		⊕ DUPLEX OUTLET RANGE HOOD
⊕ EXHAUST FAN		
⊕ INDOOR AIR QUALITY FAN		
⊕ PENDANT LIGHT		
⊕ WALL MOUNTED HIGH-EFFICACY LIGHT		
⊕ EXTERIOR WALL MOUNTED HIGH-EFFICACY LIGHT		
⊕ RECESSED HIGH-EFFICACY DOWNLIGHT		
⊕ RECESSED HIGH-EFFICACY DOWNLIGHT VAPOR PROOF		
⊕ ELECTRICAL WIRING		
	⊕ SMOKE DETECTOR/ALARM	⊕ DUPLEX OUTLET ARC-FAULT CIRCUIT INTERRUPTER
	⊕ COMBINATION SMOKE/CARBON MONOXIDE ALARM	⊕ DUPLEX OUTLET 240 VOLTS
	⊕ COMPUTER DATA LOCATION	⊕ DUPLEX OUTLET GROUND FAULT INTERRUPTER
	⊕ TELEPHONE LOCATION	⊕ DUPLEX OUTLET WATERPROOF GROUND FAULT INTERRUPTER
	⊕ CABLE TELEVISION LOCATION	⊕ DUPLEX OUTLET AFCI-HALF HOT
	⊕ ELECTRICAL JUNCTION BOX	⊕ DUPLEX OUTLET DISH WASHER
		⊕ DUPLEX OUTLET RANGE HOOD
	⊕ COLD WATER STUB OUT	
	⊕ HOT WATER STUB OUT	
	⊕ WATER HOSE BIBB	
	⊕ WATER HOSE BIBB WITH SHUT OFF VALVE	
	⊕ ICE MACHINE STUB OUT	
	⊕ UNDER CABINET HIGH-EFFICACY LIGHT	
	⊕ 22"x30" MIN. CEILING ACCESS PANEL	
	⊕ AIR HANDLER UNIT, PROVIDE DEDICATED OUTLET	

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
FINISH, MECHANICAL, & ELECTRICAL PLANS


DATE  
11/28/2023  
SHEET  
A4-111



**3 GROUND FLOOR FINISH PLAN**  
A1-201 | A4-111 | SCALE: 1/4" = 1'-0"



**2 LOFT ELECTRICAL PLAN**  
A1-201 | A4-111 | SCALE: 1/4" = 1'-0"



**1 GROUND FLOOR ELECTRICAL PLAN**  
A1-201 | A4-111 | SCALE: 1/4" = 1'-0"

### FINISH PLAN GENERAL NOTES

1. REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
2. REFER TO ELECTRICAL PLANS FOR FURTHER INFORMATION.
3. REFER TO PLUMBING PLANS FOR FURTHER INFORMATION.
4. REFER TO DETAILS FOR FLOOR/CEILING ASSEMBLIES AND INTERIOR FINISH DETAILS.
5. ALL HARD SURFACE FLOORING SHALL BE SLIP RESISTANT AND MEET THE ANSI A326.3 STANDARD FOR MEASURING THE DYNAMIC COEFFICIENT OF FRICTION (DCOF).
6. ALL FLOORING MATERIALS SHALL COMPLY WITH CBC SEC. 804.1.
7. ALL WALL AND CEILING FINISHES SHALL COMPLY WITH CBC TABLE 803.13 FOR MAXIMUM FLAME SPREAD AND SMOKE DENSITY.

FINISH SCHEDULE PLAN 4				
NAME	FLOOR	WALL	CEILING	NOTES
KITCHEN	LVP	GWB	GWB	WR GWB BEHIND KITCHEN COUNTER
BATH	CT	WR GWB	WR GWB	AT CERAMIC TILE IN TUB/SHOWER AREAS. PROVIDE BACKER BOARD PER CRC TABLE R702.4.2
BED 1	CPT	GWB	GWB	
CL 1	CPT	GWB	GWB	
LAUNDRY	LVP	GWB	GWB	

### FINISH LEGEND

LUXURY VINYL PLANK (LVP)	CARPET (CPT)
CERAMIC TILE (CT)	CONCRETE (EC)

### VENTILATION SUMMARIES

**1) LOCAL EXHAUST VENTILATION**

BATHROOM	OPTION A	OPTION B
BATHROOM FAN FLOW (cfm)	50 CFM	50
DUCT TYPE	FLEX DUCT	SMOOTH DUCT
DUCT SIZE (in)	4"	4"
MAX. ALLOWABLE DUCT LENGTH (ft)	70'	105'
THIS EXHAUST FAN IS REQUIRED TO BE RATED FOR SOUND AT A MAX. OF 3 SONES.		

KITCHEN	OPTION A	OPTION B
KITCHEN FAN FLOW (cfm)	10 CFM	50
DUCT TYPE	FLEX DUCT	SMOOTH DUCT
DUCT SIZE (in)	35"	5"
MAX. ALLOWABLE DUCT LENGTH (ft)	0'	85'
THIS EXHAUST FAN IS REQUIRED TO BE RATED FOR SOUND AT A MAX. OF 3 SONES.		

**2) WHOLE BUILDING VENTILATION**

PER ASHRAE STANDARD 62.2, CEC EQUATION 150.0-B	OPTION A	OPTION B
BUILDING FAN FLOW (cfm)	50 CFM	50
DUCT TYPE	FLEX DUCT	SMOOTH DUCT
DUCT SIZE (in)	4"	4"
MAX. ALLOWABLE DUCT LENGTH (ft)	70'	105'
THIS EXHAUST FAN IS REQUIRED TO BE RATED FOR SOUND AT A MAX. OF 1 SONE.		
THIS EXHAUST FAN IS REQUIRED TO OPERATE CONTINUOUSLY TO ENSURE CONTINUOUSLY TO ENSURE INDOOR AIR QUALITY.		


**TOTAL (MINIMUM) REQUIRED VENTILATION RATE**  
PER ASHRAE STANDARD 62.2, CEC EQUATION 150.0-B  
QCFM = .03(FLOOR AREA) + 7.5 (# OF BEDROOMS + 1)

**1 BED - MINIMUM CUBIC FEET PER MINUTE (CFM)**  
Qcfm = .03(X) + 7.5 (0 + 1) = XX.XX  
.03(578 sf) + 7.5 (1) = 24.84 CFM < 50 CFM

### ELECTRICAL NOTES

1. CONFORM WITH CURRENT CEC, NFPA, MFR'S, AND LOCAL REQUIREMENTS.
2. ELECTRICAL SYSTEM GROUND TO BE PROVIDED PER NEC ARTICLE 250-81.
3. ALL MATERIALS TO BE U.L. LABELED.
4. METER: "SQUARE D", 120 VOLT/240 VOLT, 1 AND 3 WIRE GROUND OR EQUAL.
5. ELECTRICAL SUB PANEL: FLUSH MOUNT, 30" CLEARANCE, 100 AMP.
6. CONDUCTORS: TW, THW, COPPER, MINIMUM 14 AT LIGHTING, 12 AT OTHER CIRCUITS.
7. ALL LUMINAIRES SHALL COMPLY WITH 2022 CEC SECTION 150.0 (K) AND TABLE 150.0-A AS REFERENCED IN ENERGY NOTES, LUMINAIRE REQUIREMENTS SHEET G-101.
8. ALL ELECTRICAL OUTLETS INSTALLED IN BATHROOMS, GARAGES, BASEMENTS, CRAWL SPACES, OUTDOORS, KITCHEN COUNTERS, AND AT WET BAR SINKS SHALL HAVE GROUND-FAULT CIRCUIT-INTERRUPTER PROTECTION IN COMPLIANCE WITH NEC Art. 210-8, CONSISTING OF 125 VOLT, SINGLE-PHASE, 15- AND 20- AMPERE RECEPTACLES.
9. ALL BATHROOM RECEPTACLE OUTLETS SHALL BE SUPPLIED BY A MINIMUM OF ONE 120-VOLT, 20-AMPERE BRANCH CIRCUIT. SUCH CIRCUITS SHALL HAVE NO OTHER OUTLETS. THIS DEDICATED CIRCUIT MAY SERVE MORE THAN ONE BATHROOM. (2022 CEC 210.11(C))
10. THERMOSTAT SHALL BE A PROGRAMMABLE TYPE, HONEYWELL TH8320 OR EQUAL.
11. CEILING-SUSPENDED (PADDL) FANS SHALL BE SUPPORTED INDEPENDENTLY OF AN OUTLET BOX OR BY LISTED OUTLET BOX OR OUTLET BOX SYSTEMS IDENTIFIED FOR THE USE AND INSTALLED IN ACCORDANCE WITH 2022 CEC 314.27(C) (2022 CEC 422.18).
12. ALL LUMINAIRES, LAMP HOLDERS, AND RETROFIT KITS SHALL BE LISTED (2022 CEC 410.6).
13. ALL 120-VOLT, SINGLE PHASE 15- AND 20- AMPERE BRANCH CIRCUITS SUPPLYING OUTLETS INSTALLED IN DWELLING UNIT KITCHENS, FAMILY ROOMS, LIVING ROOMS, DINING ROOMS, PARLORS, LIBRARIES, DEN, BEDROOMS, SUNROOMS, RECREATION ROOMS, CLOSETS, HALLWAYS OR SIMILAR ROOMS OR AREAS SHALL BE PROTECTED BY A LISTED ARC-FAULT CIRCUIT INTERRUPTER, COMBINATION-TYPE, INSTALLED TO PROVIDE PROTECTION OF THE BRANCH CIRCUIT. (2022 CEC 210-12(A)).
14. ALL NON-LOCKING TYPE 125-VOLT, 15 AND 20 AMPERE RECEPTACLES IN A DWELLING UNIT SHALL BE LISTED TAMPER-RESISTANT RECEPTACLES. EXCEPTIONS: (1) RECEPTACLES MORE THAN 6' ABOVE THE FLOOR, (2) RECEPTACLES PART OF A LUMINAIRE OR APPLIANCE, (3) A SINGLE RECEPTACLE OR A DUPLEX RECEPTACLE FOR TWO APPLIANCES THAT ARE NOT EASILY MOVED AND LOCATED WITHIN DEDICATED SPACE AND ARE CHORD-AND-PLUG CONNECTED AS PER CEC 400.10, AND (4) NON-GROUNDING RECEPTACLES USED FOR REPLACEMENTS AS PERMITTED IN CEC 408.4(D)(2)(A).
15. HIGH EFFICACY LUMINAIRES OTHER THAN OUTDOOR HID LIGHTING CONTAIN ONLY ONLY HIGH EFFICACY LAMPS AS OUTLINED IN TABLE 150-C OF THE RESIDENTIAL ENERGY CODE AND NOT CONTAIN A MEDIUM SCREW BASE SOCKET.
16. BALLAST FOR LAMPS 13 WATTS OR GREATER SHALL BE ELECTRONIC AND HAVE AN OUTPUT FREQUENCY NO LESS THAN 20 KHZ.
17. SMOKE DETECTORS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING AND PROVIDED WITH A BATTERY BACK-UP. ALL SMOKE DETECTORS SHALL BE INTERCONNECTED. ALL SMOKE DETECTORS SHALL MAINTAIN A MINIMUM 3 FOOT CLEARANCE TO HVAC SUPPLY OR RETURN AIR REGISTERS.
18. CARBON MONOXIDE ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING AND PROVIDED WITH A BATTERY BACK-UP. ALL CARBON MONOXIDE ALARMS SHALL BE INTERCONNECTED.
19. EXHAUST FANS WILL BE CONTROLLED BY A HUMIDISTAT PER THE GREEN BUILDING STANDARDS CODE SECTION 4.506. EXHAUST FANS MUST BE SWITCHED SEPARATELY FROM LIGHTS (2022 CEC 150.0(k)2G).
20. IN ADDITION TO THE NUMBER OF BRANCH CIRCUITS REQUIRED BY OTHER PARTS OF THE CODE, TWO OR MORE 20-AMPERE SMALL-APPLIANCE BRANCH CIRCUITS SHALL BE PROVIDED FOR ALL RECEPTACLE OUTLETS IN THE KITCHEN, PANTRY, BREAKFAST ROOM, DINING ROOM, OR SIMILAR AREA PER 2022 CEC, ARTICLE 210.11 (C)(1). THE CIRCUITS SHALL HAVE NO OTHER OUTLETS PER 2022 CEC, ARTICLE 210.52(B).
21. IN ADDITION TO THE NUMBER OF BRANCH CIRCUITS REQUIRED BY OTHER PARTS OF THE CODE, AT LEAST ONE ADDITIONAL 20-AMPERE BRANCH CIRCUIT SHALL BE PROVIDED TO SUPPLY THE LAUNDRY RECEPTACLE OUTLET(S) REQUIRED BY 2022 CEC, ARTICLE 210.52 (F). THIS CIRCUIT SHALL HAVE NO OTHER OUTLETS PER 2022 CEC, ARTICLE 201.11(C)(2).

NOTE: SIZE, DESIGN, AND SELECTION OF HVAC EQUIPMENT SHALL BE PROVIDED FOR PROJECT BY ONE OF THE FOLLOWING:  
A. HEAT LOSS AND GAIN PER "RESIDENTIAL LOAD CALCULATION" [ANSI/ACCA 2 MANUAL J - 2011, ASHRAE]  
B. DUCT SIZING PER "RESIDENTIAL DUCT SYSTEMS" [ANSI/ACCA 1 MANUAL D - 2014, ASHRAE]  
C. SELECTION PER "RESIDENTIAL EQUIPMENT SELECTION" [ANSI/ACCA 3 MANUAL S - 2014]



**4 GROUND FLOOR MECHANICAL PLAN**  
A1-201 | A4-111 | SCALE: 1/4" = 1'-0"



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
 ACCESSORY DWELLING UNIT  
 SAN LUIS OBISPO, CA  
 ROOF PLAN & REFLECTED  
 CEILING PLAN

DATE  
 11/28/2023  
 SHEET

A4-122

**ROOF PLAN GENERAL NOTES**

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS
- REFER TO STRUCTURAL PLANS FOR ROOF FRAMING INFORMATION INCLUDING MEMBER SIZES AND CONNECTION HARDWARE
- REFER TO MECHANICAL/ELECTRICAL SHEETS FOR ROOF PENETRATION LOCATIONS
- PROVIDE A MINIMUM OF 1 INCH OF AIRSPACE BETWEEN THE INSULATION AND ROOF SHEATHING
- WHERE THE ROOF PROFILE ALLOWS A SPACE BETWEEN THE ROOF COVERING AND DECKING, THE SPACES SHALL BE CONSTRUCTED TO PREVENT THE INTRUSION OF FLAMES AND EMBERS, BE FIRE STOPPED WITH APPROVED MATERIALS OR HAVE ONE LAYER OF MINIMUM 72 POUND MINERAL-SURFACED NONPERFORATED CAP SHEET OVER THE COMBUSTIBLE DECKING
- ALL ROOFING MATERIALS TO BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS
- OVERHANG DIMENSIONS ARE FROM FACE OF EXTERIOR WALL FRAMING TO ROOF EDGE
- ROOF COVERINGS AND UNDERLAYMENT SHALL BE APPLIED IN ACCORDANCE WITH **CRC R806**, AND MANUFACTURER'S INSTALLATION INSTRUCTIONS
- ROOF VENTS SHALL BE APPLIED PER MANUFACTURER'S SPECIFICATIONS
- FURNISHED DIMENSIONS FOR VENTS ARE GUIDES ONLY. INSTALL PER MANUFACTURER'S SPECIFICATIONS AND ADJUST TO ACCOMMODATE TRUSS LOCATIONS, PLUMBING VENTS, AND SOLAR COLLECTORS
- ENCLOSED ATTICS AND ENCLOSED RAFTER SPACES FORMED WHERE CEILINGS ARE APPLIED DIRECTLY TO THE UNDERSIDE OF ROOF RAFTERS SHALL HAVE CROSS VENTILATION FOR EACH SEPARATE SPACE BY VENTILATING OPENINGS PROTECTED AGAINST THE ENTRANCE OF RAIN OR SNOW. VENTILATING OPENINGS SHALL HAVE A LEAST DIMENSION OF 1/16 INCH MINIMUM AND 1/4 INCH MAXIMUM. OPENINGS IN ROOF FRAMING MEMBERS SHALL CONFORM TO THE REQUIREMENTS OF SECTION R802.7. REQUIRED VENTILATING OPENINGS SHALL OPEN DIRECTLY TO THE OUTSIDE AIR AND SHALL BE PROTECTED TO PREVENT THE ENTRY OF BIRDS, RODENTS, SNAKES AND OTHER SIMILAR CREATURES
- THE MINIMUM NET FREE VENTILATING AREA SHALL COMPLY WITH **CRC R806.2**
- IN THE INSTANCE OF UPPER VENTS, VENTS SHALL BE LOCATED NO MORE THAN 3 FT BELOW THE RIDGE OR HIGHEST POINT OF THE SPACE, MEASURED VERTICALLY. **CRC R806.2**
- FOR VENTED ROOF ASSEMBLIES: PROVIDE A MINIMUM OF 1 INCH OF AIRSPACE BETWEEN THE INSULATION AND ROOF SHEATHING
- FOR UN-VENTED ROOF ASSEMBLIES: ROOF ASSEMBLY TO MEET CODE REQUIREMENTS OF **CRC R806.5**. PROVIDE MINIMUM 2" HIGH DENSITY CLOSE CELL INSULATION. PROVIDE ADDITIONAL INSULATION AS NEEDED TO MEET MINIMUM ROOF ASSEMBLY R-VALUE REQUIRED BY TITLE-24
- ALL ROOFING TO BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS
- OVERHANG DIMENSIONS ARE FROM FACE OF EXTERIOR WALL FRAMING TO ROOF EDGE

**ROOF INSULATION NOTES**

ROOF ASSEMBLY SHALL MEET REQUIREMENTS OF CRC CHAPTER 9.  
**CRC R806.5 UNVENTED ATTIC**  
 ROOF ASSEMBLY **MINIMUM R-VALUE R-38** REQUIRED PER TITLE-24.  
 PROPOSED INSULATION: 7.25" OF AIR-IMPERMEABLE CLOSED CELL SPRAY FOAM INSULATION WITH R-VALUE OF 5.25 MINIMUM.  
 7.25" (MIN.) (X) R-5.25 = **R-38 TOTAL**  
**NOTE:** HIGHER PERFORMING AIR-IMPERMEABLE CLOSED CELL SPRAY INSULATION MAY BE USED TO MEET THE R-38 REQUIRED TOTAL.  
 EXAMPLE: 5.5" OF AIR IMPERMEABLE CLOSED CELL SPRAY FOAM INSULATION WITH R-VALUE OF 7.  
 5.43" (MIN.) (X) R-7 = **R-38 TOTAL**  
**NOTE:** MINIMUM INSULATION DEPTH REQUIRED FOR MOISTURE CONTROL VARIES BY CLIMATE LOCATION. SEE CALIFORNIA ENERGY CODE PROVISIONS, FIGURE 100. 1-A OF THE CALIFORNIA ENERGY CODE FOR SITE SPECIFIC PROJECT.  
 AN UNVENTED ATTIC IN CLIMATE ZONE 5 REQUIRES MINIMUM AIR-IMPERMEABLE INSULATION OF **R-20** PER **CRC 806.5** TABLE R806.5 FOR MOISTURE CONTROL.  
 AN UNVENTED ATTIC IN CLIMATE ZONE 4B REQUIRES MINIMUM AIR-IMPERMEABLE INSULATION OF **R-15** PER **CRC 806.5** TABLE R806.5 FOR MOISTURE CONTROL.

**RCP GENERAL NOTES**

- REFER TO GENERAL NOTES SHEET G-102 FOR ADDITIONAL REQUIREMENTS
- HEIGHT OF CEILINGS SHALL BE MEASURED FROM TOP OF SLAB OR FLOOR TO FINISH FACE OF G.W.B. U.N.O.
- REFER TO ELECTRICAL PLANS FOR LIGHT FIXTURE AND EXHAUST LOCATIONS
- DIMENSIONS ARE TO THE FACE OF FRAMING UNLESS OTHERWISE NOTED
- LABEL MATERIAL SELECTIONS ON ALL RAKES, EAVES, PORCH SOFFITS, & OVERHANGS (A, B, C...)

**KEYNOTES**

- H07 BUILDING LINE BELOW.  
 K08 METAL ROOF. SEE MATERIALS LEGEND FOR MORE INFO.  
 M01 GUTTER. CONNECT TO DOWNSPOUT. PROVIDE MEANS TO PREVENT ACCUMULATION OF LEAVES AND DEBRIS IN GUTTER PER CRC R337.5.4  
 M02 DOWNSPOUT. CONNECT TO STORM DRAIN SYSTEM OR APPROVED DRAINAGE SYSTEM BY COUNTY.

**MATERIALS LEGEND**


**GRAPHICS LEGEND:** OWNER/APP. TO PROVIDE MANUFACTURER, COLOR/FINISH SPECIFICATIONS, & WUI (WHEN REQ.) PRODUCT LISTINGS:

- ROOFING: SEE MATERIALS LEGEND ON ELEVATION SHEET FOR MORE INFORMATION. CLASS A ROOF REQ. BY WUI.
- INTERIOR CEILING FINISH, TYP. 5/8" GYP. INSTALL PER MFR RECOMMENDATIONS  
**NOTE:** SEE MANUFACTURER'S PRODUCT LISTINGS FOR IMPROVED SOUND AND/OR MOISTURE/MOLD/MILDEW-RESISTANT PERFORMANCE PRODUCTS. VISIT GYPSUM.ORG FOR MORE INFORMATION.
- EXTERIOR EAVES, PORCH SOFFITS, & OVERHANGS  
 A) 2X TONGUE & GROOVED (SOLID SAWN LUMBER)  
 B) FIBER CEMENT SOFFIT PANELS  
 C) HARDBOARD SOFFIT PANELS  
 D) EXT. GRADE FIRE RETARDANT TREATED SHEATHING  
 (LABEL SELECTION ON REFLECTED CEILING PLAN)


- NOTES:**
- SOFFIT MATERIALS TO MEET REQ. OF **CRC 337** & **CRC 704**
  - INSTALL ALL MATERIALS, FASTENERS, & COMPONENTS PER MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS
  - INSTALL ADDITIONAL BLOCKING AS NEEDED TO MEET ATTACHMENT REQUIREMENTS PER **CRC TABLE R702.3.5**
  - A PROJECT SITE WITHIN THE WILDLAND-URBAN INTERFACE FIRE AREA SHALL COMPLY WITH THE **CRC SECTION R337**. IF WUI APPROVED PRODUCTS ARE REQUIRED, PROVIDE SELECTED PRODUCT LISTINGS IN THE SPACES PROVIDED.

**ROOF PLAN & RCP LEGEND**


- XX'-X" CEILING HEIGHT (SEE PLAN FOR ACTUAL HEIGHTS)
- X:12 ROOF SLOPE (REFER TO PLANS FOR ACTUAL SLOPE)
- X:12 CEILING SLOPE (REFER TO PLANS FOR ACTUAL SLOPE)
- 22"X30" MIN. ATTIC ACCESS PANEL (WHERE REQ.)
- VENTING OPTION A RIDGE VENT, MARK WITH "X" IF NOT USED. SEE ROOF VENTING CALCS.
- VENTING OPTION A SOFFIT VENT, MARK WITH "X" IF NOT USED. SEE ROOF VENTING CALCS.
- ATTIC ROOF VENT OPTION B, MARK WITH "X" IF NOT USED. SEE ROOF VENTING CALCS.
- OUTLINE OF WALL BELOW
- GUTTER, CONNECT TO DOWNSPOUT; SEE DETAIL: 12/A-904
- APPROXIMATE LOCATION OF DOWNSPOUT/LEADER TO ROOF OR SPLASHBLOCK BELOW; SEE DETAILS:
- XX SF AVAILABLE SOLAR ZONE LOCATIONS, PV SYSTEM UNDER SEPARATE PERMIT. SEE TITLE 24 REPORT FOR MORE INFORMATION
- AREA OF ATTIC WITH 30" HEIGHT OR GREATER. 22" X 30" CLEAR OPENING ACCESS REQUIRED IF TOTAL AREA GREATER THAN 30 SQ. FT. PER CRC R807.1




**1 ROOF PLAN**  
 A1-201 | A4-122 SCALE: 1/4" = 1'-0"



**3 REFLECTED CEILING PLAN**  
 A1-201 | A4-122 SCALE: 1/4" = 1'-0"



**2 ROOF PLAN - NO FRONT PORCH OPTION**  
 A1-201 | A4-122 SCALE: 1/4" = 1'-0"



**4 REFLECTED CEILING PLAN NO FRONT PORCH OPTION**  
 A1-201 | A4-122 SCALE: 1/4" = 1'-0"



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

### GENERAL ELEVATION NOTES


1. REFER TO GENERAL NOTES SHEET G-102 FOR ADDITIONAL REQUIREMENTS
2. SEE DETAILS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
3. REFER TO ROOF PLAN FOR OVERHANGS, FASCIA PER DETAILS. PROVIDE ALUMINUM GUTTER. SEE ROOF PLAN FOR APPROXIMATE DOWNSPOUT LOCATIONS, U.N.O.
4. REFER TO DOOR AND WINDOW SCHEDULES AND TYPES FOR DOOR AND WINDOW INFORMATION.
5. THE NOMINAL THICKNESS AND ATTACHMENT OF EXTERIOR WALL COVERINGS SHALL BE IN ACCORDANCE WITH CRC TABLE R703.3(1).
6. GYPSUM SHEATHING SHALL BE ATTACHED TO EXTERIOR WALLS IN ACCORDANCE WITH CRC TABLE R602.3.

### SECTIONS GENERAL NOTES


1. THE PURPOSE OF THESE DRAWINGS IS TO SHOW CONSTRUCTION MATERIALS/ASSEMBLIES. FOR SPECIFIC SIZES AND DETAILS REFER TO ARCHITECTURAL PLANS, ELEVATIONS, DETAILS, AND STRUCTURAL PLANS. \*KEYNOTES ONLY APPLY IF REFERENCED ON PLANS.
2. WALL ASSEMBLIES TO BE PER FLOOR PLAN.
3. DOORS AND WINDOWS TO BE PER APPLICABLE SCHEDULE. REFER TO FLOOR PLANS FOR IDENTIFICATION.
4. INSULATION: REFER TO TITLE 24 REPORT AND "INSULATION" NOTES ON SHEET FOR ADDITIONAL RATINGS, REQUIREMENTS, AND INFORMATION.
5. FIREBLOCKING TO BE LOCATED AT THE FOLLOWING LOCATIONS PER 2022 CRC SECTION R302.11:
  - A. SECTION R302.11.1 - FIREBLOCKING SHALL BE PROVIDED IN CONCEALED SPACES OF STUD WALLS AND PARTITIONS, INCLUDING FURRED SPACES AND PARALLEL ROWS OF STUDS OR STAGGERED STUDS, AS FOLLOWS:
    1. VERTICALLY AT CEILING AND FLOOR LEVELS
    2. HORIZONTALLY AT INTERVALS NOT EXCEEDING 10 FEET.
  - AT INTERCONNECTIONS BETWEEN CONCEALED VERTICAL AND HORIZONTAL SPACES SUCH AS SOFFITS, DROP CEILINGS AND COVE CEILINGS.
  - IN CONCEALED SPACES BETWEEN STAIR STRINGERS AT THE TOP AND BOTTOM OF THE RUN. ENCLOSED SPACES UNDER STAIRS SHALL COMPLY WITH SECTION R302.7.
  - AT OPENINGS AROUND VENTS, PIPES, DUCTS, CABLES AND WIRES AT CEILING AND FLOOR LEVEL. WITH AN APPROVED MATERIAL TO RESIST THE FREE PASSAGE OF FLAME PRODUCTS OF COMBUSTION. THE MATERIAL FILLING THIS ANNULAR SPACE SHALL NOT BE REQUIRED TO MEET THE ASTM E136 REQUIREMENTS.
  - FOR THE FIREBLOCKING OF CHIMNEYS AND FIREPLACES, SEE SECTION R1003.19.
  - FIREBLOCKING OF CORNICES OF A TWO-FAMILY DWELLING IS REQUIRED AT THE LINE OF DWELLING-UNIT SEPARATION.
- A. SECTION R302.11.1 - FIREBLOCKING MATERIALS SHALL CONSIST OF FOLLOWING MATERIALS:
  1. TWO-INCH NOMINAL LUMBER
  2. TWO THICKNESSES OF ONE-INCH NOMINAL LUMBER WITH BROKEN LAP JOINTS
  3. THE THICKNESS OF 0.719-INCH WOOD STRUCTURAL PANELS WITH JOINTS BACKED BY 0.719-INCH WOOD STRUCTURAL PANELS
  4. THE THICKNESS OF 0.75-INCH PARTICLE BOARD WITH JOINTS BACKED BY 0.75-INCH PARTICLE BOARD
  5. ONE-HALF-INCH GYPSUM BOARD
  6. ONE-FOURTH-INCH CEMENT-BASED MILLBOARD
  7. BATTS OR BLANKETS OF MINERAL WOOL, MINERAL FIBER OR OTHER APPROVED MATERIAL. INSTALLED IN SUCH A MANNER AS TO BE SECURELY RETAINED IN PLACE
  8. CELLULOSE INSULATION INSTALLED AS TESTED IN ACCORDANCE WITH ASTM E119 OR UL 263. FOR THE SPECIFIC APPLICATION.
- PER 2022 CRC SECTION R317 SLEEPERS AND SILLS ON A CONCRETE OR MASONRY SLAB THAT IS IN DIRECT CONTACT WITH GROUND, UNLESS SEPARATED BY AN IMPERVIOUS MOISTURE BARRIER SHALL BE NATURALLY DURABLE OR PRESERVATIVE-TREATED WOOD IN ACCORDANCE WITH AWPA U1.

### KEYNOTES


- B38 MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION, 3" MIN. ABOVE GRADE.
- C18 INTERIOR LOFT GUARD (PER CRC AQ104.2.5). ONE HALF OF THE CLEAR HEIGHT TO THE CEILING OR 36" MIN. U.N.O. SEE LOFT GUARD DETAIL 42 ON SHEET A-906 FOR MORE INFORMATION.
- C31 LOFT ACCESS LADDER (PER CRC AQ104.2.2). SEE DETAILS FOR MORE INFORMATION.
- H05 ROOF EDGE/FASCIA. SEE DETAILS FOR FASCIA TYPE.
- K02 EXTERIOR GRADE WOOD SIDING. SEE TITLE SHEET & MATERIALS LEGEND FOR SELECTIONS & MORE INFO.
- K05 COMPOSITE ROOF SHINGLES. SEE MATERIALS LEGEND FOR MORE INFO.
- K08 METAL ROOF. SEE MATERIALS LEGEND FOR MORE INFO.
- K10 SOFFIT. SEE REFLECTED CEILING PLAN AND RCP MATERIALS LEGEND FOR MORE INFO.
- L19 LIGHT FIXTURE LOCATION. SEE DETAILS & ELECTRIC PLAN FOR MORE INFO.
- L20 BUILDING SHALL HAVE ADDRESS NUMBERS PLACED IN A POSITION THAT IS PLAINLY LEGIBLE AND VISIBLE FROM STREET, MINIMUM OF 4" HIGH WITH A MIN. STROKE OF 1/2" (EXACT LOCATION PER OWNER/APPLICANT).
- M01 GUTTER. CONNECT TO DOWNSPOUT. PROVIDE MEANS TO PREVENT ACCUMULATION OF LEAVES AND DEBRIS IN GUTTER PER CRC R337.5.4
- M02 DOWNSPOUT. CONNECT TO STORM DRAIN SYSTEM OR APPROVED DRAINAGE SYSTEM BY COUNTY.
- S04 2X6 WALL INSULATION. R-19 MIN.
- S05 SPRAY FOAM INSULATION. SEE 'ROOF INSULATION NOTES' ON ROOF PLAN.
- U11 WOOD BEAM / HEADER. REFER TO STRUCTURAL.




**1 FRONT ELEVATION**  
A4-102 | A4-202 SCALE: 1/4" = 1'-0"




**2 LEFT ELEVATION**  
A4-102 | A4-202 SCALE: 1/4" = 1'-0"




**3 FRONT ELEVATION NO FRONT PORCH OPTION**  
A4-102 | A4-202 SCALE: 1/4" = 1'-0"




**4 REAR ELEVATION**  
A4-102 | A4-202 SCALE: 1/4" = 1'-0"




**5 RIGHT ELEVATION**  
A4-102 | A4-202 SCALE: 1/4" = 1'-0"




**6 RIGHT ELEVATION NO FRONT PORCH OPTION**  
A4-202 SCALE: 1/4" = 1'-0"



**7 SECTION 01**  
A4-102 | A4-202 SCALE: 1/4" = 1'-0"



**8 SECTION 02**  
A4-202 SCALE: 1/4" = 1'-0"



**9 SECTION 02 - NO FRONT PORCH OPTION**  
A4-102 | A4-202 SCALE: 1/4" = 1'-0"

### MATERIALS LEGEND MODERN

1. COLOR SCHEMES AND FINISH OF PRODUCT SELECTIONS RECOMMENDED TO MATCH PRIMARY RESIDENCE. INSTALL ALL MATERIAL SELECTIONS PER MANUFACTURER'S RECOMMENDATIONS.
2. A PROJECT SITE WITHIN THE WILDLAND-URBAN INTERFACE FIRE AREA SHALL COMPLY WITH THE CRC SECTION R337. IF WUI APPROVED PRODUCTS ARE REQUIRED, PROVIDE SELECTED PRODUCT LISTINGS IN THE SPACES PROVIDED. WHEN NOT REQUIRED, WRITE "NOT APPLICABLE."
3. APPROVED PRODUCT LISTINGS CAN BE FOUND IN THE (CURRENT) CAL-FIRE STATE FIRE MARSHAL LISTED WILDLAND URBAN INTERFACE WUI PRODUCT HANDBOOK.
4. IF PROJECT SITE REQUIRES WUI COMPLIANCE, IN THE CASE THAT PRODUCT SELECTIONS ARE NOT BML LISTED, NOR IN THE HANDBOOK, MATERIALS SHALL COMPLY WITH THE PRESCRIPTIVE STANDARDS OF CHAPTER 7A.

### GRAPHICS LEGEND: MARK ALL THAT APPLY AND LABEL ALL SURFACES ON THE ELEVATIONS

- E) FIBER CEMENT HORIZONTAL LAP SIDING (SHALL MEET ALL REQ. OF CRC 337 & CRC R703.10.2)
- F) EXT. GRADE WOOD HORIZONTAL LAP SIDING (SHALL MEET ALL REQ. OF CRC 337 & CRC R703.5.3)
- G) EXT. GRADE WOOD PANEL SIDING (SHALL MEET ALL REQ. OF CRC 337 & CRC R703.5.2)

### OWNER/APP. TO PROVIDE MANUFACTURER, COLOR/FINISH SPECIFICATIONS, & WUI (WHEN REQ.) PRODUCT LISTINGS:


### GRAPHICS LEGEND:

- STANDING SEAM METAL ROOF CLASS-A ROOF ASSEMBLY REQ. PER WUI: YES NO
- ROOF COVERING SHALL COMPLY WITH ALL REQ. OF CRC 337 & CRC R905.10 METAL ROOF PANELS.
- SEE REFERENCE DETAILS ON SHEE A-941.

### OWNER/APP. TO PROVIDE MANUFACTURER, COLOR/FINISH SPECIFICATIONS, & WUI (WHEN REQ.) PRODUCT LISTINGS:



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.




**41 TYP. PORCH BEAM**  
SCALE: 1/2" = 1'-0"

MATERIAL PER REFLECTED CEILING PLANS. INSTALL PER MFR'S SPECIFICATIONS

**41 TYP. PORCH BEAM**

SCALE: 1/2" = 1'-0"

TYP. NOTES  
1. CALK ALL JOINTS.  
2. PRIME TRIM ALL SIDES.



**32 TYP. POST W/ ROOF @ PORCHES**  
SCALE: 3/4" = 1'-0"

1/4" MIN. G-P GYP. DENSDECK OR EQ. WHERE WUI APPLIES  
1/2" SHEATHING; RE: STRUCT  
2x T&G SHOWN; SEE TITLE SHEET & REFLECTED CEILING PLAN FOR MATERIAL SELECTION  
ASPHALT SHINGLE ROOFING; SEE MATERIALS LEGEND.  
BN FOR SHTG 18d @ 12" O.C.  
26GA. GSM DRIP EDGE FLASHING. 1" MIN. VERTICAL O/ STARTER FELT  
GUTTER W/ GUARD. SEE DETAIL: 12/A-904  
2x FASCIA  
SHAPE PER STYLE PREFERENCE  
ROOF FRAMING 4X6 DF # 2 @ 16"OC  
SOLID 2x BLOCKING EACH FACE OF BEAM  
4x8 MIN. BEAM. REFER TO STRUC.  
POST TO BEAM CONNECT. REFER TO STRUC.  
6X6 (MIN.) POST. REFER TO STRUC.


A35 CLIP EVERY OTHER BLOCK  
SDWC SCREW EACH RAFTER

2x12 MIN. RS WOOD TRIM BAND. CAULK W/ W.P. SEALANT  
COLUMN BASE, RE: STRUCTURAL PLANS  
CONCRETE FOOTING, RE: STRUCTURAL PLANS  
3" MIN.  
ALL SIDES  
PER PLAN  
REF TO STRUC.

NOTE: PRIMER & 2 COATS OF EXTERIOR GRADE PAINT REQ. FOR ALL EXTERIOR LUMBER.  
NOTE: FASTENER SIZE AND LOCATIONS PER STRUC. FOR ADDITIONAL HARDWARE INFORMATION, REF. TO MFR'S SPECS.

TYP. NOTES  
1. CALK ALL JOINTS.  
2. PRIME TRIM ALL SIDES.

0'-8" MIN. TO ADJACENT GRADE  
0'-2" MIN. TO ADJACENT FINISH SURFACE



**21 EXTERIOR DOOR THRESHOLD - TYPICAL**  
SCALE: 6" = 1'-0"

**21 EXTERIOR DOOR THRESHOLD - TYPICAL**

SCALE: 6" = 1'-0"


EXTERIOR  
ALUMINUM DOOR THRESHOLD OVER PVC LINER. SILICONE CAULK AT ALL SCREW HOLES.  
APPLY CONTINUOUS BEAD OF SEALANT TO UNDERSIDE OF THRESHOLD.

INTERIOR  
LANDING TO BE 1/4" / 12" MIN. SLOPE AWAY FROM OPENING AND MEET CRC R311.3.1 AND CRC R311.7

CONCRETE SLAB; SEE STRUCTURAL FOR MORE INFORMATION

**R311.3.1 FLOOR ELEVATIONS AT THE REQUIRED EGRESS DOORS**  
LANDINGS OR FINISHED FLOORS AT THE REQUIRED EGRESS DOOR SHALL BE NOT MORE THAN 1 1/2 INCHES LOWER THAN THE TOP OF THE THRESHOLD. THE LANDING OR FLOOR ON THE EXTERIOR SIDE SHALL BE NOT MORE THAN 7 3/4 INCHES BELOW THE TOP OF THE THRESHOLD PROVIDED THAT THE DOOR DOES NOT SWING OVER THE LANDING OR FLOOR.

WHERE EXTERIOR LANDINGS OR FLOORS SERVING THE REQUIRED EGRESS DOOR ARE NOT AT GRADE, THEY SHALL BE PROVIDED WITH ACCESS TO GRADE BY MEANS OF A RAMP IN ACCORDANCE WITH CRC R311.8 OR A STAIRWAY IN ACCORDANCE WITH CRC R311.7.



**12 TYP. GUTTER TO EXT. DOWNSPOUT**  
SCALE: 1/2" = 1'-0"


PERFORATED LEAF GUTTER GUARD TO MATCH ROOF SLOPE (UP TO 5:12) MAX PER CRC R337.5.4 (REQ. IN HIGH/VERY HIGH FIRE ZONE PER WUI)

PREFINISHED ALUMINUM GUTTER WITH SPACERS @ 36" O.C.


12  
2  
BLOCKING  
TYP. DOWNSPOUT SUPPORT BRACKET

NOTE:  
SPLASH BLOCK OCCURS: AT ANY DOWNSPOUT ENDING AT GRADE LEVEL


EXTERIOR WALL  
PRECAST CONCRETE SPLASH BLOCK AT LANDSCAPE AREAS ADJACENT FINISH SURFACE- REFER TO CIVIL PLANS



**43 TOILET BLOCKING - AGING-IN-PLACE**  
SCALE: 1/2" = 1'-0"



**44 TUB BLOCKING - AGING-IN-PLACE**  
SCALE: 1/2" = 1'-0"



**34 TYP. POST**  
SCALE: 3/4" = 1'-0"

2x6 BEAM  
1x4 CAP TRIM  
WOOD POST. REFER TO STRUC.

2x10 BASE TRIM  
1" MIN.  
0'-8" MIN.  
0'-4" MIN.  
HT OF FLATWORK


HT OF EARTH

PER PLAN  
REF TO STRUC.

TOP PLAN VIEW  
PLAN VIEW

POSTS AND COLUMNS THAT ARE EITHER EXPOSED TO THE WEATHER OR LOCATED IN BASEMENTS OR CELLARS, SUPPORTED BY CONCRETE PIERS OR METAL PEDESTALS, SHALL BE PROJECTED AT LEAST 1 INCH ABOVE THE SLAB OR DECK AND 8 INCHES ABOVE EXPOSED EARTH AND SHALL BE SEPARATED BY AN IMPERVIOUS MOISTURE BARRIER (ALTERNATE, PROVIDE A PRESERVATIVE-TREATED WOOD POST OR COLUMN). 2304.12.2.2 & EXCEPTION 1 CBC

NOTE: PRIMER & 2 COATS OF EXTERIOR GRADE PAINT REQ. FOR ALL EXTERIOR LUMBER.  
NOTE: FASTENER SIZE AND LOCATIONS PER STRUC. FOR ADDITIONAL HARDWARE INFORMATION, REF. TO MFR'S SPECS.



**23 TYP. FOUNDATION**  
SCALE: 3" = 1'-0"

BATT INSULATION (REFER TO SECTIONS FOR R-VALUE)  
WALL FRAMING AND SHEATHING PER PLANS/ STRUCTURAL

SIDING PER ELEVATION; SEE MATERIALS LEGEND FOR MORE INFORMATION

WATER-RESISTIVE BARRIER IN COMPLIANCE WITH CRC 703 OVER 26 GA. FLASHING. 4" LAP EXTENSION


FLASHING PER CRC R703.4

MIN. 2%  
2" MIN. EARTH TO FLASH  
4" MIN. EARTH TO FLASH  
6" MIN. GRADE TO SILL

NOTE: WHERE LOT LINES, WALLS, SLOPES, OR OTHER BARRIERS PROHIBIT A 5% SLOPE, DRAINS OR SWALES SHALL BE CONSTRUCTED TO ENSURE DRAINAGE AWAY FROM STRUCTURE CRC R401.3

OPTION A - NO BASE TRIM

MIN. 5%



**12 TYP. GUTTER TO EXT. DOWNSPOUT**  
SCALE: 1/2" = 1'-0"

WATER-RESISTIVE BARRIER IN COMPLIANCE WITH CRC 703 OVER 26 GA. FLASHING. 4" LAP EXTENSION

SIDING PER ELEVATION; SEE MATERIALS LEGEND FOR MORE INFORMATION

METAL FLASHING PER CRC R703.4 W/ DRIP EDGE. 3-1/2" UPSTAND.

2" MIN. TRIM, 14" MAX. MATERIAL SHALL BE SAME AS ELEVATION ABOVE. SEE MATERIALS LEGEND FOR MORE INFORMATION. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.

FLASHING SEALANT  
MIN. 2%  
2-1/2" MIN. EARTH TO FLASH  
4" MIN. EARTH TO FLASH  
6" MIN. GRADE TO SILL

NOTE: WHERE LOT LINES, WALLS, SLOPES, OR OTHER BARRIERS PROHIBIT A 5% SLOPE, DRAINS OR SWALES SHALL BE CONSTRUCTED TO ENSURE DRAINAGE AWAY FROM STRUCTURE CRC R401.3

OPTION B - WITH BASE TRIM

MIN. 5%

**24 TYP. FOUNDATION @ HORIZONTAL LAP SIDING**  
SCALE: 3" = 1'-0"

BATT INSULATION (REFER TO SECTIONS FOR R-VALUE)  
WALL FRAMING AND SHEATHING PER PLANS/ STRUCTURAL

SIDING PER ELEVATION; SEE MATERIALS LEGEND FOR MORE INFORMATION

WATER-RESISTIVE BARRIER IN COMPLIANCE WITH CRC 703 OVER 26 GA. FLASHING. 4" LAP EXTENSION

FLASHING PER CRC R703.4

MIN. 2%  
2" MIN. EARTH TO FLASH  
4" MIN. EARTH TO FLASH  
6" MIN. GRADE TO SILL

NOTE: WHERE LOT LINES, WALLS, SLOPES, OR OTHER BARRIERS PROHIBIT A 5% SLOPE, DRAINS OR SWALES SHALL BE CONSTRUCTED TO ENSURE DRAINAGE AWAY FROM STRUCTURE CRC R401.3

OPTION A - NO BASE TRIM

MIN. 5%

**12 TYP. GUTTER TO EXT. DOWNSPOUT**  
SCALE: 1/2" = 1'-0"

WATER-RESISTIVE BARRIER IN COMPLIANCE WITH CRC 703 OVER 26 GA. FLASHING. 4" LAP EXTENSION

SIDING PER ELEVATION; SEE MATERIALS LEGEND FOR MORE INFORMATION

METAL FLASHING PER CRC R703.4 W/ DRIP EDGE. 3-1/2" UPSTAND.

2" MIN. TRIM, 14" MAX. MATERIAL SHALL BE SAME AS ELEVATION ABOVE. SEE MATERIALS LEGEND FOR MORE INFORMATION. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.

FLASHING SEALANT  
MIN. 2%  
2-1/2" MIN. EARTH TO FLASH  
4" MIN. EARTH TO FLASH  
6" MIN. GRADE TO SILL

NOTE: WHERE LOT LINES, WALLS, SLOPES, OR OTHER BARRIERS PROHIBIT A 5% SLOPE, DRAINS OR SWALES SHALL BE CONSTRUCTED TO ENSURE DRAINAGE AWAY FROM STRUCTURE CRC R401.3

OPTION B - WITH BASE TRIM

MIN. 5%



COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA

ARCHITECTURAL DETAILS - LOFT



1/28/2023 10:26:17 AM  
C:\Users\jacob\Documents\227-01\_SLO County ADU\_CD\_CENTRAL\_2022\_jacob\DWG\A-904.dwg





THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.





**52 BEAM TO WALL FLASHING**  
SCALE: 1" = 1'-0"





**43 FLASHING - PROTRUSIONS**  
SCALE: 1 1/2" = 1'-0"





**32 FLASHING - WINDOW CORNER TYP.**  
SCALE: 12" = 1'-0"




**22 FLASHING - FASCIA TO WALL TYP.**  
SCALE: 1 1/2" = 1'-0"




**12 ROOF TO WALL TYP. FLASHING 2**  
SCALE: 3" = 1'-0"




**43 FLASHING - DETAILED PROTRUSION**  
SCALE: 1 1/2" = 1'-0"




**33 FLASHING - DOOR AT GRADE**  
SCALE: 3" = 1'-0"




**23 FLASHING PAN @ DOOR THRESHOLD**  
SCALE: 3" = 1'-0"




**13 ROOF TO WALL TYP. FLASHING 3**  
SCALE: 3" = 1'-0"




**53 FLASHING - G.I. VENT**  
SCALE: 1" = 1'-0"




**43 FLASHING - DETAILED PROTRUSION**  
SCALE: 1 1/2" = 1'-0"



**33 FLASHING - DOOR AT GRADE**  
SCALE: 3" = 1'-0"



**23 FLASHING PAN @ DOOR THRESHOLD**  
SCALE: 3" = 1'-0"



**13 ROOF TO WALL TYP. FLASHING 3**  
SCALE: 3" = 1'-0"



**52 BEAM TO WALL FLASHING**  
SCALE: 1" = 1'-0"



**42 FLASHING - PROTRUSIONS**  
SCALE: 1 1/2" = 1'-0"



**32 FLASHING - WINDOW CORNER TYP.**  
SCALE: 12" = 1'-0"



**22 FLASHING - FASCIA TO WALL TYP.**  
SCALE: 1 1/2" = 1'-0"



**12 ROOF TO WALL TYP. FLASHING 2**  
SCALE: 3" = 1'-0"



**53 FLASHING - G.I. VENT**  
SCALE: 1" = 1'-0"



**43 FLASHING - DETAILED PROTRUSION**  
SCALE: 1 1/2" = 1'-0"



**33 FLASHING - DOOR AT GRADE**  
SCALE: 3" = 1'-0"



**23 FLASHING PAN @ DOOR THRESHOLD**  
SCALE: 3" = 1'-0"



**13 ROOF TO WALL TYP. FLASHING 3**  
SCALE: 3" = 1'-0"


COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
ARCHITECTURAL DETAILS - LOFT

DATE  
11/28/2023  
SHEET  
A-905


11/28/2023 10:26:19 AM  
C:\Users\jacobdocuments\2727-01\_SLO\_County\_ADU\_CD\_CENTRAL\_2022\_jacob\REV1.rvt




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRACT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.




**41 LOFT ACCESS LADDER**  
SCALE: 1/2" = 1'-0"




**21 ROOF ASSEMBLY (1-HOUR) - LOFT**  
SCALE: 1" = 1'-0"




**11 DETAILED HEAD FLASHING**  
SCALE: 12" = 1'-0"




**52 INT. RAILING CONNECTION DETAIL**  
SCALE: 3" = 1'-0"




**42 LOFT GUARDS**  
SCALE: 1" = 1'-0"



**22 WATER HEATER MOUNTING - LOFT**  
SCALE: 12" = 1'-0"



**12 DETAILED JAMB FLASHING**  
SCALE: 12" = 1'-0"



**1. WALL ASSEMBLY**  
THE 1 OR 2 HR. FIRE RATED GYPSUM WALLBOARD/STUD WALL ASSEMBLY SHALL BE CONSTRUCTED OF THE MATERIALS AND IN THE MANNER SPECIFIED IN THE INDIVIDUAL U300 OR U400 SERIES WALL AND PARTITION DESIGNS IN THE UL FIRE RESISTANCE DIRECTORY AND SHALL INCLUDE THE FOLLOWING CONSTRUCTION FEATURES:

**A. STUDS-**  
WALL FRAMING MAY CONSIST OF EITHER WOOD STUDS OR STEEL CHANNEL STUDS. WOOD STUDS TO CONSIST OF NOM. 2 IN. BY 4 IN. LUMBER SPACED 16 IN. O.C. STEEL STUDS TO BE MIN. 3 1/2 IN. WIDE AND SPACED MAX. 24 IN. O.C.

**B. GYPSUM BOARD (BEARING THE UL CLASSIFICATION MARKING)-**  
THICKNESS, TYPE, NUMBER OF LAYERS AND FASTENERS AS REQUIRED IN THE INDIVIDUAL WALL AND PARTITION DESIGN. MAX. DIAM. OF OPENING IS 5 IN.

THE HOURLY F RATING OF THE FIRESTOP SYSTEM IS EQUAL TO THE HOURLY FIRE RATING OF THE WALL ASSEMBLY IN WHICH IT IS INSTALLED.

**2. THROUGH-PENETRATIONS**  
ONE METALLIC PIPE, CONDUIT OR TUBING INSTALLED EITHER CONCENTRICALLY OR ECCENTRICALLY WITHIN THE FIRESTOP SYSTEM. THE ANNULAR SPACE BETWEEN THE PIPE, CONDUIT OR TUBING AND PERIPHERY OF THE OPENING SHALL BE MIN. OF 0 IN. (POINT CONTACT) TO A MAX. 1/8 IN. PIPE, CONDUIT OR TUBING TO BE RIGIDLY SUPPORTED ON BOTH SIDES OF WALL ASSEMBLY. THE FOLLOWING TYPES AND SIZES OF METALLIC PIPES, CONDUITS OR TUBING MAY BE USED:

**A. COPPER TUBING-**  
NOM. 4 IN. DIAM. (OR SMALLER) TYPE M (OR HEAVIER) COPPER TUBING.

**B. COPPER PIPE-**  
NOM. 4 IN. DIAM. (OR SMALLER) REGULAR (OR HEAVIER) COPPER PIPE.

**C. STEEL PIPE-**  
NOM. 4 IN. DIAM. (OR SMALLER) SCHEDULE 5 (OR HEAVIER) STEEL PIPE.


**D. CONDUIT-**  
NOM. 4 IN. DIAM. (OR SMALLER) STEEL ELECTRICAL METALLIC TUBING OR RIGID STEEL CONDUIT

**E. IRON PIPE-**  
NOM. 4 IN. DIAM. (OR SMALLER) CAST OR DUCTILE IRON PIPE.

**3. FILL, VOID OR CAVITY MATERIALS (BEARING THE UL CLASSIFICATION MARKING) -**  
CAULK OR PUTTY-MIN. 1/2 IN. DIAMETER BEAD CAULK OR PUTTY APPLIED CONTINUOUSLY AROUND THE PENETRANT ON THE WALL SURFACES ON BOTH SIDES OF THE WALL.

3M COMPANY - CP 25WB+ CAULK OR MPS-2+ PUTTY

**34 THROUGH PENETRATION @ WALL - LOFT**  
SCALE: 1 1/2" = 1'-0"



**1. WOOD STUDS**  
NOMINAL 2X4 SPACED 16" O.C. WITH (2) 2X4 TOP PLATES (1) 2X4 BOTTOM PLATE. STUDS LATERALLY-BRACED BY WOOD STRUCTURAL PANEL SHEATHING (ITEM 5) AND EFFEECTIVELY FIRE STOPPED AT TOP AND BOTTOM OF WALL.

**2. GYPSUM BOARD**  
ANY CLASSIFIED 5/8" THICK, 48" WIDE, APPLIED VERTICALLY AND NAILED TO STUDS AND BEARING PLATES 7" O.C. WITH 6D CEMENT-COATED NAILS, 1 7/8" LONG WITH 1/4" DIAM. HEAD.

JOINTS AND NAILHEADS (NOT SHOWN) - WALLBOARD JOINTS COVERED WITH TAPE AND JOINT COMPOUND. NAIL HEADS COVERED WITH JOINT COMPOUND.

**3. BATTS AND BLANKETS**  
MINERAL FIBER OR GLASS INSULATION, 3 1/2" THICK. PRESSURE FIT TO FILL WALL CAVITIES BETWEEN STUDS AND PLATES. MINERAL FIBER INSULATION TO BE UNFACED AND TO HAVE A MIN. DENSITY OF 3 PCF. GLASS FIBER INSULATION TO BE FACED WITH ALUMINUM FOIL OR FRAFT PAPER AND TO HAVE A MIN. DENSITY OF 0.9 PCF (MIN. R-13 THERMAL INSULATION RATING). FIBER SPRAYED - AS AN ALTERNATE TO BATTS AND BLANKETS (ITEM 4) - SPRAY APPLIED CELLULOSE INSULATION MATERIAL. THE FIBER IS APPLIED WITH WATER TO COMPLETELY FILL THE ENCLOSED CAVITY IN ACCORDANCE WITH THE APPLICATION INSTRUCTIONS SUPPLIED WITH THE PRODUCT. NOMINAL DRY DENSITY OF 3.0 LB/CU.FT.

**4. WOOD STRUCTURAL PANEL SHEATHING**  
MIN 7/16" THICK, 4 FT. WIDE WOOD STRUCTURAL PANELS, MIN. GRADE "C-D" OR "SHEATHING". INSTALLED WITH LONG DIMENSION OF SHEET (STRENGTH AXIS) OR FACE GRAIN OF PLYWOOD PARALLEL WITH OR PERPENDICULAR TO STUDS. VERTICAL JOINTS CENTERED ON STUDS. HORIZONTAL JOINTS BACKED WITH NOMINAL 2X4 WOOD BLOCKING, ATTACHED TO STUDS ON EXTERIOR SIDE OF WALL WITH 6D CEMENT COATED BOX NAILS SPACED 6" O.C. AT PERIMETER OF PANELS AND 12" O.C. ALONG INTERIOR STUDS.


**5. EXTERIOR FACING**  
INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTION. ONE OF THE FOLLOWING EXTERIOR FACINGS IS TO BE APPLIED OVER THE SHEATHING. REFER TO PLAN FOR INFOEMATION:

**D.** CEMENTITIOUS STUCCO - PORTLAND CEMENT OR SYNTHETIC STUCCO SYSTEM WITH SELF-FURRING METAL LATH OR ADHESIVE BASE COAT. THICKNESS FROM 3/8" TO 3/4", DEPENDING ON SYSTEM.


**H.** FIBER-CEMENT SIDING - FIBER-CEMENT EXTERIOR SIDING INCLUDING SMOOTH AND PATTERNED PANEL OR LAP SIDING.

**UL DES U306**  
AT INTERIOR WALL USE:  
5/8" SHEETROCK FIRECODE CORE PANELS,  
5/8" SHEETROCK ULTRALIGHT PANELS FIRE CODE X OR  
5/8" FIBEROCK PANELS -  
2 X 4 WOOD STUD 16" OR 24" O.C.

**24 1-HR EXTERIOR RATED WALL ASSEMBLY**  
SCALE: 3" = 1'-0"



**13 DETAILED SILL FLASHING**  
SCALE: 12" = 1'-0"



**14 WALL VENT - LOFT**  
SCALE: 3" = 1'-0"

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
ARCHITECTURAL DETAILS - LOFT

DATE  
11/28/2023  
SHEET  
A-906



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



















HAMPTON BAY HURLEY MODERN MATTE BLACK OUTDOOR WALL LANTERN SCONCE (44833) OR EQUAL

**LIGHT OPTION A**

ROBERT STEVENSON LIGHTING - JAXON AGED TUSCAN OUTDOOR METAL AND SEEDY GLASS WALL SCONCE (EC1323C) OR EQUAL

**LIGHT OPTION B**

**NOTE: ALL EXTERIOR LIGHTING MUST BE DARK SKY COMPLIANT PER ZONING REGULATIONS SECTION 17.70.100.**



COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA

ARCHITECTURAL DETAILS - LOFT

DATE  
11/28/2023

SHEET  
A-921.


1/28/2023 10:26:20 AM  
C:\Users\jca\Documents\22727-01\_SLO County ADU\_CD\_CENTRAL\_2022\_jca\REV1\1.rvt




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA


ARCHITECTURAL DETAILS - LOFT




**51 METAL ROOF TYP. PIPE FLASHING**  
SCALE: 3\"/>




**52 METAL ROOF - HEADWALL**  
SCALE: 3\"/>




**41 DORMER VENT WITH (WUI COMPLIANT)**  
SCALE: 12\"/>




**42 RIDGE VENT FIRE & EMBER PROTECTION**  
SCALE: 12\"/>




**43 STANDING SEAM METAL RIDGE WITH VENTING**  
SCALE: 12\"/>




**44 EAVE VENT WITH ATTIC VENTING OPTION A**  
SCALE: 12\"/>




**21 EAVE WITH VENTING**  
SCALE: 1 1/2\"/>




**22 EAVE W/ NO VENTING REQUIRED**  
SCALE: 1 1/2\"/>




**11 EAVE**  
SCALE: 1 1/2\"/>




**12 TYP. RAKE**  
SCALE: 3\"/>




**54 EAVE VENT FIRE & EMBER PROTECTION**  
SCALE: 1\"/>



**33 MATERIAL TRANSITION**  
SCALE: 3\"/>




**23 RAKE @ OVERHANG**  
SCALE: 3\"/>




**14 TYP. METAL ROOF VALLEY**  
SCALE: 1\"/>




**55 METAL ROOF - SIDE WALL**  
SCALE: 3\"/>




**34 METAL ROOF HIP/RIDGE W/ INSULATION**  
SCALE: 1 1/2\"/>



**24 TYP. METAL ROOF HIP/RIDGE**  
SCALE: 1 1/2\"/>



**15 TYP. METAL ROOF VALLEY**  
SCALE: 1\"/>



**14 TYP. METAL ROOF VALLEY**  
SCALE: 1\"/>

1/18/2023 10:26:22 AM C:\Users\jacob\Documents\227-01\_SLO County ADU\_CD\_CENTRAL\_2022\_jacob\REV1.rvt


DATE  
11/28/2023

SHEET

A-923




FOR USE IN THE COUNTY OF SAN LUIS OBISPO




**NOTES:**  
 1. Place either F4J or 1/2" J Trim on wall of the building.  
 2. Make sure that the F4J or 1/2" J Trim is parallel with upper fascia.  
 3. Once F4J or 1/2" J Trim is installed either install wall panels or soffit panel.

DISCLAIMER: BRIDGER STEEL DETAILS INCLUDED FOR REFERENCE ONLY. INSTALL ALL COMPONENTS PER SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.




**NOTES:**  
 1. Install continuous cleat along fascia.  
 2. Install eave trim hooking onto drip edge.  
 3. Nail upper flange of eave flange to roof deck 12" o.c.  
 4. Apply underlayment over top of rafter flange.  
 5. Notch upper roof panel 1" and form around style D eave.

DISCLAIMER: BRIDGER STEEL DETAILS INCLUDED FOR REFERENCE ONLY. INSTALL ALL COMPONENTS PER SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.




**NOTES:**  
 1. Run panels across roof deck cutting and field bending last panel to fit.  
 2. Install Z closure in continuous butyl tape along rake/gable edge on top of roof panel.  
 3. Install continuous cleat along fascia.  
 4. Install rake/gable trim hooking onto cleat.  
 5. Install rake/gable on Z closure fastening 12" o.c.

DISCLAIMER: BRIDGER STEEL DETAILS INCLUDED FOR REFERENCE ONLY. INSTALL ALL COMPONENTS PER SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.




**NOTES:**  
 1. Install underlayment over edge of prong gable.  
 2. Lay prong gable trim down and fasten 2" from the outside edge every 12" o.c.  
 3. Apply universal closure under panel leaving panel 1" from flashing closure.  
 4. Install offset cleat.  
 5. Notch panels 1" and form around offset cleat.

DISCLAIMER: BRIDGER STEEL DETAILS INCLUDED FOR REFERENCE ONLY. INSTALL ALL COMPONENTS PER SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.




**NOTES:**  
 1. Install underlayment in bottom of the valley.  
 2. Lay valley panel down and fasten 2" from the outside edge every 12" o.c.  
 3. Apply second layer of underlayment over outer edge of valley approximately 3" down on both sides of the valley.  
 4. Install offset cleats on both sides of valley.  
 5. Notch panels 1" and form around offset cleat.

DISCLAIMER: BRIDGER STEEL DETAILS INCLUDED FOR REFERENCE ONLY. INSTALL ALL COMPONENTS PER SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.




**NOTES:**  
 1. Install lower roof panels.  
 2. Install Z closures to lower roof panels.  
 3. Install High/Low Transition over Z closure, make sure the transition covers closure. Fasten 12" o.c.  
 4. Fasten upper leg of transition every 12".  
 5. Install offset cleat on upper leg of transition.  
 6. Notch upper roof panel 1" and form around offset cleat.

DISCLAIMER: BRIDGER STEEL DETAILS INCLUDED FOR REFERENCE ONLY. INSTALL ALL COMPONENTS PER SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.




**NOTES:**  
 1. Install underlayment over edge of prong gable.  
 2. Lay prong gable trim down and fasten 2" from the outside edge every 12" o.c.  
 3. Apply universal closure under panel leaving panel 1" from flashing closure.  
 4. Install offset cleat.  
 5. Notch panels 1" and form around offset cleat.

DISCLAIMER: BRIDGER STEEL DETAILS INCLUDED FOR REFERENCE ONLY. INSTALL ALL COMPONENTS PER SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.



**NOTES:**  
 1. Install underlayment in bottom of the valley.  
 2. Lay valley panel down and fasten 2" from the outside edge every 12" o.c.  
 3. Apply second layer of underlayment over outer edge of valley approximately 3" down on both sides of the valley.  
 4. Install offset cleats on both sides of valley.  
 5. Notch panels 1" and form around offset cleat.

DISCLAIMER: BRIDGER STEEL DETAILS INCLUDED FOR REFERENCE ONLY. INSTALL ALL COMPONENTS PER SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.



**NOTES:**  
 1. Install underlayment in bottom of the valley.  
 2. Lay valley panel down and fasten 2" from the outside edge every 12" o.c.  
 3. Apply second layer of underlayment over outer edge of valley approximately 3" down on both sides of the valley.  
 4. Install offset cleats on both sides of valley.  
 5. Notch panels 1" and form around offset cleat.

DISCLAIMER: BRIDGER STEEL DETAILS INCLUDED FOR REFERENCE ONLY. INSTALL ALL COMPONENTS PER SELECTED MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS.



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
 ACCESSORY DWELLING UNIT  
 SAN LUIS OBISPO, CA

METAL ROOF DETAIL REFERENCES

DATE  
 11/28/2023

SHEET  
 A-941.



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

**SYMBOLS**

**WALL TYPES**

**SHEET INDEX**

	DETAIL REFERENCE BUBBLE WITH LEADER		INDICATES SHEAR WALL TYPE AND LENGTH. PER SHEAR WALL SCHEDULE		INDICATES TOP PLATE SPLICE NAILING PER SCHEDULE
	DETAIL REFERENCE BUBBLE		INDICATES SPAN AND DIRECTION OF PREFABRICATED ROOF TRUSS (BY OTHERS)		INDICATES SHEAR WALL STRAP / HOLD-DOWN TYPE PER SCHEDULE
	FULL HEIGHT SECTION INDICATOR		INDICATES SPAN AND DIRECTION OF ROOF RAFTER OR FLOOR JOIST WITH WEB STIFFENER		INDICATES PAD FOOTING TYPE PER SCHEDULE
	ELEVATION OF WALL OR FRAME		INDICATES SPAN AND DIRECTION OF ROOF RAFTER OR FLOOR JOIST		INDICATES CONTINUOUS FOOTING TYPE PER SCHEDULE
	NORTH ARROW		INDICATES HEADER @ OPENING PER HEADER SCHEDULE		ANGLE BRACE
	TOP/BOTTOM OF ELEVATIONS		EARTH LAYER		DOUBLE ANGLE BRACE
	SLOPE		INDICATES SAND OR GROUT		DRAG STRUT CONNECTION
	WELDED WIRE FABRIC (WWF LAYER)		INDICATES GRAVEL		FULL HEIGHT STIFFENER CONNECTION
	STEPPED SURFACE: FLOOR DEPRESSION		STEEL IN CROSS SECTION		MOMENT CONNECTION
	SLOPED SURFACE		INDICATES BEARING WALL		MEMBER SPLICE
	STEPPED FOOTING		SHADED AREA INDICATES CALIFORNIA FRAMING		TOP OF STEEL ± ELEVATION
	BOTTOM STEPPED FOOTING		SHADED AREA INDICATES FOOTPRINT OF FLOOR ABOVE		NUMBER OF EVENLY SPACED SHEAR STUDS
			STEEL HSS TUBE COLUMN		SPECIAL STUD SPACING SEE TYPICAL STEEL DETAILS
			STEEL HSS OR PIPE COLUMN		BEAM CAMBER AT MID-SPAN
			WIDE FLANGE STEEL COLUMN		
			WOOD POST		

	INDICATES PLYWOOD SIDE FOR SHEAR WALL
	INDICATES BEARING WOOD WALL BELOW
	INDICATES BEARING WOOD WALL ABOVE
	INDICATES NON-BEARING WOOD WALL BELOW
	INDICATES NON-BEARING WOOD WALL ABOVE
	INDICATES EXISTING BEARING WOOD WALL
	INDICATES EXISTING NON-BEARING WOOD WALL
	INDICATES BEARING CMU WALL BELOW
	INDICATES BEARING CMU WALL ABOVE
	INDICATES NON-BEARING CMU WALL BELOW
	INDICATES NON-BEARING CMU WALL ABOVE
	INDICATES EXISTING BEARING CMU WALL
	INDICATES EXISTING NON-BEARING CMU WALL
	INDICATES BEARING CONCRETE WALL BELOW
	INDICATES BEARING CONCRETE WALL ABOVE
	INDICATES NON-BEARING CONCRETE WALL BELOW
	INDICATES NON-BEARING CONCRETE WALL ABOVE
	INDICATES EXISTING BEARING CONCRETE WALL
	INDICATES EXISTING NON-BEARING CONCRETE WALL

S-101	SHEET INDEX, ABBREVIATION & SYMBOLS
S-102	GENERAL NOTES
S-103	GENERAL NOTES, SPECIAL INSPECTION & TESTS
S-201	MODERN PLANS
S-301	TYPICAL CONCRETE DETAILS
S-311	CONCRETE DETAILS
S-312	CONCRETE DETAILS
S-401	TYPICAL WOOD DETAILS
S-402	TYPICAL WOOD DETAILS
S-403	TYPICAL WOOD DETAILS
S-404	TYPICAL WOOD DETAILS
S-411	FLOOR FRAMING DETAILS
S-421	ROOF FRAMING DETAILS

**ABBREVIATIONS**

A & B	ABOVE AND BELOW	DBL	DOUBLE	HDR	HEADER	PA	POST ABOVE	T & B	TOP AND BOTTOM
AB	ANCHOR BOLT	DEPT	DEPTH	HGR	HANGER	PARA OR //	PARALLEL	T & G	TONGUE & GROOVE
ABV	ABOVE	DET	DETAIL	HP	HIGH POINT	PC	PRECAST; PIECE	TO	TOP OF
ACI	AMERICAN CONCRETE INSTITUTE	DF	DOUGLAS FIR/LARCH	HSR	HORIZONTALLY SLOTTED HOLES	PERP	PERPENDICULAR	TOC	TOP OF CURB; TOP OF CONCRETE
ADDL	ADDITIONAL	DIA OR Ø	DIAMETER	HT	HEIGHT	PLY	PLYWOOD INDEX	TOF	TOP OF FOOTING
ADJ	ADJACENT	DIAG	DIAGONAL	ID	INSIDE DIAMETER	R OR PL	PLATE	TEMP	TEMPERATURE; TEMPORARY
AESS	ARCHITECTURAL EXPOSED STRUCTURAL STEEL	DIAPH	DIAPHRAGM	IF	INSIDE FACE	PL	PROPERTY LINE	THRU	THROUGH
AISC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION	DIM	DIMENSION	I-JST	I-JOIST	PLF	PONDS PER LINEAL FOOT	THK	THICKNESS/THICK
ALT	ALTERNATE	DN	DOWN	IN	INCH	PLCS	PLACES	THR	THREADED
ALUM	ALUMINUM	DO	DO OVER	INCL	INCLUDE	PLY	PLYWOOD	TOP OF 1	TOP
ANCH	ANCHOR	DWG	DRAWING	INFO	INFORMATION	PROP	PROPERTY	TOS	TOP OF STEEL/TOP OF SLAB
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE	DWL	DOWEL	INSP	INSPECTION	PT	PRESSURE TREATED	TOW	TOP OF WALL
APA	ENGINEERED WOOD ASSOCIATION (FORMERLY THE AMERICAN PLYWOOD ASSOCIATION)	EA	EACH	INT	INTERIOR	PW	PLATE WASHER	TS	TRIMMER STUD
APPVD	APPROVED	EJ	EACH FACE	JST	JOIST	PJP	PARTIAL JOINT PENETRATION WELD	TYP	TYPICAL
APPROX	APPROXIMATE	EF	EACH FACE	JT	JOINT	PREFAB	PREFABRICATED	UNO	UNLESS NOTED OTHERWISE
ARCH	ARCHITECTURAL; ARCHITECT	EK	EXPANSION JOINT	K	KIPS	PSF	POUNDS PER SQUARE FOOT	UT	ULTRA-SONIC TEST
AWPA	AMERICAN WOOD PRESERVERS ASSOCIATION	EL	ELEVATION	KS	KING STUD	PSI	POUNDS PER SQUARE INCH	VERT	VERTICAL
AWS	AMERICAN WELDING SOCIETY	ELEC	ELECTRICAL	KP	KING POST	PSL	PARALLEL STRAND LUMBER	VSH	VERTICAL SLOTTED HOLES
AITC	AMERICAN INSTITUTE OF TIMBER CONSTRUCTION	ELEV	ELEVATOR	KSI	KIPS PER SQUARE INCH	PVMT	PAVEMENT	W/	WITH
ASTM	AMERICAN SOCIETY FOR TESTING MATERIALS	EMBED	EMBEDMENT	LB(S) OR #	POUND(S)	#	POUND; NUMBER	W/O	WITHOUT
BLDG	BUILDING	EN	EDGE NAIL	LF	LINEAL FOOT	REF	REFERENCE	WO	WHERE OCCURS
BLK	BLOCK	ENGR	ENGINEER	LN	LINEAL; LINEAR	REINF	REINFORCE; REINFORCING	WD	WOOD
BLKG	BLOCKING	EQ	EQUAL OR EQUIVALENT	LH	LONG LEG HORIZONTAL	REQD	REQUIRED	WP	WORK POINT; WATERPROOF
BM	BEAM	EQUIP	EQUIPMENT	LLV	LONG LEG VERTICAL	RF	ROOF	WWF	WELDED WIRE FABRIC
BN	BOUNDARY NAIL	ES	EACH SIDE	LP	LOW POINT	RR	ROOF RAFTER		
BOT OR B	BOTTOM	EW	EACH WAY	LSH	LONG SLOTTED HOLES	Ø	ROUND; DIAMETER		
BRC	BRACE	EXIST or [E]	EXISTING	LSL	LAMINATED STRAND LUMBER	SCHED	SCHEDULE	W	W SHAPE
BRG	BEARING	EXT	EXTERIOR	LT WT	LIGHTWEIGHT	SECT	SECTION	C	AMERICAN STD CHANNEL SHAPE
BTWN	BETWEEN	FDN	FOUNDATION	LVL	LEVEL OR LAMINATED VENEER LUMBER	SEP	SEPARATION	MC	MISC CHANNEL SHAPE
CANT	CANTILEVER	FIN	FINISH	MAT	MASONRY	SHT	SHEET	L	ANGLE SHAPE
CAMR OR C	CAMBER	FJ	FLOOR JOIST	MAS	MASONRY	SHTG	SHEATHING	WT, ST, MT	STRUCT TEE SHAPE
CC	CENTER TO CENTER	FLG	FLANGE	MATL	MATERIAL	SIM	SMILAR	PIPE	STANDARD PIPE SHAPE
CG	CENTER OF GRAVITY	FLR	FLOOR	MAX	MAXIMUM	SOG	SLAB ON GRADE	PIPE-X	EXTRA STRONG PIPE SHAPE
CP	CAST-IN-PLACE	FN	FIELD NAIL	MB	MACHINE BOLT	SN	SHEAR NAIL	PIPE-XX	DBL EXTRA STRONG PIPE SHAPE
CJ	CONSTRUCTION JOINT; CONTROL JOINT	FOC	FACE OF CONCRETE	MECH	MECHANICAL	SPCG	SPACING	HSS	HOLLOW STRUCTURAL SECTION
CL	CENTER LINE	FOM	FACE OF MASONRY	MFR	MANUFACTURER	SPECS	SPECIFICATIONS		
CLR	CLEARANCE; CLEAR	FOS	FACE OF STUD	MIN	MINIMUM; MINUTE	SQ	SQUARE		
CMU	CONCRETE MASONRY UNIT	FOW	FACE OF WALL	MISC	MISCELLANEOUS	SS	STAINLESS STEEL		
COL	COLUMN	FRMG	FRAMING	[N]	NEW	SSL	SHORT SLOTTED HOLES		
COMP	COMPRESSION	FT	FOOT; FEET	N	NORTH	STD	STANDARD		
CONC	CONCRETE	FTA	FLOOR TIE ABOVE	NO or #	NUMBER	STGR	STAGGER		
CONN	CONNECTION; CONNECT	FTG	FOOTING	NTS	NOT TO SCALE	STIFF	STIFFENERS		
CONSTR	CONSTRUCTION	GA	GAUGE	OC	ON CENTER	STIRR	STIRRUP		
CONT	CONTINUE; CONTINUOUS	GALV	GALVANIZED	OD	OUTSIDE DIAMETER	STL	STEEL		
CONTR	CONTRACTOR	GB	GRADE BEAM	OF	OUTSIDE FACE	STRUCT	STRUCTURAL		
CJP	COMPLETE JOINT PENETRATION WELD	GLB	GLUED LAMINATED BEAM	OH	OPPOSITE HAND	SW	SHEAR WALL		
CTR	CENTER	GR	GRADE	OPNG	OPENING	SYM	SYMMETRICAL		
CTS&K	COUNTERSINK; COUNTERSUNK	GRND	GROUND	OPP	OPOSITE	TB	TIE BEAM		
CU FT	CUBIC FOOT	H or HORIZ	HORIZONTAL	ORIG	ORIGINAL				
				OSB	ORIENTED STRAND BOARD				

**COUNTY OF SAN LUIS OBISPO**  
**ACCESSORY DWELLING UNIT**  
 SAN LUIS OBISPO, CA  
**SHEET INDEX,**  
**ABBREVIATION & SYMBOLS**

N:\2020\2727-01\c229-alo-county\ad\Structural\Sheet\Plan\_4\Moedem\2727-01\_C1027-1101.dwg, 5.4.10, No. 20, 2023, 3:36pm, dlp@z



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRACT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT

SAN LUIS OBISPO, CA

GENERAL NOTES

DATE  
11/20/2023

SHEET

S-102

### GENERAL

- ALL WORK SHALL CONFORM TO THE MINIMUM STANDARDS OF THE FOLLOWING CODES AND STANDARDS:
  - 2022 CALIFORNIA BUILDING CODE, PART 2, VOLUME 2 OF 2, AND TITLE 24 C.C.R. 2022 EDITION AND LATEST REGULATIONS (INCLUDING SUPPLEMENTS AND ERRATA) HEREIN REFERRED TO AS "THE CODE".
  - ANY OTHER REGULATING AGENCIES WHICH HAVE AUTHORITY OVER ANY PORTION OF THE WORK, INCLUDING THE STATE OF CALIFORNIA DIVISION OF OCCUPATIONAL SAFETY AND HEALTH (CAL/OSHA).
  - CODES & STANDARDS REFERENCED IN THE CODE OR LISTED IN THESE NOTES AND SPECIFICATIONS.
- ALL DRAWINGS ARE CONSIDERED TO BE A PART OF THE CONSTRUCTION DOCUMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REVIEW AND COORDINATION OF ALL DRAWINGS AND SPECIFICATIONS PRIOR TO THE START OF CONSTRUCTION. ANY DISCREPANCIES THAT OCCUR SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO START OF CONSTRUCTION SO THAT A CLARIFICATION CAN BE ISSUED. ANY WORK PERFORMED IN CONFLICT WITH THE CONTRACT DOCUMENTS OR ANY CODE REQUIREMENTS SHALL BE CORRECTED BY THE CONTRACTOR AT THEIR OWN EXPENSE AND AT NO EXPENSE TO THE OWNER OR ARCHITECT.
- NOTES AND DETAILS ON DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE GIVEN, CONSTRUCTION SHALL BE AS SHOWN FOR SIMILAR WORK.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO STARTING CONSTRUCTION. THE ARCHITECT SHALL BE NOTIFIED OF ANY DISCREPANCIES OR INCONSISTENCIES. IN NO INSTANCE SHALL DIMENSIONS BE SCALED FROM THE DRAWINGS.
- SEE ARCHITECTURAL DRAWINGS FOR THE FOLLOWING:
  - SIZE AND LOCATION OF ALL DOOR AND WINDOW OPENINGS, EXCEPT AS NOTED
  - SIZE AND LOCATION OF ALL INTERIOR AND EXTERIOR NON-BEARING PARTITIONS' UNLESS NOTED AND/OR DETAILED ON THE STRUCTURAL DRAWINGS
  - SIZE AND LOCATION OF ALL CONCRETE CURBS, EQUIPMENT PADS, PITS, FLOOR DRAINS, SLOPES, DEPRESSED AREAS, CHANGE IN LEVEL, CHAMFERS, GROOVES, INSERTS, ETC.
  - SIZE AND LOCATION OF ALL FLOOR AND ROOF OPENINGS EXCEPT AS SHOWN
  - FLOOR AND ROOF FINISHES
  - MISCELLANEOUS DRAINAGE AND WATERPROOFING
  - ALL FIREPROOFING REQUIREMENTS INCLUDING FIREPROOFING OF STRUCTURAL STEEL
  - DIMENSIONS NOT SHOWN ON STRUCTURAL DRAWINGS
- SEE MECHANICAL, PLUMBING AND ELECTRICAL DRAWINGS FOR THE FOLLOWING:
  - PIPE RUNS, SLEEVES, HANGERS, TRENCHES, WALL AND SLAB OPENINGS, ETC., EXCEPT AS SHOWN OR NOTED.
  - ELECTRICAL CONDUIT RUNS, BOXES, OUTLETS IN WALLS AND SLABS.
  - CONCRETE INSERTS FOR ELECTRICAL, MECHANICAL OR PLUMBING FIXTURES.
  - SIZE AND LOCATION OF MACHINE OR EQUIPMENT BASES, ANCHOR BOLTS FOR MOTOR MOUNTS.
- SEE CIVIL DRAWINGS FOR THE FOLLOWING:
  - HEIGHT AND/OR ELEVATION OF:
    - FINISHED SURFACE
    - TOP OF WALL
    - TOP OF GRADE
    - FINISHED GRADE
    - SLOPE
  - SITE CONCRETE WALKWAYS, CURBS & PAVING
- THE CONTRACT STRUCTURAL DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE STRUCTURE DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, SHORING FOR LOADS DUE TO CONSTRUCTION EQUIPMENT ETC.. THE CONTRACTOR IS RESPONSIBLE FOR PROVISION OF TEMPORARY SHORING AND OTHER CONSTRUCTION AIDS, INCLUDING ALL ENGINEERING OF SUCH SYSTEMS, FOR TEMPORARY SUPPORT OF NEW AND/OR EXISTING STRUCTURAL ELEMENTS AS REQUIRED FOR ERECTION AND OTHER CONTRACTOR'S MEANS AND METHODS OF CONSTRUCTION (I/N/O). OBSERVATION VISITS TO THE SITE BY THE STRUCTURAL ENGINEER SHALL NOT INCLUDE INSPECTION OF THE ABOVE ITEMS OR CONCERN CONSTRUCTION MEANS AND METHODS OR CONSTRUCTION SAFETY.
- BACKFILL SHALL NOT BE PLACED BEHIND EXTERIOR AND INTERIOR RETAINING WALLS UNTIL THE CONCRETE / CMU HAS ACHIEVED FULL DESIGN STRENGTH. FOR BRACED WALLS SUPPORTED BY STRUCTURAL DIAPHRAGMS, BACKFILL SHALL NOT BE PLACED BEHIND THE WALL UNTIL THE DIAPHRAGM HAS BEEN INSTALLED, AND FOR CONCRETE DIAPHRAGMS, HAS ACHIEVED FULL DESIGN STRENGTH.
- THE CONTRACT STRUCTURAL DRAWINGS SHOW THE BUILDING IN ITS FINAL INTENDED POSITION. CONTRACTOR SHALL MAKE PROVISIONS IN THE LAYOUT OF THE BUILDING TO TAKE INTO ACCOUNT SHRINKAGE, CREEP, SHORTENING, ETC..
- OPENINGS, POCKETS, ETC., LARGER THAN 6" SHALL NOT BE PLACED IN CONCRETE SLABS, DECKS, WALLS, UNLESS SPECIALLY DETAILED ON THE STRUCTURAL DRAWINGS. NOTIFY THE STRUCTURAL ENGINEER WHEN DRAWINGS BY OTHERS SHOW OPENINGS, POCKETS, ETC., LARGER THAN 6" NOT SHOWN ON THE STRUCTURAL DRAWINGS, BUT WHICH ARE LOCATED IN STRUCTURAL MEMBERS.
- ASTM SPECIFICATIONS ON THE DRAWINGS SHALL BE THE VERSION REFERENCED IN CHAPTER 35 OF THE CODE OR AS REFERENCED IN THE APPLICABLE DESIGN STANDARD.
- CONTRACTOR SHALL INVESTIGATE SITE DURING CLEARING AND EARTHWORK OPERATIONS FOR FILLED EXCAVATIONS OR BURIED STRUCTURES, SUCH AS CESSPOOLS, CISTERNS, FOUNDATIONS, ETC., IF ANY SUCH STRUCTURES ARE FOUND, THE STRUCTURAL ENGINEER AND GEOTECHNICAL ENGINEER SHALL BE NOTIFIED IMMEDIATELY.
- CONSTRUCTION MATERIAL SHALL BE SPREAD OUT IF PLACED ON FRAMED ROOF OR FLOOR. LOAD SHALL NOT EXCEED THE DESIGN LIVE LOAD PER SQUARE FOOT. THE CONTRACTOR TO DESIGN AND PROVIDE ADEQUATE SHORING AND/OR BRACING WHERE STRUCTURE HAS NOT ATTAINED DESIGN STRENGTH.
- CONTRACTOR SHALL COORDINATE SHORING WITH DRAWINGS OF RECORD TO INSURE PROVISIONS FOR POCKETS, BLOCKOUTS, OFFSETS, STEPPED FOOTINGS AND ANY OTHER ITEMS AFFECTED BY THE SHORING
- AN UNDERGROUND SERVICE ALERT INQUIRY IDENTIFICATION NUMBER MUST BE OBTAINED AT LEAST TWO WORKING DAYS BEFORE STARTING WORK WITH THIS PERMIT.
  - FOR PROJECTS IN SOUTHERN CALIFORNIA TELEPHONE NO. 1-800-422-4133.
  - FOR PROJECTS IN NORTHERN CALIFORNIA TELEPHONE NO. 1-800-227-2600.
- EDGE OF SLAB DIMENSIONS TO BE COORDINATED AND VERIFIED BY THE GENERAL CONTRACTOR PRIOR TO FABRICATION.

### DIMENSIONS

- DIMENSIONS SHALL BE DEFINED TO INCLUDE BOTH HORIZONTAL DIMENSIONS AND VERTICAL DIMENSIONS (ELEVATIONS).
- WRITTEN DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALED DRAWINGS.
- SEE ARCHITECTURAL DRAWINGS FOR DIMENSION NOT NOTED ON STRUCTURAL DRAWINGS.
- SEE ARCHITECTURAL AND/OR CIVIL DRAWINGS FOR FINISH FLOOR ELEVATIONS.
- SEE ARCHITECTURAL DRAWINGS FOR ALL TOP OF SHEATHING AND/OR ROOF ELEVATIONS.
- THE CONTRACTOR SHALL REVIEW AND VERIFY ALL DIMENSIONS PRIOR TO STARTING CONSTRUCTION. THE ARCHITECT SHALL BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCIES OR INCONSISTENCIES.

### DESIGN INFORMATION

FLOOR LIVE LOADS			
OCCUPANCY OR USE	UNIFORM (PSF)	CONC. (LBS)	REFERENCE
RESIDENTIAL ONE- AND TWO-FAMILY DWELLINGS UNINHABITABLE ATTICS WITHOUT STORAGE UNINHABITABLE ATTICS WITH STORAGE HABITABLE ATTICS AND SLEEPING AREAS ALL OTHER AREAS	10 20 30 40	—	2022 CBC TABLE 1607.1

ROOF LIVE LOADS			
OCCUPANCY OR USE	UNIFORM (PSF)	CONC. (LBS)	REFERENCE
ROOF ORDINARY FLAT, PITCHED AND CURVED ROOFS (THAT ARE NOT OCCUPIABLE)	20	—	2022 CBC TABLE 1607.1

SNOW DESIGN DATA		
PARAMETER	VALUE	REFERENCE
GROUND SNOW LOAD	P <sub>g</sub> = 0 PSF	ASCE 7-16 7.2

WIND DESIGN DATA		
PARAMETER	VALUE	REFERENCE
ULTIMATE DESIGN WIND SPEED (3-SEC GUST)	V <sub>ult</sub> = 92 MPH	2022 CBC FIG. 1609.3
NOMINAL DESIGN WIND SPEED (3-SEC GUST)	V <sub>ult</sub> = 72 MPH	2022 CBC 1609.3.1
EXPOSURE CATEGORY	C	2022 CBC 1609.4.3
INTERNAL PRESSURE COEFFICIENT:	GCp1 = ± 0.18	ASCE 7-16 TABLE 26.13-1

COMPONENTS & CLADDING WIND PRESSURES (PSF)				
LOCATION	ZONE	COMPONENT TRIBUTARY AREA (SQ FT)		
		10	100	500
ROOF	ZONE 1	-31.0	-16.0	-16.0
	ZONE 2a	-31.0	-16.0	-16.0
	ZONE 2b	-34.1	-21.6	-18.4
	ZONE 2c	-31.0	-16.0	-16.0
	ZONE 3a	-41.9	-26.3	-18.4
	ZONE 3c	-34.1	-21.6	-18.4
	ALL ZONES	16.9	16.0	16.0
	ZONE 1	-43.5	-27.8	-27.8
	ZONE 2a	-43.5	-27.8	-27.8
OVERHANG	ZONE 2b	-46.6	-34.1	-31.0
	ZONE 2c	-43.5	-27.8	-27.8
	ZONE 3a	-54.4	-38.8	-31.0
	ZONE 3c	-46.6	-34.1	-31.0
WALL	ZONE 4	-20.0	-17.4	-16.0
	ZONE 5	-24.7	-19.2	-16.0
	POSITIVE	18.4	16.0	16.0

- EARTHQUAKE DESIGN DATA (2022 CBC SECTION 1603.1.5):

SITE AND OCCUPANCY PARAMETERS		
PARAMETER	VALUE	REFERENCE
RISK CATEGORY	II	2022 CBC TABLE 1604.5
SEISMIC IMPORTANCE FACTOR	I <sub>p</sub> = 1.0	ASCE 7-16 TABLE 1.3-2
MAPPED SPECTRAL RESPONSE ACCELERATIONS:	S <sub>1</sub> = 2.47 g	2022 CBC 1613.2.1
	S <sub>1</sub> = 1.05 g	
SITE CLASS	D (DF)	2022 CBC 1613.2.2
SPECTRAL RESPONSE COEFFICIENTS:	S <sub>DS</sub> = 1.97 g	2022 CBC 1613.2.4
	S <sub>1</sub> = 1.19 g	
	S <sub>1/8</sub> = 1.19 g	

BUILDING PARAMETERS		
PARAMETER	VALUE	REFERENCE
SEISMIC DESIGN CATEGORY	SDC = D	2022 CBC 1613.2.5
BASIC SEISMIC FORCE RESISTING SYSTEM	LIGHT FRAME (WOOD) WALLS SHEATHED WITH WOOD STRUCTURAL PANELS RATED FOR SHEAR RESISTANCE	ASCE 7-16 TABLE 12.2-1
RESPONSE MODIFICATION FACTOR	R = 4 1/2	ASCE 7-16 TABLE 12.2-1
SYSTEM OVERSTRENGTH FACTOR	Ω <sub>o</sub> = 3	
DEFLECTION AMPLIFICATION FACTOR	C <sub>d</sub> = 4	
DESIGN BASE SHEAR	V = 7.8 k	ASCE 7-16 12.8.1
SEISMIC RESPONSE COEFFICIENTS	C <sub>s</sub> = 0.304	ASCE 7-16 12.8.1.1
ANALYSIS PROCEDURE USED	EQUIVALENT LATERAL FORCE PROCEDURE	ASCE 7-16 12.8

- GEOTECHNICAL INFORMATION (2022 CBC SECTION 1603.1.6): REFER TO FOUNDATION GENERAL NOTES

### FOUNDATION

1. GEOTECHNICAL INFORMATION AND FOUNDATION DESIGN IS BASED ON THE FOLLOWING:

- DESIGN LATERAL SOIL LOADS ARE IN ACCORDANCE WITH 2022 CBC TABLE 16.01.1
- ALLOWABLE FOUNDATION BEARING AND LATERAL PRESSURES ARE IN ACCORDANCE WITH 2022 CBC TABLE 1806.2

2. SPREAD OR CONTINUOUS FOOTINGS:

ELEMENT	ALLOWABLE BEARING CAPACITY (PSF) <sup>4</sup>	ALLOWABLE LATERAL RESISTANCE <sup>8</sup>	
		PASSIVE RESISTANCE (PSF/FT BELOW GRADE) <sup>1</sup>	COHESION (PSF)
SHALLOW FOUNDATION	1,500	100	130

- NOTES:
- THE ALLOWABLE CAPACITY MAY BE INCREASED BY ONE-THIRD WHEN CONSIDERING LOADS OF SHORT DURATION SUCH AS WIND OR SEISMIC FORCES.
  - THE ALLOWABLE LATERAL RESISTANCE CAN BE TAKEN AS THE SUM OF THE FRICTIONAL RESISTANCE AND PASSIVE RESISTANCE.
  - THE UPPER FOOT OF SOIL NOT PROTECTED BY PAVEMENT SHALL BE NEGLECTED WHEN CALCULATING POUND RESISTANCE.
  - COMPACTED FILL SHOULD BE PREPARED AS FOLLOWS: A MIN OF 12" OF COMPACTED FILL SHALL BE PROVIDED, COMPACTED TO A MIN OF 90 PERCENT MODIFIED PROCTOR IN ACCORDANCE WITH ASTM D 1557 (2022 CBC 1804.6)

- WHEN NOT SHOWN ON THE DRAWINGS, CONTRACTOR TO PROVIDE FOR DESIGN AND INSTALLATION OF ALL CURBING, SHEATHING AND SHORING REQUIRED AND SHALL BE SOLELY RESPONSIBLE FOR ALL EXCAVATION PROCEDURES INCLUDING LAGGING, SHORING, AND PROTECTION OF ADJACENT PROPERTY, STRUCTURES, STREETS, AND UTILITIES IN ACCORDANCE WITH ALL NATIONAL, STATE AND LOCAL SAFETY ORDINANCES.
- CONTRACTOR TO PROVIDE FOR DE-WATERING OF EXCAVATIONS FROM SURFACE WATER, GROUND WATER AND/OR SEEPAGE.
- EXCAVATION FOR FOOTINGS SHALL BE APPROVED BY THE INSPECTOR OR GEOTECHNICAL ENGINEER PRIOR TO PLACING CONCRETE AND REINFORCING.
- ALL EXCAVATIONS SHALL BE PROPERLY BACKFILLED. DO NOT PLACE BACKFILL BEHIND RETAINING WALLS BEFORE CONCRETE OR GROUT HAS ACHIEVED FULL DESIGN STRENGTH. CONTRACTOR SHALL PROVIDE FOR DESIGN, PERMITS AND INSTALLATION OF SUCH BRACING.
- EXCAVATIONS SHALL BE CUT SQUARE AND SMOOTH, WITH LEVEL BOTTOMS.
- FOOTING BACKFILL AND UTILITY TRENCH BACKFILL WITHIN BUILDING AREA SHALL BE MECHANICALLY COMPACTED IN LAYERS IN ACCORDANCE WITH THE GEOTECHNICAL INVESTIGATION REPORT AND APPROVED BY THE GEOTECHNICAL ENGINEER. FLOODING WILL NOT BE PERMITTED. ALL FILLS USED TO SUPPORT FOUNDATIONS SHALL BE INSPECTED BY THE GEOTECHNICAL ENGINEER REPRESENTATIVE PER SECTION 1705.6 OF THE CODE.
- ALL ABANDONED FOOTINGS, UTILITIES, ETC. SHALL BE REMOVED. NEW FOOTINGS MUST EXTEND INTO UNDISTURBED SOILS.
- THIS PLAN IS INTENDED FOR FLAT LOTS, WITHOUT HIGHLY EXPANSIVE OR LIQUEFABLE SOILS. IF THE PROJECT SITE IS DETERMINED TO HAVE ANY OF THESE QUALITIES, AS DETERMINED BY THE BUILDING OFFICIAL, THESE PERMITTED ADU FOUNDATION PLANS AND DETAILS ARE NOT APPLICABLE.

### EXISTING CONDITIONS

- ALL INFORMATION SHOWN ON THE PLANS RELATIVE TO EXISTING CONDITIONS IS GIVEN AS THE BEST PRESENT KNOWLEDGE FROM PLANS SUPPLIED BY THE OWNER, BUT WITHOUT GUARANTEE OF ACCURACY.
- WHERE ACTUAL CONDITIONS ARE NOT IN ACCORDANCE WITH THE INFORMATION PRESENTED, THE ARCHITECT AND/OR STRUCTURAL ENGINEER SHALL BE NOTIFIED IMMEDIATELY. NO MODIFICATIONS OF THE PLANS FOR NEW CONSTRUCTION SHALL BE MADE WITHOUT THE WRITTEN APPROVAL OF THE ARCHITECT.

### EXISTING UNDERGROUND UTILITIES

- THE ARCHITECT AND ENGINEERS ARE NOT RESPONSIBLE FOR THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES WHETHER OR NOT SHOWN ON THE DRAWINGS. DRAWINGS, IF ANY, IS APPROXIMATE. THE CONTRACTOR SHALL EXERCISE EXTREME CAUTION IN EXCAVATING AND TRENCHING ON THE SITE. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ARCHITECT AND/OR STRUCTURAL ENGINEER SHOULD ANY SUCH UNIDENTIFIED CONDITIONS BE DISCOVERED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES WHICH MAY RESULT FROM HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ALL EXISTING UNDERGROUND UTILITIES.
- AN UNDERGROUND SERVICE ALERT INQUIRY IDENTIFICATION NUMBER MUST BE OBTAINED AT LEAST TWO WORKING DAYS BEFORE STARTING WORK WITH THIS PERMIT.
  - FOR PROJECTS IN SOUTHERN CALIFORNIA TELEPHONE NO. 1-800-422-4133.
  - FOR PROJECTS IN NORTHERN CALIFORNIA TELEPHONE NO. 1-800-227-2600.

### DEMOLITION

- ALL DEMOLITION SHALL BE CARRIED ON IN SUCH A WAY AS NOT TO DAMAGE EXISTING ELEMENTS, WHICH ARE TO REMAIN IN THE FINISHED STRUCTURE.
- ALL ELEMENTS OF THE STRUCTURE, WHICH ARE TO REMAIN, AND WHICH ARE DAMAGED DURING DEMOLITION WORK SHALL BE REPLACED AT NO ADDITIONAL COST. EXISTING ELEMENTS SHALL BE PROTECTED TO THE FULLEST EXTENT POSSIBLE, IN ORDER TO MITIGATE DAMAGE.
- CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND REPLACEMENT OF ALL EXISTING ELEMENTS THAT ARE NECESSARY FOR THE INSTALLATION OF ALL NEW WORK.
- WHERE EXISTING PARTITION WALLS ARE TO BE DEMOLISHED, CONTRACTOR SHALL VERIFY WALLS ARE NON-BEARING PRIOR TO DEMOLITION. IF WALLS ARE FOUND TO BE BEARING, CONTRACTOR SHALL NOTIFY ARCHITECT IMMEDIATELY

### CONCRETE

1. ALL CONCRETE CONSTRUCTION SHALL CONFORM WITH CHAPTER 19 OF THE CODE AND WITH THE PROVISIONS OF ACI 318-19.

2. CONCRETE MATERIALS SHALL BE IN ACCORDANCE WITH THE FOLLOWING STANDARDS:

MATERIAL	ASTM STANDARD
PORTLAND CEMENT (TYPE II) <sup>1</sup>	C150
CONCRETE AGGREGATES (HARDROCK)	C33
WATER <sup>2</sup>	C1602
COAL FLY ASH OR POZZOLAN (CLASS F)	C618
NATURAL OR MANUFACTURED SAND	C33
SLAG	C989

- FOR SOILS WITH HIGH CONCENTRATIONS OF SULFATES (EXPOSURES S2 OR S3 PER ACI 318-19 TABLE 19.3.2.1) PORTLAND CEMENT SHALL BE TYPE V. VERIFY WITH PROJECT GEOTECHNICAL REPORT.
  - WATER SHOULD ONLY BE ADDED AT THE BATCH PLANT. IN NO CASE SHALL THE DESIGN WATER/ CEMENT RATIO BE EXCEEDED.
3. CONCRETE MIXES SHALL BE PROPORTIONED BASED ON SECTION 26.4.3 OF ACI 318-19, WHICH REFERENCES ACI 301-10 ARTICLE 4.2.3. MIX DESIGNS SHALL INCLUDE DOCUMENTATION OF MIX AVERAGE COMPRESSIVE STRENGTH THROUGH FIELD TEST DATA OR TRAIL MIXTURES IN ACCORDANCE WITH ACI 301-10 ARTICLE 4.2.3.4. SCHEDULE OF STRUCTURAL CONCRETE STRENGTHS AND LOCATIONS (I/N/O):

LOCATION IN STRUCTURE	MINIMUM STRENGTH (PSI)	DENSITY (PCF)	MAX SLUMP (IN/1)	MAX WATER/CEMENT RATIO	SLAG/ FLY ASH <sup>4</sup> (MAX)
CONCRETE FOUNDATIONS, GRADE BEAMS, TIE BEAMS	2,500	150	4	0.5	0.15
CONCRETE SLAB ON GRADE	2,500	150	4	0.45	0.15

- AS MEASURED BY CEMENTIUMUS WEGHT
- DEPOSITING AND CONVEYING OF CONCRETE SHALL CONFORM TO SECTION 26.5 OF ACI 318-19 AND PROJECT SPECIFICATIONS.
- ALL CONCRETE SURFACES AGAINST WHICH NEW CONCRETE IS TO BE PLACED SHALL BE CLEANED AND ROUGHENED TO 1/4" AMPLITUDE.
- ALL REINFORCING BARS, ANCHOR BOLTS AND OTHER CONCRETE INSERTS SHALL BE WELL SECURED IN POSITION PRIOR TO PLACING CONCRETE.
- PROVIDE SLEEVES FOR PLUMBING AND ELECTRICAL OPENINGS IN CONCRETE BEFORE PLACING. DO NOT CUT ANY REINFORCING WHICH MAY CONFLICT. CORING IN CONCRETE IS NOT PERMITTED WITHOUT SEOR APPROVAL. NOTIFY THE SEOR IN ADVANCE OF CONDITIONS NOT SHOWN ON THE DRAWINGS. SEE THE DRAWINGS FOR ADDITIONAL RESTRICTIONS ON THE PLACEMENT OF OPENINGS IN SLABS AND WALLS.
- PIPES EMBEDDED IN CONCRETE:
  - CONCRETE
    - PIPES LARGER THAN 1-1/2" DIAMETER SHALL NOTE BE EMBEDDED IN STRUCTURAL CONCRETE EXCEPT WHERE SPECIFICALLY APPROVED BY SEOR.
    - NO CONDUITS SHALL BE PLACED IN CONCRETE FILL OVER METAL DECK.
    - PIPES SHALL NOT DISPLACE OR INTERRUPT REINFORCING BARS.
    - DO NOT STACK CONDUITS. SPACE EMBEDDED PIPES AND CONDUITS AT A MINIMUM OF 3 DIAMETERS CLEAR FROM OTHER EMBEDDED PIPES/CONDUITS AND REBAR.

### REINFORCING STEEL

- REINFORCING BARS SHALL CONFORM TO THE REQUIREMENTS OF CHAPTER 19 OF THE CODE AND WITH THE PROVISIONS OF ACI 318-19, ASTM A706, GRADE 60 UNO, ASTM A615 GR 60 STEEL, MAY BE SUBSTITUTED FOR ASTM A706 GR60 STEEL PER ACI 318-19 SECTION 20.2.2.5 PROVIDED THE FOLLOWING CONDITIONS ARE MET:
  - THE ACTUAL YIELD STRENGTH BASED ON MILL TESTS DOES NOT EXCEED THE SPECIFIED YIELD STRENGTH BY MORE THAN 18,000 PSI.
  - THE RATIO OF THE ACTUAL ULTIMATE TENSILE STRESS TO THE ACTUAL YIELD STRENGTH IS NOT LESS THAN 1.25.
  - WHERE REINFORCEMENT COMPLYING WITH ASTM A615 IS TO BE WELDED, CHEMICAL TESTS SHALL BE PERFORMED TO DETERMINE WELDABILITY IN ACCORDANCE WITH SECTION 26.4.4 OF ACI 318-19.
- BARs SHALL BE CLEAN OF OIL, GREASE, OR OTHER MATERIALS LIKELY TO IMPAIR BOND. ALL REINFORCING BAR BENDS SHALL BE MADE COLD.
- REINFORCING BAR LAP SPICES SHALL BE MADE AS INDICATED ON THE DRAWINGS. LAP ALL HORIZONTAL BARS AT CORNERS AND INTERSECTIONS. STAGGER ALL SPICES UNLESS NOTED OTHERWISE ON PLANS.
  - MINIMUM LAP SPICE LENGTH FOR REINFORCING STEEL BARS IN CONCRETE SHALL BE PER ACI 318-19 SECTION 25.5.2 AND THE REINFORCING SCHEDULE ON THE DRAWINGS.
- REINFORCING STEEL SHALL BE ACCURATELY PLACED AND ADEQUATELY SUPPORTED BEFORE THE CONCRETE IS PLACED AND SHALL BE SECURED AGAINST DISPLACEMENT DURING CONSTRUCTION WITHIN PERMITTED TOLERANCES. ADEQUATE SUPPORTS ARE ALSO NECESSARY TO KEEP THE REINFORCING STEEL AT THE PROPER DISTANCE FROM THE FORMS. USE WIRE BAR SUPPORTS, PRECAST CONCRETE SUPPORTS, SPACERS, BOLSTERS, REINFORCEMENT OR OTHER MEANS OF SUPPORT PER THE "CRSI MANUAL OF STANDARD PRACTICE", LATEST EDITION.
- EDJITEMS MAY BE CORRECTED PRIOR TO PLACEMENT OF OVERLYING GRIDS OR REINFORCING STEEL.
- CONCRETE PROTECTION FOR REINFORCEMENT

THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCEMENT IN CAST-IN-PLACE CONCRETE (NON-PRESTRESSED):	MINIMUM COVER, IN.
A. CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH	3
B. CONCRETE EXPOSED TO EARTH OR WEATHER: NO. 6 THROUGH NO. 18 BAR NO. 5 BAR, W31 OR D31 WIRE & SMALLER	2 1 1/2
C. CONCRETE NOT EXPOSED TO WEATHER OR IN CONTACT WITH GROUND: SLABS, WALLS, JOISTS NO. 14 AND NO. 18 BARS NO. 11 BAR & SMALLER BEAMS, COLUMNS, PRIMARY REINFORCEMENT TIES, STIRRUPS, SPIRALS	1 1/2 1 1/2 3/4 1 1/2

### WOOD (GENERAL)

- PRESERVATIVE TREATMENT:
  - WOOD MEMBERS SHALL BE PRESERVATIVE TREATED IN ACCORDANCE WITH A10C 1109-07, STANDARD FOR PRESERVATIVE TREATMENT, BASED ON THE SERVICE CONDITION PER THE USE CATEGORIES (UC) SPECIFIED IN AFWA U1-06.
    - UC 1 - INTERIOR CONSTRUCTION, ABOVE GROUND, DRY - NO PRESERVATIVE TREATMENT REQUIRED
    - UC 2 - INTERIOR CONSTRUCTION, ABOVE GROUND, WET - PRESERVATIVE TREATMENT REQUIRED IF THE HUMIDITY OR MOISTURE CONDENSATION IS 20% OR GREATER.
    - UC 3 - EXTERIOR CONSTRUCTION ABOVE GROUND - PRESERVATIVE TREATMENT REQUIRED.
  - FOR ALL TREATED WOOD MEMBERS, ALL CUTS, HOLES AND INJURIES SUCH AS ABRASIONS OR HOLES FROM REMOVAL OF NAILS AND SPIKES WHICH MAY PENETRATE THE TREATED ZONE SHALL BE FIELD TREATED IN ACCORDANCE WITH AFWA M4-06. THE FOLLOWING FIELD TREATMENTS SHALL BE USED:
    - BORED HOLES: HOLES FOR CONNECTORS OR BOLTS MAY BE TREATED BY PUMPING COAL TAR ROOFING CEMENT MEETING ASTM D5643 INTO HOLES USING A GREASE GUN OR SIMILAR DEVICE
    - EXTERIOR: COPPER NAPHTHENEATE
    - INTERIOR: INORGANIC BORON PRESERVATIVES LIMITED TO USE IN APPLICATIONS NOT IN CONTACT WITH GROUND AND CONTINUOUSLY PROTECTED FROM LIQUID WATER

### SAWN LUMBER

1. FRAMING LUMBER SHALL MEET THE FOLLOWING MINIMUM STANDARDS EXCEPT WHERE OTHERWISE NOTED:

SAWN LUMBER PROPERTIES				
USE	SIZE	SPECIES	GRADE	REFERENCE
MIDSILLS	2 X 4	D.F.	STANDARD OR BETTER PRESSURE TREATED	2022 CBC 2303.1.9
	2 X 6 AND LARGER	D.F.	NO. 2 OR BETTER PRESSURE TREATED	
	2 X	REDWOOD	FOUNDATION GRADE	
HORIZONTAL FRAMING LUMBER				
ROOF JOISTS AND RAFTERS	2 x	D.F.	NO. 2	WCLIB & WWPA
FLOOR JOISTS	2 X	D.F.	NO. 2	
HEADERS AND BEAMS	4 X	D.F.	NO. 2	
ANY OTHER HORIZONTAL	4 X 4 AND SMALLER 6 X 6 AND LARGER	D.F.	NO. 2 NO. 1	
VERTICAL FRAMING LUMBER				
TOP PLATES	2 X	D.F.	NO. 2	WCLIB & WWPA
STUDS	2 X 4 & 3 X 4	D.F.	STUD	
	2 X 6 & 2 X 8	D.F.	NO. 2	
POSTS	4 X 4 & 4 X 6 POSTS 6 X 6 & LARGER POSTS	D.F.	NO. 2 NO. 1	
ALL OTHER FRAMING LUMBER				
ALL OTHER FRAMING LUMBER (UNO)	ALL SIZES	D.F.	STANDARD & BETTER	WCLIB & WWPA

- FLOOR JOISTS SHALL BE GRADE STAMPED "S-DRY" WHICH INDICATES A MOISTURE CONTENT NOT EXCEEDING 19 PERCENT.
- ALL SOLE PLATES AND TOP PLATES SHALL BE GRADE STAMPED "KD" WHICH INDICATES KILN DRIED WITH A MOISTURE CONTENT NOT EXCEEDING 15 PERCENT.
- STUD WALLS SHOWN ON PLANS ARE NON-BEARING PARTITIONS WALLS. BEARING WALLS OR SHEAR WALLS BELOW THE FRAMING LEVEL, UNLESS NOTED OTHERWISE. STUDS SHALL BE SIZE AND SPACING AS NOTED IN THE DRAWINGS. SEE PLANS AND ARCHITECTURAL DRAWINGS. UNLESS OTHERWISE NOTED.
- MINIMUM FRAMING NAILING SHALL CONFORM TO CBC TABLE 2304.10.2. ALL NAILS SHALL BE COMMON WIRE NAILS. PREDRILL NAIL HOLES TO 70% OF NAIL SHANK DIAMETER WHERE NAILING TENDS TO SPLIT WOOD.
- UNLESS OTHERWISE NOTED, ALL WOOD SILL PLATES UNDER BEARING, EXTERIOR, OR SHEAR WALLS IN CONTACT WITH CONCRETE OR MASONRY SHALL BE BOLTED TO THE CONCRETE OR MASONRY WITH 5/8" Ø X 12" BOLTS W/ 0.229" X 3" X 3" PLATE WASHER (GALV) AT 4'-0" O.C. BEGINNING AT 9" O.C. MAXIMUM FROM EACH END OF THE PLATES. THE BOLTS SHALL EXTEND A MINIMUM OF 7" INTO THE CONCRETE OR MASONRY. POWDER DRIVEN PINS AT 1/3 OF THE BOLT SPACING OR 24" O.C. MAXIMUM MAY BE SUBSTITUTED FOR THE ANCHOR BOLTS AT INTERIOR NON-SHEAR WALLS ONLY.
- ALL LUMBER IN CONTACT WITH CONCRETE SHALL BE PRESSURE TREATED LUMBER WITH AFWA TREATMENT C2 USING EITHER ALKALINE QUAT (AQO TYPE B AND D), COPPER AZOLE (CBA-A, CA-B), OR SODIUM BORATES (SBK). ANCHOR BOLTS, FASTENERS, AND METAL FRAMING CONNECTORS IN CONTACT WITH PRESSURE TREATED LUMBER SHALL BE HOT-DIPPED GALVANIZED TO A RATING OF F-185 PER ASTM A653.
- PROVIDE 2 STUDS UNDER ALL 4 X 10 AND LARGER BEAMS OR HEADERS AT SPANS 6 FEET OR LONGER, UNLESS OTHERWISE NOTED. WHERE POSTS OR MULTIPLE STUDS UNDER BEAMS OR HEADERS ARE CALLED FOR ON DRAWINGS THOSE POSTS OR MULTIPLE STUDS SHALL BE CARRIED TO THE FOUNDATION/PODIUM LEVEL.
- PROVIDE THE FOLLOW

**REQUIRED VERIFICATION AND INSPECTIONS**

WOOD CODE CHAPTER 17 AND REFERENCED 2018 NDS AND AWC SDPWS-2015			
SPECIAL INSPECTION OR TEST	CONTINUOUS	PERIODIC	CBC REFERENCE
1. HIGH LOAD DIAPHRAGM WOOD STRUCTURAL PANELS - VERIFY THE FOLLOWING: - GRADE - THICKNESS - NOMINAL SIZE OF FRAMING MEMBERS AT ADJOINING PANEL EDGES - NAIL OR STAPLE DIAMETER AND LENGTH - NUMBER OF FASTENER LINES - SPACING BETWEEN FASTENERS IN EACH LINE - SPACING BETWEEN FASTENERS AT EDGE MARGINS	---	X	1705.5.1 2304.2
2. FIELD GLUING OPERATIONS OF ELEMENTS OF THE SEISMIC FORCE RESISTING SYSTEM.	X	---	1705.13.2
3. WOOD LATERAL FORCE-RESISTING SYSTEM WITH FASTENER SPACING OF THE SHEATHING LESS THAN OR EQUAL TO 4" O.C. - WOOD SHEAR WALLS - WOOD DIAPHRAGMS - DRAG STRUTS - SHEAR PANELS - HOLD-DOWNS	---	X	1705.13.2
4. WOOD LATERAL FORCE-RESISTING SYSTEM WITH FASTENER SPACING OF THE SHEATHING GREATER THAN 4" O.C. (NOT REQUIRED) - WOOD SHEAR WALLS - WOOD DIAPHRAGMS - DRAG STRUTS - SHEAR PANELS - HOLD-DOWNS	---	---	1705.13.2
5. METAL PLATE CONNECTED WOOD TRUSSES SPANNING 40 FEET OR GREATER - TEMPORARY INSTALLATION RESTRAINT/BRACING - PERMANENT INDIVIDUAL TRUSS MEMBER RESTRAINT/BRACING IN ACCORDANCE WITH APPROVED TRUSS SUBMITTAL PACKAGE	---	X	1705.5.2

SOILS CODE TABLE 1705.6			
SPECIAL INSPECTION OR TEST	CONTINUOUS	PERIODIC	
1. VERIFY MATERIALS BELOW SHALLOW FOUNDATIONS ARE ADEQUATE TO ACHIEVE THE DESIGN BEARING CAPACITY	---	X	
2. VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIAL.	---	X	
3. PERFORM CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIALS	---	X	
4. VERIFY USE OF PROPER MATERIALS, DENSITIES, AND LIFT THICKNESSES DURING PLACEMENT AND COMPACTION OF COMPACTED FILL.	X	---	
5. PRIOR TO PLACEMENT OF COMPACTED FILL, INSPECT SUBGRADE AND VERIFY THAT SITE HAS BEEN PREPARED PROPERLY.	---	X	

CONCRETE CONSTRUCTION CODE TABLE 1705.3				
SPECIAL INSPECTION OR TEST	CONTINUOUS	PERIODIC	REFERENCED STANDARD	CBC REFERENCE
3. INSPECT ANCHORS CAST IN CONCRETE	---	X	ACI 318: 26.7	---
4. INSPECT ANCHORS POST-INSTALLED IN HARDENED CONCRETE MEMBERS <sup>(a)</sup> (a) ADHESIVE ANCHORS INSTALLED IN HORIZONTALLY OR UPWARDLY INCLINED ORIENTATIONS TO RESIST SUSTAINED TENSION LOADS (b) MECHANICAL ANCHORS AND ADHESIVE ANCHORS NOT DEFINED IN 4.c.	X	X	ACI 318: 26.7.1 ACI 318: 26.7.1	---

**STATEMENT OF SPECIAL INSPECTIONS**

- THIS STATEMENT OF SPECIAL INSPECTIONS HAS BEEN PREPARED PURSUANT TO SECTION 1704.3 OF THE CODE. THIS SECTION DETAILS BOTH REQUIRED SPECIAL INSPECTIONS AND TESTS INCLUDING TESTING PER SECTION 1705 OF THE CODE. THE FOLLOWING SHALL BE OBSERVED DURING THEIR IMPLEMENTATION:
  - GENERAL:
    - STRUCTURAL VERIFICATIONS, INSPECTIONS AND TESTS SHALL BE PERFORMED IN ACCORDANCE WITH CHAPTER 17 OF THE CODE AND/OR THE APPLICABLE REFERENCE STANDARD.
  - OWNER REQUIREMENTS:
    - THE OWNER OR OWNER'S AGENT SHALL EMPLOY ONE OR MORE APPROVED AGENCIES TO PERFORM INSPECTIONS DURING CONSTRUCTION ON THE TYPES OF WORK LISTED IN SECTION 1705 OF THE CODE AND IN THIS STATEMENT OF INSPECTIONS.
  - SPECIAL INSPECTOR QUALIFICATIONS:
    - THE SPECIAL INSPECTIONS SHALL PROVIDE WRITTEN DOCUMENTATION TO THE BUILDING OFFICIAL DEMONSTRATING HIS OR HER COMPETENCE AND RELEVANT EXPERIENCE OR TRAINING. THE EXPERIENCE OR TRAINING SHALL BE CONSIDERED RELEVANT WHEN THE DOCUMENTED EXPERIENCE OR TRAINING IS RELATED IN COMPLEXITY TO THE SAME TYPE OF SPECIAL INSPECTION ACTIVITIES FOR PROJECTS OF SIMILAR COMPLEXITY AND MATERIAL QUANTITIES.
  - CONTRACTOR REQUIREMENTS:
    - SPECIAL INSPECTIONS IN ADDITION TO THE CONTRACTOR'S QUALITY CONTROL INSPECTIONS AND TESTING. THE CONTRACTOR'S QUALITY CONTROL INSPECTIONS AND TESTING SHALL OCCUR PRIOR TO SPECIAL INSPECTION AND REPORTS SHALL BE AVAILABLE TO THE SPECIAL INSPECTOR.
    - THE CONTRACTOR SHALL ENSURE THAT THE WORK FOR WHICH SPECIAL INSPECTION IS REQUIRED REMAINS ACCESSIBLE AND EXPOSED FOR SPECIAL INSPECTION PURPOSES UNTIL COMPLETION OF THE REQUIRED SPECIAL INSPECTION.
    - ANY CONTRACTOR RESPONSIBLE FOR THE CONSTRUCTION OF THE MAIN WIND OR SEISMIC FORCE RESISTING SYSTEM SHALL SUBMIT A WRITTEN STATEMENT OF RESPONSIBILITY TO THE BUILDING OFFICIAL AND OWNER PRIOR TO COMMENCEMENT OF WORK ON THE SYSTEM OR COMPONENT. THE STATEMENT OF RESPONSIBILITY SHALL CONTAIN ACKNOWLEDGEMENT OF AWARENESS OF THE SPECIAL INSPECTION REQUIREMENTS CONTAINED IN THE STATEMENT OF SPECIAL INSPECTIONS.
  - SPECIAL INSPECTOR REPORT REQUIREMENTS:
    - THE SPECIAL INSPECTOR SHALL KEEP RECORD OF INSPECTIONS
    - THE SPECIAL INSPECTOR SHALL FURNISH INSPECTION REPORTS TO THE BUILDING OFFICIAL AND TO THE ARCHITECT AND STRUCTURAL ENGINEER OF RECORD.
    - REPORTS SHALL INDICATE THAT WORK INSPECTED WAS OR WAS NOT COMPLETED IN CONFORMANCE TO APPROVED CONSTRUCTION DOCUMENTS.
    - DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION.
    - IF NOT CORRECTED DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE BUILDING OFFICIAL AND THE ARCHITECT AND STRUCTURAL ENGINEER OF RECORD PRIOR TO THE COMPLETION OF THAT PHASE OF WORK.
    - A FINAL CONTRACTOR DOCUMENTING SPECIAL INSPECTIONS AND CORRECTION OF ANY DISCREPANCIES NOTED SHALL BE SUBMITTED TO THE BUILDING OFFICIAL.
- WOOD BUILDINGS
  - WOOD STRUCTURAL PANELS (SHEATHING) SHALL BE IDENTIFIED BY THE APA TRADEMARK.

**SHOP FABRICATION**

- SHOP FABRICATION REQUIRES SPECIAL INSPECTION IN ACCORDANCE WITH CODE SECTION 1704.2.5. EXCEPTION: SHOP SPECIAL INSPECTIONS ARE NOT REQUIRED WHEN WORK IS DONE ON THE PREMISES OF FABRICATOR REGISTERED AND APPROVED TO PERFORM SUCH WORK IN ACCORDANCE WITH CODE SECTION 1704.2.5.1. THE FOLLOWING ACCREDITATIONS MEET THE REQUIREMENTS OF THIS EXCEPTION:
  - STEEL BUILDINGS (OR STEEL ELEMENTS IN OTHER BUILDINGS)
    - FOR GENERAL STEEL BUILDINGS OR ELEMENTS THE FABRICATOR SHALL BE AN AISC CERTIFIED FABRICATOR IN ACCORDANCE WITH THE AISC CERTIFICATION PROGRAM FOR STRUCTURAL STEEL FABRICATORS (AISC 201-04).
    - OTHER ACCREDITATION DEEMED ACCEPTABLE BY THE AUTHORITY HAVING JURISDICTION.
  - IF FABRICATION IS PERFORMED BY AN APPROVED FABRICATOR A CERTIFICATE OF COMPLIANCE MUST BE PROVIDED TO THE BUILDING INSPECTOR THAT THE MATERIALS SUPPLIED AND WORK PERFORMED BY THE FABRICATOR ARE IN CONFORMANCE WITH THE CONSTRUCTION DOCUMENTS.
  - IF FABRICATION IS NOT PERFORMED BY AN APPROVED FABRICATOR WELDING INSPECTION REPORTS MUST BE SUBMITTED TO THE BUILDING OFFICIAL BY AN APPROVED TESTING AGENCY.
    - NONDESTRUCTIVE TESTING (NDT) MAY BE PERFORMED BY THE FABRICATOR, HOWEVER THE QA AGENCY SHALL REVIEW THE FABRICATOR'S NDT REPORTS.
- WOOD BUILDINGS
  - WOOD STRUCTURAL PANELS (SHEATHING) SHALL BE IDENTIFIED BY THE APA TRADEMARK.

**PRE-FABRICATED WOOD TRUSS NOTES**

- THE DESIGN OF METAL PLATE CONNECTED WOOD TRUSSES SHALL BE IN ACCORDANCE WITH THE FOLLOWING:
  - CODES AND STANDARDS:
    - THE GOVERNING CODE LISTED IN THE PROJECT GENERAL NOTES
    - MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES (ASCE 7-16)
    - NATIONAL DESIGN STANDARD FOR WOOD CONSTRUCTION AND SUPPLEMENT (ANSI/AWC NDS 2018)
    - SPECIAL DESIGN PROVISIONS FOR WIND & SEISMIC (AWC SDPWS-2015)
    - THE NATIONAL DESIGN STANDARD FOR METAL PLATE CONNECTED WOOD TRUSS CONSTRUCTION (ANSI/TPI 1-2014)
  - DESIGN CRITERIA:
    - TRUSSES SHALL BE DESIGNED FOR THE FOLLOWING MINIMUM VERTICAL LOADS AND OTHER LOADS INDICATED ON THE CONSTRUCTION DOCUMENTS (ATTIC MECHANICAL UNITS, ETC.)  

ROOF TRUSS LOADING:	
ASPHALT SHINGLE W/ GYP CEILING:	
TOP-CHORD DEAD LOAD:	13.0 PSF * (11.9 PSF SUPERIMPOSED)
BOT CHORD DEAD LOAD:	8.3 PSF (6.7 PSF SUPERIMPOSED)
ROOF - LIVE LOAD:	20 PSF
ASPHALT SHINGLE W/ STUCCO CEILING:	
TOP-CHORD DEAD LOAD:	13.0 PSF * (11.9 PSF SUPERIMPOSED)
BOT CHORD DEAD LOAD:	12.7 PSF (11.1 PSF SUPERIMPOSED)
ROOF - LIVE LOAD:	20 PSF
  - DEFLECTION CRITERIA:
 

DEAD + LIVE LOAD	L/240
LIVE LOAD ONLY	L/360

\*INCLUDES 4 PSF ALLOWANCE FOR PV PANELS
  - ( ) INDICATES HORIZONTAL SEISMIC/WIND LOAD ON COLLECTOR TRUSSES. THE TRUSS DESIGNER SHALL DESIGN FOR THE TRUSSES FOR THE INDICATED HORIZONTAL LOAD ACTING IN BOTH THE TOP AND BOTTOM TRUSS CHORDS AND FOR THE TRANSFER OF THE FORCE TO THE CHORDS THROUGH THE WEB.
- CONTRACTOR REQUIREMENTS:
  - THE CONTRACTOR SHALL MEET ALL THE REQUIREMENTS LISTED IN SECTION 2.3.4 OF ANSI/TPI 1-2014 INCLUDING THE FOLLOWING:
    - MEANS AND METHODS: THE CONTRACTOR IS RESPONSIBLE FOR ALL MEANS AND METHODS, TECHNIQUES, SEQUENCES, PROCEDURES, PROGRAMS AND SAFETY IN CONNECTION WITH THE RECEIPT, STORAGE, HANDLING, INSTALLATION, RESTRAINING, AND BRACING OF THE TRUSSES. REFER TO THE GUIDE TO GOOD PRACTICE FOR HANDLING, INSTALLING, RESTRAINING & BRACING OF METAL PLATE CONNECTED WOOD TRUSSES (BCSI-81)
    - TRUSS INSTALLATION SHALL COMPLY WITH INSTALLATION TOLERANCES SHOWN IN BCSI-81
    - TEMPORARY INSTALLATION RESTRAINT/BRACING FOR THE TRUSS SYSTEM AND THE PERMANENT TRUSS SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH BCSI-82.
    - CONSTRUCTION LOADING ON TRUSSES SHALL BE DONE IN ACCORDANCE WITH BCSI-84.
    - TRUSS DAMAGE, JOBSITE MODIFICATIONS & INSTALLATION ERRORS SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE EOR AND THE TRUSS DESIGNER. REFERENCE BCSI-85.
    - SUBMIT THE DRAWINGS FROM THE TRUSS DESIGNER/MANUFACTURER TO THE BUILDING DEPARTMENT PRIOR TO FABRICATION FOR APPROVAL. A COPY OF THIS SUBMITTAL SHALL BE PROVIDED TO THE ENGINEER OF RECORD FOR REVIEW OF GENERAL CONFORMANCE TO THE DESIGN INTENT. THE CONTRACTOR SHALL INCORPORATE THE TIME REQUIRED FOR THE SUBMITTAL TO BE REVIEWED, STAMPED AND APPROVED BY ALL PARTIES AND SHALL HAVE THE APPROVED TRUSS PLANS ON THE JOB SITE PRIOR TO FOUNDATION INSPECTION.
  - TRUSS DESIGNER REQUIREMENTS:
    - THE TRUSS DESIGNER SHALL MEET ALL THE REQUIREMENTS LISTED IN SECTION 2.3.5 OF ANSI/TPI 1-2014 INCLUDING THE FOLLOWING:
      - TRUSS DESIGNER SHALL SUPERVISE THE PREPARATION OF THE TRUSS DESIGN DRAWINGS WHICH SHALL CONTAIN THE INFORMATION LISTED IN SECTION 2.3.5.5 OF ANSI/TPI 1-2014. THIS INCLUDES ALL TRUSS TO TRUSS CONNECTIONS, AND DETAILS FOR THE "CALIFORNIA FILL" AREAS.
      - TRUSS DESIGNER SHALL COMPLY WITH THE REFERENCED CODE AND DESIGN CRITERIA ABOVE.
      - TRUSS DESIGNER SHALL SHOW ALL HANGERS, BRACING AND RESTRAINTS AS WELL AS METHOD OF RESTRAINT/BRACING ON THE TRUSS PLANS TO MEET ANY SEISMIC AND WIND REQUIREMENTS OF THE CODE.
      - SUBMIT TRUSS DESIGN DRAWINGS INCLUDING ALL RELEVANT DETAILS FOR THE FABRICATION OF THE TRUSSES AND PREPARE CALCULATIONS. ALL PLANS, DETAILS AND CALCULATIONS FOR THE TRUSSES SHALL BE STAMPED AND SIGNED BY A LICENSED PROFESSIONAL ENGINEER (CIVIL OR STRUCTURAL), LICENSED TO PRACTICE IN THE STATE OF CALIFORNIA.

**WOOD STRUCTURAL PANELS (SHEATHING)**

- WOOD STRUCTURAL PANELS SHALL MEET THE FOLLOWING MINIMUM STANDARDS EXCEPT WHERE OTHERWISE NOTED:
 

WOOD STRUCTURAL PANEL PROPERTIES							
USE	PLY	BOND CLASSIFICATION <sup>c</sup>	SHEATHING GRADE	PERFORMANCE RATING	SPAN RATING	RATING <sup>3</sup>	REFERENCE <sup>4</sup>
ROOF	5	EXPOSURE 1	REFER TO TYPICAL DIAPHRAGM SCHEDULE			APA	2022 CBC 2303.1.5 (DOC PS 1-09 OR PS 2-10)
FLOOR	5	EXPOSURE 1				APA	
WALL <sup>2</sup>	5	EXPOSURE 1	REFER TO TYPICAL SHEAR WALL SCHEDULE			APA	

TABLE NOTES:

  - WOOD STRUCTURAL PANELS SHALL CONFORM TO THE REQUIREMENTS FOR THEIR TYPE IN ACCORDANCE WITH THE FOLLOWING VOLUNTARY STANDARDS BY THE ENGINEERED WOOD ASSOCIATION (AWC):
    - VOLUNTARY PRODUCT STANDARD, STRUCTURAL PLYWOOD, PS 1-09
    - VOLUNTARY PRODUCT STANDARD, PERFORMANCE STANDARD FOR WOOD-BASED STRUCTURAL-USE PANELS, PS 2-10
  - WOOD STRUCTURAL PANELS SHALL BE IDENTIFIED BY THE APA TRADEMARK INDICATING CONFORMANCE TO THE APPLICABLE VOLUNTARY STANDARD
  - WHERE PANELS ARE EXPOSED TO REPEATED WETTING AND REDRYING, LONG-TERM EXPOSURE TO WEATHER, OR CONDITIONS OF SIMILAR SEVERITY, "EXTERIOR" APA RATED PLYWOOD SHEATHING SHALL BE USED. C-D "EXPOSURE 1" APA RATED PLYWOOD SHEATHING (CDX) SHALL NOT BE USED FOR CONDITIONS INVOLVING LONG-TERM EXPOSURE TO WEATHER.
    - EXCEPTION: WOOD STRUCTURAL PANEL ROOF SHEATHING EXPOSED TO THE OUTDOORS ON THE UNDERSIDE IS PERMITTED TO BE "EXPOSURE 1" TYPING.
    - WOOD STRUCTURAL PANELS TO BE USED AS SIDING SHALL COMPLY WITH ANS/APA PRP-210.
  - ORIENTED STRAND BOARD (OSB) WITH EQUIVALENT CLASSIFICATION AND RATINGS MAY BE USED IN LIEU OF PLYWOOD FOR WOOD STRUCTURAL PANEL WALL SHEATHING.
  - TRANSPORTATION, STORAGE, AND HANDLING:
    - TRANSPORTATION
      - IN TRANSPORTING PANELS ON OPEN TRUCK BEDS, COVER THE BUNDLES WITH A TARP.
    - STORAGE
      - ALWAYS STORE THE PANELS UNDER COVER WHENEVER POSSIBLE
      - WHEN STORING PANELS OUTSIDE STACK THEM ON A LEVEL SURFACE ON TOP OF STRINGERS OR OTHER BLOCKING, THREE STRINGERS MINIMUM.
      - NEVER LEAVE PANELS IN CONTACT WITH THE GROUND
      - COVER THE STACK WITH A PLASTIC TARP, ENSURING THAT THE BUNDLE IS WELL VENTILATED TO PREVENT MILDEW.
      - IF MOISTURE ABSORPTION IS EXPECTED, CUT THE STEEL BAND TO PREVENT DAMAGE
      - KEEP SANDED OR OTHER APPEARANCE GRADE PANELS AWAY FROM HIGH TRAFFIC AREAS
    - HANDLING
      - ALWAYS PROTECT ENDS AND EDGES, ESPECIALLY TONGUE AND GROOVE PRODUCTS, FROM PHYSICAL DAMAGE.
      - ACCLIMATE THE PANELS FOR 24 HOURS MINIMUM BEFORE INSTALLATION BY STANDING THE PANELS ON EDGE WITH A GAP BETWEEN EACH TO ALLOW FOR AIR CIRCULATION OR PER MANUFACTURER'S RECOMMENDATIONS.
  - PLYWOOD ORIENTATION
    - ROOF AND FLOOR SHEATHING SHALL BE LAID WITH THE GRAIN OF THE OUTER PILES PERPENDICULAR TO THE FRAMING MEMBERS. SHALL BE CONTINUOUS OVER 2 JOIST BAYS MINIMUM AND END JOINTS SHALL BE JOINED OVER FRAMING AND STAGGERED. LEAVE A 1/8" GAP BETWEEN PANELS TO ALLOW FOR PANEL EXPANSION UNLESS RECOMMENDED OTHERWISE BY THE PANEL MANUF. REFER TO SPECIFIC DETAILS IN THE DRAWINGS FOR FURTHER PARAMETERS.
    - PLYWOOD OR OSB WALL SHEATHING MAY BE APPLIED VERTICALLY OR HORIZONTALLY. ALL END JOINTS BE JOINED OVER FRAMING AND STAGGERED.
  - BLOCKING:
    - ROOF: ALL ROOF SHEATHING SHALL BE BLOCKED UNLESS SPECIFICALLY ALLOWED ON PLANS, WHERE PERMITTED TO BE UNBLOCKED. ALL UNBLOCKED EDGES SHALL BE TONGUE AND GROOVE.
    - FLOOR SHEATHING SHALL BE BLOCKED UNLESS SPECIFICALLY ALLOWED ON PLANS, WHERE PERMITTED TO BE UNBLOCKED. ALL UNBLOCKED EDGES SHALL BE TONGUE AND GROOVE.
    - WALLS: ALL SHEAR WALLS SHALL BE FULLY BLOCKED AT PLYWOOD EDGES.
  - FASTENERS
    - USE SHEATHING NAILS SAME GAUGE AS COMMON WIRE NAILS WITH LENGTHS AT LEAST EQUAL TO SHEATHING THICKNESS PLUS REQUIRED PENETRATION PER AWS SDPWS TABLE 4.2A OR 4.3A (AS REQUIRED).
    - EQUIVALENT PNEUMATIC DRIVE NAILS OR STAPLES MAY BE USED IF FASTENER MANUFACTURER HAS RECEIVED ICC OR IAPMO APPROVAL FOR THE INTENDED USE. FASTENERS TO BE SUBSTITUTED SHALL BE EQUIVALENT IN LATERAL AND WITHDRAWAL STRENGTH TO THE SIZE OF COMMON NAIL SPECIFIED.
    - USE OF MACHINE NAILING IS SUBJECT TO A SATISFACTORY JOB SITE DEMONSTRATION FOR EACH PROJECT AND THE APPROVAL BY THE PROJECT ARCHITECT OR STRUCTURAL ENGINEER. THE APPROVAL IS SUBJECT TO CONTINUED SATISFACTORY PERFORMANCE. MACHINE NAILING WILL NOT BE APPROVED IN 5/16" PLYWOOD OR OSB SHEATHING. IF NAIL HEADS PENETRATE THE OUTER PLY MORE THAN WOULD BE NORMAL FOR A HAND HAMMER OR IF MINIMUM ALLOWABLE EDGE DISTANCES ARE NOT MAINTAINED, THE PERFORMANCE WILL BE DEEMED UNSATISFACTORY.
    - TYPICAL NAILING SHALL BE 10D AT 6" O.C. AT ALL SUPPORTED EDGES AND OVER SHEAR WALLS, AND 10D AT 12" O.C. AT ALL INTERMEDIATE SUPPORTS, UNLESS OTHERWISE NOTED. SEE PLANS AND REFER TO SHEAR WALL SCHEDULE.



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

**COUNTY OF SAN LUIS OBISPO**  
**ACCESSORY DWELLING UNIT**  
 SAN LUIS OBISPO, CA  
**GENERAL NOTES, SPECIAL**  
**INSPECTION & TESTS**



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

**FRAMING PLAN NOTES**

- GENERAL**
- SEE THE FOLLOWING SHEETS FOR GENERAL NOTES AND TYPICAL DETAILS.
  - SEE ARCHITECTURAL DRAWINGS FOR FINISHED FLOOR ELEVATIONS. REFERENCE FINISHED FLOOR ELEVATION = 0'-0" CORRESPONDS TO FINISHED FLOOR ELEVATION.
  - SEE ARCHITECTURAL DRAWINGS FOR ALL EXTERIOR CONCRETE PAVING, SLABS, BASES, CURBS, ETC.
  - FOR ANY DIMENSIONAL INFORMATION NOT SHOWN, SEE ARCHITECTURAL DRAWINGS.
  - ALL DIMENSIONS SHOWN ARE FROM FACE OF MASONRY, FACE OF SHEATHING, OR CENTERLINE OF COLUMN, UNLESS NOTED OTHERWISE. ALL COLUMNS ARE CENTERED IN STUD WALLS.
  - SEE ARCHITECTURAL DRAWINGS FOR SIZE AND LOCATION OF ALL DOOR AND WINDOW OPENINGS IN BEARING AND NON-BEARING WALLS.
  - SEE ARCHITECTURAL DRAWINGS FOR LOCATION OF INTERIOR NON-BEARING PARTITIONS.
  - ALL POSTS IN 6" WALLS SHALL BE 6x6 UNLESS NOTED OTHERWISE. ALL POSTS IN 4" WALLS SHALL BE 4x4 UNLESS NOTED OTHERWISE.
  - ALL POSTS IN 6" WALLS SHALL BE 6x6, UNLESS NOTED OTHERWISE.
- TYPICAL WALL FRAMING SHALL BE:  
 2x6 @ 16" OC @ ALL EXTERIOR WALLS, UNO  
 2x4 @ 16" OC @ ALL INTERIOR BEARING WALLS, UNO  
 2x4 @ 16" @ ALL INTERIOR NON-BEARING WALLS, UNO

- FOUNDATION**
- SEE PLANS AND ARCHITECTURAL DRAWINGS FOR DEPRESSIONS AND/OR SLOPES IN CONCRETE SLABS.
  - SEE ARCHITECTURAL, PLUMBING, MECHANICAL, AND ELECTRICAL DRAWINGS FOR ADDITIONAL EMBEDDED ITEMS AND SLAB PENETRATIONS.
  - FOR TYPICAL SLAB-ON-GRADE REQUIREMENTS, INCLUDING SLAB JOINTS, SEE DETAIL 31/S-301.
  - ALL POSTS IN 6" WALLS SHALL BE 6x6 UNLESS NOTED OTHERWISE. ALL POSTS IN 4" WALLS SHALL BE 4x4 UNLESS NOTED OTHERWISE.
  - PLATE WASHERS ARE REQUIRED FOR ALL SILL PLATE ANCHOR BOLTS.
  - ALL HOLD-DOWN ANCHOR NUTS SHALL BE TIGHTENED JUST PRIOR TO COVERING.
  - ALL BOLT HOLES IN WOOD MEMBERS, SHALL BE DRILLED A MAXIMUM OF 1/16" OVERSIZED. INSPECTOR TO VERIFY.
  - THE BUILDING PAD SHALL BE PREPARED AS OUTLINED IN DETAIL 53/S-301. THE BUILDING OFFICIAL SHALL REQUIRE PAD CERTIFICATION BY A GEOTECHNICAL ENGINEER AT THEIR DISCRETION.
  - BOTTOM OF FOOTINGS SHALL BE, UNLESS DEEPER FOUNDATIONS ARE REQUIRED BY THE BUILDING OFFICIAL:
    - 21" BELOW PAD OR ADJACENT GRADE AT PERIMETER, WHICHEVER IS DEEPER, UNO
    - 21" BELOW PAD OR ADJACENT GRADE AT INTERIOR GRADE BEAMS, WHICHEVER IS DEEPER, UNO
 NOTE: FOOTING MUST BE DEEPENED LOCALLY PER DETAIL 32/S-301 TO ACCOMMODATE ANCHOR BOLT HOLD-DOWN EMBED DEPTHS.
  - ALL THIS PLAN IS INTENDED FOR FLAT LOTS, WITHOUT HIGHLY EXPANSIVE OR LIQUEFIABLE SOILS. IF THE PROJECT SITE IS DETERMINED TO HAVE ANY OF THESE QUALITIES, AS DETERMINED BY THE BUILDING OFFICIAL, THESE PRE-APPROVED ADU FOUNDATION PLANS AND DETAILS ARE NOT APPLICABLE.
- FRAMING**
- ALL LINES OR MEMBERS INDICATED AS 'STRUT' SHALL RECEIVE (2) ROWS OF BOUNDARY NAILING (BN), STAGGERED.
  - ALL INTERIOR WALLS NOT SHOWN ON THE STRUCTURAL FRAMING PLANS BUT SHOWN ON THE ARCHITECTURAL DRAWINGS SHALL BE CONSTRUCTED PER NON-BEARING PARTITION WALL DETAIL 43/S-401, UNO.
  - PLYWOOD SHEATHED DIAPHRAGM TYPES:  
ALL ROOF DIAPHRAGMS SHALL BE TYPE B, UNO  
REFER TO 12/S-403

**SYMBOL LEGEND**

- XX'-X" / x INDICATES SHEAR WALL TYPE AND LENGTH. SEE SCHEDULE ON 13/S-402
- INDICATES BLOCKING & STRAPPING ABOVE & BELOW WINDOW OPENINGS PER DETAIL 44/S-402
- INDICATES HEADER @ OPENING. REFER TO 32/S-401 FOR HEADER SIZE, UNO ON PLANS
- INDICATES TOP PLATE SPICE NAILING PER 33/S-403. NOTE THAT NAILING APPLIES TO ENTIRE LENGTH OF TOP PLATE. PROVIDE TYPE C SPICE, UNO
- INDICATES STRAP PER 31/S-411, UNO
- INDICATES CONT BLK & STRAP PER 32/S-411 @ ROOF, UNO

**SCHEDULES**

**HOLD-DOWN SCHEDULE**

SPECIFIES HOLD-DOWN/STRAP DETAIL	INDICATES HOLD-DOWN/STRAP TYPE	DETAIL
2x4	INDICATES SIMPSON SSTB HOLD-DOWN TO CONC FOUNDATION:	34/S-411
6x6	INDICATES SIMPSON SSTB HOLD-DOWN TO CONC FOUNDATION:	12/S-311

**ROOF BEAM SCHEDULE**

MARK	SIZE	REMARKS
B1	4x8	
B2	4x10	
B3	6x10	
B4	1 1/2" x 14" LVL (2.0E)	

**CONTINUOUS FOOTING SCHEDULE**

MARK	WIDTH	MIN EMBED BELOW LOWEST PAD GRADE	LONG REINF	TRANS REINF	DETAIL
C1.25	1'-3"	SEE NOTE 18	(2) #5 T&B	#3 @ 12" OC, BOT	31/S-311

**ROOF RAFTER SCHEDULE**

MARK	SIZE	REMARKS
R1	2x8 @ 24" OC	
R2	2x10 @ 18" OC	

**GRADE BEAM SCHEDULE**

TYPE	WIDTH	THICKNESS	MIN EMBED BELOW LOWEST PAD GRADE	LONG REINF	TRANS REINF	DETAIL
GB1	1'-0"	1'-0"	SEE NOTE 18	(2) #4 @ TOP (2) #4 @ BOT	#3 @ 24" OC	13/S-312

**FLOOR JOIST SCHEDULE**

MARK	SIZE	REMARKS
J1	2x10 @ 18" OC	


**PAD FOOTING SCHEDULE**

TYPE	WIDTH	LENGTH	THICKNESS	MIN EMBED BELOW LOWEST PAD GRADE	TOP REINF	BOT REINF	DETAIL
F2	2'-0"	2'-0"	1'-6"	SEE NOTE 18	(3) #5, EW	(3) #5 @, EW	33/S-312


**HEADER SCHEDULE**

MARK	SIZE	REMARKS
H1	6x6	


NOTE: FOOTING MUST BE DEEPENED LOCALLY PER DETAIL 32/S-301 TO ACCOMMODATE AB HOLD-DOWN EMBED DEPTHS




**1 FOUNDATION PLAN - MODERN**  
SCALE: 1/4" = 1'-0"




**2 FLOOR FRAMING PLAN - MODERN**  
SCALE: 1/4" = 1'-0"



**3 ROOF FRAMING PLAN - MODERN**  
SCALE: 1/4" = 1'-0"



**3 FOUNDATION PLAN - MODERN - PORCH OPT.**  
SCALE: 1/4" = 1'-0"



**3 ROOF FRAMING PLAN - MODERN - PORCH OPT.**  
SCALE: 1/4" = 1'-0"

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
MODERN PLANS

DATE  
11/20/2023  
SHEET



S-201

N:\2000\2127-01-cuz2-40-county\ad\structural\ConDoc\Sheet\ModPlan-4\Modern\2127-01-CUZ2-Plan-4.dwg, 5/1/2023, 4:23pm, albjpc






THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
TYPICAL CONCRETE DETAILS



- NOTES:
- IF SAW CUT CONTRACTION OR CONTROL JOINT IS USED, SAW-CUT WITHIN 24 HOURS. EARLY ENTRY SAWS MAY BE USED WITHIN 1-4 HOURS OF POUR, AND CONVENTIONAL SAWS 4-12 HOURS OF POUR DEPENDING ON WEATHER.
  - FILL CONTRACTION JOINT WITH AN ELASTOMERIC JOINT COMPOUND RATED FOR ITS USE. FOR INDUSTRIAL FLOORS SUBJECT TO HARD WHEELED TRAFFIC, USE SEALANTS RATED FOR SUCH APPLICATIONS BY THE MANUFACTURER.
  - DOWELS IN INDUSTRIAL FLOOR APPLICATIONS SHOULD BE SMOOTH ALIGNED, AND SUPPORTED SO THEY WILL REMAIN PARALLEL IN BOTH HORIZONTAL AND VERTICAL PLANES DURING PLACING AND FINISHING.
  - IN STEEL AND/OR CONC. BUILDINGS DO NOT POUR DIAMOND UNTIL STRUCTURAL STEEL AND CONCRETE ABOVE HAS BEEN INSTALLED.




REINFORCING TENSION DEVELOPMENT LENGTH AND LAP SPICE SCHEDULE

BAR SIZE	DEVELOPMENT LENGTH $l_d$ (CLASS B LAP SPICE)		LAP SPICE $l_s$ (CLASS B LAP SPICE)	
	$f_c$ (psi)		$f_c$ (psi)	
	2,500	3,000	2,500	3,000
#3	1'-6"	1'-5"	1'-3"	1'-10"
#4	2'-0"	1'-10"	1'-7"	2'-5"
#5	2'-6"	2'-4"	2'-0"	3'-0"
#6	3'-0"	2'-9"	2'-5"	3-11"
#7	4'-5"	4'-0"	3'-6"	5-2"
#8	5'-0"	4-7"	4-0"	6-6"
#9	5-8"	5-2"	4-6"	6-9"
#10	6-5"	5-10"	5-1"	7-7"
#11	7-1"	6-6"	5-7"	8-5"

- NOTES:
- VALUES ABOVE ARE FOR REINFORCEMENT WITH THE FOLLOWING PARAMETERS:
    - A. GRADE 60 REINFORCEMENT
    - B. NORMAL WEIGHT CONCRETE
      - FOR LIGHTWEIGHT CONCRETE MULTIPLY THE VALUES ABOVE BY 1.3
    - C. NON-EPOXY COATED REINFORCEMENT
    - D. HORIZONTAL BARS WITHOUT 12" OF CONCRETE BELOW (BOTTOM BARS), AND VERTICAL BARS
      - FOR TOP BARS WITH 12" OR MORE OF CONCRETE BELOW THE BAR MULTIPLY THE VALUES ABOVE BY 1.3
    - E. CLEAR SPACING NOT LESS THAN  $d_b$ , CLEAR COVER NOT LESS THAN  $d_b$  AND STIRRUPS THROUGH  $l_d$  NOT LESS THAN MIN OR
      - CLEAR SPACING NO LESS THAN  $2d_b$  AND CLEAR COVER NOT LESS THAN  $d_b$
      - FOR OTHER SPACING AND COVER CONDITIONS MULTIPLY THE VALUES ABOVE BY 1.5
    - F. REINFORCEMENT NOT IN SHEAR WALLS
      - FOR REINFORCEMENT IN SHEAR WALLS MULTIPLY THE VALUES ABOVE BY 1.25
  - THE MULTIPLIERS LISTED IN NOTE 1 ABOVE ARE CUMULATIVE INCREASES IN DEVELOPMENT/LAP SPICE LENGTH.
  - ALL LAP SPICES REFERENCED IN THE PLANS SHALL BE CLASS B UNLESS NOTED OTHERWISE.
  - WHEN REINFORCING BARS OF TWO SIZES ARE LAP SPICED IN TENSION, USE THE LARGER OF THE TENSION CLASS B, LAP SPICE LENGTH  $l_s$  OF THE SMALLER BAR, AND THE CLASS A, TENSION DEVELOPMENT LENGTH  $l_d$  OF THE LARGER BAR.



SLAB ON GRADE JOINTS



- NOTES:
- PREPARATION OF THE SLAB SUBGRADE SHALL BE BASED ON THE GEOTECHNICAL INVESTIGATION REPORT AS REFERENCED IN THE FOUNDATION GENERAL NOTES, THE FOLLOWING INFORMATION IS FOR REFERENCE ONLY.
    - A. OVER-EXCAVATION SHALL EXTEND 5 FEET BEYOND PERIMETER FOUNDATION, TO PROPERTY LINES OR EXISTING IMPROVEMENTS, WHICHEVER IS LEAST.
  - NATIVE MATERIALS
    - a. SHALL BE OVER-EXCAVATED 36" BELOW (E) GRADE OR 18" BELOW BOTTOM OF FOOTINGS, WHICHEVER IS GREATEST.
    - b. THE EXPOSED SURFACE SHALL BE SCARIFIED TO A DEPTH OF 6", MOISTURE CONDITIONED TO 3 PERCENT OVER OPTIMUM MOISTURE CONTENT AND COMPACTED TO A MINIMUM RELATIVE DENSITY OF 90 PERCENT (ASTM D1557)
  - ENGINEERED COMPACTED FILL
    - a. REFER TO THE GEOTECHNICAL INVESTIGATION REPORT FOR RECOMMENDATIONS FOR STRUCTURAL FILL
    - b. STRUCTURAL FILL SHALL BE PLACED IN HORIZONTAL LAYERS, EACH APPROXIMATELY 8" THICK BEFORE COMPACTATION, AND SHOULD BE CONDITIONS WITH WATER TO PRODUCE A SOIL WATER CONTENT NEAR OPTIMUM MOISTURE AND COMPACTED TO A MINIMUM RELATIVE DENSITY OF 90 PERCENT (ASTM D1557)
  - 4" THICK, CLEAN FREE-DRAINING MATERIAL SUCH AS 1/2" COARSE AGGREGATE
  - REFER TO GEOTECH REPORT AND ARCH DRAWINGS FOR VAPOR BARRIER. INSTALL PER MANUFACTURER'S RECOMMENDATIONS FOR SEALING OF PENETRATIONS, JOINTS AND EDGES.
    - a. VAPOR BARRIER IS NOT TO BE PUNCTURED DURING CONSTRUCTION OF SLAB ON GRADE.
    - b. 2" THICK OPTIONAL SAND LAYER, SHALL BE LIGHTLY MOISTENED PRIOR TO PLACING CONCRETE.



SLAB ON GRADE EDGE AND SUBGRADE PREP

DEEPEND FTG @ ANCHOR BOLT




SLEEVE THROUGH FOUNDATION (SLAB TURN-DOWN)


STEP FOOTING




STEPPED FOOTING (BOTTOM ONLY)



STEP IN CONCRETE SLAB ON GRADE




SLAB ON GRADE DEPRESSION





CONC REINF @ INTERSECTION

REIN TIES AND STIRRUPS




SOG OPENING



CONC REINF @ INTERSECTION

REIN DEVELOPMENT LENGTH AND SPICES




STANDARD HOOK DEVELOPMENT LENGTH  $l_{dh}$





BAR SIZE	D	$l_{dh}$	NORMAL WEIGHT		
			2,500	3,000	4,000
#3	2 1/4"	6"	0-9"	0-9"	0-8"
#4	3"	8"	1'-0"	0'-11"	0'-10"
#5	3 3/4"	10"	1'-3"	1'-2"	1'-0"
#6	4 1/2"	12"	1'-6"	1'-5"	1'-3"
#7	5 1/4"	1'-2"	1'-9"	1'-8"	1'-5"
#8	6"	1'-4"	2'-0"	1'-10"	1'-7"
#9	9 1/2"	1'-7 1/2"	2'-3"	2'-1"	1'-10"
#10	10 3/4"	1'-10"	2'-7"	2'-4"	2'-1"
#11	12"	2'-0 1/2"	2'-10"	2'-7"	2'-3"

- NOTE:
- ALL HOOKED BARS SHALL EXTEND AS FAR AS POSSIBLE WITH A MINIMUM 2" END COVER AND WITH EMBEDMENT NOT LESS THAN SHOWN ON THE SCHEDULE UNLESS NOTED OTHERWISE ON PLANS.
  - MINIMUM SIDE COVER = 2d.
  - FOR LIGHTWEIGHT CONCRETE MULTIPLY LENGTHS IN SCHEDULE BY 1.3.

REIN HOOK DEVELOPMENT LENGTH AND BENDS



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



TYPE	HOLDOWN	ANCHOR	DIA (IN)	FASTENERS	BOUNDARY MEMBER MIN THICKNESS (IN)	MIN EMBED 1 <sub>e</sub> (IN)	ALLOWABLE LOADS (R <sub>u</sub> )	
							CORNER	MIDWALL
ⓂA	HDU4-SDS2.5	SSB16		10-SDS 1/2" x 2 1/2"	3	12 3/4	3,780	3,780
ⓂB	HDU5-SDS2.5	SSB20	3/4"	14-SDS 1/2" x 2 1/2"	3	16 3/4	4,785	4,785
ⓂC	HDU5-SDS2.5	SSB24		14-SDS 1/2" x 2 1/2"	3	20 3/4	5,645*	5,645*
ⓂD	HDQ8-SDS3	SSB28	1"	20-SDS 1/2" x 3"	4 1/2	24 3/4	9,230*	9,230*





1. MINIMUM EDGE DISTANCE IS SHOWN ABOVE. ANCHOR LOCATIONS PER PLAN
2. MINIMUM ANCHOR TO ANCHOR SPACING IS 3L<sub>e</sub>
3. \* = CAPACITY LIMITED BY HOLDDOWN
4. DEEPEN FOOTING AT HOLDDOWN ANCHOR AS REQ'D PER DETAIL 32/-

51 CONTINUOUS WALL FOOTING  
2227-01-C1022 - S311

31 PIPES PARALLEL TO FOOTINGS  
2227-01-C1022 - S311

21 PIPES PARALLEL TO FOOTINGS  
2227-01-C1022 - S311

12 SSB ANCHOR & HOLDDOWN @ FOUNDATION  
2227-01-C1022 - S311






52 MINIMUM DISTANCE FROM GRADE TO WOOD FRAMING  
2227-01-C1022 - S311

32 PIPES PERPENDICULAR TO FOOTINGS W/ STEM WALL  
2227-01-C1022 - S311

22 PIPES PERPENDICULAR TO FOOTINGS W/ STEM WALL  
2227-01-C1022 - S311

13 PIPES PERPENDICULAR TO FOOTINGS  
2227-01-C1022 - S311





53 SOG DEPRESSION @ FTG  
2227-01-C1022 - S311

43 EXTERIOR CONTINUOUS WALL FTG W/ CURB  
2227-01-C1022 - S311

33 PIPES PERPENDICULAR TO FOOTINGS  
2227-01-C1022 - S311

23 PIPES PERPENDICULAR TO FOOTINGS  
2227-01-C1022 - S311

13 PIPES PERPENDICULAR TO FOOTINGS  
2227-01-C1022 - S311



54 NON-BEARING WALL ANCHORAGE @ SOG  
2227-01-C1022 - S311

44 NON-BEARING WALL ANCHORAGE @ SOG  
2227-01-C1022 - S311

34 NON-BEARING WALL ANCHORAGE @ SOG  
2227-01-C1022 - S311

24 TYPICAL VERT PIPES OR COND THROUGH FOOTING  
2227-01-C1022 - S311

24 TYPICAL VERT PIPES OR COND THROUGH FOOTING  
2227-01-C1022 - S311

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
CONCRETE DETAILS


DATE  
11/20/2023  
SHEET

S-311

N:\2000\2227-01-c1022-01-01\2227-01-c1022-01-01.dwg, PLAN 4 - S311, Nov 20, 2023, 3:29pm, ocbpce



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



51

41


**SPREAD FOOTING @ BEARING WALL POST**

2727-01-C102-1312


3/4" = 1'-0" 11

52



42



POST SIZE	MIN. SIDE COVER
4x4	0'-3"
6x6	0'-3"
8x8	0'-3"



POST SIZE	MIN. SIDE COVER
4x4	0'-4"
6x6	0'-5"
8x8	0'-6"



53

43

**PORCH PAD FOOTING**

2727-01-C102-1312

33

**MOMENT BASE POST @ POLE FOOTING**


2727-01-C102-1312

23

**GRADE BEAM**

2727-01-C102-1312

13



54

44

24

**DEEPEND EXTERIOR FOOTING**

2727-01-C102-1312

3/4" = 1'-0" 14

**COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT**

SAN LUIS OBISPO, CA

**CONCRETE DETAILS**

DATE  
11/20/2023  
SHEET

**S-312**

N:\2600\2727-01-c102-acc-county\adu\structural\ConDoc\Sheet\Rein\2727-01-C102-1312.dwg, PLAN 4 - 5312, Nov 20, 2023, 3:29pm, edipee






THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

BEARING/SHEAR WALL HEADER SCHEDULE												
4 INCH WALLS				3-STORY			2-STORY			1-STORY		
OPENING WIDTH	4x HEADER	SILL AT WINDOW	POST / TRIMMER	KING STUDS	3-STORY	2-STORY	1-STORY	OPENING WIDTH	6x HEADER	SILL AT WINDOW	POST / TRIMMER	KING STUDS
UP TO 3'-0"	4x4	2x	2x4	2x4				UP TO 3'-0"	6x4	2x	2x6	2x6
3'-0" - 5'-0"	4x6	2x	2x4	2x4				3'-0" - 5'-0"	6x6	2x	2x6	2x6
5'-0" - 7'-0"	4x8	(2) 2x	(2) 2x4	(2) 2x4				5'-0" - 7'-0"	6x8	(2) 2x	2x6	(2) 2x6

BEARING/SHEAR WALL HEADER SCHEDULE												
8 INCH WALLS				3-STORY			2-STORY			1-STORY		
OPENING WIDTH	8x HEADER	SILL AT WINDOW	POST / TRIMMER	KING STUDS	3-STORY	2-STORY	1-STORY	OPENING WIDTH	6x HEADER	SILL AT WINDOW	POST / TRIMMER	KING STUDS
UP TO 3'-0"	6x6 FLAT	2x	2x6	2x6				UP TO 3'-0"	6x6	2x	2x6	2x6
3'-0" - 5'-0"	6x8 FLAT	2x	2x6	2x6				3'-0" - 5'-0"	6x8	2x	2x6	2x6
5'-0" - 7'-0"	6x8 FLAT	(2) 2x	2x6	2x6				5'-0" - 7'-0"	6x12	(2) 2x	2x6	(2) 2x6


NOTES:  
 1. THIS DETAIL APPLIES AT ALL EXT WALLS AND INT LOAD BEARING WALLS AND ALSO APPLIES TO SHEAR WALL FRAMING  
 A. FOR SHEAR WALLS SEE 3415-402 FOR ADD'L REQUIREMENTS.  
 B. FOR INTERIOR NON-BEARING PARTITIONS SEE DETAIL 431.  
 2. HEADERS, KING STUDS AND OTHER REFERENCES ON PLAN GOVERN OVER THIS TYPICAL SCHED/DETAILS  
 3. PROVIDE A34 @ 4" WALLS & A35 @ 6" OR GREATER WALLS (ICC-ESR 2353)



FASTENING SCHEDULE PER 2022 CBC 2304.10.1		
CONNECTION	FASTENING	LOCATION
1. BLOCKING BETWEEN CEILING JOISTS, RAFTERS OR TRUSSES TO TOP PLATE OR OTHER FRAMING BELOW	3-8d COMMON	EACH END, TOENAIL
2. BLOCKING BETWEEN RAFTERS OR TRUSSES NOT AT THE WALL TO TOP PLATE, TO RAFTER OR TRUSS	2-8d COMMON	EACH END, TOENAIL
3. FLAT BLOCKING TO TRUSS AND WEB FILLER	2-16d COMMON	END NAIL
4. CEILING JOIST TO TOP PLATE	1-6d COMMON @ 6" OC	FACE NAIL
5. CEILING JOIST NOT ATTACHED TO PARALLEL RAFTER, LAPS OVER PARTITIONS	3-8d COMMON	EACH JOIST, TOENAIL
6. CEILING JOIST ATTACHED TO PARALLEL RAFTER (HEEL JOINT)	3-16d COMMON	FACE NAIL
7. COLLAR TIE TO RAFTER	3-10d COMMON	FACE NAIL
8. RAFTER OR ROOF TRUSS TO PLATE	3-10d COMMON	TOENAIL <sup>2</sup>
9. ROOF RAFTER TO RIDGE VALLEY OR HIP RAFTER; OR ROOF RAFTER TO 2-INCH RIDGE BEAM	2-16d COMMON	END NAIL
10. STUD TO STUD AND ABUTTING STUDS AT INTERSECTING WALL CORNERS	3-10d COMMON	TOENAIL
11. BUILT-UP HEADER (2" TO 2" HEADER)	1-6d COMMON	1/4" OC EACH EDGE, FACE NAIL
12. CONTINUOUS HEADER TO STUD	4-10d COMMON	TOENAIL
13. TOP PLATE TO TOP PLATE	1-6d COMMON	1/4" OC FACE NAIL
14. TOP PLATE TO TOP PLATE, AT END JOINTS	8-16d COMMON	EACH SIDE OF END JOINT, FACE NAIL (MINIMUM 24" LAP SPURCE LENGTH EACH SIDE OF END JOINT)
15. BOTTOM PLATE TO JOIST, RIM JOIST, BAND JOIST OR BLOCKING	2-16d COMMON	1/4" OC FACE NAIL
16. STUD TO TOP OR BOTTOM PLATE	4-8d COMMON	TOENAIL
17. TOP PLATES, LAPS AT CORNERS AND INTERSECTIONS	2-16d COMMON	FACE NAIL
18. JOIST TO SILL, TOP PLATE, OR GIRDER	3-8d COMMON	TOENAIL
20. RIM JOIST, BAND JOIST, OR BLOCKING TO TOP PLATE, SILL OR OTHER FRAMING BELOW	8d COMMON	6" OC, TOENAIL
21. 1"x6" SUBFLOOR OR LESS TO EACH JOIST	2-8d COMMON	FACE NAIL
22. 2" SUBFLOOR TO JOIST OR GIRDER	2-16d COMMON	FACE NAIL
23. BUILT-UP GIRDER AND BEAMS, 2" LUMBER LAYERS	20d COMMON (4" x 0.192)	3/2" OC FACE NAIL AT TOP AND BOTTOM STAGGERED ON OPPOSITE SIDE
24. LEDGER STRIP SUPPORTING JOIST OR RAFTERS	3-16d COMMON	EACH JOIST OR RAFTER, FACE NAIL
26. JOIST TO BAND JOIST OR RIM JOIST	3-16d COMMON	END NAIL
27. BRIDGING OR BLOCKING TO JOIST, RAFTER OR TRUSS	2-8d COMMON	EACH END, TOENAIL

NOTES:  
 a. THIS NAILING SCHEDULE SHALL ONLY BE USED IF CONDITION IS NOT OTHERWISE DETAILED OR SPECIFIED ON THE CONSTRUCTION DOCUMENTS. COMMON NAILS SHALL BE USED EXCEPT WHERE OTHERWISE STATED  
 b. WHERE A RAFTER IS FASTENED TO AN ADJACENT PARALLEL CEILING JOIST IN ACCORDANCE WITH THIS SCHEDULE AND THE CEILING JOIST IS FASTENED TO THE TOP PLATE IN ACCORDANCE WITH THIS SCHEDULE, THE NUMBER OF TOENAILS IN THE RAFTER SHALL BE PERMITTED TO BE REDUCED BY ONE NAIL


EXTERIOR WALL / INTERIOR WALL BEARING WALL FRAMING




HEADER SCHEDULE		
OPENING WIDTH	2x4 WALL HEADER	2x6 WALL HEADER
< 4'-0"	4x4	4x6 FLAT
4'-0" - 6'-0"	4x4	4x6 FLAT
6'-0" - 8'-0"	4x6	4x6 FLAT
8'-0" - 10'-0"	4x6	6x6

NOTE:  
 1. HEADERS, KING STUDS AND OTHER REFERENCES ON PLAN GOVERN OVER THESE TYPICAL SCHEDULES/DETAILS.  
 2. NAIL SILL PLATE TO WOOD FRAMED FLOORS WITH 1-6d @ 12" O.C.  
 3. SEE NON-BEARING PARTITION ANCHORAGE DETAIL 3415-311 FOR CONN TO CONC SLAB  
 4. PRESSURE TREATED SILL PL.

INTERIOR NON-BEARING PARTITION WALL FRAMING



CEILING JOIST SCHED & DETAILS




CEILING JOIST SCHED	
JOIST SIZE	MAX SPAN
2x4 @ 16" OC	9'-0"
2x6 @ 16" OC	14'-0"
2x8 @ 16" OC	18'-0"

TYPICAL WOOD STUD INTERSECTIONS




MULTI-PLY MEMBER CONNECTION




CEILING JOIST SCHED & DETAILS



TYPICAL WOOD STUD INTERSECTIONS



MULTI-PLY MEMBER CONNECTION



N:\2020\2727-01-cu22-acc-county\ad\Structural\Drawings\2727-01-CU22-540.dwg, PLAN 4 - 540, Nov 20, 2023, 3:29pm, ostep


COUNTY OF SAN LUIS OBISPO  
 ACCESSORY DWELLING UNIT  
 SAN LUIS OBISPO, CA  
 TYPICAL WOOD DETAILS

DATE  
 11/20/2023  
 SHEET


S-401



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.




**SHEAR WALL INTERSECTION** NTS 42




**TYPICAL SHEAR WALL ELEVATION AND SCHEDULE** NTS 13

WALL SYMBOL	STRUCT SHEATHING	FRAMING SIZE	NAILING			SILL NAILING		A35s	ANCHOR BOLTING	CAPACITY PER 2015 AWC SDPWS
			(2) 2x STUD	EDGE	INTERMEDIATE SUPPORTS	NAILS / LAG SCREWS	SDS SCREWS OPTION			
△	15/32" STRUCT 1 PLYWOOD	2x	10d @ 7" OC	8d @ 6" OC	8d @ 12" OC	16d @ 6" OC	12" OC	24" OC	5/8" DIA @ 48" OC	280 PLF
△	15/32" STRUCT 1 PLYWOOD	2x	10d @ 8" OC	10d @ 6" OC	10d @ 12" OC	5/8" LAG SCREWS @ 16" OC	12" OC	16" OC	5/8" DIA @ 48" OC	340 PLF
△	15/32" STRUCT 1 PLYWOOD	2x	10d @ 5" OC	10d @ 4" OC	10d @ 12" OC	5/8" LAG SCREWS @ 16" OC	8" OC	12" OC	5/8" DIA @ 32" OC	510 PLF
△	15/32" STRUCT 1 PLYWOOD	2x	10d @ 4" OC	10d @ 3" OC	10d @ 12" OC	5/8" LAG SCREWS @ 16" OC	6" OC	8" OC	5/8" DIA @ 32" OC	665 PLF
△	15/32" STRUCT 1 PLYWOOD	2x	10d @ 3" OC	10d @ 2" OC	10d @ 12" OC	5/8" LAG SCREWS @ 8" OC	4" OC	8" OC	5/8" DIA @ 24" OC	860 PLF
△	15/32" STRUCT 1 PLYWOOD (EACH FACE OF WALL)	3x	(2) 10d @ 5" OC	10d @ 4" OC	10d @ 12" OC	5/8" LAG SCREWS @ 8" OC	(2) @ 8" OC *	6" OC	5/8" DIA @ 16" OC	1020 PLF
△	15/32" STRUCT 1 PLYWOOD (EACH FACE OF WALL)	3x	(2) 10d @ 4" OC	10d @ 3" OC	10d @ 8" OC	5/8" LAG SCREWS @ 8" OC	(2) @ 6" OC *	A34 @ 4" OC	5/8" DIA @ 16" OC	1330 PLF
△	15/32" STRUCT 1 PLYWOOD (EACH FACE OF WALL)	3x	(2) 10d @ 3" OC	10d @ 2" OC	10d @ 6" OC	5/8" LAG SCREWS @ 6" OC	(2) @ 4" OC *	LTP4 @ 4" OC	5/8" DIA @ 8" OC	1740 PLF


- NOTES:
- ALL PLYWOOD SHALL BE 5 PLY MINIMUM WITH A SPAN RATING OF 32/16 AND ALL PANEL EDGES SHALL BE BLOCKED. PROVIDE 1/8" GAP AT ALL PANEL JOINTS.
  - ALL NAILS SHALL BE COMMON NAILS.
  - PROVIDE E.N. AT ALL END STUDS, STUDS/POSTS WITH HOLDOWNS OR TIE DOWN STRAPS, SILL PLATES AND TOP PLATES.
  - WHERE 10d NAILS ARE 3 INCHES ON CENTER OR LESS, NAILS SHALL BE STAGGERED.
  - NAILS SHALL BE 1/2" INCH MINIMUM FROM PLYWOOD PANEL EDGE AND 3/8" INCH MINIMUM FROM CONNECTING MEMBER EDGE WHERE SHEAR EXCEEDS 300 PLF.
  - USE 3x FRAMING AT BOTTOM SILL PLATES. BLOCKING AND ALL STUDS AT ADJACENT PANEL EDGES WHERE SHEAR EXCEEDS 300 PLF. STRUCTURALLY ACCEPTABLE TO USE (2) 2x INSTEAD OF 3x FRAMING AT BOTTOM SILL PLATES.
  - WHERE SILL SHEAR TRANSFER IS THROUGH LAG SCREWS, SILL PLATE SHALL BE A MINIMUM OF 2 1/2" THICK.
  - LAG SCREWS SHALL BE 6 INCHES LONG AND HOLES ARE TO BE PRE-DRILLED AS TO NOT SPLIT BLOCKING/RIM.
  - SEE ELEVATION ABOVE FOR TYPICAL CONSTRUCTION.
  - REFER TO PLATE WASHER DETAIL FOR REQUIREMENTS.
  - LENGTHY ANCHOR BOLTS AS REQUIRED FOR EMBEDMENT AND SILL PLATE THICKNESS.
  - ORIENTED STRAND BOARD (OSB) MAY BE SUBSTITUTED FOR PLYWOOD NOTED ABOVE PROVIDED IT IS RATED BY APA'S PERFORMANCE STANDARD RATING AND IS OF THE SAME NUMBER OF LAYERS AS PLYWOOD PLY INDICATED.
  - LIMITATIONS OF MECHANICAL PENETRATIONS IN SHEAR WALLS:
    - A. 4 1/2" MAX PENETRATION.
    - B. NO CUTS OR HOLES IN SHEATHING WITHIN 16" OF CORNERS. SQUARE PENETRATIONS SHALL RADIUS EDGES. DO NOT OVER CUT HOLE WITH SAW.
  - ASSUMES A 1 1/4" MIN LSI RIM BOARD. FASTENER EDGE DIST IS 5/8" MIN & 6" END DISTANCE MIN. 2" MIN PENETRATION INTO RIM BOARD.
  - WALL W/ DOUBLE SIDED PLYWOOD REQUIRE (2) RIM BOARDS.
  - SIMPSON LTP4 CLIP SHALL BE INSTALLED IN A HORIZONTAL ORIENTATION. IF CLIP IS INSTALLED OVER THE SHEATHING, 0.131" x 2 1/2" NAILS SHALL BE USED.




**TYPICAL BLOCKING DETAIL** NTS 43



**FORCE TRANSFER AROUND OPENINGS** NTS 44



**PLATE WASHER DETAIL** NTS 34



**DOUBLE SIDED SHEAR WALL** NTS 24

**COUNTY OF SAN LUIS OBISPO**  
**ACCESSORY DWELLING UNIT**  
 SAN LUIS OBISPO, CA


**TYPICAL WOOD DETAILS**

DATE  
11/20/2023


SHEET

**S-402**

N:\7400\2727-01-cu22-ak-county-adu\Structural\Sheet\2727-01-CU22-5402.dwg, PLAN 4 - 5402, Nov 20, 2023, 3:28pm, odepce




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



TOP PLATE LAP NAILING		
WALL TYPE	MIN LAP SPLICE	NAILS EA SIDE
NON-BEARING	2'-0"	(8) 16d

TOP PLATE LAP NAILING			
SYMBOL	MIN LAP SPLICE	NAILS EA SIDE	ALLOWABLE TOP CHORD CAPACITY
⊙	4'-0"	(8) 16d	1,800#
⊙	4'-0"	(12) 16d	2,700#
⊙	4'-0"	(16) 16d	3,600#
⊙	4'-0"	(20) 16d	4,500#
⊙	4'-0"	(24) 16d	5,400#
⊙	4'-0"	(28) 16d	6,300#
⊙	4'-0"	(32) 16d	7,200#




DIAPHRAGM SCHEDULE												
TYPE	LOCATION	SHEATHING THICKNESS	SHEATHING GRADE	SPAN RATING	BLOCKING	NAILS	BOUNDARY NAILING (BN)	EDGE NAILING AT CONT. PANEL EDGES (EN)	EDGE NAILING AT OTHER PANEL EDGES (EN)	FIELD NAILING (FN)	PANEL EDGE SUPPORT OR NOMINAL MEMBER WIDTH AT PANEL EDGES	LINES OF FASTENERS
A	ROOF	SEE NOTE 5	SHEATHING	32 / 16	NO	10d	6	-	6	12	H-CLIPS	1
B	FLOOR	3/4"	STURD-FLOOR	48 / 24	NO	10d	6	-	6	12	T&G	1
C	FLOOR	3/4"	STURD-FLOOR	48 / 24	YES	10d	2 1/2	2 1/2	4	12	2x4 FLAT	1

- NOTES:
- DIAPHRAGM SHALL BE GLUED TO FLOOR FRAMING PRIOR TO NAILING, REFER TO PROJECT GENERAL NOTES.
  - MINIMUM EDGE DISTANCE FOR NAILS SHALL BE 1/2" FROM SHEATHING EDGE AND 3/8" FROM LUMBER EDGE.
  - NAILS SHALL BE DRIVEN TIGHT TO TOP OF PLYWOOD SURFACE AND SHALL NOT PENETRATE THE TOP OF PLYWOOD MORE THAN COMMONLY EXPECTED WITH HAMMER DRIVEN NAILS.
  - WHERE H-CLIPS ARE SPECIFIED, THEY SHOULD BE INSTALLED AS FOLLOWS:
    - ONE H-CLIP SHALL BE PLACED BETWEEN ABUTTING PANELS AT A LOCATION MIDWAY BETWEEN EACH PAIR OF TRUSSES, RAFTERS OR JOISTS. HOWEVER, (2) H-CLIPS ARE REQUIRED BETWEEN SUPPORTS WHEN SPACED 48 INCHES ON CENTER.
    - USE THE SAME SIZE PANEL EDGE CLIP AS THE PANEL THICKNESS. H-CLIPS MUST FIT SNUGLY.
    - ABUTTING WOOD STRUCTURAL PANELS BE FITTED AS CLOSELY AS CLIPS PERMIT. OCCASIONAL MISFIT OF ABUTTING SHEETS MAY BE TOLERATED PROVIDING THAT GAPS DO NOT EXCEED MAXIMUM OPENING OF 1/8".
  - ROOF SHEATHING THICKNESS SHALL BE INSTALLED AS FOLLOWS:
    - 1/2" @ SINGLE PLY OR ASPHALT SHINGLES
    - 3/4" @ TILE
    - 3/4" @ TILE WITH MORTAR
  - STRUCTURALLY ACCEPTABLE TO USE "SHEATHING" SHEATHING GRADE @ FLOOR LOCATIONS WITHOUT GYPCRETE TOPPING


51 DBL TOP PLATE SPLICE NAILING 2272-01-C1022-1403 NTS 32

52 42 32 PLYWOOD DIAPHRAGM SHEATHING NTS 12




NOTE: FOR LARGER OPENINGS REFER TO FRAMING PLAN

53 43 33 OPENING AT FRAMING NTS 23



NTS 13

54 44 34 TYP JOIST BLOCKING NTS 14



NTS 14

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
TYPICAL WOOD DETAILS

DATE  
11/20/2023  
SHEET


S-403

N:\2000\2272\01-c1022-acc-county\add\structural\ContDocs\Sheet\2272-01-C1022-1403.dwg, PLAN 4 - 5403, Nov 20, 2023, 3:25pm, edpate



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.


	51	41	31



HEADER OR BEAM DEPTH	MAX ROUND HOLE SIZE
9 1/2"	3"
11 7/8"	3 3/8"
14'-16"	4 3/8"


- 1.55E LSL NOTES:
- ALLOWED HOLE ZONE SUITABLE FOR HEADERS AND BEAMS WITH UNIFORM AND/OR CONCENTRATED LOADS ANYWHERE ALONG THE MEMBER.
  - ROUND HOLES ONLY.
  - NO HOLES IN HEADERS OR BEAMS IN PLANK ORIENTATION.

	52	42	32




HEADER OR BEAM DEPTH	MAX ROUND HOLE SIZE
4 1/2"	1"
5 1/2"	1 3/4"
7 1/4' - 20'	2"

- LVL/PSL/1.3E LSL:
- ALLOWED HOLE ZONE SUITABLE FOR HEADERS AND BEAMS WITH UNIFORM LOADS ONLY.
  - ROUND HOLES ONLY.
  - NO HOLES IN CANTILEVERS.
  - NO HOLES IN HEADERS OR BEAMS IN PLANK ORIENTATION.




	53	43	33



- NOTES:
- NOTCHING AND BORING NOT PERMITTED IN THE SAME JOIST CROSS SECTION WITHOUT STRUCTURAL ENGINEER'S APPROVAL.
  - NOTCH WIDTHS GREATER THAN SHOWN IN TABLE NOT PERMITTED WITHOUT STRUCTURAL ENGINEER'S APPROVAL.
  - NO NOTCHES OR HOLES PERMITTED ANYWHERE IN CANTILEVERED ELEMENTS WITHOUT STRUCTURAL ENGINEER'S APPROVAL.


JOIST SIZE	MAX HOLE	MAX NOTCH DEPTH	MAX END NOTCH	MAX NOTCH LENGTH
2x4	NONE	NONE	NONE	NONE
2x6	1 1/2"	1/2"	1 3/8"	1 1/2"
2x8	2 3/8"	1 1/2"	1 3/8"	2 3/8"
2x10	3"	1 1/2"	2 3/8"	3"
2x12	3 3/4"	1 1/2"	2 3/8"	3 3/4"

	54	44	34



STUD SIZE (IN)	APPLICATION	MAX HOLE DIAMETER (IN)	MAX NOTCH DEPTH (IN)
2x4	NON-BEARING	2 3/8"	1 3/8"
	EXTERIOR/BEARING	1 3/8"	7/8"
2x6	NON-BEARING	3 1/4"	2 3/8"
	EXTERIOR/BEARING	2 3/8"	1 3/8"

- NOTES:
- NOTCHING AND BORING NOT PERMITTED IN THE SAME STUD SECTION.
  - NO MORE THAN 2 SUCCESSIVE DBL. STUDS ARE PERMITTED TO HAVE 60% MAX BORED HOLES.



TOP PL OR SILL PL	A	B	C	D	E	F
2x4	3/8"	1/2"	1/2"	1/2"	3/4"	6
2x6	1/2"	3/4"	3/4"	3/4"	1"	9
2x8	3/4"	3"	3/4"	3/4"	1 1/4"	12

- 1 1/2" WIDE x 1/4" GAGE GALVANIZED STRAP FASTENED TO EA PL ACROSS THE OPNG & ATTACHED ON EA SIDE OF THE OPNG W/ NOT LESS THAN "E" 16d COMMON NAILS

N:\2000\2727-01\_c029-00-county\ad\Structural\Drawings\Sheet\2727-01-C102-1-5404.dwg, P:\AN 4 - 5404, Nov 20, 2023, 3:29pm, obdpet


COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
TYPICAL WOOD DETAILS

DATE  
11/20/2023  
SHEET


S-404




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.




51 FLOOR FRAMING PERP BEAM @ WALL  
2727-01-CU22-S411-41 1" = 1'-0"




41 STRAP @ BALLOON FRAMED STUD WALL  
2727-01-CU22-S411-41 NTS




31 FLOOR FRAMING @ WALL  
2727-01-CU22-S411-31 1" = 1'-0"




21 FLOOR FRAMING @ WALL  
2727-01-CU22-S411-21 1" = 1'-0"




52 CANTILEVER OFFSET WALL  
2727-01-CU22-S411-42 1" = 1'-0"




42 BLOCK & STRAP PERP TO FRMG  
2727-01-CU22-S411-42 NTS




32 INTERIOR SHEAR WALL (JOIST PERPENDICULAR)  
2727-01-CU22-S411-32 1" = 1'-0"




22 EXTERIOR SHEAR WALL (JOIST PERPENDICULAR)  
2727-01-CU22-S411-22 1" = 1'-0"




53 FLOOR FRAMING PERP BEAM @ WALL  
2727-01-CU22-S411-43 1" = 1'-0"



43 STRAP @ ELEVATED FLOORS  
2727-01-CU22-S411-43 NTS




33 INTERIOR SHEAR WALL (JOIST PARA)  
2727-01-CU22-S411-33 1" = 1'-0"




23 EXTERIOR SHEAR WALL (JOIST PERPENDICULAR)  
2727-01-CU22-S411-23 1" = 1'-0"




54 STRAP @ ELEVATED FLOORS  
2727-01-CU22-S411-44 1" = 1'-0"



44 NON-BEARING TOP PLATE CONNECTION  
2727-01-CU22-S411-34 1" = 1'-0"



34 INTERIOR SHEAR WALL (JOIST PERPENDICULAR)  
2727-01-CU22-S411-34 1" = 1'-0"




24 EXTERIOR SHEAR WALL (JOIST PERPENDICULAR)  
2727-01-CU22-S411-24 1" = 1'-0"

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
FLOOR FRAMING DETAILS


DATE  
11/20/2023  
SHEET

S-411


N:\2000\2727-01-cu22-acc-county\adu\structural\CondDoc\Sheet\2727-01-CU22-S411.dwg, PLAN 4 - S411, Nov 20, 2023, 3:29pm, adp@cs




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.




INTERIOR SHEAR WALL (JOIST PARALLEL) 1" = 1'-0" 51




BEAM TO POST CONNECTION 1" = 1'-0" 41



OUTLOOK AT PORCH ROOF NTS or 1" = 1'-0" 31




ROOF RIDGE 1" = 1'-0" 21




RAFTER @ EXTERIOR SHEAR WALL 1" = 1'-0" 11




ROOF RAFTER ABOVE FLOOR (PARALLEL JOIST) 1" = 1'-0" 52



LOW ROOF @ FLOOR FRAMING 1" = 1'-0" 32




ROOF RAFTER ABOVE BEAM 1" = 1'-0" 22




RAFTER @ EXTERIOR SHEAR WALL 1" = 1'-0" 12




ROOF RAFTER ABOVE FLOOR (PARA JOIST) 1" = 1'-0" 53



BEAM POCKET THROUGH EXTERIOR WALL NTS or 3/4" = 1'-0" 33




EXTERIOR SHEAR WALL (JOIST PARALLEL) 1" = 1'-0" 23




OUTLOOKER @ EXTERIOR SHEAR WALL 1" = 1'-0" 13



RAFTER TO WALL BELOW 1" = 1'-0" 54



BEAM POCKET THROUGH EXTERIOR WALL NTS 34



ROOF RAFTER TO EXTERIOR WALL (PARA) NTS or 1" = 1'-0" 24

FOR USE WITH THE COUNTY OF SAN LUIS OBISPO

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
ROOF FRAMING DETAILS

Energy Use	Standard Design Source Energy (EDR1) (kBtu/ft <sup>2</sup> -yr)	Standard Design TDV Energy (EDR2) (KTDV/ft <sup>2</sup> -yr)	Proposed Design Source Energy (EDR1) (kBtu/ft <sup>2</sup> -yr)	Proposed Design TDV Energy (EDR2) (KTDV/ft <sup>2</sup> -yr)	Compliance Margin (EDR1)	Compliance Margin (EDR2)
Space Heating	1.29	5.94	2.54	19.71	-1.25	-13.77
Space Cooling	1.24	39.44	0.58	26.57	0.66	12.87
IAQ Ventilation	0.51	5.47	0.51	5.47	0	0
Water Heating	4.74	51	3.27	39.57	1.46	11.43
Self Utilization/Flexibility Credit				0		0
<b>North Facing Efficiency Compliance Total</b>	<b>7.78</b>	<b>101.85</b>	<b>6.91</b>	<b>91.32</b>	<b>0.87</b>	<b>10.53</b>
Space Heating	1.29	5.94	2.16	16.48	-0.87	-10.54
Space Cooling	1.24	39.44	0.59	26.02	0.65	13.42
IAQ Ventilation	0.51	5.47	0.51	5.47	0	0
Water Heating	4.74	51	3.27	39.42	1.47	11.58
Self Utilization/Flexibility Credit				0		0
<b>East Facing Efficiency Compliance Total</b>	<b>7.78</b>	<b>101.85</b>	<b>6.53</b>	<b>87.39</b>	<b>1.25</b>	<b>14.46</b>

CF1R-PRF-01E (Page 2 of 12)  
 Calculation Date/Time: 2023-10-30 11:44:04-07:00  
 Input File Name: 1 Bedrm Plan -Plan 4b CZ 4.rbd22x

Energy Design Ratings	Standard Design		Proposed Design		Compliance Margins	
	Source Energy (EDR1)	Efficiency Factor (EDR2/EDR1)	Source Energy (EDR1)	Efficiency Factor (EDR2/EDR1)	Source Energy (EDR1)	Efficiency Factor (EDR2/EDR1)
North Facing	36.3	36.3	36.3	27.7	1.4	4.2
East Facing	38.8	34.8	36.3	69.3	1.9	5.7
South Facing	36	37.5	36.3	62.3	1.7	3
West Facing	36.3	38.4	36.3	63.8	1.4	2.1

HERS Provider: CZ-4-03  
 Report Generated: 2023-10-30 11:44:26

CF1R-PRF-01E (Page 1 of 12)  
 Calculation Date/Time: 2023-10-30 11:44:04-07:00  
 Input File Name: 1 Bedrm Plan -Plan 4b CZ 4.rbd22x

GENERAL INFORMATION		Project Information		Building Information		Compliance Results	
01	Project Name	Residential Building	Project Location	City	San Luis Obispo, CA	Standard Design Version	2022
02	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
03	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
04	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
05	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
06	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
07	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
08	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
09	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
10	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
11	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
12	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
13	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
14	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
15	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
16	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
17	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
18	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
19	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
20	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
21	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
22	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26
23	Project Location	City	County	San Luis Obispo	Standard Design Version	2022	Report Generated: 2023-10-30 11:44:26



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CAN NOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

01	02	03	04	05	06	07	08	09	10	11	12
DC System Size (kWdc)	Exception	Module Type	Array Type	Power Electronics	CFI	Asimuth (deg)	Tilt Input	Array Angle (deg)	Tilt: (x in 12)	Inverter Eff (%)	Annual Solar Access (%)
0		Standard (14-17%)	Fixed	none	true	n/a	n/a	n/a	n/a	n/a	n/a

**REQUIRED SPECIAL FEATURES**  
 The following are features that must be installed as condition for meeting the modeled energy performance for this computer analysis.  
 • PV exception 2: No PV required when minimum PV size (Section 150.1(c)(14) < 1.8 kWdc (0 kW))  
 • Variable capacity heat pump compliance option (verification details from VCHP Staff report, Appendix B, and RA3)  
 • Compact distribution system basic credit  
 • Northwest Energy Efficiency Alliance (NEEA) rated heat pump water heater; specific brand/model, or equivalent, must be installed

**HERS FEATURE SUMMARY**  
 The following is a summary of the features that must be field-verified by a certified HERS Rater as a condition for meeting the modeled energy performance for this computer analysis. Additional detail is provided in the building tables below. Registered CF2Rs and CF3Rs are required to be completed in the HERS Registry  
 • Quality insulation installation (QII)  
 • Indoor air quality ventilation  
 • Kitchen range hood  
 • Verified EER/EER2  
 • Verified SEER/SEER2  
 • Verified Refrigerant Charge  
 • Airflow in habitable rooms (SC3.1.4.1.7)  
 • Verified HSPF2  
 • Verified heat pump rated heating capacity  
 • Wall-mounted thermostat in zones greater than 150 ft<sup>2</sup> (SC3.4.5)  
 • Ductless indoor units located entirely in conditioned space (SC3.1.4.1.8)

01	02	03	04	05	06	07
Project Name	Conditioned Floor Area (ft <sup>2</sup> )	Number of Dwelling Units	Number of Bedrooms	Number of Zones	Number of Ventilation Cooling Systems	Number of Water Heating Systems
Residential Building	409	1	1	1	1	1

Energy Use Intensity	Standard Design (kBtu/ft <sup>2</sup> -yr)	Proposed Design (kBtu/ft <sup>2</sup> -yr)	Compliance Margin (kBtu/ft <sup>2</sup> -yr)	Margin Percentage
<b>North Facing</b>				
Gross EUI <sup>1</sup>	36.54	34.84	1.7	4.65
Net EUI <sup>2</sup>	36.54	34.84	1.7	4.65
<b>East Facing</b>				
Gross EUI <sup>1</sup>	36.54	34.51	2.03	5.56
Net EUI <sup>2</sup>	36.54	34.51	2.03	5.56
<b>South Facing</b>				
Gross EUI <sup>1</sup>	36.54	34.73	1.81	4.95
Net EUI <sup>2</sup>	36.54	34.73	1.81	4.95
<b>West Facing</b>				
Gross EUI <sup>1</sup>	36.54	34.94	1.6	4.38
Net EUI <sup>2</sup>	36.54	34.94	1.6	4.38

Notes:  
 1. Gross EUI is Energy Use Total (not including PV) / Total Building Area.  
 2. Net EUI is Energy Use Total (including PV) / Total Building Area.

Energy Use	Standard Design Source Energy (EDR1) (kBtu/ft <sup>2</sup> -yr)	Standard Design TDV Energy (EDR2) (KTDV/ft <sup>2</sup> -yr)	Proposed Design Source Energy (EDR1) (kBtu/ft <sup>2</sup> -yr)	Proposed Design TDV Energy (EDR2) (KTDV/ft <sup>2</sup> -yr)	Compliance Margin (EDR1)	Compliance Margin (EDR2)
Space Heating	1.29	5.94	2.05	15.93	-0.76	-9.99
Space Cooling	1.24	39.44	0.8	33.54	0.44	5.9
IAQ Ventilation	0.51	5.47	0.51	5.47	0	0
Water Heating	4.74	51	3.26	39.34	1.48	11.66
Self Utilization/Flexibility Credit				0		0
<b>South Facing Efficiency Compliance Total</b>	<b>7.78</b>	<b>101.85</b>	<b>6.62</b>	<b>94.28</b>	<b>1.16</b>	<b>7.57</b>
Space Heating	1.29	5.94	2.39	18.99	-1.1	-13.05
Space Cooling	1.24	39.44	0.73	32.63	0.51	6.81
IAQ Ventilation	0.51	5.47	0.51	5.47	0	0
Water Heating	4.74	51	3.27	39.52	1.47	11.48
Self Utilization/Flexibility Credit				0		0
<b>West Facing Efficiency Compliance Total</b>	<b>7.78</b>	<b>101.85</b>	<b>6.9</b>	<b>96.61</b>	<b>0.88</b>	<b>5.24</b>

01	02	03	04	05	06	07	08
Construction Name	Surface Type	Construction Type	Framing	Total Cavity R-value	Interior / Exterior Continuous R-value	U-factor	Assembly Layers
R-19 Wall	Exterior Walls	Wood Framed Wall	2x6 @ 16 in. O.C.	R-19	None / None	0.074	Inside Finish: Gypsum Board Cavity / Frame: R-19 in S-1/2 in. (R-18) / 2x6 Exterior Finish: 3 Coat Stucco
R-38 Roof No Attic	Cathedral Ceilings	Wood Framed Ceiling	2x12 @ 16 in. O.C.	R-38	None / None	0.03	Roofing: Light Roof (Asphalt Shingle) Roof Deck: Wood Siding/Sheathing/Decking Cavity / Frame: R-38 / 2x12 Inside Finish: Gypsum Board

01	02	03	04	05
Quality Insulation Installation (QII)	High R-value Spray Foam Insulation	Building Envelope Air Leakage	CFM50	CFM50
Required	Not Required	N/A	n/a	n/a

01	02	03	04	05	06	07	08	09
Name	System Type	Distribution Type	Water Heater Name	Number of Units	Solar Heating System	Compact Distribution	HERS Verification	Water Heater Name (R)
DHW Sys 1	Domestic Hot Water (DHW)	Standard	DHW Heater 1	1	n/a	Basic	n/a	DHW Heater 1 (1)

01	02	03	04	05	06	07	08	09	10	11	12	13	14
Name	Type	Surface	Orientation	Azimuth	Width (ft)	Height (ft)	Mult.	Area (ft <sup>2</sup> )	U-factor	U-factor Source	SHGC	SHGC Source	Exterior Shading
Window	Window	Front Wall	Front	0	1	39	0.3	NFRC	0.23	NFRC	0.23	NFRC	Bug Screen
Front Door	Window	Front Wall	Front	0	1	20	0.3	NFRC	0.23	NFRC	0.23	NFRC	Bug Screen
Window 2	Window	Left Wall	Left	90	1	55	0.3	NFRC	0.23	NFRC	0.23	NFRC	Bug Screen
Window 3	Window	Rear Wall	Back	180	1	9	0.3	NFRC	0.23	NFRC	0.23	NFRC	Bug Screen
Window 4	Window	Right Wall	Right	270	1	15	0.3	NFRC	0.23	NFRC	0.23	NFRC	Bug Screen

01	02	03	04
Name	Side of Building	Area (ft <sup>2</sup> )	U-factor
Insulated Door HPWH	Rear Wall	20	0.2

01	02	03	04	05	06	07	08
Name	Zone	Area (ft <sup>2</sup> )	Perimeter (ft)	Edge Insul. R-value and Depth	Edge Insul. R-value and Depth	Carpeted Fraction	Heated
Slab	Zone 1	406	80	none	0	80%	No

01	02	03	04	05	06	07
Zone Name	Zone Type	HVAC System Name	Zone Floor Area (ft <sup>2</sup> )	Avg. Ceiling Height	Water Heating System 1	Status
Zone 1	Conditioned	HVAC System1	409	8	DHW Sys 1	New

01	02	03	04	05	06	07	08
Name	Zone	Construction	Azimuth	Orientation	Gross Area (ft <sup>2</sup> )	Window and Door Area (ft <sup>2</sup> )	Tilt (deg)
Front Wall	Zone 1	R-19 Wall	0	Front	173	59	90
Left Wall	Zone 1	R-19 Wall	90	Left	168	55	90
Rear Wall	Zone 1	R-19 Wall					

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

CF1R-PRF-01E

Project Name: Residential Building

Calculation Date/Time: 2023-10-30 11:44:04-07:00

(Page 12 of 12)

Calculation Description: Title 24 Analysis

Input File Name: 1 Bedrm Plan - Plan 4b CZ 4.ribd22x

DOCUMENTATION AUTHOR'S DECLARATION STATEMENT

1. I certify that this Certificate of Compliance documentation is accurate and complete.

Documentation Author Name: Jennifer Rennick  
 Signature Date: 10/30/2023  
 Company: In Balance Green Consulting  
 Address: [Redacted]  
 City/State/Zip: [Redacted]

RESPONSIBLE PERSON'S DECLARATION STATEMENT

I certify the following under penalty of perjury, under the laws of the State of California:  
 1. I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design identified on this Certificate of Compliance.  
 2. I certify that the energy features and performance specifications identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.  
 3. The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with this building permit application.  
 Responsible Designer Name: [Redacted] Responsible Designer Signature: [Redacted]  
 Date Signed: [Redacted]  
 License: [Redacted]  
 City/State/Zip: [Redacted]

Registration Number: [Redacted] Registration Date/Time: [Redacted] HERS Provider: CZ-4-12  
 CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000 Schema Version: rev 20220901 Report Generated: 2023-10-30 11:44:26

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

CF1R-PRF-01E

Project Name: Residential Building

Calculation Date/Time: 2023-10-30 11:44:04-07:00

(Page 11 of 12)

Calculation Description: Title 24 Analysis

Input File Name: 1 Bedrm Plan - Plan 4b CZ 4.ribd22x

HVAC - HEAT PUMPS

01	02	03	04	05	06	07	08	09	10	11	12	13
Name	System Type	Number of Units	Heating Efficiency Type	HSPF/HS PF2/COP	Cap 47	Cap 17	Cooling Efficiency Type	SEER/SE ER2	EER/EER 2/CEER	Zonally Controlled	Compressor Type	HERS Verification
Heat Pump System 1	VCHP-ductless	2	HSPF2	8	9000	7200	EER/SEER2	16	12.4	Not Zonal	Multi-speed	Heat Pump System 1-hers-htpump

HVAC HEAT PUMPS - HERS VERIFICATION

01	02	03	04	05	06	07	08	09
Name	Verified Airflow	Airflow Target	Verified EER/EER2	Verified SEER/SEER2	Verified Refrigerant Charge	Verified HSPF/HSPF2	Verified Heating Cap 47	Verified Heating Cap 17
Heat Pump System 1-hers-htpump	Not Required	0	Required	Required	Yes	Yes	Yes	Yes

VARIABLE CAPACITY HEAT PUMP COMPLIANCE OPTION - HERS VERIFICATION

01	02	03	04	05	06	07	08	09	10
Name	Certified Low-Static VCHP System	Airflow to Habitable Rooms	Ductless Units in Conditioned Space	Wall Mount Thermostat	Air Filter Sizing & Pressure Drop Rating	Low Leakage Ducts in Conditioned Space	Minimum Airflow per RA3.3 and SC3.3.3.4.1	Certified non-continuous Fan	Indoor Fan not Running Continuously
Heat Pump System 1	Not required	Required	Required	Required	Not required	Not required	Not required	Not required	Not required

INDOOR AIR QUALITY (IAQ) FANS

01	02	03	04	05	06	07	08	09
Dwelling Unit	Airflow (CFM)	Fan Efficacy (W/CFM)	IAQ Fan Type	Includes Heat/Energy Recovery?	IAQ Recovery Effectiveness - SRE/ASRE	Includes Fault Indicator Display?	HERS Verification	Status
Sfam IAQVentRgt	27	0.35	Exhaust	No	n/a / n/a	No	Yes	

Registration Number: [Redacted] Registration Date/Time: [Redacted] HERS Provider: CZ-4-11  
 CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000 Schema Version: rev 20220901 Report Generated: 2023-10-30 11:44:26

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

CF1R-PRF-01E

Project Name: Residential Building

Calculation Date/Time: 2023-10-30 11:44:04-07:00

(Page 10 of 12)

Calculation Description: Title 24 Analysis

Input File Name: 1 Bedrm Plan - Plan 4b CZ 4.ribd22x

WATER HEATERS - NEEA HEAT PUMP

01	02	03	04	05	06	07	08
Name	# of Units	Tank Vol. (gal)	NEEA Heat Pump Brand	NEEA Heat Pump Model	Tank Location	Duct Inlet Air Source	Duct Outlet Air Source
DHW Heater 1	1	40	Generic	Tier3Generic40	TankZone	Zone 1	Zone 1

WATER HEATING - COMPACT DISTRIBUTION

01	02	03	04	05	06	07
Dwelling Unit type	Water Heating System Name	Master Bath distance of furthest fixture to Water Heater (ft)	Kitchen distance of furthest fixture to Water Heater (ft)	Furthest Third furthest fixture to Water Heater (ft)	Compactness Factor	HERS Verification
Dwelling	DHW Sys 1	n/a	n/a	n/a	0.7	n/a


WATER HEATING - HERS VERIFICATION

01	02	03	04	05	06	07
Name	Pipe Insulation	Parallel Piping	Compact Distribution	Compact Distribution Type	Recirculation Control	Shower Drain Water Heat Recovery
DHW Sys 1 - 1/1	Not Required	Not Required	Not Required	Basic	Not Required	Not Required

SPACE CONDITIONING SYSTEMS

01	02	03	04	05	06	07	08	09
Name	System Type	Heating Unit Name	Heating Equipment Count	Cooling Unit Name	Cooling Equipment Count	Fan Name	Distribution Name	Required Thermostat Type
HVAC System1	Heat pump heating cooling	Heat Pump System 1	2	Heat Pump System 1	2	n/a	n/a	Setback

Registration Number: [Redacted] Registration Date/Time: [Redacted] HERS Provider: CZ-4-10  
 CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000 Schema Version: rev 20220901 Report Generated: 2023-10-30 11:44:26



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
 ACCESSORY DWELLING UNIT  
 SAN LUIS OBISPO, CA  
 ENERGY COMPLIANCE - PLAN 4B

DATE  
 11/28/2023  
 SHEET  
 T24 - 406

FOR USE IN THE COUNTY OF SAN LUIS OBISPO



Energy Use	Standard Design Source Energy (EDR1) (kBtu/ft <sup>2</sup> -yr)	Standard Design TDV Energy (EDR2) (KTDV/ft <sup>2</sup> -yr)	Proposed Design Source Energy (EDR1) (kBtu/ft <sup>2</sup> -yr)	Proposed Design TDV Energy (EDR2) (KTDV/ft <sup>2</sup> -yr)	Compliance Margin (EDR1)	Compliance Margin (EDR2)
Space Heating	1.17	5.56	2.73	21.22	-1.56	-15.66
Space Cooling	0.13	4.5	0.01	0.57	0.12	3.93
IAQ Ventilation	0.51	5.51	0.51	5.51	0	0
Water Heating	5.39	60.13	3.58	45.57	1.81	14.56
Self Utilization/Flexibility Credit				0		0
<b>North Facing Efficiency Compliance Total</b>	<b>7.2</b>	<b>75.7</b>	<b>6.83</b>	<b>72.87</b>	<b>0.37</b>	<b>2.83</b>
Space Heating	1.17	5.56	1.88	14.41	-0.71	-8.85
Space Cooling	0.13	4.5	0.03	1.12	0.1	3.38
IAQ Ventilation	0.51	5.51	0.51	5.51	0	0
Water Heating	5.39	60.13	3.56	45.23	1.83	14.9
Self Utilization/Flexibility Credit				0		0
<b>East Facing Efficiency Compliance Total</b>	<b>7.2</b>	<b>75.7</b>	<b>5.98</b>	<b>66.27</b>	<b>1.22</b>	<b>9.43</b>

CF1R-PRF-01E (Page 2 of 12)

Project Name: Residential Building  
 Calculation Date/Time: 2023-10-30 11:46:01-07:00  
 Input File Name: 1 Bedrm Plan -Plan 4b CZ 5.rbd22x

Energy Use Intensity	Standard Design (kBtu/ft <sup>2</sup> -yr)	Proposed Design (kBtu/ft <sup>2</sup> -yr)	Compliance Margin (kBtu/ft <sup>2</sup> -yr)	Margin Percentage
North Facing	35.41	34.43	0.98	2.77
East Facing	35.41	33.74	1.67	4.72
South Facing	35.41	33.67	1.74	4.91
West Facing	35.41	34.35	1.06	2.99

HERS Provider: CZ-5-05  
 Report Generated: 2023-10-30 11:46:24

CF1R-PRF-01E (Page 5 of 12)

Project Name: Residential Building  
 Calculation Date/Time: 2023-10-30 11:46:01-07:00  
 Input File Name: 1 Bedrm Plan -Plan 4b CZ 5.rbd22x

Energy Use Intensity	Standard Design (kBtu/ft <sup>2</sup> -yr)	Proposed Design (kBtu/ft <sup>2</sup> -yr)	Compliance Margin (kBtu/ft <sup>2</sup> -yr)	Margin Percentage
North Facing	35.41	34.43	0.98	2.77
East Facing	35.41	33.74	1.67	4.72
South Facing	35.41	33.67	1.74	4.91
West Facing	35.41	34.35	1.06	2.99

HERS Provider: CZ-5-05  
 Report Generated: 2023-10-30 11:46:24

CF1R-PRF-01E (Page 4 of 12)

Project Name: Residential Building  
 Calculation Date/Time: 2023-10-30 11:46:01-07:00  
 Input File Name: 1 Bedrm Plan -Plan 4b CZ 5.rbd22x

Energy Use	Standard Design Source Energy (EDR1) (kBtu/ft <sup>2</sup> -yr)	Standard Design TDV Energy (EDR2) (KTDV/ft <sup>2</sup> -yr)	Proposed Design Source Energy (EDR1) (kBtu/ft <sup>2</sup> -yr)	Proposed Design TDV Energy (EDR2) (KTDV/ft <sup>2</sup> -yr)	Compliance Margin (EDR1)	Compliance Margin (EDR2)
Space Heating	1.17	5.56	1.74	13.49	-0.57	-7.93
Space Cooling	0.13	4.5	0.05	1.59	0.08	2.91
IAQ Ventilation	0.51	5.51	0.51	5.51	0	0
Water Heating	5.39	60.13	3.58	45.02	1.86	15.11
Self Utilization/Flexibility Credit				0		0
<b>South Facing Efficiency Compliance Total</b>	<b>7.2</b>	<b>75.7</b>	<b>5.83</b>	<b>65.61</b>	<b>1.37</b>	<b>10.09</b>
Space Heating	1.17	5.56	2.49	19.76	-1.32	-14.2
Space Cooling	0.13	4.5	0.03	0.89	0.1	3.61
IAQ Ventilation	0.51	5.51	0.51	5.51	0	0
Water Heating	5.39	60.13	3.56	45.4	1.83	14.73
Self Utilization/Flexibility Credit				0		0
<b>West Facing Efficiency Compliance Total</b>	<b>7.2</b>	<b>75.7</b>	<b>6.59</b>	<b>71.56</b>	<b>0.61</b>	<b>4.14</b>

HERS Provider: CZ-5-04  
 Report Generated: 2023-10-30 11:46:24

DC System Size (kWdc)	Exception	Module Type	Array Type	Power Electronics	CFI	Azimuth (deg)	Tilt Input	Array Angle (deg)	Tilt: (x in 12)	Inverter Eff (%)	Annual Solar Access (%)
0		Standard (14-17%)	Fixed	none	true	n/a	n/a	n/a	n/a	n/a	n/a

- REQUIRED SPECIAL FEATURES**
- The following are features that must be installed as condition for meeting the modeled energy performance for this computer analysis.
- PV exception 2: No PV required when minimum PV size (Section 150.1(c)(14) < 1.8 kWdc (0 kW)
  - Variable capacity heat pump compliance option (verification details from VCHP Staff report, Appendix B, and RA3)
  - Compact distribution system basic credit
  - Northwest Energy Efficiency Alliance (NEEA) rated heat pump water heater, specific brand/model, or equivalent, must be installed

- HERS FEATURE SUMMARY**
- The following is a summary of the features that must be field-verified by a certified HERS Rater as a condition for meeting the modeled energy performance for this computer analysis. Additional detail is provided in the building tables below. Registered CF2Rs and CF3Rs are required to be completed in the HERS Registry
- Quality insulation installation (QII)
  - Indoor air quality ventilation
  - Kitchen range hood
  - Verified EER/EER2
  - Verified SEER/SEER2
  - Verified Refrigerant Charge
  - Airflow in habitable rooms (SC3.1.4.1.7)
  - Verified HSPF2
  - Verified heat pump rated heating capacity
  - Wall-mounted thermostat in zones greater than 150 ft<sup>2</sup> (SC3.4.5)
  - Ductless indoor units located entirely in conditioned space (SC3.1.4.1.8)

Project Name	Conditioned Floor Area (ft <sup>2</sup> )	Number of Dwelling Units	Number of Bedrooms	Number of Zones	Number of Ventilation Cooling Systems	Number of Water Heating Systems
Residential Building	409	1	1	1	0	1

**FENESTRATION / GLAZING**

Name	Type	Surface	Orientation	Azimuth	Width (ft)	Height (ft)	Mult.	Area (ft <sup>2</sup> )	U-factor	U-factor Source	SHGC	SHGC Source	Exterior Shading
Window	Window	Front Wall	Front	0	1	39	0.3	NFRC	0.35	NFRC			Bug Screen
Front Door	Window	Front Wall	Front	0	1	20	0.3	NFRC	0.35	NFRC			Bug Screen
Window 2	Window	Left Wall	Left	90	1	55	0.3	NFRC	0.35	NFRC			Bug Screen
Window 3	Window	Rear Wall	Back	180	1	9	0.3	NFRC	0.35	NFRC			Bug Screen
Window 4	Window	Right Wall	Right	270	1	15	0.3	NFRC	0.35	NFRC			Bug Screen

**OPAQUE DOORS**

Name	Side of Building	Area (ft <sup>2</sup> )	U-factor
Insulated Door HPWH	Rear Wall	20	0.2

**SLAB FLOORS**

Name	Zone	Area (ft <sup>2</sup> )	Perimeter (ft)	Edge Insul. R-value and Depth	Edge Insul. R-value and Depth	Carpeted Fraction	Heated
Slab	Zone 1	409	80	none	0	80%	No

HERS Provider: CZ-5-08  
 Report Generated: 2023-10-30 11:46:24

**ZONE INFORMATION**

Zone Name	Zone Type	HVAC System Name	Zone Floor Area (ft <sup>2</sup> )	Avg. Ceiling Height	Water Heating System 1	Status
Zone 1	Conditioned	HVAC System1	409	8	DHW Sys 1	New

**OPAQUE SURFACES**

Name	Zone	Construction	Azimuth	Orientation	Gross Area (ft <sup>2</sup> )	Window and Door Area (ft <sup>2</sup> )	Tilt (deg)
Front Wall	Zone 1	R-19 Wall	0	Front	173	59	90
Left Wall	Zone 1	R-19 Wall	90	Left	168	55	90
Rear Wall	Zone 1	R-19 Wall	180	Back	173	29	90
Right Wall	Zone 1	R-19 Wall	270	Right	252	15	90
Exterior Wall 2	Zone 1	R-19 Wall	90	Left	20	0	90
Exterior Wall 2	Zone 1	R-19 Wall	270	Right	20	0	90

**OPAQUE SURFACES - CATHEDRAL CEILINGS**

Name	Zone	Construction	Azimuth	Orientation	Area (ft <sup>2</sup> )	Skylight Area (ft <sup>2</sup> )	Roof Rise (x in 12)	Roof Reflectance	Roof Emittance	Cool Roof
Roof	Zone 1	R-38 Roof No Attic	270	Right	100	0	4	0.1	0.85	No
Roof 2	Zone 1	R-38 Roof No Attic	90	Left	300	0	4	0.1	0.85	No
Roof 3	Zone 1	R-38 Roof No Attic	180	Back	10	0	3	0.1	0.85	No

HERS Provider: CZ-5-07  
 Report Generated: 2023-10-30 11:46:24

**OPAQUE SURFACE CONSTRUCTIONS**

Construction Name	Surface Type	Construction Type	Framing	Total Cavity R-value	Interior / Exterior Continuous R-value	U-factor	Assembly Layers
R-19 Wall	Exterior Walls	Wood Framed Wall	2x6 @ 16 in. O. C.	R-19	None / None	0.074	Inside Finish: Gypsum Board Cavity / Frame: R-19 in S-1/2 in. (R-18) / 2x6 Exterior Finish: 3 Coat Stucco
R-38 Roof No Attic	Cathedral Ceilings	Wood Framed Ceiling	2x12 @ 16 in. O. C.	R-38	None / None	0.03	Roofing: Light Roof (Asphalt Shingle) Roof Deck: Wood Siding/Sheathing/Decking Cavity / Frame: R-38 / 2x12 Inside Finish: Gypsum Board

**BUILDING ENVELOPE - HERS VERIFICATION**

Quality Insulation Installation (QII)	High R-value Spray Foam Insulation	Building Envelope Air Leakage	CFM50
Required	Not Required	N/A	n/a

**WATER HEATING SYSTEMS**

Name	System Type	Distribution Type	Water Heater Name	Number of Units	Solar Heating System	Compact Distribution	HERS Verification	Water Heater Name (F)
DHW Sys 1	Domestic Hot Water (DHW)	Standard	DHW Heater 1	1	n/a	Basic	n/a	DHW Heater 1 (1)

HERS Provider: CZ-5-09  
 Report Generated: 2023-10-30 11:46:24

**FENESTRATION / GLAZING**

Name	Type	Surface	Orientation	Azimuth	Width (ft)	Height (ft)	Mult.	Area (ft <sup>2</sup> )	U-factor	U-factor Source	SHGC	SHGC Source	Exterior Shading
Window	Window	Front Wall	Front	0	1	39	0.3	NFRC	0.35	NFRC			Bug Screen
Front Door	Window	Front Wall	Front	0	1	20	0.3	NFRC	0.35	NFRC			Bug Screen
Window 2	Window	Left Wall	Left	90	1	55	0.3	NFRC	0.35	NFRC			Bug Screen
Window 3	Window	Rear Wall	Back	180	1	9	0.3	NFRC	0.35	NFRC			Bug Screen
Window 4	Window	Right Wall	Right	270	1	15	0.3	NFRC	0.35	NFRC			Bug Screen

**OPAQUE DOORS**

Name	Side of Building	Area (ft <sup>2</sup> )	U-factor
Insulated Door HPWH	Rear Wall	20	0.2

**SLAB FLOORS**

Name	Zone	Area (ft <sup>2</sup> )	Perimeter (ft)	Edge Insul. R-value and Depth	Edge Insul. R-value and Depth	Carpeted Fraction	Heated
Slab	Zone 1	409	80	none	0	80%	No

HERS Provider: CZ-5-08  
 Report Generated: 2023-10-30 11:46:24

**ZONE INFORMATION**

Zone Name	Zone Type	HVAC System Name	Zone Floor Area (ft <sup>2</sup> )	Avg. Ceiling Height	Water Heating System 1	Status
Zone 1	Conditioned	HVAC System1	409	8	DHW Sys 1	New

**OPAQUE SURFACES**

Name	Zone	Construction	Azimuth	Orientation	Gross Area (ft <sup>2</sup> )	Window and Door Area (ft <sup>2</sup> )	Tilt (deg)
Front Wall	Zone 1	R-19 Wall	0	Front	173	59	90
Left Wall	Zone 1	R-19 Wall	90	Left	168	55	90
Rear Wall	Zone 1	R-19 Wall	180	Back	173	29	90
Right Wall	Zone 1	R-19 Wall	270	Right	252	15	90
Exterior Wall 2	Zone 1	R-19 Wall	90	Left	20	0	90
Exterior Wall 2	Zone 1	R-19 Wall	270	Right	20	0	90

**OPAQUE SURFACES - CATHEDRAL CEILINGS**

Name	Zone	Construction	Azimuth	Orientation	Area (ft <sup>2</sup> )	Skylight Area (ft <sup>2</sup> )	Roof Rise (x in 12)	Roof Reflectance	Roof Emittance	Cool Roof
Roof	Zone 1	R-38 Roof No Attic	270	Right	100	0	4	0.1	0.85	No
Roof 2	Zone 1	R-38 Roof No Attic	90	Left	300	0	4	0.1	0.85	No
Roof 3	Zone 1	R-38 Roof No Attic	180	Back	10	0	3	0.1	0.85	No

HERS Provider: CZ-5-07  
 Report Generated: 2023-10-30 11:46:24



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRACT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
 ACCESSORY DWELLING UNIT  
 SAN LUIS OBISPO, CA  
 ENERGY COMPLIANCE - PLAN 4B

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CF1R-PRF-01E  
(Page 12 of 12)

Project Name: Residential Building Calculation Date/Time: 2023-10-30 11:46:01-07:00  
 Calculation Description: Title 24 Analysis Input File Name: 1 Bedrm Plan -Plan 4b CZ 5.rbd22x

**DOCUMENTATION AUTHOR'S DECLARATION STATEMENT**

I, certify that this Certificate of Compliance documentation is accurate and complete.

Documentation Author Name: <b>Jennifer Rennick</b>	Documentation Author Signature:
Company: <b>In Balance Green Consulting</b>	Signature Date: <b>10/30/2023</b>
Address:	CEA/ HERS Certification Identification (if applicable):
City/State/Zip:	Phone:

**RESPONSIBLE PERSON'S DECLARATION STATEMENT**

I certify the following under penalty of perjury, under the laws of the State of California:

- I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design identified on this Certificate of Compliance.
- I certify that the energy features and performance specifications identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.
- The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with the building permit application.

Responsible Designer Name:	Responsible Designer Signature:
Company:	Date Signed:
Address:	License:
City/State/Zip:	Phone:

Registration Number: Registration Date/Time: HERS Provider: **CZ-5-12**  
 CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000  
Schema Version: rev 20220901 Report Generated: 2023-10-30 11:46:24

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CF1R-PRF-01E  
(Page 11 of 12)

Project Name: Residential Building Calculation Date/Time: 2023-10-30 11:46:01-07:00  
 Calculation Description: Title 24 Analysis Input File Name: 1 Bedrm Plan -Plan 4b CZ 5.rbd22x

**HVAC - HEAT PUMPS**

01	02	03	04	05	06	07	08	09	10	11	12	13
Name	System Type	Number of Units	Heating Efficiency Type	HSPF/HS PF2/COP	Cap 47	Cap 17	Cooling Efficiency Type	SEER/SE ERZ	EER/EEER 2/CEER	Zonally Controlled	Compressor Type	HERS Verification
Heat Pump System 1	VCHP-ductless	2	HSPF2	8	6000	5400	EER/SEER2	16	12.4	Not Zonal	Multi-speed	Heat Pump System 1-hers-htpump

**HVAC HEAT PUMPS - HERS VERIFICATION**

01	02	03	04	05	06	07	08	09
Name	Verified Airflow	Airflow Target	Verified EER/EEER2	Verified SEER/SEER2	Verified Refrigerant Charge	Verified HSPF/HSPF2	Verified Heating Cap 47	Verified Heating Cap 17
Heat Pump System 1-hers-htpump	Not Required	0	Required	Required	Yes	Yes	Yes	Yes

**VARIABLE CAPACITY HEAT PUMP COMPLIANCE OPTION - HERS VERIFICATION**

01	02	03	04	05	06	07	08	09	10
Name	Certified Low-Static VCHP System	Airflow to Habitable Rooms	Ductless Units in Conditioned Space	Wall Mount Thermostat	Air Filter Sizing & Pressure Drop Rating	Low Leakage Ducts in Conditioned Space	Minimum Airflow per RA3.3 and SC3.3.3.4.1	Certified non-continuous Fan	Indoor Fan not Running Continuously
Heat Pump System 1	Not required	Required	Required	Required	Not required	Not required	Not required	Not required	Not required

**INDOOR AIR QUALITY (IAQ) FANS**

01	02	03	04	05	06	07	08	09
Dwelling Unit	Airflow (CFM)	Fan Efficacy (W/CFM)	IAQ Fan Type	Includes Heat/Energy Recovery?	IAQ Recovery Effectiveness - SRE/ASRE	Includes Fault Indicator Display?	HERS Verification	Status
Sfam IAQVentRgt	27	0.35	Exhaust	No	n/s / n/a	No	Yes	

Registration Number: Registration Date/Time: HERS Provider: **CZ-5-11**  
 CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000  
Schema Version: rev 20220901 Report Generated: 2023-10-30 11:46:24

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CF1R-PRF-01E  
(Page 10 of 12)

Project Name: Residential Building Calculation Date/Time: 2023-10-30 11:46:01-07:00  
 Calculation Description: Title 24 Analysis Input File Name: 1 Bedrm Plan -Plan 4b CZ 5.rbd22x

**WATER HEATERS - NEEA HEAT PUMP**

01	02	03	04	05	06	07	08
Name	# of Units	Tank Vol. (gal)	NEEA Heat Pump Brand	NEEA Heat Pump Model	Tank Location	Duct Inlet Air Source	Duct Outlet Air Source
DHW Heater 1	1	40	Generic	Tier3Generic40	TankZone	Zone 1	Zone 1

**WATER HEATING - COMPACT DISTRIBUTION**

01	02	03	04	05	06	07
Dwelling Unit type	Water Heating System Name	Master Bath distance of furthest fixture to Water Heater (ft)	Kitchen distance of furthest fixture to Water Heater (ft)	Furthest Third furthest fixture to Water Heater (ft)	Compactness Factor	HERS Verification
Dwelling	DHW Sys 1	n/a	n/a	n/a	0.7	n/a

**WATER HEATING - HERS VERIFICATION**

01	02	03	04	05	06	07
Name	Pipe Insulation	Parallel Piping	Compact Distribution	Compact Distribution Type	Recirculation Control	Shower Drain Water Heat Recovery
DHW Sys 1 - 1/1	Not Required	Not Required	Not Required	Basic	Not Required	Not Required

**SPACE CONDITIONING SYSTEMS**

01	02	03	04	05	06	07	08	09
Name	System Type	Heating Unit Name	Heating Equipment Count	Cooling Unit Name	Cooling Equipment Count	Fan Name	Distribution Name	Required Thermostat Type
HVAC System1	Heat pump heating cooling	Heat Pump System 1	2	Heat Pump System 1	2	n/a	n/a	Setback

Registration Number: Registration Date/Time: HERS Provider: **CZ-5-10**  
 CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000  
Schema Version: rev 20220901 Report Generated: 2023-10-30 11:46:24



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

FOR USE IN THE COUNTY OF SAN LUIS OBISPO

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA

ENERGY COMPLIANCE - PLAN 4B

Table 03: GreenPoint Rated New Home Single Family Checklist Version 8.0. Includes sections G2 (Water-Efficient Fixtures), H (Heating, Ventilation, and Air Conditioning), I (Renewable Energy), J (Building Performance and Testing), and K (Indoor Air Quality).

Table 02: GreenPoint Rated New Home Single Family Checklist Version 8.0. Includes sections C13 (Reduced Light Pollution), C14 (Large Stature Trees), C15 (Third Party Landscape Program Certification), C16 (Maintenance Contract with Certified Professional), D1 (Optimal Vents Engineering), D2 (Non-Lead Bearing Door and Window Headers Sealed for Load), D3 (Construction Material Efficiencies), D4 (Engineered Lumber), D5 (FSC-Certified Wood), D6 (Solid Wall Systems), D7 (Energy Heels on Roof Trusses), D8 (Overhangs and Gutters), D9 (Reduced Pollution Entering the Home from the Garage), D10 (Structural Pest and Rot Controls), D11 (All Wood Located At Least 12 Inches Above the Soil), D12 (Wood Framing Treated With Borates or Factory-impregnated, or Wall Materials Other Than Wood), and D13 (Moisture-Resistant Materials in Wet Areas).

Table 01: GreenPoint Rated New Home Single Family Checklist Version 8.0. Includes sections A (Site), B (Foundation), C (Landscape), and D (Flooring). Also includes a summary table at the bottom of the page.

Table 05: GreenPoint Rated New Home Single Family Checklist Version 8.0. Includes sections L (Community), M (Appliances and Lighting), and N (Flooring). Also includes a summary table at the bottom of the page.

Table 04: GreenPoint Rated New Home Single Family Checklist Version 8.0. Includes sections O (Community), P (Appliances and Lighting), and Q (Flooring). Also includes a summary table at the bottom of the page.

Table 04: GreenPoint Rated New Home Single Family Checklist Version 8.0. Includes sections R (Community), S (Appliances and Lighting), and T (Flooring). Also includes a summary table at the bottom of the page.



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
ENERGY COMPLIANCE - PLAN 4