

DANA RESERVE

SPECIFIC PLAN | AUGUST 2025
PUBLIC REVIEW DRAFT



This Page Intentionally Blank.

Table of Contents

CHAPTERS

1	Introduction	1-1
2	Land Use and Development Standards	2-1
3	Conservation, Open Space, and Recreation	3-1
4	Circulation	4-1
5	Infrastructure and Phasing	5-1
6	Public Services	6-1
7	Implementation and Administration	7-1
8	Financing	8-1

APPENDICES

A	Objective Design Standards and Design Guidelines	A-1
B	Phasing and Public Improvements Implementation Matrix	B-1
C	Mitigation Monitoring and Reporting Program	C-1

This Page Intentionally Blank.

Exhibits and Tables

List of Exhibits

<i>Exhibit 1-1: Regional Location</i>	1-1
<i>Exhibit 1-2: Community Location</i>	1-2
<i>Exhibit 1-3: Aerial Photograph of the Dana Reserve Property</i>	1-3
<i>Exhibit 1-4: View from U.S. Highway 101 Looking Southwest</i>	1-4
<i>Exhibit 1-5: Relationship of DRSP to Other Adopted County Documents</i>	1-9
<i>Exhibit 2-1a: Land Use Map</i>	2-4
<i>Exhibit 2-1b: Land Use Map Legend</i>	2-5
<i>Exhibit 2-2a: Concept Master Plan</i>	2-6
<i>Exhibit 2-2b: Concept Master Plan Legends</i>	2-7
<i>Exhibit 2-3: Residential Single-Family Concept</i>	2-10
<i>Exhibit 2-4: DR-SF1 Development Standards</i>	2-13
<i>Exhibit 2-5: DR-SF2 Development Standards</i>	2-13
<i>Exhibit 2-6: Northern DRSP Property Line Edge Condition at Neighborhoods 5, 6, and 9</i>	2-17
<i>Exhibit 2-7: Southern DRSP Property Line Edge Condition at Neighborhood 3</i>	2-17
<i>Exhibit 2-8: Southern DRSP Property Line Edge Condition at Neighborhood 7</i>	2-17
<i>Exhibit 2-9: Western DRSP Property Line Edge Condition at Neighborhood 8</i>	2-18
<i>Exhibit 2-10: Western DRSP Property Line Edge Condition at Neighborhood 9</i>	2-18
<i>Exhibit 2-11: Village Commercial Neighborhood Barn Concept</i>	2-22
<i>Exhibit 2-12: Village Commercial Site Plan Concept</i>	2-22
<i>Exhibit 2-13: Neighborhood Park Concept</i>	2-29
<i>Exhibit 3-1: Open Space and Recreation Map</i>	3-2
<i>Exhibit 3-2: Biological Mitigation Site</i>	3-5
<i>Exhibit 3-3: Neighborhood Park Site Plan Concept</i>	3-8
<i>Exhibit 3-4: Neighborhood Park Birds-Eye</i>	3-8
<i>Exhibit 3-5: Pocket Park Concept</i>	3-9
<i>Exhibit 3-6: Equestrian Trail Concept</i>	3-10

<i>Exhibit 4-1: Primary Public Roadways.....</i>	<i>4-3</i>
<i>Exhibit 4-2: Local Roadways.....</i>	<i>4-4</i>
<i>Exhibit 4-3: Collector ‘A’ and ‘B’ Typical.....</i>	<i>4-6</i>
<i>Exhibit 4-4: Collector ‘A’ Adjacent to Village Commercial.....</i>	<i>4-7</i>
<i>Exhibit 4-5: Collector ‘A’ and ‘B’ at Left Turn Lane.....</i>	<i>4-8</i>
<i>Exhibit 4-6: Entries and Roundabouts.....</i>	<i>4-9</i>
<i>Exhibit 4-7: Park and Ride Concept.....</i>	<i>4-10</i>
<i>Exhibit 4-8: Park and Ride: Collector ‘A’.....</i>	<i>4-11</i>
<i>Exhibit 4-9: Collector ‘C’.....</i>	<i>4-12</i>
<i>Exhibit 4-10: Transit Stop at Collector.....</i>	<i>4-14</i>
<i>Exhibit 4-11: Local Road ‘D’.....</i>	<i>4-15</i>
<i>Exhibit 4-12: Single-Family Street, Typical.....</i>	<i>4-16</i>
<i>Exhibit 4-13: Single-Family Street, Alternative.....</i>	<i>4-17</i>
<i>Exhibit 4-14: Motorcourt – Private.....</i>	<i>4-18</i>
<i>Exhibit 4-15: Bicycle Network.....</i>	<i>4-22</i>
<i>Exhibit 4-16: Trails Map.....</i>	<i>4-24</i>
<i>Exhibit 4-17: Equestrian Trails Standards (County of San Luis Obispo – Parks and Recreation Element, Appendix B).....</i>	<i>4-25</i>
<i>Exhibit 4-18: Equestrian Trailhead Concept.....</i>	<i>4-26</i>
<i>Exhibit 4-19: Equestrian Trail Crossing.....</i>	<i>4-26</i>
<i>Exhibit 4-20: Pedestrian Trail Standards (County of San Luis Obispo – Parks and Recreation Element, Appendix B).....</i>	<i>4-28</i>
<i>Exhibit 5-1: Proposed Water Backbone Infrastructure.....</i>	<i>5-3</i>
<i>Exhibit 5-2: Recycled Water Infrastructure.....</i>	<i>5-4</i>
<i>Exhibit 5-3: Proposed Sewer Backbone Infrastructure.....</i>	<i>5-7</i>
<i>Exhibit 5-4: Existing Drainage Watershed Areas.....</i>	<i>5-9</i>
<i>Exhibit 5-5: Proposed Drainage Conditions.....</i>	<i>5-12</i>
<i>Exhibit 5-6: Proposed Conceptual Phasing.....</i>	<i>5-16</i>

List of Tables

<i>Table 2.1: Land Use Summary.....</i>	<i>2-3</i>
<i>Table 2.2: Residential Single-Family Development Standards.....</i>	<i>2-12</i>
<i>Table 2.3: Residential Multi-Family Development Standards.....</i>	<i>2-14</i>
<i>Table 2.4: Accessory Dwelling Unit Development Standards.....</i>	<i>2-16</i>
<i>Table 2.5: Residential Use Table</i>	<i>2-16</i>
<i>Table 2.6: Residential Fencing Standards</i>	<i>2-19</i>
<i>Table 2.7: Commercial Development Standards.....</i>	<i>2-24</i>
<i>Table 2.8: Commercial Use Table.....</i>	<i>2-26</i>
<i>Table 2.9: Commercial Fencing Standards.....</i>	<i>2-27</i>
<i>Table 2.10: Recreation and Open Space Development Standards.....</i>	<i>2-30</i>
<i>Table 2.11: Recreation and Open Space Use Table.....</i>	<i>2-31</i>
<i>Table 2.12: Recreation and Open Space Fencing Standards.....</i>	<i>2-31</i>
<i>Table 3.1: Recreation and Open Space Land Use Summary</i>	<i>3-1</i>
<i>Table 3.2: Required Parkland.....</i>	<i>3-7</i>
<i>Table 5.1: DRSP Water Use Factor and Demand</i>	<i>5-2</i>
<i>Table 5.2: DRSP Wastewater Generation</i>	<i>5-7</i>
<i>Table 6.1: Existing LMUSD School Capacity</i>	<i>6-1</i>
<i>Table 6.2: Student Generation by DRSP.....</i>	<i>6-2</i>
<i>Table 6.3: Anticipated Student Generation Rate by DRSP Phasing.....</i>	<i>6-2</i>

This Page Intentionally Blank.

1 Introduction

1.1 Scope and Legal Authority for the Specific Plan

Under California Law (Governmental Code Section 65450-65457) a specific plan is a planning tool that allows a county/community to articulate a vision for a defined area and apply guidelines and regulations to implement that vision.


The Dana Reserve Specific Plan (DRSP) provides a vision and guides development of “The Dana Reserve” (project) by defining land uses and development standards, circulation, parks and trails, and infrastructure for the future residential, commercial, and open space uses. The DRSP also provides a phasing/implementation plan and public facility financing options to accommodate this future development.

1.2 Location and Setting

The DRSP is located in the southern portion of San Luis Obispo County, California (see Exhibit 1-1). This property is located within the Urban Reserve Line of the Nipomo community. It is bounded by Willow Road and Cherokee Place to the north, existing residential large lots and ranchettes to the south and west, and U.S. Highway 101 to the east (see Exhibit 1-2). The property is less than a mile north of the Tefft Street corridor, a primary commercial corridor servicing the community, and is within 1,500 feet of the prominent Nipomo Regional Park from the property’s southwest corner.

Exhibit 1-1: Regional Location





The DRSP is located within the Nipomo Urban Reserve Line (URL) and is located in the Nipomo Community Services District (NCSD) Boundary Service area, for water and wastewater services. As part of the DRSP, these properties were brought into the URL and the NCSD service area through the County and Local Agency Formation Commission (LAFCO) processes.

1.3 Planning Area Character

1.3.1 Historic Setting

The community of Nipomo has a rich history in agriculture and a strong connection to the Dana Family and Dana Adobe. The Dana Reserve property was once part of the Dana Rancho Nipomo and was owned by the Cañada family beginning in 1912. The property has mainly been used for seasonal grazing for the last 100 years. There are no structures or other improvements on the site. No formal roads exist on the property, although informal unpaved ranch roads traverse portions of the property.

1.3.2 Cultural Setting

The project has been designed to protect and avoid identified cultural resources, as further discussed in Chapter 3.

1.3.3 Natural Setting

The property has three primary natural features. These include open grasslands in level areas, oak savannahs on gently rolling hills and oak woodlands and forest along several steeper slopes, and small clusters of native plants. Each of these features will be incorporated into the design of the project or mitigated off-site. There are no creeks, wetlands, or riparian habitats present on the property. The soil types are Class III and IV non-prime.

Exhibit 1-3: Aerial Photograph of the Dana Reserve Property (as of 2018)



1.3.4 Existing Setting

Portions of the DRSP property can be viewed from U.S. Highway 101, as shown below. The property also borders Pomeroy Road at the southwest, Hetrick Avenue to the west, and Cherokee Place to the north.

Exhibit 1-4: View from U.S. Highway 101 Looking Southwest (Source: Google Earth 2018)



1.4 Specific Plan Vision and Goals

1.4.1 Vision

The DRSP is a master-planned neighborhood that is envisioned to capture the essence of the central coast lifestyle – where living and working locally, celebrating family, and recreating are combined.

The DRSP will provide extensions of existing public roadway networks through the property in order to enhance access to Willow Road and the broader community roadway network.

Overall design and building architecture of the DRSP is intended to reflect the rural history of the property, while a diversity of housing types have been included to create new opportunities for home ownership or apartments.

To generate new employment opportunities and provide access to day-to-day goods and services, a village commercial center and flex commercial area have been included. These provide opportunities for businesses, a hotel, small daycare center, and an educational campus for life-long learning and job training.

By integrating a network of walking, bicycling, and equestrian facilities within the DRSP area, both the existing community as well as future residents will find new avenues for embracing a healthy lifestyle.



Architecture connects to the area history, while providing indoor/outdoor community spaces.



A variety of residential home types/sizes creates expanded opportunities for home ownership and apartments.



Pedestrian and bicycle lanes connect residents to parks and open space areas.

1.4.2 *Specific Plan Goals and Objectives*

The following goals and objectives have guided the design, layout, and configuration of the DRSP:

Goal 1: Provide a mix of land uses that offers a range of amenities accessible to residents and community members.

Goal 2: Respect Old Town Nipomo, the small, neighborhood-oriented village commercial area has been designed to complement, rather than compete with, Old Town Nipomo.

Goal 3: Provide a neighborhood park and pocket parks and open space areas within each residential neighborhood, linking the neighborhoods together through a network of trails and open spaces.

Goal 4: Incorporate the rural history of the community through architectural design, as guided by Appendix A – Objective Design Standards and Design Guidelines.

Goal 5: Provide a diversity of housing types and opportunities for home ownership and rental, including affordable homes consistent with the goals and policies of the Housing Element of the General Plan and regional housing needs.

Goal 6: Create new employment and job training opportunities for the community and the broader south San Luis Obispo County area.

Goal 7: Enhance circulation within the Specific Plan area and existing community by continuing the existing public roadway network through the DRSP property to connect to Willow Road, providing a new Park and Ride lot to encourage carpooling, and creating new public transportation points of connection to facilitate public transit use and reduce single-occupant automobile use.

Goal 8: Integrate a network of walking, bicycling, and equestrian facilities to connect on-site residential neighborhoods and the broader community.

Goal 9: Maintain the large, centrally located oak forest area as a site feature and minimize impacts to special-status plants and animals on-site.

Goal 10: Meet the State law requirements for energy efficiencies, State law and Nipomo Community Services District (NCSD) policies and ordinances relating to water conservation, and County Building Code requirements for energy efficiencies and water savings.

Goal 11: Reduce uncertainty in planning for and securing the orderly development of the Specific Plan area.

Goal 12: Provide effective and efficient development of public facilities, infrastructure, and services appropriate for the Specific Plan area.

Goal 13: Meet or exceed the requirements of the NCSD District Code and Annexation Policy to ensure that the DRSP funds or constructs the water and wastewater infrastructure necessary to serve the project without adverse impacts on the NCSD's ability to serve existing and future users.

1.5 Specific Plan Format

The DRSP is under the County of San Luis Obispo (County) jurisdiction. The property is designated as an expansion area under the South County Area Plan (SCAP) Section 4.5 and 4.8 as well as the San Luis Obispo County Code – Title 22, Land Use Ordinance (LUO) Section 22.98.072. As required by the General Plan, a specific plan was adopted for this site and the URL of the Community of Nipomo was adjusted to include the DRSP.

The DRSP provides a guide for future private and public development in conformance with the requirements set forth in California Government Code §65450 through §65457. The DRSP provides a bridge between the County’s General Plan and detailed plans such as development plans and subdivisions. It directs all facets of future development within the DRSP area and includes the following chapters and appendices:

- *Chapter 1 – Project introduction and background;*
- *Chapter 2 – Designation of land uses and development standards;*
- *Chapter 3 – Overview of open space, recreation, and conservation;*
- *Chapter 4 – Designation of circulation elements;*
- *Chapter 5 – Location and sizing of infrastructure;*
- *Chapter 6 – Ensuring adequate public facilities;*
- *Chapter 7 – Options for development and financing methods for public improvements;*
- *Chapter 8 – Financing Public Infrastructure;*
- *Appendix A – Objective Design Standards and Design Guidelines;*
- *Appendix B – Phasing and Public Improvements Implementation Matrix; and*
- *Appendix C - Mitigation Monitoring and Reporting Program.*

1.6 General Plan and Land Use Ordinance Guidance for Cañada Ranch

The SCAP description and policies applicable to the Cañada Ranch (now known as Dana Reserve) were adopted in 1994, almost 30 years ago. At the time, the objectives of the SCAP were aimed at job creation opportunities as well as addressing the jobs housing balance in Nipomo. Although the SCAP described the broad objective for job creation, it did not identify specific requirements for the type, size, or scale of these expected uses. The SCAP also indicates that housing should be provided on the Cañada Ranch site, again without identifying the type, size, or scale of the residential development.

Since the adoption of the SCAP, much has changed in the State and in the County. A period of significant economic expansion (housing bubble) and the “great recession” (the housing crash) occurred. As of the writing of this document and into the foreseeable future, California faces significant challenges in providing housing for the State’s population. Prices and rents for existing housing have increased dramatically and are continuing to increase. For the first time in many years, the State has begun to intervene in local housing policies. During 2018-2022, over 15 housing bills

were passed by the State that set standards, incentives, and enforceable requirements for local agencies to meet their housing goals. During the time of preparation and review of the DRSP, California, the nation, and the world experienced a pandemic caused by the COVID-19 virus that has further exacerbated housing challenges.

1.7 Goals and Consistency with the General Plan

The DRSP is located in the County of San Luis Obispo's jurisdiction and is therefore under the jurisdiction and governance of the County's General Plan. The General Plan sets policy direction for allowable land uses for both public and private lands and acts to provide applicable review bodies appropriate guidance and direction for making future land use decisions. There are seven required general plan elements, which include: Land Use, Circulation, Open Space, Conservation, Noise, Housing, and Safety. In addition to these required elements, the County of San Luis Obispo has also adopted five optional elements, which include Agriculture, Offshore Energy, Economic, Master Water and Sewer Plan, and Parks and Recreation. These elements are implemented through County of San Luis Obispo adopted area plans, community plans, and specific plans as well as other codified ordinances.

The DRSP has been designed to meet the goals and objectives established in the County's General Plan by providing a framework for future development of the property. The DRSP is consistent with, and serves as an extension of, the County's General Plan. The policies and standards in the DRSP will take precedence over more general policies and standards during the review of private and public development projects within the DRSP area. In situations where policies or standards relating to an aspect of development have not been provided in the DRSP, the existing policies and standards of the County's General Plan and LUO will apply. Refer to Chapter 7 – Implementation and Administration for more information.

1.8 Land Use and Circulation Elements

The Land Use and Circulation Elements (LUCE) is the over-arching guidance document for the County and addresses the County's land use pattern and circulation system. The LUCE consists of 1) Framework for Planning, 2) South County Area Plan, 3) Community Plan, and 4) Official Maps. It identifies the layout and intensity of land uses, including housing, commercial, industrial, open space, education, public facilities, and other categories of both public and private uses. The LUCE also establishes a balanced circulation network that includes both existing and proposed road network system improvements.

1.8.1.a. Framework for Planning (Inland)

The Framework for Planning (Inland) contains policies and procedures that apply to the unincorporated area outside of the coastal zone, defining how the LUCE is used together with the Land Use Ordinance and other adopted plans. It also explains the criteria used in applying land use categories and combining designations to the land, and the operation of the Resource Management System.


1.8.1.b. South County Area Plan (SCAP)

The South County Area Plan is encompassed within the Land Use and Circulation Elements (LUCE) of the County General Plan. This plan sets land use strategies to balance housing types, economic growth, conserve resources, and integrate a well-balanced land use pattern throughout South County area, including the Nipomo Mesa.

1.8.1.c. Nipomo Community Plan

The Nipomo Community Plan (Community Plan) sets a vision for the future of the community and the proposed land uses and circulation/infrastructure improvements at the community level. The Community Plan is also part of the LUCE of the County General Plan and is intended to be consistent with and implemented by other County plans, policies, and programs.

Exhibit 1-5: Relationship of DRSP to Other Adopted County Documents



1.9 Implementing Ordinances/Plans

Existing implementing ordinances and plans of the County include the Land Use Ordinance, Real Property Division Ordinance, Growth Management Ordinance, Address and Road Name Ordinance, Building and Construction Ordinance, Public Facilities Fee Ordinance, Specific Plans, Design Plans, and Capital Improvement Plans.

The DRSP is the implementing plan for the Dana Reserve property. While there may be instances where a portion(s) of the County's existing ordinances and plans apply to future development in the DRSP, the DRSP will take precedence. Where the DRSP is silent on a topic or matter, the relevant County ordinance or plan will prevail.

1.9.1.a Land Use Ordinance – Inland (Title 22)

The Land Use Ordinance – Inland (Title 22) provides standards for land use regulations and site-specific development that guide and regulate the size, shape, and type of use for development within the non-coastal areas of the County. The DRSP customizes some of the standards and regulations found within Title 22 to implement the DRSP vision. The DRSP document will take precedence and where the DRSP is silent on a topic or matter, the Land Use Ordinance – Inland requirements will prevail.

1.9.1.b Real Property Division Ordinance (Title 21)

The Real Property Division Ordinance (RPDO) regulates division of land in the County to promote the orderly development of real property. Applicant requirements pursuant to the Subdivision Map Act are enacted in this title. Subdivision activity within the DRSP area will be consistent with the relevant RPDO requirements, unless otherwise specified herein.

1.9.1.c San Luis Obispo County Design Guidelines

The San Luis Obispo County Design Guidelines document consists of design objectives, guidelines, and examples that are intended to help retain and enhance the unique character of the unincorporated communities and rural areas of San Luis Obispo County. Since the DRSP will provide its own design direction to inform the design and planning of future development, the County's Design Guidelines document will not be applied in the review of development projects within the DRSP area. Applicants should refer to Appendix A – Objective Design Standards and Design Guidelines for DRSP specific design direction.

1.9.1.d San Luis Obispo County Bikeways Plan

The San Luis Obispo County Bikeways Plan (Bikeways Plan) prioritizes bikeway facilities in the unincorporated areas of the County. It recognizes a variety of facilities, including bicycle lanes, routes, parking, connections with public transportation, educational programs, and funding. The DRSP has taken guidance found in the Bikeways Plan and expanded it to provide an interconnected bikeway system within the DRSP that connects to existing bicycle facilities adjacent to the project area. Since the DRSP provides its own standards to implement and enhance the Bikeways Plan, the Bikeways Plan will not be applied in the review of development projects within the DRSP area.

2 Land Use and Development Standards

2.1 Introduction

This Chapter contains the land use goals, policies, development standards, and allowable uses applicable to the DRSP. In general, the DRSP consists of both single-family and multi-family residential land uses as well as commercial land uses planned near the project's frontage adjacent to U.S. Highway 101. More specifically, individual commercial land uses include a village center, flex commercial, neighborhood barn, hotel, as well as an educational/training campus. A component of the DRSP includes areas reserved for a daycare center, public recreation, pocket parks, trails, and open space.

Public Benefits Associated with Adoption of the Specific Plan

As part of the DRSP, a variety of public benefits will be included. Examples include a day care center, satellite junior college campus for Cuesta College, and affordable housing consistent with the County's General Plan Housing Element, as described further within this Chapter.

2.2 Land Use Categories

The Land Use Element of the County's General Plan defines and identifies the purpose and character for each of the County's 14 land use categories. These land use categories, which serve as both the County's Land Use Element and zoning maps, comprise the County's "single map" system for land use and development. To implement the DRSP, the subject property will be redesignated from the Residential Rural land use category to a 15th County land use category called "DRSP." The DRSP land use category will direct future landowners and developers to this Specific Plan for allowable land uses, development standards, and permitting requirements.

The DRSP contains its own land use categories separate from the County's 14 land use categories. These categories determine the intended future use of each parcel of land within the DRSP. They describe allowable uses and development standards. The proposed land uses are separated into three primary categories, which include Residential, Commercial, and Recreation and Open Space.

The DRSP includes the following land use categories:

Residential Land Uses

- *Residential Single-Family-1 (DR-SF1)*
- *Residential Single-Family-2 (DR-SF2)*
- *Residential Multi-Family (DR-MF)*

Commercial Land Uses

- *Village Commercial (DR-VC)*
- *Flex Commercial (DR-FC)*

Recreation and Open Space Land Uses

- *Recreation (DR-REC)*
- *Open Space (DR-OS)*

As part of the DRSP, no change of the existing Residential Rural land use categories are proposed for APN's 091-301-031 and 091-301-029 and they are included within the DRSP only for the purposes of providing access and infrastructure, open space, and potential location for public safety facilities as described herein.

Table 2.1 includes an overview of all proposed land uses and the associated numeric information within the DRSP area. This table lists the proposed land uses and is correlated with the Land Use Map (Exhibit 2-1a/b) and Concept Master Plan Map (Exhibit 2-2a/b).



Table 2.1: Land Use Summary

<i>Land Use</i>	<i>Acres</i>	<i>Density Range</i>	<i>Potential Units</i>	<i>Potential Square Feet²</i>
RESIDENTIAL				
Residential Single-Family-1 (DR-SF1)	128.1 ¹	4-7 du/ac	695	
Residential Single-Family-2 (DR-SF2)	16.2 ¹	7-13 du/ac	124	
Residential Multi-Family (DR-MF)	22.2 ¹	14-26 du/ac	423	
Recreation (DR-REC) • Neighborhood Park (4.8 ac) • Equestrian Staging (1 ac) • Daycare (0.5 ac)	6.3 ⁵			
Pocket Parks ³	-			
Primary Roads	22			
Residential Rural (RR) – Existing ⁶	10			
<i>SUBTOTAL</i>	<i>204.84</i>		<i>1,242</i>	
COMMERCIAL AND NON-RESIDENTIAL				
Village and Flex Commercial Visitor Serving / Hotel Education	22.3 ¹			113k sf 60k sf 30k sf
Internal Neighborhood Roads ³	-			
Park and Ride ⁴	-			
<i>SUBTOTAL</i>	<i>22.3</i>			<i>203k sf</i>
OPEN SPACE/RECREATION				
Open Space (DR-OS) ○ Open Space ○ Trails ○ Basins	60.86 ⁵			
<i>SUBTOTAL</i>	<i>60.86</i>			
<i>TOTAL</i>	<i>288.0</i>		<i>1,242</i>	<i>110-203k sf</i>
<i>Notes:</i> ¹ All acreage and potential units can be adjusted up to 10% to address site specific constraints and more suitable site design, subject to County review. ² k indicates thousand. ³ Internal Neighborhood Roads and Pocket Park acreage located within Residential Single-Family land use acreage calculation. ⁴ Park and Ride acreage located within public Collector Roads. ⁵ Minimum Requirement. ⁶ Includes approximately 2-acre fire station and a potential 1-acre public safety facility.				

Exhibit 2-1a: Land Use Map



Exhibit 2-1b: Land Use Map Legend

COLOR	LAND USE	ACRES	%
	RESIDENTIAL MULTI-FAMILY (DR-MF)	22.2	7.7%
	RESIDENTIAL SINGLE FAMILY- TRADITIONAL (DR-SF1)	128.1	44.5%
	RESIDENTIAL SINGLE FAMILY (DR-SF2)	16.2	5.7%
	RECREATION (DR-REC)	6.34	2.2%
	PRIMARY ROADS	22	7.6%
	RURAL RESIDENTIAL (RR) - EXISTING	10	3.5%
	RESIDENTIAL SUBTOTAL:	204.84	71.2%
	FLEX COMMERCIAL (DR-FC)	17.9	6.2%
	VILLAGE COMMERCIAL (DR-VC)	4.4	1.5%
	COMMERCIAL SUBTOTAL:	22.3	7.7%
	OPEN SPACE (DR-OS)	60.86	21.1%
	TOTAL:	288	100%

GROSS TOTAL ACREAGE OF SITE = 288 ACRES

*** ALL STATISTICS ARE APPROXIMATE**

Exhibit 2-2a: Concept Master Plan



Exhibit 2-2b: Concept Master Plan Legends

GROSS ACREAGE SUMMARY:		
UNDEVELOPED SITE ACRES*=	70.86 ACRES=	24.6%
DEVELOPED SITE ACRES=	217.14 ACRES=	75.4%
GROSS ACREAGE OF SITE = 288 ACRES		

UNDEVELOPED SITE COMPRISE OF 60.86 AC OF OPEN SPACE (OS) & 10 AC OF RESIDENTIAL RURAL (RR)

NET DEVELOPED AREAS		% OF NET SITE
HOUSING DEVELOPMENT=	166.5 ACRES =	76.68%
PARKS/RECREATION=	6.34 ACRES =	2.92%
PUBLIC COLLECTORS=	22.0 ACRES =	10.13%
COMMERCIAL=	22.3 ACRES =	10.27%
DEVELOPED ACREAGE OF SITE = 217.14 ACRES		

MAP FEATURES

-  Primary Entry Feature
-  Secondary Entry Feature
-  8' deep Storm water Basin
-  Shallow 2 foot deep Storm Water Basin
-  Lots Requiring Single Story Architecture
-  Traffic Signal Controlled Intersection
-  Bus Pullout / Transit Stop Locations
-  Equestrian Trail Head
-  Equestrian Trail (3.3 miles)
-  Pedestrian Trail (3.8 miles)

HOUSING DEVELOPMENT NEIGHBORHOOD TOTALS ON GROSS SITE

LAND USE TOTALS

NBD	PRODUCT TYPE	LAND USE	LAND USE ACRES	% OF GROSS SITE	UNIT COUNT
1	MULTI-FAMILY	DR-MF	8.7	3.0%	193
2	MULTI-FAMILY	DR-MF	10.5	3.7%	152
3	3,300-4,499 SF LOT	DR-SF2	16.2	5.7%	124
4	4,000-10,000 SF LOT	DR-SF1	11.4	4.0%	72
5	4,000-10,000 SF LOT	DR-SF1	16.9	5.9%	104
6	4,000-10,000 SF LOT	DR-SF1	18.6	6.5%	114
7	4,000-10,000 SF LOT	DR-SF1	27.5	9.5%	149
8	4,000-10,000 SF LOT	DR-SF1	16.8	5.8%	62
9	4,000-10,000 SF LOT	DR-SF1	36.9	12.8%	194
SUBTOTAL:			163.5	56.9%	1,164
10	AFFORDABLE	DR-MF	3.0	1.0%	78 MIN
AFFORDABLE SUBTOTAL:		DR-MF	3.0	1.0%	78 MIN
N/A	INTERNAL NEIGHBORHOOD ROADS ¹	-	-	-	-
N/A	POCKET PARKS (PARK) ¹	-	-	-	-
N/A	RECREATION	DR-REC	6.34	2.2%	-
N/A	PRIMARY ROADS	-	22	7.6%	-
N/A	PARK AND RIDE ²	-	-	-	-
N/A	RESIDENTIAL RURAL ³	RR	10	3.5%	-
TOTAL:			204.84	71.2%	1,242

* All land use, % of gross site, and unit counts shown above are approximate.

¹ Internal Neighborhood Roads and Pocket Park acreage accounted for under Residential Neighborhood totals.

² Park and Ride acreage accounted for under public Collector Roads.

³ Residential Rural is an existing land use and only included for the purposes of access and infrastructure.

COMMERCIAL TOTALS ON GROSS SITE

LAND USE TOTALS

	LAND USE	LAND USE ACRES	% OF GROSS SITE
FLEX COMMERCIAL	DR-FC	17.9	6.2%
VILLAGE COMMERCIAL	DR-VC	4.4	1.5%
TOTAL:		22.3	7.7%

OPEN SPACE ON GROSS SITE

LAND USE TOTALS

	LAND USE	LAND USE ACRES	% OF GROSS SITE
OPEN SPACE	DR-OS	60.86	21.1%
TOTAL:		60.86	21.1%

* All land use, % of gross site, and unit counts shown above are approximate.

2.3 Residential Land Uses

2.3.1. *Residential Land Use Descriptions*

The DRSP contains a variety of residential land uses with varying density ranges. These include Residential Single-Family 1, Residential Single-Family 2, and Residential Multi-Family, as further described below.

Residential Single-Family 1 (DR-SF1)

Purpose

- a. To provide for single-family homes on lots ranging from 4,000 sf to 10,000 sf that may be detached or attached and one- or two-stories.
- b. To allow accessory uses that complement single-family neighborhoods.
- c. To discourage incompatible non-residential uses in single-family neighborhoods.

Character

- a. Areas with single-family dwellings at gross densities from four to seven dwelling units per acre.
- b. Areas having appropriate level of services and located within an urban reserve line.

Residential Single-Family 2 (DR-SF2)

Purpose

- a. To provide for single-family homes on lots ranging from 3,300 sf to 4,499 sf that may be detached or attached and one- or two-stories.
- b. To allow accessory uses that complement single-family neighborhoods.
- c. To discourage incompatible non-residential uses in single-family neighborhoods.

Character

- a. Areas with single-family dwellings at gross densities from seven to thirteen dwelling units per acre.
- b. Areas having appropriate level of services and located within an urban reserve line.

Residential Multi-Family (DR-MF)

Purpose

- a. To provide areas for residential multi-family development with a wide range of housing types that may be detached or attached and one-, two-, or three-stories.
- b. To locate higher residential densities in close proximity to commercial areas and community services and facilities.
- c. To relate allowed densities to adequate outdoor space supportive of private recreational activity.

Character

- a. Areas with multiple-family dwellings at gross densities from fourteen to twenty-six dwelling units per acre.
- b. Areas having appropriate level of services and located within an urban reserve line.
- c. Areas close to neighborhood commercial, where infrastructure, circulation, and neighborhood facilities can accommodate multi-family residential development.

Exhibit 2-3: Residential Single-Family Concept



2.3.2. *Residential Land Use Goals, Objectives, and Policies*

The following overarching DRSP goals and objectives are brought forward from Chapter 1 of this document and associated policies are provided to guide the range and density of residential development envisioned within the DRSP area.

Goal 1

Provide a mix of land uses that offers a range of amenities accessible to residents and community members.

Residential Policy 1.a

A variety of single-family and multi-family residential land uses shall be provided in varying configurations and densities.

Residential Policy 1.b

Single-family land uses shall be located within the DRSP area to transition from existing, surrounding Residential Suburban land uses.

Goal 4

Incorporate the rural history of the community through architectural design, as guided by Appendix A – Objective Design Standards and Design Guidelines.

Residential Policy 4.a

Each residential neighborhood within the DRSP area should provide a unique aesthetic and design – including signage, consistent with the overarching vision for the DRSP area.

Residential Policy 4.b

While no specific architectural style is dictated herein, residential architecture character should be reflective of the rural history of the community, as outlined in Appendix A – Objective Design Standards and Design Guidelines.

Goal 5

Provide a diversity of housing types and opportunities for home ownership and rental, including affordable homes consistent with goals and policies of the Housing Element of the General Plan and regional housing needs.

Residential Policy 5.a

A variety of for sale single-family and for sale/rental multi-family housing types shall be provided within the DRSP area to appeal to a broad range of customers.

Residential Policy 5.b

Affordable housing shall be constructed within the DRSP area to provide housing to meet the needs of area employees.

Residential Policy 5.c

Multi-family homes should have private open space features, such as balconies or patios, and have access to common outdoor areas on-site.

Residential Policy 5.d

All common outdoor areas (pocket parks, trails, and open space) within individual residential neighborhoods shall be privately maintained.

Goal 10

Meet the State law requirements for energy efficiencies, State law and Nipomo Community Services District (NCSD) policies and ordinances relating to water conservation, and County Building Code requirements for energy efficiencies and water savings.

Residential Policy 10.a

All residential development within the DRSP area shall meet the Building Code requirements for energy efficiencies and water savings at the time of development.

2.3.3. Residential Development Standards

Residential development standards ensure consistency with the overarching DRSP vision while guiding the implementation and review of housing development project proposals by the County.

Customized land use categories are provided to implement the land uses identified in Chapter 2. Land use categories included herein supersede the County's Land Use Ordinance (Title 22) except

where the DRSP is silent. In such cases, existing County land use category standards, including specific use standards in Article 4, shall apply.

The development standards for Residential Single-Family and Residential Multi-Family are provided in Table 2.2 and Table 2.3 and are categorized based on land use type and density. It is assumed that these standards will be supplemented by additional covenants, conditions, and restrictions (CC&Rs), which will also be consistent with the DRSP. To guide potential development of Accessory Dwelling Units within the DRSP, Table 2.4 has been provided to outline relevant development standards.

Applicants should refer to Appendix A for applicable design direction for residential site planning, architecture, and landscaping.

Table 2.2: Residential Single-Family Development Standards

	<i>DR-SF1</i>	<i>DR-SF2</i>
<i>Minimum Setbacks</i>		
<i>Front</i>	15 ft; 10 ft if ADU provided	10 ft
<i>Side</i>	5 ft	0 - 5 ft
<i>Street</i>	10 ft	10 ft
<i>Rear</i>	10 ft	5 ft
<i>Garage</i>	20 ft from back of sidewalk	5 ft from Motorcourt
<i>Maximum Porch Encroachment</i>		
	6 ft	N/A
<i>Maximum Lot Coverage¹</i>		
	NBD 4-7 = 55% NBD 8-9 = 60%	65%
<i>Maximum Height²</i>		
	30 ft, 2-stories; refer to Special Height Restrictions for NBDs 7, 8, and 9 below	35 ft, 2- stories; refer to Special Height Restrictions for NBD 3 below
<i>Special Height Restrictions</i>		
<i>Neighborhoods 3, 7, 8, and 9 (Refer to Exhibit 2.2a for location)</i>	Lots directly adjacent to Hetrick Ave. and Sandydale Dr. are limited to 22 ft, 1-story in height.	Lots adjacent to the southern property line are limited to 22 ft, 1-story in height - two lots deep in Neighborhood 3.
<i>Lot Size Ranges³</i>		
	4,000 sf - 10,000 sf	3,300 sf - 4,499 sf

	DR-SF1	DR-SF2
Pocket Park Space ^{3,4}		
NBD 3		0.6 - 1.0 ac
NBD 4	0.5 - 0.9 ac	
NBD 5	1.0 - 1.5 ac	
NBD 6	0.7 - 1.0 ac	
NBD 7	1.9 - 2.5 ac	
NBD 8	0.5 - 1.1 ac	
NBD 9	1.5 - 2.0 ac	
Pocket Park Total	6.7 – 10 ac	
Minimum Private Open Space		
	200 sf rear yard w/ 12 ft min. depth	200 sf side and/or rear yard w/ 10 ft min. depth
Parking		
	2 enclosed off-street parking spaces per home	2 enclosed off-street parking spaces per home; plus 1 guest space per 5 homes
Notes:		
¹ Accessory Dwelling Units are allowable and do not count towards lot coverage.		
² A building may exceed the height indicated if it has a pitched roof with a slope greater than 2.5/ 12, and the additional height above the maximum allowed is used to achieve this pitched roof.		
³ Sizes shown are approximate and may vary.		
⁴ In addition to pocket park space, one private amenity space of approximately 3 acres in size may be located in Neighborhoods 7, 8, or 9 for use by residents of these neighborhoods.		




Exhibit 2-4: DR-SF1 Standards




Exhibit 2-5: DR-SF2 Standards

Table 2.3: Residential Multi-Family Development Standards

	DR-MF
Minimum Setbacks	
Front	10 ft
Side	5 ft
Street	10 ft
Rear	10 ft
Garage/Carport	20 ft from back of sidewalk
Minimum Building Separation	
Principal Building	10 ft
Between Facing Garages	28 ft
Porch Encroachment	
	3 ft
Allowable Density	
	14-26 du/ac ^{1,2}
Maximum Lot Coverage⁵	
	70% (net)
Maximum Height³	
	45 ft, 3-stories ⁴
Minimum Lot Size	
	600 sf ⁶
Minimum Common Open Space	
	30% net site area
Minimum Private Open Space	
	80 sf per home (may include patios, decks, balconies, or porches)
Parking	
	1 sp./studio or 1 bdrm.; 1.5 sp./2-bdrm.; 2.0 sp./3+ bdrm. 1 guest sp. per 5 homes.
Notes: ¹ Allowable dwellings for DR-MF land use based on units per gross acre. ² Excludes density bonuses ³ A building may exceed the height indicated if it has a pitched roof with a slope greater than 2.5/12, and the additional height above the maximum allowed is used to achieve this pitched roof. ⁴ 36-ft to the top of plate, 45-ft to the roof. ⁵ Accessory Dwelling Units are allowable and do not count towards lot coverage. ⁶ Not applicable to PUDs, Condos, or Townhomes.	

Table 2.4: Accessory Dwelling Unit Development Standards

	<i>Attached</i>	<i>Detached</i>
<i>Minimum Setbacks</i>		
<i>Front</i>	Shall comply with the requirements applicable to the attached single-family dwelling.	n/a
<i>Side</i>	Per state law.	
<i>Rear</i>	Per state law.	
<i>Maximum Size</i>	Per state law.	
<i>Maximum Height</i>	Per state law.	
<i>Parking</i>		
	Per state law.	

2.3.4. *Residential Allowable Uses*

Table 2.5 below outlines the allowable land uses and permit requirements for the Residential Single-Family and Multi-Family land uses within the DRSP area. Table 2.5 supersedes the permitting requirements in Article 2 and Article 4 of the Land Use Ordinance (LUO), except as otherwise provided herein. The land uses in the DRSP may be subject to LUO standards, including specific use standards, when this chapter is silent on a standard or requirement. For example, a detached garage will continue to be subject to a 1,000 square-foot size limitation as provided in LUO Section 22.30.410 because the DRSP does not allow for a larger detached garage. An applicant for a use within the DRSP may request to waive or modify an LUO standard through a MUP or CUP when there are procedures to do so in the LUO. In which case, the MUP or CUP requirement would supersede the permit level in Table 2.5. The Director has the authority to refer a Zoning Clearance or Site Plan to the Planning Commission if questions arise regarding the applicability of a policy, standard, or mitigation measure to a proposed land use or development within the DRSP.

As indicated in the table, primary uses are those that are a primary use within the residential land use category, while secondary uses are those that are subordinate to or in support of a primary use.

To review applicable permit types and processes referenced in Table 2.5, refer to Chapter 7 – Implementation and Administration.

Table 2.5: Residential Use Table

	<i>DR-SF1</i>	<i>DR-SF2</i>	<i>DR-MF</i>
<i>Primary Uses</i>			
Single-Family Dwellings (Neighborhoods 3, 4, 5, and 6)	ZC	ZC	N
Single-Family Dwellings (Neighborhoods 7, 8, and 9)	CUP	N	N
Multi-Family Dwellings (Neighborhoods 1, 2, and 10)	N	N	SP
<i>Secondary Uses</i>			
Accessory Dwelling Unit (Secondary Dwelling) ¹	ZC	ZC	ZC
Child DayCare – Family Day Care Homes (less than 12 children)	SP	SP	SP
Child DayCare – Family Day Care Homes (12 or more children)	MUP	MUP	MUP
Community Center/Clubhouse/Pool	SP	SP	SP
Community Garden	SP	SP	SP
Home Occupation ²	ZC	ZC	ZC
Pocket Park	ZC	ZC	ZC
Residential Accessory Uses ³	SP	SP	SP
Residential Care Home, 6 or Fewer Boarders	ZC	ZC	ZC
Residential Care Home, 7 or More Boarders	N	N	MUP
<i>Notes:</i> ZC: Zoning Clearance SP: Site Plan Review MUP: Minor Use Permit CUP: Conditional Use Permit N: Not Permitted Uses listed above consistent with County use definitions, where applicable. ¹ Governed by applicable State law and County LUO Section 22.30.470 ² Home Occupation uses are home business that meet the County's home occupation requirements in LUO Section 22.30.230 (e.g., no more than one customer at a time, no signage, etc.) ³ Residential Accessory Uses include garages, sheds, workshops, guesthouses, studio, etc. These uses are subject to the standards in LUO Section 22.30.410.			


2.3.5. *Edge Condition Development Standards*

With the property being located in between existing residential development to the north, south, and west, layout of the DRSP has been conducted to allow for additional buffering of these existing residential areas, as described further below. It should be noted that the referenced building to building setbacks shown below are minimums when considering existing building locations on properties adjacent to the DRSP.

Northern DRSP Property Line

For Neighborhoods 5, 6, and 9, edge conditions along the northern property line will result in a minimum separation between buildings of 97 feet (Exhibit 2-6). Beginning in Neighborhood 5 and 6 on the DRSP property, this includes a minimum 10-foot rear yard setback, 30-foot equestrian trail, 25-foot Cherokee Place, and a minimum 30-foot rear yard setback for the existing Residential Rural lots north of Cherokee Place.


Exhibit 2-6: Northern DRSP Property Line Edge Condition at Neighborhoods 5, 6, and 9



Southern DRSP Property Line


For Neighborhood 3, edge conditions along the southern property line will result in a minimum separation between buildings of 85 feet (Exhibit 2-7). Beginning in Neighborhood 3 on the DRSP property, this includes a minimum 5-foot rear yard setback, 50-foot equestrian trail, and a minimum 30-foot rear yard setback for the existing Residential Suburban lots fronting onto Sandydale Drive. Homes in Neighborhood 3 immediately adjacent to the southern DRSP property line, two lots deep, will be one-story.

Exhibit 2-7: Southern DRSP Property Line Edge Condition at Neighborhood 3



For Neighborhood 7, edge conditions along the southern property line will result in a minimum separation between buildings of 72 feet (Exhibit 2-8). Beginning in Neighborhood 7 on the DRSP property, this includes a minimum 10-foot rear yard setback, 30-foot equestrian trail, and a minimum 30-foot rear yard setback for the existing Residential Suburban lots fronting onto Sandydale Drive. Homes in Neighborhood 7 immediately adjacent to the southern DRSP property line will be one-story.


Exhibit 2-8: Southern DRSP Property Line Edge Condition at Neighborhood 7



Western DRSP Property Line


For Neighborhood 8, edge conditions along the western property line will result in a minimum separation between buildings of 102 feet (Exhibit 2-9). Beginning in Neighborhood 8 on the DRSP property, this includes a minimum 10-foot rear yard setback, 60-foot Hetrick Avenue right-of-way, and a minimum 30-foot side/rear yard setback for the existing Residential Suburban lots fronting onto Pomeroy Road or Calimex Place. Homes in Neighborhood 8 immediately adjacent to the western DRSP property line will be one-story.

Exhibit 2-9: Western DRSP Property Line Edge Condition at Neighborhood 8



For Neighborhood 9, edge conditions along the western property line will result in a minimum separation between buildings of 230 feet (Exhibit 2-10). Beginning in Neighborhood 9 on the DRSP property, this includes a minimum 10-foot rear yard setback, 130-foot open space with equestrian trail, 60-foot Hetrick Avenue right-of-way, and a minimum 30-foot rear yard setback for the existing Residential Suburban lots siding onto Hetrick Avenue. Homes in Neighborhood 9 immediately adjacent to the western DRSP property line will be one-story.

Exhibit 2-10: Western DRSP Property Line Edge Condition at Neighborhood 9



2.3.6. *Architectural Design Guidance*

As noted above, no specific architectural style is required for the DRSP. However, in order to implement the vision and character of the DRSP outlined in Chapter 1, objective design standards and design guidelines have been provided in Appendix A that will guide the design of future projects as they are submitted. Applicants should refer to Appendix A for applicable design direction for residential site planning, architecture, and landscaping.

2.3.7. *Residential Fencing Standards*

Table 2.6: Residential Fencing Standards below outline fencing standards which apply to all residentially designated land uses within the DRSP. This includes fencing standards related to location, height, type and materials, as well as prohibited styles. In general, the intent of the residential fencing standards is to allow for individual properties to take advantage of adjacencies

to park and open spaces on-site while providing privacy for future homeowners. All fences to be provided by the developer and maintained by the Homeowners Association. Refer to Appendix A – Objective Design Standards and Design Guidelines for recommended locations for residential fencing.

Table 2.6: Residential Fencing Standards

<i>Location</i>
A. Fencing is permitted along the front, side, and rear property lines. Fencing within the required street setback area is prohibited. B. Property line fencing at the side or street yards connecting to the primary residence shall be setback a minimum of 5-feet from the primary street facing facade.
<i>Height</i>
A. Front – Forty-Two (42) inches maximum. B. Side and Rear Yard – Six (6) feet minimum/maximum.

2.3.8. *Affordable Housing*

As discussed below, the County’s Housing Element (2020-2028) outlines the goals, objectives, policies, and implementation programs to provide for a variety of housing types at various affordability levels across the County. It is the goal of the DRSP to provide for a diversity of housing types and opportunities for home ownership and apartments, with priority given to those who live and work in southern San Luis Obispo County. For more specific housing related policies, refer to Section 2.3.2 above.

General Plan Housing Element

The County’s current Housing Element (2020-2028) is intended to facilitate the provision of needed housing in the context of the General Plan Land Use Element and related ordinance. It is also intended to meet the requirements of State law. It contains a number of relevant goals, objectives, policies, and implementation programs to ensure the County meets its goals of meeting the housing needs while remaining consistent with State law.

The overall goal of the County Housing Element is to:

“Achieve an adequate supply of safe and decent housing that is affordable to all residents of the unincorporated county.”

Relevant primary objectives and associated policies include:

“Objective HE 1.00 – Facilitate the development and preservation of housing units that are diverse in type, size, and ownership level to meet the needs of residents of varying lifestyles and income levels.”

Policy HE 1.01 - Support and prioritize new residential development in areas identified for strategic regional residential development and other areas that are (a) located along priority transportation corridors (i.e. highways identified by San Luis Obispo Council of Governments as priorities for regional infrastructure investments), (b) located in or between areas with higher concentration of jobs and services, and (c) located within or in close proximity to existing urbanized areas or communities. This includes, but is not limited to, supporting and prioritizing the following in such areas:

- *improvements to infrastructure and facilities;*
- *reductions in infrastructure constraints for the development of housing to the extent possible; and*
- *increases in the supply of land for residential uses.*

Policy HE 1.02 - Prioritize proximity to jobs, services, schools, parks, and transportation systems when designating land for housing.

Policy HE 1.04 - Encourage proposed residential developments to provide safe and attractive living environments through incorporation of high-quality architectural design, materials, site planning, and site amenities.

To ensure the County meets this objective and associated policies during the current Housing Element term and to position the County to meet future, longer-term housing needs, the following implementation program is identified:

“Program C: Designation of additional land for residential uses.”

Specific Plan Application

The DRSP will implement the goals and policies of the County Housing Element by donating improved land to a local non-profit to allow for construction of deed-restricted affordable units on-site. As shown on Exhibit 2-2a, Neighborhood 10 has been appropriately sized and located to accommodate these 78 affordable units.

Local Preference Program

Following recordation of the Final Map, Neighborhood 10 will be donated to the Lucia Mar School District, which will enter into a ground lease with People’s Self-Help Housing, for development of the 78 affordable units, evenly split between very low- and low-income units. The affordable units will be available to qualifying households in the following order of preference: first to employees of the Lucia Mar School District, second to other local municipal employees, and third to other local qualifying households identified by People’s Self-Help Housing. As part of the DRSP, a local preference program for housing will be included. The local preference program will give priority to individuals who live or work in the Lucia Mar Unified School District boundaries.

2.4 Commercial Land Uses

2.4.1 Commercial Land Uses

The DRSP contains a variety of commercial land uses with varying density ranges. These include Village Commercial and Flex Commercial, as further described below.

Village Commercial (DR-VC)

Purpose

- a. To provide convenient locations for retail commercial and service establishments to meet daily shopping needs of residents and visitors.
- b. To provide opportunities for community gathering and meeting spaces.

Character

- a. Focused areas where small-scale neighborhood commercial, services, and community uses can be allowed to provide day-to-day shopping needs for adjacent residential neighborhoods.
- b. Locations adjacent to residential areas along Collector or Arterial streets which will reduce the number of shipping trips for daily needs and encourage walking or bicycling.
- c. Areas having appropriate level of services and located within an urban reserve line.

Flex Commercial (DR-FC)

Purpose

- a. To provide areas for commercial, office, and light manufacturing to support local job generating businesses.
- b. To provide limited areas for highway traveler services and uses associated with tourists and vacationers within urban areas on Collectors.
- c. To provide areas for development of public facilities and/or educational facilities to meet the public needs.

Character

- a. Areas characterized by commercial, service, and small-scale industrial uses.
- b. Areas where uses serve both occasional needs and day-to-day needs.
- c. Areas that serve resident, transient, and tourist needs.
- d. Areas that satisfy the specialized site location requirements of public agencies and/or educational facilities, where facilities will be visible and accessible to their users.
- e. Areas having appropriate level of services and located within an urban reserve line.

Exhibit 2-11: Village Commercial Neighborhood Barn Concept



Exhibit 2-12: Village Commercial Site Plan Concept



2.4.2 *Commercial Land Use Goals, Objectives, and Policies*

The following overarching DRSP goals and objectives brought forward from Chapter 1 of this document and associated policies are provided to guide the range of commercial development envisioned within the DRSP area.

Goal 1

Provide a mix of land uses that offers a range of amenities accessible to residents and community members.

Commercial Policy 1.a

A range of commercial, office, hospitality, and education space shall be provided within the commercial areas of the DRSP to provide flexibility of future uses.

Commercial Policy 1.b

Outdoor seating and pedestrian amenities should be provided in conjunction with commercial land uses for residents, visitors, and employees.

Goal 2

Respect Old Town Nipomo, the small, neighborhood-oriented village commercial area has been designed to be limited in size, rather than compete with, Old Town Nipomo.

Commercial Policy 2.a

The Village Commercial Center shall include a variety of neighborhood serving uses that accommodate the day-to-day needs of the neighborhood. This may include a neighborhood barn, an event venue to accommodate neighborhood or community events.

Goal 4

Incorporate the rural history of the community through architectural design, as guided by Appendix A – Objective Design Standards and Design Guidelines.

Commercial Policy 4.a

While no specific architectural style is dictated, commercial or residential architecture character should be reflective of the rural history of the community, as outlined in Appendix A – Objective Design Standards and Design Guidelines

Goal 6

Create new employment and job training opportunities for the community and the broader south San Luis Obispo County area.

Commercial Policy 6.a

The Flex and Village Commercial land use categories shall provide a variety of tenant space configurations to accommodate a range of business types and sizes for new employment opportunities and through a donation will also include an educational campus to provide ongoing job training and life-long learning opportunities. High speed fiber optic will also be provided for work from home opportunities.

Goal 10

Meet the State law requirements for energy efficiencies, State law and Nipomo Community Services District (NCSD) policies and ordinances relating to water conversation, and County Building Code requirements for energy efficiencies and water savings.

Commercial Policy 10.a

All commercial development within the DRSP shall meet the minimum Building Code requirements for energy efficiencies and water savings.

2.4.3 Commercial Development Standards

Commercial development standards apply to the Village Commercial (DR-VC) and Flex Commercial (DR-FC) land uses within the DRSP and are intended to ensure consistency with the DRSP vision while guiding the implementation and review of individual development proposals by the County.

Customized land use categories are provided to implement the land uses identified in Chapter 2. Land use categories included herein supersede the County's Land Use Ordinance (Title 22) except where the DRSP is silent. In such cases, the existing County land use category standards shall apply.

The commercial development standards for Village Commercial and Flex Commercial land uses are provided in Table 2.7 below.

Applicants should refer to Appendix A for applicable design direction for commercial site planning, architecture, and landscaping.

Table 2.7: Commercial Development Standards

	<i>DR-VC</i>	<i>DR-FC</i>
Minimum Building Setbacks		
<i>Front</i>	0-ft	10-ft
<i>Interior Side</i>	0-ft	0-ft
<i>Street</i>	0-ft	10-ft
<i>Rear</i>	Per Building Code requirements, except 10' when adj. to a Res. use.	20-ft
Minimum Lot Size		
	No minimum	0.5 ac
Maximum Lot Coverage		
	100%	70%
Maximum Floor Area Ratio		
	1.5; 2.5 for lodging or school uses	1.5; 2.5 for lodging or school uses
Maximum Height		
	35-ft, 2-stories; 50-ft, 4-stories for lodging or schools uses	35-ft, 2-stories; 50-ft, 4-stories for lodging or school uses

	DR-VC	DR-FC
<i>Minimum Private/Common Area Landscaping</i>		
	5% of parking area	10%
<i>Landscape Buffer</i>		
	-	20-ft along Highway 101 ³
<i>Minimum Parking Requirements</i> ^{1, 2}		
	<i>Restaurants & Bars –</i> 1/200 sf <i>Commercial/Retail -</i> 1 sp/250 sf <i>Lodging -</i> 1 sp/room + 5% of total spaces <i>Schools (Colleges/University)</i> – 1 sp/3.4 students <i>Child Day Care Centers –</i> 1 sp/1 staff member plus 1 sp for each 5 children <i>Office –</i> 1/300 sf <i>Medical Office –</i> 1/200 sf <i>Residential –</i> as required by Table 2.3: Residential Multi-Family Development Standards	<i>Restaurant & Bars –</i> 1/200 sf <i>Commercial/Retail -</i> 1 sp/250 sf <i>Commercial Service –</i> 1 sp/250 sf <i>Schools (Pre-Schools to Secondary) –</i> 1 sp/staff member plus 1 space per 5 children <i>Schools (Colleges/University)</i> – 1 sp/3.4 students <i>Lodging -</i> 1 sp/room + 5% of total spaces <i>Small Scale Manufacturing –</i> 1 sp/500 <i>Office –</i> 1/300 sf <i>Medical Office –</i> 1/200 sf <i>Residential –</i> as required by Table 2.3: Residential Multi-Family Development Standards
<i>Notes:</i> ¹ Where two or more nonresidential uses are located on a single property, the number of parking spaces may be reduced at a rate of 5% for each nonresidential use, up to a maximum of 20%. ² Minimum parking requirements shall be calculated based on the net floor area in both Village and Flex Commercial areas of useable space within a building. However, parking requirement calculations shall not include storage areas or mechanical space. ³ In addition to landscaping, vehicular circulation and fencing may be located within the westerly 10 feet of the landscape buffer development standard requirements.		

2.4.4 Commercial Allowable Uses

Table 2.8 below outlines the allowable land uses for the Village Commercial and Flex Commercial/Light Industrial land uses within the DRSP area. Table 2.8 supersedes the permitting requirements in Article 2 and Article 4 of the LUO, except as otherwise provided herein. The land uses in the DRSP may be subject to LUO standards, including specific use standards, when this chapter is silent on a standard or requirement. An applicant for a use within the DRSP may request to waive or modify an LUO standard through a MUP or CUP when there are procedures to do so in the LUO. In which case, the MUP or CUP requirement would supersede the permit level in Table 2.8. The Director has the authority to refer a Zoning Clearance or Site Plan to the Planning Commission if questions arise regarding the applicability of a policy, standard, or mitigation measure to a proposed land use or development within the DRSP.

To review applicable permit types and processes referenced in Table 2.8, refer to Chapter 7 – Implementation and Administration. Other uses not listed below may be approved by the Director that are consistent with the intent of the DRSP and will not result in increased impacts through a MUP.

Table 2.8: Commercial Use Table²

	<i>DR-VC</i>	<i>DR-FC</i>
Alternative Fueling Stations	ZC	ZC
Animal Hospitals and Veterinary Medical Facilities	N	CUP
Automobile, Mobile Home & Vehicular Dealers and Supplies	N	N
Automobile Service Stations & Gas Stations	N	N
Building Materials and Hardware	N	CUP
Child Day Care Centers	ZC	ZC
Drive-In and Drive-Thru Services	N	CUP
Food and Beverage Products	N	CUP
Furniture & Fixture Products, Cabinet Shops	N	CUP
General Retail	CUP	CUP
Health Care Services	CUP	CUP
Indoor Amusement and Recreation - Health/Fitness Club	CUP	CUP
Heavy Manufacturing	N	N
Lodging – Hotels & Motels, 40 or more units	CUP	CUP
Grocery – Neighborhood Market (<10,000 sf)	CUP	CUP
Grocery – Neighborhood Market (<50,000 sf)	N	CUP
Personal Services	CUP	CUP
Public Assembly and Entertainment Facilities	CUP	CUP
Offices	CUP	CUP
Residential ¹	CUP	CUP
Restaurant and Bars (including breweries, wine tasting, and distilleries)	CUP	CUP
Schools – Specialized Education and Training	CUP	CUP

	<i>DR-VC</i>	<i>DR-FC</i>
Schools – College and University	CUP	CUP
Schools – Preschool to Secondary	CUP	CUP
Small Scale Manufacturing	N	CUP
Warehousing	N	N
Notes: ZC: Zoning Clearance SP: Site Plan MUP: Minor Use Permit CUP: Conditional Use Permit N: Not Permitted Uses listed above consistent with County use definitions, where applicable. ¹ Governed by applicable State law and relevant portions of the County Land Use Ordinance. ² New tenants in existing buildings shall be subject to the requirements of LUO Section 22.08.030, Table 2-3 (5).		

2.4.5 Architectural Design Guidance

As noted above, no specific architectural style is required for the DRSP. However, in order to implement the vision and character of the DRSP outlined in Chapter 1, objective design standards and design guidelines have been provided in Appendix A that will guide the design of future projects as they are submitted. Applicants should refer to Appendix A for applicable design direction for commercial site planning, architecture, and landscaping.

2.4.6 Commercial Fencing Standards

Table 2.9: Commercial Fencing Standards below outlines the fencing standards which apply to all commercially designated land uses within the DRSP. This includes fencing standards related to location, height, type and materials, as well as prohibited styles. Refer to Appendix A – Objective Design Standards and Design Guidelines for recommended locations for commercial fencing.

Table 2.9: Commercial Fencing Standards

<i>Location</i>
A. Fencing is permitted along the side and rear yard property lines. Fencing within the front setback areas is prohibited. B. No fencing is required adjacent to U.S. Highway 101, other than required by Caltrans. C. No fencing is required adjacent to the Recreation or Open Space land use, unless otherwise specified.
<i>Height</i>
A. Side and Rear Yard – Six (6) feet minimum/maximum.

2.5 Recreation and Open Space Land Uses

2.5.1 *Recreation and Open Space Land Use Descriptions*

The DRSP contains a variety of recreation and open space land uses. These include Recreation (DR-REC) and Open Space (DR-OS), as further described below.

Recreation (DR-REC)

Purpose

- a. To identify areas having recreational potential where private or public development of recreational uses can be encouraged.
- b. To provide for private or public park, equestrian trailhead, and recreation areas to serve neighborhood and community residents and visitors.
- c. To allow for child day care centers to serve neighborhood and community residents.

Character

- a. Areas of existing or proposed recreational uses that emphasize and retain a recreational resource on a portion of a property.
- b. Areas with natural or man-made recreational resource that will serve particular private or public recreational needs.
- c. Areas adjacent to recreational uses that can accommodate a child day care center.

Open Space (DR-OS)

Purpose

- a. To identify lands having value as natural areas.
- b. To identify lands that are capable of supporting passive recreational activities.

Character

- a. Portions of a site with natural features such as unique topography or vegetation.
- b. Areas for passive, non-intensive recreational uses such as picnic areas and hiking trails.

Exhibit 2-13: Neighborhood Park Concept



2.5.2 *Recreation and Open Space Land Use Goals, Objectives, and Policies*

The following DRSP goals and objectives brought forward from Chapter 1 of this document and associated policies are provided to guide the recreation and open space land use categories envisioned within the DRSP area. For additional goals and policies related to Recreation and Open Space, refer to Chapter 3.

Goal 1

Provide a mix of land uses that offers a range of amenities accessible to residents and community members.

Recreation and Open Space Policy 1.a

Recreation and Open Space land uses shall be distributed throughout the DRSP area to provide access to both residents and the community.

Recreation and Open Space Policy 1.b

Recreation and Open Space land uses should be utilized to provide a buffer between the DRSP area and the surrounding neighborhoods to the extent practical.

Recreation and Open Space Policy 1.c

Open space land uses shall serve a variety of functions including but not limited to recreation, trails, stormwater management, and habitat conservation.

Recreation and Open Space Policy 1.d

Recreation land use shall, through a donation of an improved site, provide a child day care center to a non-profit organization to accommodate both residents and the community.

2.5.3 Recreation and Open Space Standards

Recreation and open space standards apply to the Recreation (REC) and Open Space (OS) land uses within DRSP. They are intended to ensure consistency with the DRSP vision while guiding the long-term implementation and review of individual proposals by the County.

Customized land use categories are provided to implement the land uses identified in Chapter 2. Land use categories included herein supersede the County's Land Use Ordinance (Title 22) except where the DRSP is silent. In such cases, the existing County land use category standards shall apply.

For additional standards related to Recreation and Open Space land uses, refer to Chapter 3.

Table 2.10: Recreation and Open Space Development Standards

	<i>DR-REC⁹</i>	<i>DR-OS</i>
<i>Minimum Parking Requirements</i>		
	<i>Daycare - 1 sp/1 staff member plus 1 sp for each 5 children</i>	-

2.5.4 Recreation and Open Space Allowable Uses

Table 2.11 below outlines the allowable land uses for the Recreation and Open Space land uses within the DRSP area. Table 2.11 supersedes the permitting requirements in Article 2 and Article 4 of the LUO, except as otherwise provided herein. The land uses in the DRSP may be subject to LUO standards, including specific use standards, when this chapter is silent on a standard or requirement. An applicant for a use within the DRSP may request to waive or modify an LUO standard through a MUP or CUP when there are procedures to do so in the LUO. In which case, the MUP or CUP requirement would supersede the permit level in Table 2.11. The Director has the authority to refer a Zoning Clearance or Site Plan to the Planning Commission if questions arise regarding the applicability of a policy, standard, or mitigation measure to a proposed land use or development within the DRSP.

Table 2.11: Recreation and Open Space Use Table

	<i>DR-REC</i>	<i>DR-OS</i>
<i>Primary Uses</i>		
Equestrian Facilities (trails and trailhead)	ZC	ZC
Neighborhood Park	SP	N
Outdoor Athletic Facilities	SP	N
Pedestrian Trails	ZC	ZC ¹
Parks and Playgrounds	SP	N
Child Day Care Centers	SP	N
<i>Secondary Uses</i>		
Mobile Homes	N	N
Public Utility Facilities (Basins, Pumphouses)	SP	SP
Outdoor Sports and Recreational Facilities - Private	SP	N
Outdoor Sports and Recreational Facilities - Public	SP	N
Storage – Accessory	MUP	MUP
Temporary Events ²	MUP	MUP
<i>Notes:</i> ZC: Zoning Clearance SP: Site Plan MUP: Minor Use Permit N: Not Permitted Per County use definitions, where applicable. ¹ Pedestrian trails in the Open Space Land Uses shall be unpaved. ² Temporary Events are subject to the Site Design Standard requirements outlined in Title 22, Section 22.30.610 of the County LUO.		

2.5.5 *Recreation and Open Space Fencing Standards*

Table 2.12: Recreation and Open Space Fencing Standards below outlines the fencing standards which apply to all recreation and open space designated land uses within the DRSP. This includes fencing standards related to location, height, type and materials, as well as prohibited styles. Refer to Appendix A – Objective Design Standards and Design Guidelines for recommended locations for recreation and open space fencing.

Table 2.12: Recreation and Open Space Fencing Standards

<i>Location</i>
A. Not required along streets or trails, unless an equestrian trail is located adjacent to a street, in which case a 4-foot high, split rail fence is required. B. Fencing within the front setback areas of child day care centers is prohibited, unless required by State law.
<i>Height</i>
A. Adjacent to Streets, Parks, and Open Space - Four (4) feet maximum. B. Adjacent to child day care centers – Six (6) feet minimum/maximum C. Adjacent to Detention Basin - Per County requirements.

This Page Intentionally Blank.

3 Conservation, Open Space, and Recreation

3.1 Introduction

This Chapter discusses the extent and location of open space, cultural resources, and recreational spaces within the Dana Reserve (DRSP) area. It also includes goals and policies for ensuring the long-term success and management of these resources and assets. The open space, trail network, and recreational amenities are envisioned as a cornerstone for the DRSP. These open space areas will provide moments to embrace tranquility and peacefulness, while recreation spaces will encourage exercise, exploration, play, and community engagement – part of the larger healthy community vision for the DRSP. Refer to Table 3.1 below for a summary of land use acreages of these areas within the DRSP and Exhibit 3-1 for their locations.

Table 3.1: Recreation and Open Space Land Use Summary

<i>Land Use</i>	<i>Acreage (ac)</i>	<i>% of Site (%)</i>
Open Space ○ Open Space ○ Trails ○ Basins	60.86	21.1
Recreation	6.34 ¹	2.2
Pocket Parks	6.7 - 10	2.3 - 3.5
<i>Totals</i>	<i>73.9 – 77.2</i>	<i>25.6 – 26.8</i>
¹ A maximum 0.5 acre site will be reserved for a child day care center and is located at the Neighborhood Park, which is in the Recreation land use category.		

Exhibit 3-1: Open Space and Recreation Map



3.2 Conservation and Open Space

The proposed DRSP Open Space includes a total of 60.86 acres (21.1%) of the total site. This land use category includes areas that remain undeveloped long-term, as well as areas that provide opportunities for passive uses. Examples of areas intended to remain undisturbed long-term include the central oak forest area, while passive open space areas will include pedestrian and equestrian trails as well as seating areas. County trail standards for pedestrian and equestrian trails are specified in Chapter 4: Circulation.

A Biological Report was conducted for the DRSP in 2020, with updates completed in 2021 through 2023 related to oak trees and Burton Mesa Chaparral. The report identified eight special status plant species located within the DRSP area. The data collected from these biological studies served as a general guide to the siting of land uses within the DRSP area in order to avoid or minimize impacts to these species.



Open space area concepts.

3.2.1 Biological

Coast Live Oaks

The DRSP contains coast live oak trees dispersed in different locations across the site. With the exception of three non-native trees, no other tree species are located on the property. While many of the coast live oaks are scattered in various configurations, most intact oak woodland (oak forest) is located centrally on the property with a denser tree coverage, canopy structure, and understory shrub cover than other areas of the site. Most of the oaks in savannah, chaparral, and managed oak woodland on the Dana Reserve resprouted from oaks harvested in the late 1800s to increase grazing area. The Dana family had 18,000 head of sheep in the area in the 1890s. The understory of multi-stemmed trees has been managed since the 1930s which are the earliest available photographs. The managed woodland has been grazed by horses and cattle in recent decades. Low tree branches and dead wood are removed to increase grass cover and reduce fire fuel.

The majority of the centrally located oak forest, not historically managed, is to be maintained as part of the DRSP. To maintain the integrity of this centrally located oak forest, development and the circulation network have been located to minimize impacts. Where development is to occur adjacent to areas where coast live oaks are to be maintained, County oak tree protection construction best practices will be implemented.

An Oak Woodland Management Plan, Tree Protection Plan, Off-Site Habitat Acquisition and Preservation Plan, and On- and Off-Site Habitat Mitigation and Monitoring Plan will be prepared. A combination of on-site mitigation plus off-site conservation will be used to offset the loss of coast live oaks. Planting locations will be selected adjacent to existing coast live oak areas to be maintained, within open spaces, recreation and park areas, or street trees within select areas. To the extent practical, on-site mitigation of coast live oak trees will be propagated from on-site acorns. Plantings shall not fulfill more than one-half of the mitigation requirements. Off-site mitigation for loss of oak woodland habitat will be provided by oak woodland habitat acquisition and conservation at a 2:1 ratio (two acres conserved for every acre of oak woodland habitat impacted). Refer to the Environmental Impact Report (EIR) for more details on oak tree mitigation measures.

Special Status Plant Species

As part of the 2020 Biological Report and subsequent 2021 through 2023 updates related to oaks and Burton Mesa Chaparral conducted for the DRSP effort, eight special status plant species were identified within the DRSP area. These include sand mesa manzanita (*Arctostaphylos rudis*), sand buck brush (*Ceanothus cuneatus* var. *fascicularis*), Michael's rein orchid (*Piperia michaelii*), mesa horkelia (*Horkelia cuneata*), California spineflower (*Mucronea californica*), Nipomo mesa ceanothus (*Ceanothus impressus* var. *nipomoensis*), and sand almond (*Prunus fasciculata* var. *punctata*).

The DRSP will avoid impacts to special status plant species to the extent practical. For those special status species that cannot be avoided, appropriate mitigation ratios will be required, as detailed in the EIR.

Listed Plant Species

During surveys and field observations on the property for the 2020 Biological Report, small patches of a state listed plant species, Pismo clarkia (*Clarkia speciosa* ssp. *immaculata*) were identified in portions of the centrally located oak forest area. Development, including roadways, have been situated on-site to avoid impacts to these areas, however a small impact to state-listed species may occur. A state Incidental Take Permit (ITP) will be obtained and mitigation implemented for impacts to this rare plant.

Biological Mitigation Area(s)

The DRSP proposes to preserve an off-site oak mitigation site within the Nipomo area. Located along the Temettate Ridge, the Dana Ridge site, will be placed into a conservation easement with a local non-profit to provide for the long-term management and maintenance of the site. Refer to Exhibit 3-2 for the location of the Dana Ridge Ranch site.

Appropriate on-site habitat will be preserved and/or restored to mitigate for impacts to rare species, as detailed in the EIR.

Exhibit 3-2: Biological Mitigation Site



3.2.2 Cultural

Cultural resources include historical, archaeological, and/or paleontological resources. An archaeological cultural resource site has been identified within the DRSP area. Site design and layout of the property has been designed to avoid impacting this location by integrating it within open space and avoiding excavation of the resource site.

Known archaeological resources shall be protected to the greatest extent practical. If additional archaeological resources are discovered during grading and construction activities the mitigation measures listed in the DRSP EIR and the County's Inland Land Use Ordinance shall be applied, which may include, but is not limited to fencing or other protective measures around identified cultural resources.

3.2.3 Conservation and Open Space Goals, Objectives, and Policies

The following DRSP goals and objectives brought forward from Chapter 1 of this document and associated policies are provided to guide the recreation and open space uses envisioned within the DRSP area.

Goal 9

Maintain the large, centrally located oak forest area as a site feature and minimize impacts to special-status plants and animals on-site.

Open Space Policy 9.a

Prepare an Oak Woodland Management Plan, On-Site Tree Protection Plan for Trees Retained, Off-Site Habitat Acquisition and Preservation Plan, and On- and Off-Site Habitat Mitigation and Monitoring Plan to mitigate loss of coast live oaks on-site, as detailed in the Environmental Impact Report (EIR).

Open Space Policy 9.b

For unmitigable impacts to special status plant species, the mitigation ratios identified in the Environmental Impact Report shall be followed. Where feasible, plant salvage and seed collection shall be conducted prior to habitat disturbance.

Open Space Policy 9.c

The open space areas shall be a separate lot or lots under the ownership of the Homeowners Association.

Open Space Policy 9.d

Ongoing maintenance of the oak forest shall be conducted consistent with the approved Oak Woodland Management Plan.

Open Space Policy 9.e

Interpretive signage may be installed at designated locations along the trail network and other open space areas to promote public awareness and education about oak woodlands and other special plant species within the DRSP area.



Example of interpretive signage identifying local habitats.

3.3 Recreation

A variety of recreational amenities are proposed within the DRSP area, including a neighborhood park, pocket parks, pedestrian trails, and equestrian trails. The County of San Luis Obispo requires the provision of a minimum of 3 acres of parkland per 1,000 residents for the County's unincorporated communities. See Table 3.2 below for detailed County Parkland requirement calculations.

Table 3.2: Required Parkland

	Single-Family (RSF)	Multi-Family (RMF)
Total Homes	819	423
County Multiplier	0.00741	0.00564
Acres Required	6.07	2.39
Total Parkland Required (acres)	8.4	
Note: Non-residential uses and ADUs are not required to provide public parkland per Chapter 21.09 of the County LUO.		

To address County parkland requirements, the DRSP includes a 5.3-acre, centrally located neighborhood park adjacent to the oak forest area and a 1-acre equestrian trailhead. An additional 6.7 - 10 acres of publicly accessible pocket parks are to be provided within the residential neighborhoods, for a total of 13.0 - 16.3 acres of parkland within the DRSP.

3.3.1 Recreation Amenities

Neighborhood Park

The County's Parks and Recreation Element states that parks and trails contribute to a high quality of life and make our communities more livable. The proposed 5.3-acre neighborhood park will be an amenity not only to the residents of the DRSP area, but also visitors and the community. This neighborhood park is envisioned to be more passive in character in order to maintain a greater

number of on-site oak trees and to better connect with the adjacent open space. Exhibits 3-3 and 3-4 demonstrate the conceptual character of the neighborhood park in the DRSP area.

Exhibit 3-3: Neighborhood Park Site Plan Concept



Exhibit 3-4: Neighborhood Park Birds-Eye



The following amenities are examples of what should be considered when developing the neighborhood park. This is not an exhaustive list and other complementary and/or similar amenities may also be included.

- Bicycle racks
- Drinking fountains
- Entry signage and landscaping
- Picnic areas
- Irrigation/Landscaping
- Parking
- Restroom
- Trail connections
- Trash and recycle bins
- Wayfinding signage

Pocket Park Areas

As a complement to recreation in the public park and trail system, pocket parks support and promote passive play, exercise, social gatherings, and family get-togethers for people of all ages and abilities. Pocket parks are accessible to residents and the public via the trails system.

These pocket park areas are specific to each neighborhood within the DRSP area and are integrated into the larger open space network. Positioning pocket parks along a system of connection trails enables users to enter the trail system and safely walk to each park within the DRSP.

Pocket parks will incorporate a variety of native plants that are appropriate to local climate and soil conditions. Native plants minimize irrigation and maintenance needs while providing areas for native pollinators, insects, and birds.

The DRSP pocket parks will be designed with multigenerational activities and needs as well as emphasize the physical and social inclusion of all ages and abilities. Playground equipment and other hardscape features may be designed to complement the character and landscape of the DRSP property. Exhibit 3-5 illustrates the pocket park character and scale.

Exhibit 3-5: Pocket Park Concept



Refer to Neighborhood Park amenities examples for features that may be included in Pocket Parks.

Equestrian Trailhead and Trails

The DRSP area will provide equestrian trailhead access at the property's perimeter, as well as through open space areas to create a trail network on the property. Approximately 3.3 miles of equestrian trails will be accessible to residents and the community. The equestrian trailhead will be integrated at the southeastern corner of the property, providing a staging area for a limited number of trailers to load/off-load horses for trail access. The equestrian trail network will be available to residents of the DRSP area as well as to visitors and the community, with connections at Willow Road, Pomeroy Road, Hetrick Avenue, and Cory Way. The equestrian trails will be owned by a Homeowners Association, with a local non-profit(s) assisting in the ongoing operations and maintenance of the trail system. For specific equestrian trail standards and trail head features, refer to Chapter 4. Exhibit 3-6 illustrates an equestrian trail concept.

Exhibit 3-6: Equestrian Trail Concept



Pedestrian Trail System

Trails are an integral component of the DRSP's open space and recreational infrastructure. Connecting residential areas with shopping, dining, recreation, and jobs is accomplished through a series of connecting pedestrian trails.

Consistent with the goals, objectives, and policies of the DRSP, the pedestrian trails are an alternative mode of transportation encouraging residents to access nearby services without using their automobile. Approximately 3.8 miles of off-street pedestrian trails will be accessible to residents and the community. Pedestrian trails provided in the DRSP area will be maintained by a Homeowners Association to ensure ongoing maintenance of the trail system. For specific pedestrian trail standards, refer to Chapter 4. The proposed pedestrian trail system configuration may change based on the ultimate configuration of each individual residential neighborhood. However, a point(s) of access from the overall pedestrian trail system into/from each residential neighborhood shall be maintained, as shown by neighborhood on Exhibit 2-2a.



Example of pedestrian trail.

3.3.2 Recreation Goals, Objectives, and Policies

The following goals and objectives brought forward from Chapter 1 of this document and associated policies are provided to guide the recreation and open space uses envisioned within the DRSP.

Goal 3

Provide a neighborhood park and pocket parks and open space areas within each residential neighborhood, linking the neighborhoods together through a network of trails and open spaces.

Recreation Policy 3.a

Provide a pocket park or common open space area within each residential neighborhood.

Recreation Policy 3.b

Incorporate a variety of native plants into pocket parks to support native pollinators, insects, and birds.

Recreation Policy 3.c

Connect parks and recreation spaces within the DRSP through a network of pedestrian trails and sidewalks, thereby encouraging non-motorized transit.

Goal 8

Integrate a network of walking, bicycling, and equestrian facilities to connect on-site residential neighborhoods and the broader community.

Recreation Policy 8.a

Ensure walking and bicycling facilities are included to provide connections from residential neighborhoods to on-site open space, parks, and commercial areas.

Recreation Policy 8.b

Provide sidewalk, pedestrian trails, and bicycle access points to public park and open space amenities within the DRSP area for the community.

Recreation Policy 8.c

Create an equestrian trailhead and trail system.

Recreation Policy 8.d

Integrate informational and directional signage within open space, trails, and pocket park, reflecting a cohesive theming and branding of DRSP.

Recreation Policy 8.e

Pedestrian and equestrian trail systems will be owned and maintained by a local non-profit or Homeowners Association. Neighborhood Park and pocket parks will be owned and maintained by a Homeowners Association.

3.4 Recreation

3.4.1 Homeowners Association

There will be a Homeowners Association(s) within the DRSP area. Refer to Chapter 8 for more information regarding Homeowners Association(s) within the DRSP.

3.4.2 Fire Protection/Vegetation Management

County Fire and CDF designate the existing DRSP area within the Moderate Fire Severity Zone as of 2022. As the DRSP is built-out over time, the level of fire severity is expected to be reduced and transition to one focused on structural defense. However, best practices in fire protection and vegetation management will be implemented within the overall DRSP site plan to ensure the safety of future residents per the 2021 Dana Reserve Fire Protection Plan and EIR. Fire protection and vegetation management within the DRSP will be consistent with CalFire/San Luis Obispo County requirements. Ongoing management will provide preemptive and preventative measures in preparing and planning for fire protection. Neighborhoods adjacent to the central oak forest area and anticipated to be subject to the fire protection and vegetation management requirements of CalFire/San Luis Obispo County include Neighborhoods 3, 7, 8, and 9.

Proposed irrigated landscaping on public and private properties adjacent to the central oak woodland area will help buffer residences. The establishment and maintenance of additional emergency vehicle access points, street names, directional signage, building identification, and fuel modification measures also establish and add to fire protection within the DRSP area. These measures and programs incorporated at the time of site design and implemented at time of construction and prior to occupation will positively influence the responsiveness and preparedness during emergencies. Updates to strategies, best practices, and/or County requirements will be conveyed to residents through the Homeowners Association.

Site-specific requirements for identified neighborhoods include but are not limited to the following:

- A minimum defensible space shall be maintained around all buildings on the site per Cal Fire/San Luis Obispo County Requirements.
- Defensible space areas containing brush shall be thinned and/or masticated in accordance with recognized methods to minimize ground level fuel loads and lessen the potential impact of fire.

- In accordance with current Cal Fire/San Luis Obispo County Requirements, within 30-feet of permanent structures, trim trees, including oaks, to a minimum clear height of 6 to 8 feet above the ground to avoid continuous ladder fuels.
- Grasses that are dead, dormant, or directed to be trimmed by County Fire Official, shall be maintained at a maximum of 4 inches to minimize light flash fuels with the intent of mitigating continuous fire spread.
- Landscaping shall be fire resistant and meet County standards for fire resistant planting.



Defensible space areas around structure requirements (Source: CDF).

This Page Intentionally Blank.

4 Circulation

4.1 Introduction

This chapter focuses on the street and other circulation systems within the Dana Reserve Specific Plan (DRSP). The goal is to provide an efficient and highly functional circulation network for pedestrians, bicycles, equestrians, automobiles, and public transit, consistent with the South County Inland Area Plan (SCAP) and Nipomo Community Plan policy direction. The overall framework for the street system design has been guided by the requirements of the County of San Luis Obispo Public Improvement Standards.

4.2 Street Network

The primary organizational element of the public street system within the DRSP area is focused on the primary roadways, or “backbone” roads, that connect to off-site roads within the vicinity or that act as a continuation of existing County maintained roads. These primary public roadways are identified as Collector ‘A,’ Collector ‘B,’ and Collector ‘C’ as described further below. In addition, other roadways within the DRSP area include those that are private and designated as Local Roads and Motorcourts, as described below. Regardless of which entity maintains the streets, a private Property/Homeowners Association will maintain non-standard roadway features and landscaping amenities on Collectors, Local Roads, and Motorcourts. See *Exhibits 4-1* and *4-2* for an overview of the circulation plan, including individual proposed roadway types and their location within the DRSP.

Collector ‘A’– North Frontage Road

Collector ‘A’ is designed as a County maintained public Collector Road that is located on the east side of the DRSP area. It is an extension of the existing North Frontage Road that currently terminates at the southeast corner of the DRSP area. This new road will complete a through connection from Tefft Street to Willow Road. At the intersection of Collector ‘A’ and Willow Road, there will be a traffic signal.

Collector ‘B’- Pomeroy to Willow Road

Collector ‘B’ is designed as a County maintained public Collector Road that is located on the west side of the DRSP area. It provides a direct connection through the DRSP area from Pomeroy Road to Willow Road. At the Pomeroy Road and Willow Road connections, there will be one-way stop intersections.

Collector ‘C’

Collector ‘C’ is designed as a County maintained public Collector Road that is located centrally within the DRSP area. It provides a direct east-west connection between the planned Collector ‘A’ and Collector ‘B.’ At the intersections with Collector ‘A’ and Collector ‘B,’ there will be roundabouts.

Local Roads - Residential

Local Roads - Residential include those located within or serving the individual residential neighborhoods of the DRSP area. These roadways vary in orientation and design and are intended to provide the connection from the residential neighborhood to the Collectors within the DRSP area. The County will not accept Local Roads into the County-maintained system. Therefore, a private mechanism for maintenance shall be established.

Private Motorcourts

Private Motorcourts are located within Neighborhood 3. These Private Motorcourts vary in orientation and are intended to provide access to adjacent Local Roads within the DRSP area. The County will not accept Private Motorcourts into the County-maintained system. Therefore, a private mechanism for maintenance shall be established.

Private Access Drive

A Private Access Drive is located to the west side of Collector B, near the intersection with Pomeroy Road. This access drive is intended to maintain access for the adjacent property owners located west of the Hetrick Avenue right-of-way to Collector B while also providing access to the storm water basin for maintenance. The Private Access Drive will be privately maintained.

Exhibit 4-1: Primary Public Roadways





Exhibit 4-2: Local Roadways



4.2.1 Circulation Goals and Policies

The following overarching DRSP goals brought forward from Chapter 1 of this document and associated policies are provided to guide the circulation pattern and development envisioned within the DRSP area.

Goal 7

Enhance the circulation within the Specific Plan area and existing community by continuing the existing public roadway network through the DRSP property to connect to Willow Road, providing a new Park and Ride lot to encourage carpooling, and creating new public transportation points of connection to facilitate public transit use and reduce single-occupant automobile use.

Circulation Policy 7.a

Extend North Frontage Road Collector through the property to connect to Willow Road.

Circulation Policy 7.b

Provide a north-south Collector roadway connection from Pomeroy Road to Willow Road through the property rather than along Hetrick Avenue right-of-way.

Circulation Policy 7.c

Interlink the north-south Collector Roads with an east-west Collector Road.

Circulation Policy 7.d

Introduce a new Park and Ride lot along North Frontage Road to encourage Countywide carpooling and reduce single-occupant automobile use.

Circulation Policy 7.e

Provide locations for new public transportation stops at the commercial land uses and Park and Ride locations, two stops north of the roundabout on Collector A and two stops at the Park and Ride along Collector A.

Circulation Policy 7.f

Create emergency access points at the neighborhood edge to allow for additional fire/safety personnel access in Neighborhoods 7 and 9.

Goal 8

Integrate a network of walking, bicycling, and equestrian facilities to connect on-site residential neighborhoods and the broader community.

Circulation Policy 8.a

Provide buffered Class II bicycle lanes along Collectors 'A', 'B', and 'C' to encourage bicycle use within and through the DRSP area.

Circulation Policy 8.b

Provide sidewalks along all road types to encourage walking and other non-motorized transportation within and through the DRSP.


4.3 Street Cross Sections (New Roads)

The following sections provide descriptions of the design of individual roadways within the DRSP by use of individual street cross-section exhibits. The design of the individual street cross-sections includes opportunities for decentralized stormwater treatment LID features within roadway right-of-way areas. For landscaping, lighting, and other features, refer to Appendix A – Objective Design Standards and Design Guidelines.

4.3.1 Collector 'A' and 'B' Typical

Collector 'A' and 'B' Typical street section is designed as a 70-foot public right-of-way. From each side of the centerline, there will be a 12-foot travel lane, 8-foot buffered Class II bicycle lane, 9- or 10-foot parkway/LID feature, and 5- or 6-foot sidewalk. No on-street parking is provided. Flush curbs, also known as mow curbs, with a 2-foot shoulder are provided at the parkway/LID feature on both sides of the street, unless otherwise specified by the County. Ten-foot PUE's are incorporated outside the right-of-way on both sides of the street to accommodate necessary utilities to serve the adjacent land uses. See *Exhibit 4-3 for Collector 'A' and 'B' Typical* cross section details.



Exhibit 4-3: Collector 'A' and 'B' Typical



4.3.2 Collector 'A' at Village Commercial Land Use

Collector 'A' at Village Commercial Land Use street section is designed as a 70-foot public right-of-way. From each side of the centerline, there will be a 12-foot travel lane, 8-foot buffered Class II bicycle lane, 9- or 10-foot parkway/LID feature, and 5- or 6-foot sidewalk. No on-street parking is provided. Traditional curbs with gutters and curb cuts are provided at the parkway/LID features on both sides of the street. Ten-foot PUE's are incorporated outside the right-of-way on both sides of the street to accommodate necessary utilities to serve the adjacent land uses. See *Exhibit 4-4 for Collector 'A' at Village Commercial cross section details*.


Exhibit 4-4: Collector 'A' Adjacent to Village Commercial



4.3.3 Collector 'A' and 'B' at Left Turn Lane

Collector 'A' and 'B' at Left Turn Lane street section is an 80-foot public right-of-way. From each side of the centerline, there will be a 12-foot left-turn lane and 4-foot median separating a 12-foot travel lane, 8-foot buffered Class II bicycle lane, 6- or 7-foot parkway/LID feature, and 5- or 6-foot sidewalk on one side of the street and a 12-foot travel lane, 8-foot bicycle lane, 6- or 7-foot parkway/LID feature, and 5- or 6-foot sidewalk on the other side of the street. No on-street parking is provided. Flush curbs with a 2-foot shoulder are provided at the parkway/LID feature on both sides of the street, unless otherwise specified by the County. Ten-foot PUE's are incorporated outside the right-of-way on both sides of the street to accommodate necessary utilities to serve the adjacent land uses. See Exhibit 4-5 for Collector 'A' and 'B' at Left Turn Lane cross section details.



Exhibit 4-5: Collector 'A' and 'B' at Left Turn Lane



4.3.4 Entries and Roundabouts, Collector 'A' and 'B'

Entries and Roundabouts, Collector 'A' and 'B' street section is an 80-foot public right-of-way. From each side of the centerline, there will be a 10-foot median separating a 12-foot travel lane, 8-foot buffered Class II bicycle lane, 9- or 10-foot parkway/LID feature, and 5- or 6-foot sidewalk. No on-street parking is provided. Flush curbs with a 2-foot shoulder are provided at the parkway/LID feature on both sides of the street, unless otherwise specified by the County. Ten-foot PUE's are incorporated outside the right-of-way on both sides of the street to accommodate necessary utilities to serve the adjacent land uses. See *Exhibit 4-6 for Entries and Roundabouts* cross section details.

Exhibit 4-6: Entries and Roundabouts



4.3.5 *Park and Ride: Collector 'A'*

Park and Ride: Collector 'A' street section is designed to accommodate future northbound and southbound vehicular movement adjacent to a Park and Ride lot. It is comprised of a minimum 156-foot public right-of-way with two separate areas – one area for Collector 'A' roadway and one for the Park and Ride lot.



From each side of the centerline, Park and Ride: Collector 'A' roadway area includes a 12-foot travel lane, 8-foot buffered Class II bicycle lane, 9- or 10-foot parkway/LID feature, and 5- or 6-foot sidewalk. No on-street parking is provided. A flush curb with a 2-foot shoulder is provided at the parkway/LID feature on both sides of the street, unless otherwise specified by the County. Ten-foot PUE's are incorporated outside the right-of-way on both sides of the street to accommodate necessary utilities. The SCAP designates improvements along North Frontage Road as eligible for reimbursement by the County.

The Park and Ride area is comprised of a 24-foot travel lane and 18-foot parking stalls on both sides of the street centerline and will contain approximately 80 parking spaces. Flush curbs with a 2-foot shoulder are provided at the parkway/LID feature on both sides of the Park and Ride area, unless otherwise specified by the County. See *Exhibit 4-7 for Park and Ride Concept* and *Exhibit 4-8 for Park and Ride, Collector 'A' cross section details*.

Exhibit 4-7: Park and Ride Concept




Exhibit 4-8: Park and Ride: Collector 'A'



4.3.6 Collector 'C'

Collector 'C' street section is designed as a 70-foot public right-of-way. From each side of the centerline, there will be a 12-foot travel lane, 8-foot buffered Class II bicycle lane, 9- or 10-foot parkway/LID feature, and 5- or 6-foot sidewalk. No on-street parking is provided. A flush curb with a 2-foot shoulder is provided at the parkway/LID feature on the south side of the street, with traditional curbs with gutters and curb cuts to allow water flow provided at the parkway/LID feature on the north side of the street and on the southern portion of the street adjacent to multi-family and commercial land uses, unless otherwise specified by the County. A 10-foot PUE is incorporated outside the right-of-way on the north side of the street to serve the adjacent, various land uses. A 5-foot PUE is incorporated outside the right-of-way on the south side of the street to provide utility access to serve the adjacent uses. See Exhibit 4-9 for Collector 'C' cross section details.



Exhibit 4-9: Collector 'C'



4.3.7 *Transit Stop at Collector*

Transit Stop at Collector street section is designed to accommodate a future transit stop along Collector 'A'. It is comprised of an 84-foot public right-of-way and from each side of the centerline includes a 12-foot travel lane, 8-foot buffered Class II bicycle lane, 12-foot transit pullout lane, and a 10-foot sidewalk. No on-street parking is provided. Traditional curbs with gutters with pedestrian landings are provided at the sidewalks on both sides of the street. A pre-fabricated pedestrian shelter will be provided based on County standards, as necessary. Ten-foot PUE's are incorporated outside the right-of-way on both sides of the street to accommodate necessary utilities to serve the adjacent uses. See *Exhibit 4-10 for Transit Stop at Collector* cross section details.


Exhibit 4-10: Transit Stop at Collector



4.3.8 Local Road 'D'

Local Road 'D' street section is designed as a 60-foot right-of-way. From each side of the centerline, there will be a 12-foot travel lane, 8-foot parking lane, 7-foot parkway/LID feature, and a 5-foot sidewalk. On-street parking is provided. Flush curbs will separate the parking lanes from the parkway/LID feature. Ten-foot PUE's are incorporated outside the right-of-way on both sides of the street to accommodate necessary utilities to serve the adjacent uses. Class III bikeways are integrated and intended to be shared with the on-street vehicle traffic. See Exhibit 4-11 for Local Road 'D' cross section details.

Exhibit 4-11: Local Road 'D'



4.3.9 Single-Family Street, Typical – Local Road

The *Single-Family Street, Typical* Local Road, street section is designed as a 60-foot right-of-way. From each side of the centerline, there will be a 10-foot travel lane, 8-foot parking lane, 7-foot parkway/LID feature, and 5-foot sidewalk. On-street parking is provided. Rolled curbs are proposed to separate the parking lane from the parkway/LID feature and will include associated spillways and depressions to allow water flow into the parkway/LID area. Ten-foot PUE's are incorporated outside the right-of-way on both sides of the street to accommodate necessary utilities to serve the adjacent land uses. This street cross-section is found within the single-family neighborhoods including portions of Neighborhoods 3, 4, 5, 6, 7, 8, and 9. Class III bikeways are integrated and intended to be shared with the on-street vehicle traffic. See *Exhibit 4-12 for Single-Family Street, Typical* cross section details.



Exhibit 4-12: Single-Family Street, Typical



4.3.10 Single-Family Street, Alternative – Local Road

The *Single-Family Street, Alternative Local Road*, street section is designed as a 60-foot wide right-of-way. From each side of the centerline, there will be a 10-foot travel lane, an 8-foot parking lane, and a 5-foot sidewalk. The right-of-way also includes a 13-foot parkway/LID feature on one side of the street only in between the sidewalk and parking lane. On-street parking is provided. A rolled curb is provided at the parkway/LID side of the street that will include associated spillways and depressions to allow flow into the parkway/LID area, while a traditional curb with no gutter is provided on the alternative side of the street. Ten-foot PUE's are incorporated outside the right-of-way on both sides of the street to accommodate necessary utilities to serve the adjacent land uses. This street cross-section is found within the single-family neighborhoods including portions of Neighborhoods 3-9. See *Exhibit 4-13 for Single Family Street, Alternative* cross section details.


Exhibit 4-13: Single-Family Street, Alternative



4.3.11 Motorcourt – Private

The Motorcourt section is designed as a 20-foot private access easement. From each side of the centerline, there will be a 10-foot travel lane providing access to residential homes with a ribbon gutter for drainage located at the centerline. No parking on the private Motorcourt is allowed, except in designated guest spaces. Traditional curbs and gutters are provided on either side, with the individual home setback 5-feet from the private access easement. Property lines of adjacent residential homes continue to the centerline of the private access easement and a 10-foot wide PUE is provided at the centerline. See *Exhibit 4-14 for Motorcourt - Private* cross section details.

Exhibit 4-14: Motorcourt - Private



4.3.12 Access Drive – Private

The Access Drive is designed as a 20-foot private shared driveway. The shared access drive will be gated and provide access to the existing residences located to the west of the Hetrick Avenue right-of-way. A 12-foot access drive branching off the main access drive will also be provided to service the adjacent storm water basin.

4.4 Street Cross Sections (Existing Off-Site Roads)

4.4.1 *North Frontage Road*

North Frontage Road is an existing off-site public Collector Road that runs parallel to U.S. Highway 101 just south of the DRSP area. It currently dead-ends at the adjacent property at the southeast corner of the DRSP area. The South County Circulation Study identifies the extension of this existing road to Willow Road. As part of the DRSP, North Frontage Road will be extended through the project to Willow Road. Refer to Section 4.3 for additional information regarding the North Frontage Road (Collector A) extension.

4.4.2 *Pomeroy Road*

Pomeroy Road is an existing off-site public Arterial Road that generally runs north to south and is located in the southwest corner of the DRSP area. It is currently designed with a 12-foot lane and a Class II bicycle lane of varying 5- to 7-foot width on both sides of the street centerline. To provide a better north-south road connection to Willow Road, Collector 'B' is proposed to run through the DRSP area beginning at Pomeroy Road. To enhance safety and minimize vehicle conflicts, a one-way stop is proposed at the Pomeroy Road and Collector Road B intersection. This would reroute a small portion of Pomeroy Road into the DRSP property to accommodate the necessary road geometry.

4.4.3 *Hetrick Avenue*

Hetrick Avenue is an existing off-site public Local Road that runs along a portion of the western boundary of the DRSP area. Under existing conditions, Hetrick Avenue turns sharply to the west along the western boundary and turns into Glenhaven Place, another local public road. The Nipomo Community Plan Circulation Element and South County Circulation Study identify a Hetrick Avenue extension that is currently unbuilt. It would turn sharply to the east at the current intersection with Glenhaven Place and travel through a dense oak woodland area before turning south along the rear yards of existing residential properties to the west. The DRSP does not propose to construct the Hetrick Avenue extension, in favor of introducing a functionally superior Collector 'B', which travels from Pomeroy Road through the DRSP and connects with Willow Road. Currently, Hetrick Avenue right-of-way at the southwest corner of the property near Pomeroy Road would be abandoned, re-routed, or deeded to the adjacent existing residential property owners to the west. Access for the three (3) existing residential properties to the west of Hetrick Avenue, most immediate to Pomeroy Road, would be maintained via an access drive to Collector B (see Section 4.3.12) that would include gated access. The proposed Collector B would have the necessary right-of-way width and reduce impacts to the existing neighborhoods on Hetrick Avenue. The portion of Hetrick Avenue to be used for emergency access to the DRSP area will be improved to County Public Improvement Standards.

4.4.4 *Cherokee Place*

Cherokee Place runs along the northern property line of the DRSP area, beginning at Hetrick Avenue in the west and terminating approximately +/- 575 feet from the U.S. Highway 101 right-of-way. It is currently an unpaved road that is approximately +/- 20 feet in width. Improvements along Cherokee Place are anticipated adjacent to APN's 091-301-031 and 091-301-029 along with right-of-way dedication, to be reviewed and approved by Public Works. Along the frontage of APN's 091-301-031 and 091-301-029, there will be a 20-foot-wide by 20-foot-long paved section

aligned with the existing unpaved road that lies within the northern 25-foot offer of dedication on Cherokee Place, except at the fire station. Improvements elsewhere along Cherokee Place are not provided as part of the DRSP.

4.4.5 *Cory Way*

Cory Way is an existing off-site public Local Road that terminates at the southern property line of the DRSP area. As discussed under Section 4.6 below, emergency access only is planned for where Cory Way terminates at the property, but pedestrian, bicycle, and equestrian connections will also be provided at this existing off-site road. No routine vehicle access will be allowed for this existing off-site public Local Road into the DRSP area.

4.5 Intersections and Roundabouts

4.5.1 *Intersections*

Five intersections connect the surrounding community to the DRSP area. These include Collector 'A' and Collector 'B' at Willow Road, Collector 'A' and Collector 'B' at Cherokee Place, and Collector 'B' at Pomeroy Road. Collector 'A' at Willow Road is envisioned as a new signalized three-way intersection, which is located approximately +/- 1,300 feet from the U.S. Highway 101 on-ramps. Collector 'B' at Willow Road will be a one-way stop where Collector 'B' meets Willow Road, allowing for unimpeded traffic flow along Willow Road. Both Collector 'A' and Collector 'B' at Cherokee Place are envisioned as two-way stops along Cherokee Place, allowing for unimpeded traffic flow along the DRSP Collectors. Lastly, Collector 'B' at Pomeroy Road is a one way stop intersection. As noted above in Section 4.4, a small portion of Pomeroy Road will be rerouted into the DRSP area to accommodate the necessary geometry for the new road connection. Ultimately, intersection control type will be reviewed and approved by Public Works.

4.5.2 *Roundabouts within DRSP*

There are two roundabouts located within the DRSP area. These are intended to enhance safety and reduce overall vehicle speeds. These roundabouts are located entirely within the DRSP and include Collector 'A' at the Village Commercial area, where this roadway intersects with Collector 'C.' Another is located along Collector 'B' adjacent to Neighborhoods 6 and 9, where this roadway intersects with Collector 'C' (refer to *Exhibit 2-1* in Chapter 2 and *Exhibits 4-1* and *4-2* for locations).



Roundabouts calm traffic and slow speeds in residential and commercial neighborhoods.

The integration of roundabouts within the DRSP provides organizing features for the overall circulation network. These features within the roundabouts enhance the overall aesthetic of the community and may include features such as specimen trees, accent landscaping, unique paving, lighting and/or project signage.

4.6 Emergency Access

Three emergency access points are located in the DRSP. These will ensure adequate service by fire and safety personnel in the future. Emergency access points are proposed within Neighborhood 9, adjacent to Hetrick Road, within Neighborhood 7, as a continuation of Cory Way, and between Neighborhood 3 and Neighborhood 7.

The emergency access points will be constructed with adequate width to accommodate fire/safety vehicles and be gated per CalFire/County Public Improvement Standards.


The DRSP also envisions these emergency access points be designed to include pedestrian, bicycle, and equestrian access as further discussed in Section 4.9 below, providing access to the existing community, with the exception of the emergency access point between Neighborhood 3 and Neighborhood 7, which will only have pedestrian and bicycle access.

4.7 Bicycle Network

To close existing gaps within the County's bicycle network and to promote non-motorized transit use within the DRSP area, an extensive bicycle network has been proposed in conjunction with the property's primary Collector roadway design (see *Exhibit 4-15*). As noted in the 2016 San Luis Obispo County Bikeways Plan, Class II bikeways exist on Pomeroy Road to the south and Willow Road to the north, with plans for expansion of Class II bikeway facilities along the North Frontage Road to the south.

Collector Roads 'A', 'B', and 'C' will have buffered Class II bicycle lanes within an 8-foot right of way. The design of these separated bikeways will include a 5-foot travel lane and 3-foot pavement markings (e.g., striping) to separate bicycle riders from automobile travel lanes. Additional pavement marking within bicycle-automobile conflict zones, such as at intersections or driveway entry points, will be painted green per County standards to bring greater attention to these conflict points. To ensure adequate storage of bicycles within the DRSP, bicycle racks will be incorporated as part of commercial developments as well as within the neighborhood park per County Standards.

Exhibit 4-15: Bicycle Network



4.8 Equestrian Network

To continue the long tradition and presence of equestrians within Nipomo, an equestrian trail network has been integrated as an amenity for use by future residents in the DRSP, as well as by community members. Two primary equestrian trail loops are proposed, one in the northern half of the property and the other in the southern half, both of which meet in the middle of the property, as outlined in *Exhibit 4-16: Trails Map*.

4.8.1 Trails

The equestrian trails are proposed to be built to the County of San Luis Obispo's Horse Trail Standards, identified in Appendix B of the Parks and Recreation Element (see *Exhibit 4-17: Equestrian Trail Standards* below). A minimum of 15 feet of right-of-way will be included to allow the trails to meander and provide for adequate landscaping and buffering/screening from adjacent properties. Where the equestrian trails travel through oak open space areas at the center of the property, the trail easement will be limited to 10-feet.

Exhibit 4-16: Trails Map






Exhibit 4-17: Equestrian Trail Standards (County of San Luis Obispo - Parks and Recreation Element, Appendix B)



4.8.2 Trailhead

A trailhead facility is also proposed as part of the DRSP. It is intended to accommodate equestrian users. The trailhead facility is located at the southeast corner of the DRSP area. It will be accessed from Collector A (North Frontage Road). Trailhead facilities will include parking to allow for eight (8) vehicles with trailers to pull through and park, hitching posts, information, and signage. Maintenance of equestrian trails and associated facilities are anticipated to be maintained by a Homeowners Association or local non-profit, as discussed in Chapter 3. Restroom facilities at the trailhead are anticipated as being provided as temporary rental or leased facilities provided by a Homeowners Association or local non-profit. Refer to *Exhibit 4-18: Equestrian Trailhead Concept*.

Exhibit 4-18: Equestrian Trailhead Concept



4.8.3 Crossings

Equestrian trail crossings occur at both Collectors 'B' and 'C' within the DRSP. Crossings will be constructed to meet the standards identified in Figure 5-3 of the U.S. Department of Agriculture – Equestrian Design Handbook, as shown in *Exhibit 4-19: Equestrian Trail Crossing*.

Exhibit 4-19: Equestrian Trail Crossing




Figure 5-3—An at-grade trail crossing (with signals) for equestrians.

4.9 Pedestrian Network

4.9.1 Sidewalks

As illustrated in the Street Cross Section exhibits in Section 4.3, most of the streets within the DRSP area contain sidewalks on both sides of the street, except for the Private Motorcourts. Depending on their location within the DRSP area, sidewalk widths vary from 5-feet to 6-feet. In general, those sidewalks located within the commercial areas have been designed to be wider than those within the residential neighborhoods.

4.9.2 Pedestrian Trails


As an amenity to the future residents of the DRSP neighborhood and the existing community, an extensive off-street pedestrian trail network has been proposed. See *Exhibit 4-16* for pedestrian trail locations. The pedestrian trails have been integrated in a manner to provide both recreational opportunities as well as connect the individual neighborhoods to the commercial and job areas of the site without the need to use an automobile.

Pedestrian trails will be built to the County of San Luis Obispo's Pedestrian Trail Standards, identified in Appendix B of the Parks and Recreation Element (see *Exhibit 4-20: Pedestrian Trail Standards*). A minimum of 10-feet of right-of-way will be provided to allow the trail to meander and provide for adequate landscaping and buffering/screening from adjacent properties.



Pedestrian trail through open space concept.

Exhibit 4-20: Pedestrian Trail Standards (County of San Luis Obispo - Parks and Recreation Element, Appendix B)



4.10 Public Transit

To encourage the use of public transit to and from the DRSP area by residents, employees, and visitors, public transit hubs are proposed. These include a transit hub adjacent to the Village Commercial area, just north of the roundabout, as well as at the Park and Ride lot located along Collector A (North Frontage Road) just south of Willow Road. Transit hubs are located within the road right-of-way and the San Luis Obispo County Regional Transit Authority (RTA) and/or other regional transit providers are expected to provide service to and stops within these designated transit hub locations. See *Exhibits 4-7* and *4-10* for conceptual transit stop locations and right-of-way interface.

4.11 Streetscape

4.11.1 Entry Feature Design

To bring attention to and highlight entry into the DRSP area for both residents and visitors, primary and secondary entry features are proposed in various locations within the neighborhood. Primary entries will be located at the intersection of Collector 'A' and Collector 'B' at Willow Road as well as Collector 'A' at the southern end of the Village Commercial land use area. Secondary entry features are located at the one way stop intersection where Collector 'B' and Pomeroy Road intersect, at Collector 'B' and Cherokee Place, and Collector 'A' and Cherokee Place. Refer to

Exhibit 2-2a in Chapter 2 for the specific locations of both the primary and secondary entry features within the DRSP area.

Future design of the primary and secondary entry features should include:

- High-quality materials that reflect the DRSP area character; and
- A combination of the following elements:
 - Primary Entry Signage
 - Secondary Entry Signage
 - Decorative Walls
 - Specimen Trees
 - Accent Landscaping
 - Enhanced Paving (colored and/or textured)



Example of neighborhood identification signage.



Example of wayfinding/trail signage identification.

4.11.2 Streetscape Accent Paving Design

Enhanced accent paving is envisioned within the DRSP area at pedestrian crossings and roundabouts along Collectors 'A', 'B', and 'C'. Utilizing accent paving at pedestrian crossings and roundabouts will provide contrasting color from the adjacent roadway and enhance visibility and safety for pedestrians and vehicles. Paving design along these Collectors should consist of material and color that is complementary to the overall design aesthetic of these primary roadways. All accent paving selected should be compliant with applicable American Disabilities Act (ADA) requirements.



Example of accent paving treatment applied at the intersection.



Example of accent paving applied at parking.

4.11.3 Landscape Design

Landscape design throughout the DRSP area will reflect local climatic and soil conditions while reflecting the bucolic character of the community. While individual landscape palettes will vary along the streets within residential neighborhoods and within the commercial areas, common landscape areas along Collectors 'A', 'B', and 'C', and Local Road 'D' will have a consistent aesthetic to establish a baseline for the overall neighborhood character. Landscape design within parkways and medians along Collectors 'A', 'B', and 'C', and Local Road 'D' should integrate the following:

- A unified design that reflects the bucolic character and local climatic and soil conditions of the neighborhood;
- Include a variety of trees, shrubs, and groundcover;
- Ensure landscaping is drought tolerant and water-wise;
- Integrate street and parkway trees to create a street tree canopy, provide shade, and define the street edge;
- Use flowering or accent trees in key locations such as project entries, roundabouts, intersections, pedestrian crossings, and other focal points for visual emphasis.
- Utilize low maintenance, long-lived, and durable plantings and minimize the use of perennials;
- Integrate accent cobbles, boulders, and/or rock mulch; and
- Locate and place plantings to accommodate roadway safety.



Unified landscape design concept with drought-tolerant landscaping incorporated.

All landscaping within parkways and medians along Collector Roads within the DRSP area will comply with applicable federal, state, and local building, public health, safety and accessibility codes, and the California Model Water Efficient Landscape Ordinance (MWEL - AB 1881).

4.11.4 Parkway/Low-Impact Development Design

Biofiltration and bioretention features reflect best management practices in stormwater management by slowing and filtering stormwater runoff. These systems are often utilized to manage runoff associated with streets, parking areas, and other hardscaped areas. These can be integrated into parkway design along streets and/or in other landscaped areas. Typically, these systems are planted with vegetation that is tolerant of heavy watering and alternatively, drought conditions.

The DRSP has incorporated an extensive network of bioretention features to further sustainable stormwater practices and maximize retention/recharge opportunities on-site. Within the DRSP area, except for the Private Motorcourts, all streets are proposed to contain parkway low-impact development (LID) areas within the street right-of-way to capture and treat runoff from impervious roadway areas.

To enhance the character of the overall DRSP area, parkway/LID features should consist of a landscape palette tolerant of heavy watering winter conditions as well as drier, drought-like conditions. The landscape palette should consist of a blend of trees, shrubs, and groundcover, as well as decorative rocks and boulders placed intermittently for both aesthetic and functional qualities within the parkway area. Where standard curbs are proposed adjacent to parkway/LID features, curb cuts should be provided intermittently to allow for sheet flow of water off the roadways and into the parkway/LID areas.



Parkway medians provide opportunities for decentralized biofiltration and retention.

This Page Intentionally Blank.

5 Infrastructure and Phasing

5.1 Introduction

This Chapter describes the major backbone infrastructure and utilities required to support development of the Dana Reserve Specific Plan (DRSP) area. Public utilities include potable water system, wastewater system, stormwater facilities and other utilities such as natural gas, electrical, telecommunications, fiber, and cable/data service. Additionally, future developers in the DRSP area will pay NCSD water and wastewater development impact fees.

5.2 Water

Potable water for the DRSP area will be supplied by NCSD. Table 5.1 on the following page summarizes the water use factors and demand calculations for the anticipated land uses in the DRSP. The total demand is estimated at 350.64 acre-feet per year (AFY), with the total demand plus a 10% contingency estimated at 385.71 AFY. An estimated 67.55 acre-feet of the total 350.64 acre-feet would be used for commercial development, daycare, public safety and landscaped common areas. The NCSD has reviewed water demands for the DRSP area and determined that there is an adequate and reliable water supply for buildout of the DRSP area.

As shown in Exhibit 5-1, the water system for the DRSP area is proposed to be comprised of a 12" main line extension from the stub in North Frontage Road, at the southeast corner of the property, to Willow Road and will also include an internally looped system of 8" public water main line, which will provide fire suppression to the development areas. These will be routed within the public roads. The main trunk lines will be owned and operated by NCSD. The private main line system for the commercial areas will be protected at each connection point to the public system with a double detector check assembly.

Domestic water services for each development area are proposed to utilize County and NCSD standard water services and meters. Service connections will connect to the above referenced 8" domestic main lines. Waterlines are proposed to be routed within streets or easements. Fire hydrants will be located adjacent to roadways and spacing will be no greater than 500 feet, except on dead end streets it shall be no more than 400 feet. The maximum distance from any point on the street frontage to a hydrant shall be 250 feet. For commercial or light industrial areas, the maximum spacing will be no greater than 250 feet or less, as required by the Fire Official. Hydrants or tie-ins for future hydrants may be required by the fire official and shall typically limit the distance from any point on the exterior of any building to 150 feet.

As shown in Exhibit 5-2 below, the DRSP will install recycled water lines to make the project "recycled water" ready. If NCSD is able to provide recycled water to the DRSP, recycled water will be utilized for landscaping within the village and flex commercial area, public recreation, neighborhood parks, and streetscape and parkway areas. Irrigation for these identified areas will be converted from potable water to recycled water at that time.

5.2.1 Operations and Maintenance

The ongoing operation of water mains, infrastructure and associated appurtenances serving the DRSP area will be owned and maintained by NCSD.

Table 5.1: DRSP Water Use Factor and Demand

<i>Land Use Category</i>	<i># of Units or Acres</i>	<i>Water Use Factor³ (af/yr)</i>	<i>Potable Water Demand(af/yr)</i>	<i>Daily Demand² (gpd)</i>
Residential				
Apartments/Condominiums	193 units	0.13 af/yr/unit	24.70	
Townhomes	152 units	0.14 af/yr/unit	21.89	
Cluster	124 units	0.21 af/yr/unit	25.79	
4,000-5,999 SF	437 units	0.21 af/yr/unit	90.90	
6,000-10,000+ SF	258 units	0.34 af/yr/unit	86.69	
Affordable	78 units	0.14 af/yr/unit	11.23	
ADUs	152 units	0.14 af/yr/unit	21.89	
<i>Subtotal:</i>			<i>283.09</i>	<i>252,559</i>
Commercial¹				
Village Commercial	4.4 ac	0.136 af/yr/1,000 sf	8.69	
Flex Commercial ⁶	17.56 ac	0.136 af/yr/1,000 sf	34.67	
<i>Subtotal:</i>			<i>43.36</i>	<i>38,683</i>
Recreation - Daycare¹				
Recreation – Daycare Facility	0.45 ac	0.136 af/yr/1,000 sf	0.89	
<i>Subtotal:</i>			<i>0.89</i>	<i>795</i>
Public Safety				
Fire Station	2.15 ac	0.136 af/yr/1,000 sf	1.63	
<i>Subtotal:</i>			<i>1.63</i>	<i>1,455</i>
Landscape				
Village and Flex Commercial Areas and Recreation – Daycare Facility ⁴	7.46 ac	1.0 af/yr/ac	7.46	
Recreation – Passive Neighborhood Park	1.0 ac	1.0 af/yr/ac	1.0	
Pocket Parks	6.7 ac	1.0 af/yr/ac	6.7	
Streetscape/Parkways	6.5 ac	1.0 af/yr/ac	6.50	
<i>Subtotal:</i>			<i>21.67</i>	<i>19,333</i>
<i>Project Total⁵:</i>			<i>350.64 af/yr</i>	<i>312,824 gpd</i>
<i>Project Total (with 10% contingency⁵:</i>			<i>385.71 af/yr</i>	<i>344,112 gpd</i>
Notes: ¹ Assumes 0.15 gpd/sf and 33% useable site area for buildings. ² Conversion factor: 1 af/yr equals 892.742 gpd. ³ Water usage factors used in the table above are derived from the following sources: 2016 NCSU Urban Water Management Plan (UWMP), The City of Santa Barbara and the County of SLO were used if there wasn't a direct water usage factor listed in the 2016 UWMP for each land use category. The water demand usage factors have been reduced by the mandated 20% as described in the 2016 UWMP. ⁴ Assumes 33% of total commercial and daycare acreage is available for landscape. ⁵ Includes potential Public Safety Facility Water Demand - 1.06 acre lot: 1.02 AF/Year/1000 sf (Institutional Land Use Category) = 1.02 ac-ft/year (Project Total) / 1.12 ac-ft/year (Project Total (with 10% contingency)). ⁶ Does not include 0.34 acre access easement as shown on the Vesting Tentative Map.				

Exhibit 5-1: Proposed Water Backbone Infrastructure





Exhibit 5-2: Recycled Water Infrastructure



5.3 Wastewater

Wastewater generated within the DRSP area will be conveyed to the existing NCSD infrastructure within North Frontage Road. The project will require an extension of the existing 12" gravity line within North Frontage Road to provide sewer to the proposed development areas. The wastewater collected from this development will be conveyed to the Southland Wastewater Treatment plant located south of the project site along U.S. Highway 101 on Old Windmill Place. See Exhibit 5-3 for proposed sewer service lines in the DRSP area. The main trunk lines will be owned and operated by NCSD. Buildout of the development would generate an estimated 248.87 acre-feet of wastewater per year based on average flow rates (see Table 5.2). For potential peak water flows, a calculation of 622.18 acre-feet is projected, based on a County peaking factor of 2.5.

There are (3) proposed sewer lift stations that will be located on separate dedicated lots. Two of the lift stations will be on the west side towards Hetrick Avenue and Pomeroy Road within the DRSP area and the third will be in the southeast corner of the site. All of them will be owned/operated by NCSD. The force main lines and connections back to the gravity sewer backbone will coincide with the neighborhood developments.

5.3.1 *Phasing*

The anticipated phasing for the proposed improvements would consist of connecting to the sewer mainline that is currently approved by the County to be installed with the widening of the Frontage Road. Phasing of the wastewater backbone infrastructure should generally follow the phasing demonstrated in Exhibit 5-6.


5.3.2 *Operation and Maintenance*

The ongoing operation of gravity sewer mains, manholes, lift stations, force mains, infrastructure and associated appurtenances serving the DRSP area will be maintained by NCSD.

Table 5.2: DRSP Wastewater Generation

Land Use Category	# of Units or Acres	Wastewater Generation Factor ^{3,4} (GPD)	Annual Demand (af/yr)	Daily Demand ² (gpd)
Residential				
Apartments/Condominiums	193 units	103/unit	22.23	
Townhomes	152 units	116/unit	19.70	
Cluster	124 units	167/unit	23.21	
4,000-5,999 SF	437 units	130/unit	63.62	
6,000-10,000+ SF	258 units	180/unit	52.01	
Affordable	78 units	116/unit	10.11	
ADUs	152 units	116/unit	19.70	
<i>Subtotal:</i>			<i>210.58</i>	<i>187,869</i>
Commercial¹				
Village Commercial	4.4 ac	100/k-sf	7.16	
Flex Commercial ⁶	17.56 ac	100/k-sf	28.56	
<i>Subtotal:</i>			<i>35.72</i>	<i>31,889</i>
Recreation - Daycare¹				
Recreation – Daycare Facility	0.45 ac	100/k-sf	0.73	
<i>Subtotal:</i>			<i>0.73</i>	<i>648</i>
Public Safety				
Fire Station	2.15 ac	100/k-sf	1.34	
<i>Subtotal:</i>			<i>1.34</i>	<i>1,196</i>
Landscape				
Recreation – Passive Neighborhood Park	1.0 ac	0.50 af-ft/yr-acre	0.50	
Pocket Parks	6.7 ac	-	-	
Streetscape/ Parkways	6.5 ac	-	-	
<i>Subtotal:</i>			<i>0.50</i>	<i>446</i>
<i>Project Total Average Flow⁵:</i>			<i>248.87 af/yr</i>	<i>222,030 gpd</i>
<i>Project Peak Flow (assumes 2.5 Peaking Factor)⁵:</i>			<i>622.18 af/yr</i>	<i>555,078 gpd</i>
Notes: ¹ Assumes 33% useable site area for buildings. ² Conversion factor: 1 af/yr equals 892,742 gpd. ³ Wastewater flow generation factors for single family are a percentage of average water demand: 60% for 6,000+, 70% for 4,000-6,000, 90% for all others. ⁴ Wastewater flow generation factors for commercial: City of San Luis Obispo, Infrastructure Renewal Strategy (Dec. 2015) ⁵ Includes potential Public Safety Facility Wastewater Flow – 1.06 acre lot = 0.85 ac-ft/yr (Project Total) / 2.13 ac-ft/yr (Project Peak Flow (assumes 2.5 Peaking Factor)). ⁶ Does not include 0.34 acre access easement as shown on the Vesting Tentative Map.				

Exhibit 5-3: Proposed Sewer Backbone Infrastructure



5.4 Drainage and Storm Water Facilities

5.4.1 Existing Conditions

Per the USDA NRCS Web Soil Survey, the hydrologic soil group for the development area is listed as Type A Soils, Oceano Sand. Per the geotechnical feasibility report prepared by Earth Systems Pacific dated September 2017, the site is well drained and there are high infiltration rates across the site.

Most of the existing terrain across the property is gradually sloped between 2% - 10% with localized mounds and some rolling hills. The average existing slope for the entire property is 5%. Localized low spots and depressions occur throughout the site. An existing hillside, or ridge, that runs from the Hetrick Avenue and the Glenhaven Place intersection to the southeast varies between 10% - 25% slope. Another localized ridge runs north-south from Willow Road to the north and Sandydale Drive to the south.

These localized ridges divide the project into (3) general watershed areas, see in Exhibit 5-4:


- *Watershed Area A:* the northwest portion of the project drains to the west towards the Hetrick Avenue and Glenhaven Place intersection.
- *Watershed Area B:* the southwest portion of the project drains to the southwest towards the Hetrick Avenue and Pomeroy Road intersection.
- *Watershed Area C:* the east portion of the project drains towards the east/southeast towards U.S. Highway 101.

Some existing off-site areas drain towards and onto the DRSP property as run-on. The associated flows from these areas will be collected in swales and/or storm drain culverts along the perimeter of the DRSP area, conveyed around the proposed neighborhoods and considered as bypass during the development of the project improvements. Drainage should be conveyed in a non-erosive manner so as not to cause damage to downstream properties.

The existing drainage along the east side of U.S. Highway 101 and Nipomo Creek is intended to remain in its current condition with no upgrades, since the County requires all post developed flows to be equal to or less than pre-developed peak flows. This will reduce the amount of anticipated flows that the existing channel will receive during the larger storm events, therefore the channel should not need to be improved from its current state.

See Exhibit 5-4 for the existing topography, localized low spots and depressions, drainage management area (DMA) watersheds and existing storm drain culverts.

Exhibit 5-4: Existing Drainage Watershed Areas



5.4.2 Proposed Construction and Post-Construction Conditions

The DRSP area post-developed conditions will mimic pre-developed conditions to the greatest extent practicable. Runoff from the identified watershed areas, or drainage management area (DMA), will be directed in the same general direction as the existing site conditions. Proposed storm drain facilities will be designed to meet both the County of San Luis Obispo traditional flooding requirements as well as the Central Coast Regional Water Quality Control Board post-construction stormwater requirements.

Proposed backbone road sections, identified as Collectors A, B, and C, include roadside low-impact development (LID) areas to treat and mitigate runoff from roadway impervious areas. Two curb types have been proposed along these backbone Collector Roads to allow for runoff to sheet flow into roadside LID areas. Curb types will either be flush curbs, or mow curbs, that allow runoff to sheet flow into the LID areas or traditional concrete curb and gutters that will collect and convey runoff to curb cuts to the LID areas. Perforated storm drain culverts may be added as underdrains as necessary. Inlets and/or catch basins will be integrated for larger storm event overflow. Storm drain inlets/culverts will be added and spaced appropriately to collect and convey large storm event overflow runoff towards proposed, downstream basins.



Examples of parkway/LID and curb cuts applications allowing for water infiltration.

Each development area will also design and incorporate its own stormwater mitigation measures within the individual DRSP neighborhoods and commercial areas. Stormwater mitigation measures examples are found in Appendix A – Design Guidelines. Neighborhood and internal road sections have been designed to also include roadside LID areas to treat and mitigate runoff. Inlets and/or catch basins will also be integrated within these areas for larger storm event overflow. Storm drain inlets/ culverts will be added and spaced appropriately to collect and convey large storm event overflow runoff towards proposed, downstream basins.

As shown in Exhibit 5-5, four (4) decentralized, eight-foot maximum ponded depth stormwater basins are proposed at the northeast, southwest, and west/northwest corners of the DRSP area. In addition, multiple, shallow, 2-foot maximum ponded depth (includes freeboard as shown on County of San Luis Obispo Detail D-1A) stormwater basins are proposed throughout the eastern half of the project. All stormwater basins will be designed to meet the County of San Luis Obispo Public Improvement standards. Each sub-system of basins will be sized to accommodate the remaining

runoff produced by the additional impervious areas within each respective DMA and neighborhood development. Storm drain inlets/culverts will also be added to connect sub-systems of basins where appropriate. Overflow structures, culverts, weirs, or other devices will be added and sized to meet discharge flows for both the County of San Luis Obispo requirements as well as the Central Coast Regional Water Quality Control Board post-construction stormwater requirements.

5.4.3 Stormwater Mitigation

Proposed stormwater mitigation will be designed so post-developed peak run-off flows are equal to or less than pre-development peak flows. The design intent is to not increase peak flows that ultimately go to the three (3) existing 24-inch reinforced concrete storm drain culverts that travel underneath U.S. Highway 101.

Storm water runoff quality will be addressed for both construction and post-construction phases of the DRSP. Temporary sediment control during construction will be implemented during construction and a Stormwater Pollution Prevention Plan (SWPPP) will be prepared for each grading project over one (1) acre in area of ground disturbance in accordance the State Water Resources Control Board (SWRCB) requirements. Construction phase impacts will be addressed by the implementation of Best Management Practices (BMPs). Operations and maintenance will be carried out by the developer's contractor during construction and will be responsible for implementing BMPs established in the County Code.

See Exhibit 5-5 for the master site plan overlaid with backbone storm drain trunk lines and proposed deep and shallow basin locations.

5.4.4 Operations and Maintenance

The operations and maintenance for all drainage and stormwater facilities outside County maintained roadways beyond curb face will be conducted by the Homeowners Association or special district and the agreement will follow the county's private stormwater system operation and maintenance template SWP- 2002c.



Example of stormwater basin.

Exhibit 5-5: Proposed Drainage Conditions



5.5 Grading

The initial rough grading of the site will occur as a single operation to establish the preliminary grades for all developed areas of the site. The final and finished grading of the DRSP area is anticipated to occur in several phases, with grading occurring in sequential construction. The timing, approval, and process of rough grading will comply with Section 2.1.3 of the County's 2019 Public Improvement Standards. The property will first be graded to support the installation of backbone road and utility infrastructure. The backbone roads subgrade will be prepared to allow circulation and construction access to the DRSP area. The adjacent commercial and multi-family designated land use areas as well as the residential neighborhood areas will be graded as necessary with the backbone roads effort in order to balance earthwork operations on-site to the greatest extent practicable. Prior to the commencement of grading operations, areas on-site that contain existing vegetation, oak trees, and/or other sensitive areas that are to remain as part of the development will be delineated with flags and/or protection fencing to ensure they are clearly identifiable.

Proposed stormwater basins in their respective areas of the property will be rough graded to create the basin shape, bottom, and top bench. Relatively flat sloped areas will be created for each adjacent commercial and multi-family areas as well as in the residential neighborhoods in order to direct storm water runoff to these proposed basins. As part of the subdivision plans, a comprehensive drainage plan should be prepared to demonstrate storm water runoff is conveyed in a non-erosive manner in accordance with County Public Improvement standards.

The owner, project team, contractors, and Qualified SWPPP Practitioner (QSP) for the property will determine the frequency and location of temporary measures. Grading-associated components will be temporary in nature and would be maintained until the permanent improvements are constructed.

5.5.1 Maintenance

Maintenance measures during grading activities will be subject to County standards and established Best Management Practices per County Code. Additionally, stockpile maintenance and storage will adhere to the County Code.

5.5.2 Retaining Walls

As determined by the County Code, retaining walls are exempt from a grading permit if deemed applicable to qualify for an exemption. Otherwise, retaining wall heights and setbacks will be subject to the standards set forth in the County Building Code.

5.6 Dry Utilities

The applicant or their appropriate representative shall provide a will-serve letter from the power and telephone providers for the DRSP area, including the following dry utilities: telecommunications, cable/data service, electric, and natural gas, as further described below. All dry utilities will be undergrounded.

5.6.1 Telecommunications/Fiber

The American Telephone and Telegraph Company (AT&T), Pac-West Telecomm Inc., and Satin Satellite are the primary telecommunications service providers to the community of Nipomo and will provide service to the DRSP area. These private companies will extend their facilities into the

DRSP area within the designated public utility easements (PUE), as identified on the street sections within Chapter 4, as it develops. All new telecommunications lines within the DRSP area will be placed underground.

High speed fiber infrastructure within the vicinity of the DRSP area is currently limited. However, due to current market demands, high speed fiber infrastructure may be provided within the DRSP area to allow the community to hook into future high-speed fiber infrastructure should it be extended to the property.

5.6.2 *Cable Service*

Cable television for the Nipomo area is provided by Charter Communications. The expanding range of broadcast services, including satellite, may be available for the DRSP area to the extent they are available throughout San Luis Obispo County.

5.6.3 *Electric*

Pacific Gas & Electric (PG&E) will provide electricity distribution to the DRSP area. Existing overhead service lines run along Cherokee Place, Pomeroy Road, and the eastern edge of the property. New service lines will be placed in or adjacent to the right-of way of the proposed commercial and residential roadways. All new electric lines will be placed underground.

Residential neighborhoods within the DRSP area will be designed to accommodate installation of solar panels on rooftops per the Building Code. Installation of solar on all residential homes will aide in generating needed electricity on-site and minimize the overall environmental impact by the community.

5.6.4 *Natural Gas*

Within the DRSP area, a natural gas main exists along the eastern property boundary adjacent to U.S. Highway 101. SoCalGas may provide natural gas distribution to the DRSP area. There are no existing gas mains located within the DRSP area. To support the proposed commercial and amenity areas, new gas mains may be constructed as part of the primary backbone roadways to serve new development areas.

5.7 Infrastructure Easements

5.7.1 *North Frontage Road*

Based on the conditions of the property located at the southeast corner of the DRSP area, an easement may be needed to accommodate the extension of infrastructure along North Frontage Road to the DRSP property. As part of the DRSP, North Frontage Road will be extended through the project to Willow Road. Refer to Section 4.3 for additional information regarding the North Frontage Road (Collector A) extension.

5.7.2 *Hetrick Avenue*

Hetrick Avenue traverses the western boundary of the DRSP property. The Nipomo Community Plan, the South County Circulation Study, and the South County Area Inland Plan identify improvements to Hetrick Avenue, designating the roadway a two-lane rural road classification with Class II bike lanes, ultimately extending from Pomeroy Road north to Aden Way. The extension of Hetrick Avenue from Glenhaven Place to Pomeroy Road in the south is currently unimproved. The

improvements within the DRSP do not include the construction of the Hetrick Avenue extension, since there is not sufficient right-of-way, and this route would not be consistent with the character of the existing residential neighborhood west of the DRSP area. The DRSP will construct Collector 'B' which travels from Pomeroy Road through the property and connects with Willow Road to the north, as a more functional alternative to the Hetrick Avenue extension. Currently at the southwest corner of the DRSP, Hetrick Avenue is an existing road with a 30-ft right-of-way serving three parcels. The DRSP includes re-routing access to this road to connect with Collector 'B' and closing where this portion of Hetrick Avenue currently connects with Pomeroy Road. This will eliminate turning movement conflicts on Pomeroy Road and provide permanent access to the three parcels mentioned above.

In order to allow for emergency access, an easement will be provided from the existing portion of Hetrick Avenue at the northwest corner of the DRSP, connecting to Neighborhood 9. This emergency access point is intended to be used only by fire and safety vehicles, pedestrians, bicycles, and equestrians.

5.7.3 *Cory Way*

Cory Way currently dead ends into the southern property line of the DRSP. In order to allow for emergency access to the community, an easement will be provided at this location connecting to Cory Way. This emergency access point is intended to be used only by fire and safety vehicles, pedestrians, bicycles, and equestrians. An easement may be needed to accommodate access.

5.7.4 *Southern California Gas*

An existing 20-ft Southern California Gas (SoCalGas) easement is located directly adjacent to the U.S. Highway 101 right-of-way on the DRSP property. This easement will include mutually agreed upon landscaping and will remain clear of obstructions to allow for any necessary or ongoing maintenance by SoCalGas.


5.7.5 *Pomeroy Road*

Based on the final alignment of the Pomeroy Road realignment into the DRSP, an easement(s) may be needed to accommodate proposed roadway and circulation improvements.

5.8 **Phasing**

Exhibit 5-6 identifies the areas anticipated in the conceptual phasing to make up the DRSP development phases. These phases address goals to accommodate orderly development and provision of services. They represent a reasonable approach to extending services and infrastructure throughout the DRSP. In some cases, property owners may wish to develop in phases concurrently or in a different order than anticipated in Exhibit 5-6. This will be permitted provided all public improvements needed to support proposed development are completed, and that circulation is provided for secondary access. For a more detailed breakdown of proposed phasing for the DRSP, refer to Appendix B – Phasing and Public Improvements Implementation Matrix.

Exhibit 5-6: Proposed Conceptual Phasing




6 Public Services

6.1 Introduction

The DRSP is served by several public services including schools, police and fire/emergency/ambulance service protection, solid waste disposal, recycling, green waste, postal service, and library services as discussed in more detail below.

6.2 Schools

Public education for the DRSP will be provided by Lucia Mar Unified School District (LMUSD), which includes elementary, middle, comprehensive high school, continuation high school, and adult education. The DRSP falls in the boundary area for the Lange Elementary School, Mesa Middle School, Central Coast New Tech High School, and Nipomo High School.



Nipomo High School outdoor common green and courtyard.

It is anticipated that the DRSP would increase demand for public school services at existing LMUSD facilities. Published LMUSD enrollment rates for 2017-18 combined with the District's Facilities Master Plan (2014) portrays existing capacity for Lange Elementary at 85%, Mesa Middle School at 88%, and Nipomo High School at 91%, as shown in Table 6.1 below.

Table 6.1: Existing LMUSD School Capacity (2023-2024)

<i>School</i>	<i>2017/18 Student Enrollments¹</i>	<i>2021/22 Student Projections²</i>	<i>Planned Capacity²</i>	<i>Current Available Capacity</i>
Lange Elementary	585	608	687	102
Mesa Middle	545	535	618	73
Nipomo High	970	1,172	1,071	101
<i>Sources:</i> ¹ 2018 School Plans for Student Achievement ² 2015/2016 LMUSD FM				

Table 6.2 identifies the anticipated number of school-age children generated by the DRSP and is based on the California Statewide Average Student Generation Rates.

Table 6.2: Student Generation by DRSP

<i>Grade Level</i>	<i>Generation Rates</i>	<i>Homes/Units</i>	<i>Additional Students</i>
Elementary (K-6)	0.5 ¹	1,242	621
Middle (7-8)	0.2 ¹	1,242	248
High (9-12)	0.2 ¹	1,242	249
<i>Total (K-12):</i>			<i>1,118</i>
<i>Notes:</i>			
¹ Statewide Average Generation Rates.			

New students will be added to the existing LMUSD system over the build-out of the DRSP, which will occur over several phases for a period of several years. These phases are shown in sequence below; however, they are not intended to occur in any particular sequence, as discussed further in Section 5.8. Table 6.3 below portrays the anticipated number of new students generated by phases of development, as noted in Chapter 5, Figure 5-6: Proposed Conceptual Phasing.

Table 6.3: Anticipated Student Generation Rate by DRSP Phasing

<i>Phase¹</i>	<i>Elementary (K-6)</i>	<i>Middle (7-8)</i>	<i>High (9-12)</i>	<i>Total Student Generation</i>
Phase 1 (NBDs 1, 2, 3, 5)	287	114	115	515
Phase 2 (NBDs 7, 8, 9)	203	81	81	365
Phase 3 (NBDs 4, 6 and 10)	132	53	53	238
<i>Total:</i>				<i>1,118</i>
<i>Notes:</i>				
¹ This sequence is for illustrative purposes only. Implementation may not occur in this sequence.				

As mandated by State law, developer impact fees will be paid to LMUSD as the DRSP area is built out over time to accommodate the anticipated increase in demand for public school facilities.

6.3 Police

Police services for the DRSP will be provided by the County of San Luis Obispo and will be based out of the San Luis Obispo County Sheriff Department offices located at 1681 Front Street in Oceano; the California Highway Patrol also assists in area calls for service. The Sheriff's Department divides the County into three areas – North Station, Coast Station, and South Station. Each of these is large in geographic area and may lead to delays in response times. Under the County's FY 2017-18 to 2021-2022 Infrastructure and Facilities Capital Improvement Plan, a new 6,000 square foot South County Substation is to be constructed in the Nipomo area to provide more timely service to the community.

Developer impact fees will be paid to the County Sheriff's Department to accommodate new demand for police services as the DRSP area is built out over time.



Public services, including police and fire stations.

6.4 Fire and Emergency Services

The San Luis Obispo County Fire Department and the California Department of Forestry and Fire Protection (CDF) will provide fire protection services to the DRSP area. Development will be primarily served by Fire Station No. 20, located off of North Oakglen Avenue at 450 Pioneer Avenue in Nipomo, approximately one-half mile away from the southern edge of the DRSP area. The Department also deploys resources from other nearby stations and personnel, such as Fire Station No. 22 located at 2391 Willow Road in Arroyo Grande, to maintain adequate response times. The County's FY 2017-18 to 2021-2022 Infrastructure and Facilities Capital Improvement Plan identifies that a new property in the West Nipomo area will be acquired to develop a new fire station to serve the community. It is anticipated that the County's current levels of fire services are sufficient to serve the DRSP area.



Fire truck and engines.

The San Luis Obispo County Fire Department and the CDF provide emergency paramedic services from both Fire Station No. 20 and No. 22. These stations have designated Medic Engines, which are staffed by a Fire Captain and a Fire Apparatus Engineer, which maintains a licensed paramedic on staff. However, the County also contracts with San Luis Ambulance to provide paramedic services throughout the County. Ambulances are dispatched via radio through the San Luis Obispo County's Sheriff Dispatch Center and respond to emergency, non-emergency, and Critical Care Transport calls. San Luis Ambulance maintains a location in Nipomo, located at 720 South

Frontage Road, with response times to the project site generally just over 5 minutes. Each ambulance is staffed with a minimum of one Paramedic and one Emergency Medical Technician.

Developer impact fees will be paid to the County Fire Department and CDF to accommodate new demand for fire as the DRSP area is built out over time. The applicant has offered to donate an improved 2-acre fire station site at the northwest intersection corner of Collector A and Cherokee Place, which will include street frontage improvements on Collector A and utilities stubbed to serve the site.

6.5 Solid Waste, Recycling, and Green Waste

Solid waste, recycling, and green waste generated by the new development will be serviced by the South County Sanitary Services. The solid waste, recycling, and green waste will be disposed of at the Cold Canyon Landfill. Based on current disposal rates, this facility has a capacity to accept solid waste until at least the year 2040. South County Sanitary Services has reviewed the conceptual plans and will provide solid waste, recycling, and green waste pick-up service to the DRSP area.

6.6 Postal Service

Postal Service for the DRSP area will be provided by the United States Postal Service (USPS) from their location at 706 West Tefft Street. The location of and type of mailbox required for each land use within the DRSP will be based upon and adhere to requirements outlined in the USPS National Delivery Planning Standards: A Guide for Builders and Developers and the Delivery Growth Management Program. Below is a discussion of the mailbox locations envisioned for each area within the DRSP, each of which will be ultimately approved by the USPS prior to construction.

For each single-family residential neighborhood and commercial within the DRSP area, a centralized delivery location will be provided. The specific location and equipment type will adhere to the USPS requirements for both USPS and customers related to access, locks, safety, accessibility, placement, and specific Americans with Disabilities Act (ADA) requirements. In specifically considering the single-family residential neighborhoods, the centralized delivery locations will be within the individual neighborhood parks.



Examples of mailbox enclosures for individual residences and multifamily neighborhoods.

For each multi-family residential community within the DRSP area, a centralized mailbox location, whether internal or external, will be provided for each of the multi-family residential communities. The centralized mailbox equipment will be approved by USPS and will meet the minimum 1:10 parcel locker/mailbox requirement. If located exterior to a building, a canopy will be provided to provide protection from weather and provide adequate nighttime lighting, per USPS requirements.

6.7 Library

Library services for the DRSP area will be provided by the existing Nipomo Library, located at 918 West Tefft Street in Nipomo. The library features a wide variety of book titles such as children, adult fiction and non-fiction, teen collection, and audiobooks as well as DVD's and music. Twelve computers, free public WIFI internet access, and a public meeting room are also provided for use by the public.

Developer impact fees will be paid to the County Public Library to accommodate new demand for library facilities as the DRSP area is built out over time.



Example of library computer desk stations.

6.8 General Government Services

Since the property lies within the unincorporated area of the County of San Luis Obispo, the DRSP area will be serviced by the County's government services, which includes, but is not limited to: administration, planning, voting, courts, environmental/public health, public works, etc.

This Page Intentionally Blank.

7 Implementation and Administration

This Chapter describes the DRSP authority, development review process, and administrative procedures controlling the DRSP adjustments and amendments, as well as outlines the intended phasing plan and the proposed construction/maintenance of improvements.

The DRSP provides County review authorities the tools and guidelines to review and approve the DRSP area development proposals. Implementation shall be administered by County review authorities and ensure consistency with the DRSP document.

7.1 Specific Plan Authority and Adoption

Specific plans must comply with California Government Code Sections 65450 through 65457. These provisions require that a specific plan be consistent with the adopted General Plan for the jurisdiction in which the specific plan area is located. In turn, all subsequent development proposals, such as tentative subdivision maps, site plans, improvement plans, and all public works projects, must be consistent with the adopted specific plan.

Pursuant to California Government Code Section 65453, a specific plan may be adopted by resolution or by ordinance. Past County practice has been to adopt a specific plan and certify the Final Environmental Impact Report (FEIR) concurrently through resolution. Customized land use categories are provided to implement the land uses identified in Chapter 2. Land use categories included herein supersede the County's Land Use Ordinance (Title 22) except where the DRSP is silent. In such cases, the existing County land use category standards shall apply.

7.2 Development Agreement

A development agreement is a planning tool that allows public agencies greater latitude to advance local planning policies in sometimes new and creative ways. A development agreement is commonly used in conjunction with specific plan projects.

Neither the applicant nor the public agency is required to enter into a development agreement as part of project proposal. When a development agreement is entered into, the allowable land uses, required infrastructure and its financing, as well as other terms and conditions of approval are negotiated between the parties involved, subject to the public agency's ultimate approval.

7.3 Environmental Review

The DRSP addresses land uses, densities, and types of development proposed, as well as streets and infrastructure anticipated to serve the area. It provides a detailed description of the project that was evaluated in the Final Project Environmental Impact Report (FEIR) for the DRSP. Under the California Environmental Quality Act (CEQA), the FEIR has assessed the potential direct and indirect environmental effects associated with the land use program described in the DRSP.

Although the EIR is a separate document, the environmental review process has been an integral component of the planning process to ensure that the DRSP minimizes environmental impacts. The EIR addresses the development of the DRSP as a single project which is projected to be developed in increments over a period of several years. This approach enables the County to comprehensively evaluate the cumulative impacts of the DRSP and consider alternatives and mitigation measures prior to adoption of the DRSP.

Development within the DRSP area shall comply with all conditions of approval and mitigation measures identified in the certified Specific Plan EIR (The Dana Reserve Specific Plan EIR SCH No. 2021060558) and any subsequent CEQA document (e.g., Addendum, Mitigated Negative Declaration, Subsequent EIR, or Supplemental EIR). The DRSP FEIR is intended to expedite the processing of future projects that are consistent with the DRSP. If, when considering subsequent development proposals, the County determines that the proposed development will not result in new effects or require additional mitigation, the County can approve the project without additional environmental review (California Government Code Section 65457 and CEQA Guidelines Section 15182). However, if there are significant changes proposed to the approved DRSP that the County concludes may result in new impacts, any additional environmental review need focus only on those specific areas or topics affected by the change.

7.4 Annexation

The DRSP is currently under County jurisdiction and is located within the Nipomo Urban Reserve Line (URL). The property is designated in the County's General Plan as a specific plan area, which was subject to preparation of a specific plan to accommodate development proposals and address pertinent issues (refer to Chapter 1). The General Plan required that a specific plan for the property be adopted prior to annexation of the DRSP area to the URL. The DRSP area was then annexed into the NCSD's Service Boundary area.

Following Board of Supervisor action of project entitlements including adoption of the DRSP and certification of the FEIR, the project was submitted by NCSD to the Local Agency Formation Commission (LAFCO) and was formally annexed into the NCSD Service Boundary area. As part of this process, LAFCO worked with the County and NCSD to ensure that a proper plan of services was in place to guide orderly development of the annexed property.

7.5 Development Review Process

Land Use Boundaries

The Land Use Element of the County's General Plan defines and identifies the purpose and character for each of the County's 14 land use categories. These land use categories, which serve as both the County's Land Use Element and zoning maps, comprise the County's "single map" system for land use and development. To implement the DRSP, the subject property will be redesignated from the Residential Rural land use category to a 15th County land use category called "Dana Reserve Specific Plan (DRSP)," except for APNs 091-301-029 and 091-301-301, which will remain Residential Rural. The DRSP land use category will direct future landowners and developers to this Specific Plan for allowable land uses, development standards, and permitting requirements.

Future development within the DRSP land use category shall correspond with the eight (8) Land Uses identified in Exhibit 2-1 and the development standards, allowable uses, and all other related requirements identified in Chapter 2 and the objective design standards and guidelines identified in Appendix A, not Table 2-3 in Section 22.08.030 or Article 4 of the County Land Use Ordinance. In instances where the DRSP is silent on a particular topic or requirement, development will instead be subject to the requirements of the County's Land Use Ordinance, Title 22 of the County Code, or by interpretation of the Director of Planning and Building as identified in Section 7.7 below, for the most closely related land use category. For example, for development in the DR-SF 1 and DR-SF 2 land uses, the requirements of the RSF Land Use Category in Title 22 will apply when the DRSP is silent on a topic.

Processing, Uses, and Plan Interpretation

Subdivisions

The precise location of streets, utilities, and boundaries of development sites will be determined upon approval of tentative subdivision maps as part of a Land Division application. Along with the review of the final map before recording, subdivision improvement plans will be reviewed and approved by the Planning Commission, which will show compliance with the DRSP, EIR, and any associated project conditions of approval. As part of the Land Division application submittal and subsequent review by Planning Commission, applicants are required to provide preliminary floor plans and architectural elevations for uses that only require a Site Plan that show height of buildings and structures, color, texture, and material of exterior finishes and roofing. Where the architecture of a project meets the relevant objective design standard requirements identified in Appendix A, the preliminary floor plans and architectural elevations provided are intended to be for informational purposes only as part of the Land Division application.

Land Use Permits

Conditional Use Permit

As part of the DRSP project, a conditional use permit will be required in conjunction with the Oak Woodland Management Plan.

Uses identified in Chapter 2, Tables 2.5, 2.8, and 2.11 requiring a Conditional Use Permit shall be processed according to County Land Use Ordinance Section 22.62.060.

Minor Use Permit

Uses identified in Chapter 2, Tables 2.5, 2.8, and 2.11 requiring a Minor Use Permit shall be processed according to County Land Use Ordinance Section 22.62.050.

Site Plan Review

Uses identified in Chapter 2, Tables 2.5, 2.8, and 2.11 requiring a Site Plan Review shall be processed according to County Land Use Ordinance Section 22.62.040.

Zoning Clearance

Uses identified in Chapter 2, Tables 2.5, 2.8, and 2.11 requiring a Zoning Clearance shall be processed according to County Land Use Ordinance Section 22.62.030.

Objective Design Standards and Guidelines

Residential, Commercial, and Recreation and Open Space land uses within the DRSP are required to adhere to the relevant objective design standards and guidelines identified in Appendix A, not the San Luis Obispo County Design Guidelines. When applicable, as part of an application submittal to the County, the applicant shall provide an analysis of how the project complies with the relevant objective design standards and guidelines for use by the County.

Building Permits

The County building permit process of plan-check, inspection, and occupancy release will typically be the final and most detailed step in County review of private site development. Impact fees are due at the time building permits are issued or as may be described in the development agreement. If required, Inclusionary housing fees will be required to pay at time of building permits.

7.6 Construction and Maintenance of Required Improvements

Public facilities required to serve the DRSP area will be funded as discussed in Chapter 8. Property in the DRSP area that is annexed into the URL will receive the same public services as other neighborhoods in the community, including school, police, fire, neighborhood park, and Collector Road maintenance. Once facilities to serve the DRSP are constructed, a Homeowners Association will be established to operate and maintain facilities, such as parkways, off-street pedestrian trails and equestrian trails, open space, neighborhood park and pocket parks, and stormwater facilities. Facilities located within individual residential neighborhoods, such as pocket parks, parkways, stormwater facilities, and local roads, will also be privately maintained by a Homeowners Association. Collector Roads A, B, and C will be maintained by the County.

7.7 Interpretations, Adjustments, and Amendments to the Specific Plan

Interpretations

In instances where the DRSP may not be clear or completely articulate a particular topic related to plan implementation, the Director of San Luis Obispo County Planning and Building (Director) or his/her designee may provide an interpretation based on whether the item in question is in keeping with the vision and intent of the DRSP. The Director has the authority to refer a Zoning Clearance or Site Plan to the Planning Commission if questions arise regarding the applicability of a policy, standard, or mitigation measure to a proposed land use or development within the DRSP.

Adjustments to LUO Development Standards

New development and land uses within the DRSP will be subject to LUO standards, when this Specific Plan is silent on a particular topic. For example, a detached garage will continue to be subject to a 1,000 square-foot size limitation as provided in LUO Section 22.30.410 because the DRSP does not allow for a larger detached garage. These development standards may be waived through a MUP or CUP when procedures to do so are provided in the LUO. For example, the LUO allows for a detached garage greater than 1,000 square feet subject to MUP approval. In such an instance, the MUP requirement would supersede the permitting requirements in Chapter 2 of the Specific Plan.

Adjustments in Project Phasing

Project features may be advanced to an earlier phase provided all required infrastructure is in place, all necessary mitigation measures are completed or will be completed with project, and the action will not significantly defer a project feature that is anticipated in a preceding phase. The determination to advance a project feature shall be made by the Director or his/her designee. Any adjustments in project phasing needs to be consistent with Section 7.3 of the DRSP and the findings of the FEIR.

Amendments

California Government Code Section 65453 et. Seq. provides that a Specific Plan “may be amended as often as deemed necessary by the legislative body”. Amendments to this plan may be initiated by a developer, any individual property owner, or by the County, in accordance with duly adopted County procedures governing the adoption and amendment of the Specific Plan. Applications for amendments shall be submitted to the County Department of Planning and Building for processing.

Necessary Findings

- A. Changes have occurred in the community since the approval of the Specific Plan which warrant the proposed amendment.
- B. The proposed amendment is consistent with the San Luis Obispo County General Plan.
- C. The proposed amendment may enable efficient and less costly delivery of necessary services, housing, and public facilities to the population within the area of this Specific Plan and the Nipomo Mesa.

This Page Intentionally Blank.

8 Financing

This Chapter describes the financing mechanisms available for the ongoing maintenance of public and private improvements required for the DRSP. Upon preparation of a DRSP master maintenance plan, it is anticipated that one or more financing mechanisms will be used to provide for the ongoing maintenance of private and public improvements. California law provides for the establishment of a variety of financing mechanisms for maintaining public facilities, including, but not limited to, Landscape Maintenance Districts (“LMD”), County Service Areas (“CSA”), Community Facilities Districts (“CFD” and together with the LMD and CSA, “Public Financing District”). Privately owned common facilities are typically maintained by a Homeowners Association (“HOA”). Public Financing Districts are established by a public agency, while an HOA is established by a private entity in compliance with standards established by the California Bureau of Real Estate. It is anticipated the maintenance of DRSP improvements (e.g., landscaping, park, drainage, trails, open space, street lights, etc.) will be maintained and funded by a combination of a Public Financing District and/or one or more HOAs. The sewer and water improvements are anticipated to be owned, operated, and maintained by the Nipomo Community Services District, provided annexation occurs.

8.1 Financing Principles and Policies

It is the objective of the DRSP to have a neutral fiscal impact on the County and other public agencies maintaining project facilities. The financing mechanisms to be established for the DRSP shall consider the following:

- Parties benefiting from the improvements;
- Security for the funding of the ongoing maintenance;
- Establishment of sufficient reserve funds for repairs and replacements;
- Flexibility for changes in annual maintenance costs;
- Interest of future residents paying annual assessments;
- Equity among contributing property owners; and
- Transparency regarding the costs of maintenance services and improvements being funded.

8.2 Public Financing Districts

The establishment of a Public Financing District generally requires:

- (i) A landowner to submit a petition requesting a public agency to establish a specific Public Financing District,
- (ii) Identifying the facilities to be maintained and corresponding estimated maintenance costs,
- (iii) The public agency establishing the proposed annual assessments or special taxes to fund the maintenance of the requested improvements pursuant to an engineer’s report or similar document, and
- (iv) The landowner voting in favor of the formation of the Public Financing District and the levy of such assessments or special taxes.

Upon a successful landowner vote, the public agency then has authority to levy the assessments on the property as authorized to fund annual maintenance costs. Although different types of Public Financing Districts can maintain many of the same improvements, the legislative provisions for establishing each type and the related requirements of each are different. For example, the assessments levied on each parcel of property for improvements maintained with an LMD need to be based on the special benefit received by such parcels of property, while a CFD special tax is based on a general benefit requirement. Many public agencies have determined the “general benefit” requirements of the CFD make it a more favorable financing mechanism and less likely to be challenged or repealed under the provisions of Proposition 218.

Appendix A - Objective Design Standards and Design Guidelines

The purpose of these objective design standards and guidelines is to ensure future development is consistent with the vision and character of the Dana Reserve Specific Plan (DRSP) project. It is also intended to provide direction for subdividers, architects, and designers when preparing plans, and to provide direction for governmental review bodies for project evaluation as future applications come forward.

Terminology

Objective design standards are mandatory items or features that are required to be incorporated into plan preparation. Design guidelines are provided to give direction that is important to consider in the plan preparation process but are not mandatory.

Applicability

The following identifies the applicability of the relevant objective design standards and design guidelines by land uses and Neighborhoods within the DRSP. Refer to Chapter 7 - Implementation and Administration for additional information on the objective design standards and design guidelines processing requirements for future development within the DRSP.

Section 1.1 Single-Family Residential (DR-SF1 and DR-SF2)

As identified in Chapter 2, Exhibit 2-2a, single-family homes in Neighborhoods 3, 4, 5, and 6 are required to only meet the objective design standards.

Section 1.2 Single-Family Residential (DR-SF1 and DR-SF2)

As identified in Chapter 2, Exhibit 2-2a, single-family homes in Neighborhoods 7, 8, and 9 are required to only meet the design guidelines.

Section 1.3 Multi-Family Residential (DR-MF)

As identified in Chapter 2, Exhibit 2-2a, multi-family homes in Neighborhoods 1, 2, and 10 are required to only meet the objective design standards.

Section 2.1 Village and Flex Commercial (DR-VC and DR-FC)

As identified in Chapter 2, Exhibit 2-2a, commercial development in the Village Commercial and Flex Commercial land uses are required to only meet the design guidelines. Multi-family homes shall meet the objective design standards of the Multi-Family Residential (DR-MF).

Section 3.1 Recreation and Open Space (DR-REC and DR-OS)

As identified in Chapter 2, Exhibit 2-2a, commercial development in the Recreation and Open Space land uses are required to only meet the design guidelines.

Section 4.1 Child Day Care Center

The Child Day Care Center planned to be located at the Neighborhood Park is required to only meet the objective design standards.

Section 5.1 Gateways and Wayfinding Signage

Gateways and wayfinding signage are required to only meet the relevant design guidelines.

Section 6.1 Park and Ride and Transit Stops

Park and Ride and transit stops in the DRSP are required to only meet the relevant design guidelines.

1.1 Single-Family Residential Objective Design Standards


The following objective design standards apply to single-family residential homes and ADUs in Neighborhoods 3, 4, 5, 6 within the DRSP. As part of a permit application submittal, an analysis shall be provided to the County demonstrating how a home complies with the relevant objective design standards.

1.1.A Architectural Styles

The architectural character for the DRSP is intended to be representative of the architectural styles typically found within the Nipomo area. Architectural styles for single-family residential units in Neighborhoods 3, 4, 5, and 6 has been provided. (Refer to Exhibits 1-1 through 1-3).

- A.1 Architectural styles for single-family neighborhoods within Dana Reserve shall be Agrarian, California Ranch, or Spanish. Exhibits 1-1, 1-2, and 1-3 define these architectural styles and project designs must provide a minimum of four (4) of the identified elements to qualify as the required architectural style.
- A.2 Individual single-family neighborhoods shall be designed with one primary architectural style and a minimum 30% mix of the other two architectural styles.
- A.3 Residential elevations within the single-family neighborhoods shall not be repeated more frequently than every fourth house. This variation may be achieved by not repeating both a color scheme and an elevation style or through the use of reverse plans.
- A.4 Single-family residential shall not exceed two stories in height, except where Chapter 2, Exhibit 2-2A limits height to one-story.


Exhibit 1-1: Agrarian Architectural Character



Single-Family (DR-SF1 and DR-SF2)

- | | |
|---|---|
| <p>① Vertical accent massing at primary entry - elements with a minimum 2-foot projection/recess carried up to roofline</p> <p>② Steep pitch gable and shed roofs - minimum 4:12</p> <p>③ Wood-like material surrounds at windows and doors</p> <p>④ Accentuated lintels and sills - minimum 2.5-inches height and minimum 1-inch depth</p> | <p>⑤ Accent features - minimum 5 types of accent features (wainscot, wood brackets, metal roofs, custom vents, shutters) provided on a primary and street-facing elevation</p> <p>⑥ Vertical accent material - board and batten siding with minimum of 30% of primary elevation</p> <p>⑦ Metal lantern, sconce, or goose neck lighting that is dark sky compliant</p> |
|---|---|


Exhibit 1-2: Spanish Architectural Character



Single-Family (DR-SF1 and DR-SF2)

- | | |
|---|---|
| <p>① Asymmetrical massing with side-gable, cross-gable, hipped-and-gabled, hipped, or flat roof type</p> <p>② Low sloping tile roofs - maximum 4:12</p> <p>③ Detailing eaves - maximum eave depth of 18-inches, minimum of 6-inches</p> | <p>④ Accent features - minimum 5 types of accent features (wrought iron, decorative tile, shutters, rafter tails, decorative venting, decorative cornices, and arched openings) provided on a primary and street-facing elevation</p> <p>⑤ Smooth or sand plaster finish</p> <p>⑥ Bronze or iron lantern, sconce, or chandelier lighting that is dark sky compliant</p> |
|---|---|

Exhibit 1-3: California Ranch Architectural Character



Single-Family (DR-SF1 and DR-SF2)

- | | |
|---|---|
| <p>① Asymmetrical massing with primary fronting gables.</p> <p>② Low pitched hipped or gabled roof with wide eaves - maximum 4:12 pitch and minimum 18-inch eaves.</p> <p>③ Wood-like material surrounds for windows and doors at lap siding - minimum 4-inches in height and 1-inch in depth</p> <p>④ Stone lintel minimum of 6-inches in height and 2-inches in depth protruding from building face</p> <p>⑤ Picture windows facing the street e.g. minimum 4-foot height and width</p> <p>⑥ Recessed windows and doors at stucco without surrounds - minimum 1.5-inches recess</p> | <p>⑦ Precast surrounds at windows or openings at stone or brick have - minimum 2-inches height and minimum 1-inch depth</p> <p>⑧ Accent features - minimum 5 types of accent features (simple moldings, lintels, wood brackets, shutters, wrought iron, decorative venting, picture window, and precast elements) provided on a primary and street-facing elevation</p> <p>⑨ Lap siding and stucco as typical materials. One accent material that is either brick or ashlar stone - minimum of 20% primary building elevation</p> <p>⑩ Metal lantern, sconce, or goose neck lighting that is dark sky compliant</p> |
|---|---|

1.1.B Lot Design

- B.1. To create variation in neighborhoods, each lot shall include a minimum of one (1) of the following elements: varied front yard setbacks, varied unit elevations, and/or varied height variation shall be used to create a diversity of architectural character.
- B.2. Yards of single-family residential uses abutting open space shall not have gates onto the open space.

1.1.C Building Form

- C.1. Massing design for buildings shall include a minimum of two (2) of the following elements: variation in wall plane with a minimum 2-foot projection/recess, a minimum 2-foot variation in wall height, and/or a minimum of two roof planes and pitches at different levels.
- C.2. A minimum of one-third of the upper story above the first story shall be stepped back a minimum of 2-feet in order to reduce the scale of the façade that faces the street and to break up the overall massing. In-lieu of an upper story setback, desired variation may be achieved through inclusion of a porch covering a minimum of 30% of the front facade.

1.1.D Roofs

- D.1. A minimum of two (2) roof planes and pitches, overhangs, and/or accent details shall be incorporated into home designs to increase the visual quality and character of a building. Refer to Exhibits 1-1, 1-2, and 1-3 for stylistic appropriate roof planes and pitches, overhangs, and accent details.
- D.2. Roof penetrations for vents shall be consolidated and located on the rear yard side of roof ridges where practical. Vents shall be painted or be a material that matches the roof color.

1.1.E Windows and Doors

- E.1. Windows shall be articulated with a minimum of two (2) of the following elements: accent trim, sills, shutters, window flower boxes, awnings, trellises, and/or other elements authentic to the architectural style of the building. Refer to Exhibits 1-1, 1-2, and 1-3 for stylistic appropriate window articulation elements.
- E.2. Garages shall be a secondary element on a home's main façade through the incorporation of a recess to minimize the visual impact of the garage door and parking apron from the street. Side loaded garages may be provided for up to 30% of a neighborhood's residences.
- E.3. Mirrored glass and/or reflective coating on doors and window glass and garage doors is prohibited.

Building Form, Roofs - Refer to page A-6 for callout text.



1.1.F Entries and Porches

- F.1. Primary residential entries for single-family residences shall include a porch for a minimum of 60% of all residences in an individual neighborhood and a minimum of one (1) of the following elements: feature window, decorative material, change in roofline or wall plane, or accent lighting.
- F.2. Single-family residences located on corner lots shall have a patio or porch that wraps around and addresses a minimum of 20% of both the primary and secondary building frontages. Corner lots shall locate the driveway on the long side frontage.
- F.3. Porches and patios shall have a minimum depth of six (6) feet and balconies shall have a minimum depth of four (4) feet (Note: porch posts or columns may protrude into the minimum depth area).

1.1.G Colors and Materials

- G.1. Building designs shall include a minimum of one (1) principal color and one (1) accent color.
- G.2. The primary exterior material for buildings shall be wood, composite wood, stone, stone veneer, granite, slate, brick, brick veneer, stucco, plaster, fiber cement, aluminum/steel (color coated only), or steel. Refer to Exhibits 1-1, 1-2, and 1-3 for stylistic appropriate colors and materials.
- G.3. Use of a minimum of two (2) accent materials, such as tile, brick, stone, concrete, or plaster, shall be incorporated to highlight building features. Refer to Exhibits 1-1, 1-2, and 1-3 for stylistic appropriate colors and materials.
- G.4. Changes in material or color shall occur at inside corners of intersecting walls or at architectural features that break up the wall plane, such as at columns or banding.

Windows and Doors, Entries and Porches, Colors and Materials - Refer to page A-8 for callout text.



1.1.H Residential Fencing/Walls

- H.1. Front yard fencing type shall be wood, composite wood-textured, open style metal, stucco wall, stone and/or a combination of the listed materials.
- H.2. Where a side or rear yard is abutting a residential or commercial land use, closed wood fencing and/or similar composite wood-textured material shall be used. Refer to Exhibit 1-4.
- H.3. Where a side or rear yard is abutting, pocket park, or open space use, wood fencing and/or similar composite wood-textured material shall be used to 4-feet in height with an additional 2-feet comprised on top of a minimum 50% open rail permeable fencing. Refer to Exhibit 1-6 and Residential Single-Family Fencing Exhibit on page A-10.
- H.4. Rear yard fencing of abutting residential neighborhoods (e.g. Neighborhood 4 and 5) shall maintain consistency in fencing type and material and Residential Single-Family Fencing Exhibit on page A-10.
- H.5. Rear yard fencing adjacent to or across from Recreation or Open Space land uses shall utilize either an open style metal fence type or wood fencing and/or similar composite wood-textured material shall be used to 4-feet in height with an additional 2-feet comprised on top of a minimum 50% open rail permeable fencing. Fencing selection shall be consistent across an individual neighborhood. Refer to the Residential Single-Family Fencing Exhibit on page A-10.
- H.6. Finished side of fencing should face street side yards, open spaces, or other public spaces. The finished side of fencing is defined as the primary face of a fence.
- H.7. Use of chain link, razor/barbed wire, non-matte finish vinyl fencing, and temporary fencing, except for construction related temporary fencing, are prohibited.
- H.8. Three-rail, split rail fence of wood or similar composite wood-textured material shall be provided at pocket parks and streets, as shown in the Recreation and Open Space Fencing exhibit.

Residential Single-Family Fencing



Fencing Concepts



Exhibit 1-4: Closed Wood Fence Example



Exhibit 1-5: Open Style Metal Fence Example



Exhibit 1-6: Semi-Open Wood Fence Example

1.1.I Private Open Spaces

I.1. All single-family residences shall have at least one usable private open space in the side or rear yard in accordance with the standards in Chapter 2.

1.1.J Landscape

J.1. Native trees, plants, and other low water using plant varieties shall be integrated into residential neighborhoods and at the front yards of individual residential lots, consistent with the County Planting List, and cover a minimum of 20% of a lot.

J.2. Native coast live oak trees shall be used in neighborhood parkways.

J.3. If irrigated turf is utilized as part of landscape design, it shall not exceed 5% of the lot area.

J.4. Front yard landscaping shall be installed by the developer prior to occupancy by a resident.

J.5. Landscape design shall be consistent with applicable Model Water Efficient Landscape Ordinance (MWELO) requirements for water efficiency.

J.6. All neighborhood and front yard landscape plans shall be prepared by a licensed landscape architect.

1.1.K Lighting

- K.1. Type and design of site and building lighting fixtures shall be “dark-sky” compliant, consistent with the International Dark-Sky Association or County of San Luis Obispo requirements.
- K.2. Building lighting shall complement the architectural style of the building it serves. Refer to Exhibits 1-1, 1-2, and 1-3 for stylistic appropriate lighting.
- K.3. Special care shall be taken to control glare and direct visibility of security lighting illumination sources, and to confine illumination to the property on which the fixtures are located.

1.1.L Utilitarian

- L.1. Rain gutters, downspouts, vents, and roof protrusions shall match the adjacent building color.
- L.2. Any outdoor mechanical or utility equipment/meters, antennae, “dish type receivers”, etc., whether on a roof, side of a structure, or ground mounted shall be screened from view to not be visible from the street frontage. Method of screening shall be architecturally integrated with the adjacent structure in terms of materials, color, shape, and size, or if ground mounted, may include landscaping.
- L.3. Garages for residences shall provide storage space for trash/recycling/green waste receptacles inside the garage or if located outside the garage shall be screened from view along a side yard.

1.1.M Accessory Structures

- M.1. Accessory structures, including detached garages and carports, accessory dwelling units, grouped mailboxes, storage and maintenance facilities, recreational facilities, picnic shelters, and outdoor shade structures, should incorporate compatible materials, scale, colors, architectural details, and roof slopes as the primary residential buildings they serve.

1.1.N Signage

Signage for the individual neighborhoods within the DRSP shall be subject to the objective design standards outlined below:

- N.1. Future neighborhoods are required to submit a sign program for review and approval, consistent with the County’s Sign Ordinance.

1.2 Single-Family Residential Design Guidelines

The following design guidelines apply to single-family residential development in Neighborhoods 7, 8, and 9 within the DRSP. As part of a permit application submittal, an analysis shall be provided to the County demonstrating how a project complies with the relevant design guidelines.

1.2.A Architectural Styles

The architectural character for the DRSP is intended to be representative of the architectural styles typically found within the Nipomo area. A list of architectural styles appropriate for single-family residential development in Neighborhoods 7, 8, and 9 has been provided. Refer to Exhibits 1-4 through 1-6 for graphics that identify architectural style elements.


A.1 Architectural styles for single-family residential land uses within Dana Reserve shall be Agrarian, California Ranch, or Spanish. Exhibits 1-7, 1-8, and 1-9 define these architectural styles.

A.2 Individual single-family neighborhoods shall be designed with a one primary style and a balanced mix of the other two architectural styles.

A.3 Residential elevations within the single-family neighborhoods shall not be repeated more frequently than every fourth house. This variation may be achieved by not repeating both a color scheme and an elevation style or through the use of reverse plans.

A.4 Single-family residential shall not exceed two stories in height, except where Chapter 2, Exhibit 2-2A limits height to one-story.

Exhibit 1-7: Agrarian Architectural Character




Single-Family (DR-SF1 and DR-SF2)

- | | |
|---|---|
| ① Vertical accent massing at primary entry | ⑤ Accent features like - wainscot, wood brackets, metal roofs, custom vents, shutters provided on a primary and street-facing elevation |
| ② Steep pitch gable and shed roofs e.g. 4:12 | |
| ③ Wood-like material surrounds at windows and doors | ⑥ Vertical accent material - board and batten siding |
| ④ Accentuated lintels and sills | ⑦ Metal lantern, sconce, or goose neck lighting that is dark sky compliant |

The graphics shown above are conceptual in nature and are not intended to be reflective of a specific project, rather they are provided as inspiration for architects and designers.

Exhibit 1-8: Spanish Architectural Character




Single-Family (DR-SF1 and DR-SF2)

- | | |
|--|--|
| <ul style="list-style-type: none"> ① Asymmetrical massing with side-gable, cross-gable, hipped-and-gabled, hipped, or flat roof type ② Low sloping tile roofs - 4:12 or less ③ Detailing at eaves ④ Arched openings e.g. windows, doors, porches | <ul style="list-style-type: none"> ⑤ Accent features - wrought iron, decorative tile, shutters, rafter tails, decorative venting, decorative cornices, and arched openings. ⑥ Smooth or sand plaster finish ⑦ Bronze or iron lantern, sconce, or chandelier lighting that is dark sky compliant |
|--|--|

The graphics shown above are conceptual in nature and are not intended to be reflective of a specific project, rather they are provided as inspiration for architects and designers.

Exhibit 1-9: California Ranch Architectural Character



Single-Family (DR-SF1 and DR-SF2)

- | | |
|---|--|
| <p>① Asymmetrical massing with primary fronting gables</p> <p>② Low pitched hipped or gabled roof with wide eaves e.g. 4:12 pitch max and 18" min eaves</p> <p>③ Wood-like material surrounds for windows and doors at lap siding</p> <p>④ Stone lintel protruding from building face</p> <p>⑤ Picture windows facing the street</p> <p>⑥ Recessed windows and doors at stucco without surrounds.</p> | <p>⑦ Precast surrounds at windows or openings at stone or brick</p> <p>⑧ Accent features - simple moldings, lintels, wood brackets, shutters, wrought iron, decorative venting, picture window, and precast elements provided on primary and street-facing elevation</p> <p>⑨ Lap siding, and stucco as typical materials. One accent material that is either brick or ashlar stone.</p> <p>⑩ Metal lantern, sconce, or goose neck lighting that is dark sky compliant</p> |
|---|--|

The graphics shown above are conceptual in nature and are not intended to be reflective of a specific project, rather they are provided as inspiration for architects and designers.

1.2.B Lot Design

- B.1. Variation in front yard setbacks, lot widths, and height variation should be used where able to create a diversity of architectural character for the single-family neighborhoods.
- B.2. Yards of single-family residential uses abutting open space shall not have gates onto the open space.

1.2.C Building Form

- C.1. Massing design should include variation in the wall plane (projection and recess), variation in wall height, and rooflines at different levels.
- C.2. Portions of the upper story above the first story should be stepped back in order to reduce the scale of the façade that faces the street and the rear yards and to break up the overall massing. In-lieu of an upper story setback, desired variation could be achieved with a porch covering a minimum of 30% of the front facade.
- C.3. Architectural elements that add visual interest, scale, and character to the neighborhood, such as recessed or projecting balconies, verandas, or porches should face the street and be included within building designs.

1.2.D Roofs

- D.1. A variety of roof planes and pitches, porches, overhangs, and accent details should be incorporated into home designs to increase the visual quality and character of a building, while reducing the bulk and size of the structure. Refer to Exhibits 1-7, 1-8, and 1-9 for stylistic appropriate roof planes and pitches, overhangs, and accent details.
- D.2. Roof penetrations for vents should be consolidated and located on the rear yard side of roof ridges whenever practical. Vents should be painted or be a material that matches the roof color.

1.2.E Windows and Doors

- E.1. Windows should be articulated with accent trim, sills, shutters, window flower boxes, awnings, trellises, and/or other elements authentic to the architectural style of the building. Refer to Exhibits 1-7, 1-8, and 1-9 for stylistic appropriate window articulation elements.
- E.2. Windows, doors, and garage doors should incorporate architectural detailing that is consistent with the overall architectural style of the building.
- E.3. Garages should be a secondary element on a home's main façade to minimize the visual impact of the garage door and parking apron from the street. Side loaded or hollywood style garages are also encourage to provide variety along street frontages.
- E.4. Mirrored glass and/or reflective coating on doors and window glass and garage doors is prohibited.

Building Form, Roofs - Refer to page A-18 for callout text.



The graphics shown above are conceptual in nature and are not intended to be reflective of a specific project, rather they are provided as inspiration for architects and designers.


1.2.F Entries and Porches

- F.1. Primary residential entries for single-family residences should be enhanced to reflect the architectural style and details of the home.
- F.2. Single-family residences located on corner lots should have patios or porches that wraps around and address both the primary and secondary building frontages. Corner lots should locate the driveway along the side frontage.
- F.3. Porches and patios shall be a primary element on the main facade have a minimum depth of six (6) feet and balconies shall have a minimum depth of four (4) feet (Note: porch posts or columns may protrude into the minimum six (6) feet of depth).

1.2.G Colors and Materials

- G.1. Materials and colors should be used in an authentic manner, reinforcing the chosen architectural style.
- G.2. The primary exterior material for buildings shall be wood, composite wood, stone, stone veneer, granite, slate, brick, brick veneer, stucco, plaster, fiber cement, aluminum/steel (color coated only), or steel. Refer to Exhibits 1-7, 1-8, and 1-9 for stylistic appropriate colors and materials.
- G.3. A variety of roof materials and color palettes consistent with the architectural style of the homes should be incorporated to enhance the character of the community.
- G.4. Changes in material or color shall occur at inside corners of intersecting walls or at architectural features that break up the wall plane, such as at columns or banding.

Windows and Doors, Entries and Porches, Colors and Materials



The graphics shown above are conceptual in nature and are not intended to be reflective of a specific project, rather they are provided as inspiration for architects and designers.

1.2.H Residential Fencing/Walls

- H.1. Front yard fencing type shall be wood, composite wood-textured, open style metal, stucco wall, stone and/or a combination of these listed materials.
- H.2. Where a side or rear yard is abutting a residential land use, closed wood fencing and/or similar composite wood-textured material shall be used. Refer to Exhibit 1-4 and Residential Single-Family Fencing Exhibit on page A-10.
- H.3. Where a side or rear yard is abutting, pocket park, or open space use, wood fencing and/or similar composite wood-textured material should be used to 4-feet in height with an additional 2-feet comprised on top of a minimum 50% open rail permeable fencing. Refer to Exhibit 1-6 and Residential Single-Family Fencing Exhibit on page A-10.
- H.4. Rear yard fencing adjacent to or across from Recreation or Open Space land uses shall utilize either an open style metal fence type or wood fencing and/or similar composite wood-textured material shall be used to 4-feet in height with an additional 2-feet comprised on top of a minimum 50% open rail permeable fencing. Fencing selection shall be consistent across an individual neighborhood. Refer to the Residential Single Family Fencing Exhibit and Residential Single-Family Fencing Exhibit on page A-10.
- H.5. Finished side of fencing should face street side yards, open spaces, or other public spaces.
- H.6. Use of chain link, razor/barbed wire, non-matte finish vinyl fencing, and temporary fencing, except for construction related temporary fencing, are prohibited.
- H.7. Three-rail, split rail fence of wood or similar composite wood-textured material shall be provided at pocket parks and streets, as shown in the Recreation and Open Space Fencing exhibit.

1.2.I Private Open Spaces

- I.1. All single-family residences should have at least one usable private open space in the side or rear yard area in accordance with the design standards in Chapter 2 of the DRSP. Multiple usable outdoor areas (i.e. front, side, and/or rear) are preferable and encouraged where practical.

1.2.J Landscape

- J.1. Native trees, plants, and other low water using plant varieties are encouraged within the DRSP and should be integrated into the residential neighborhoods and at the front yards of individual residential lots, consistent with the County Planting List.
- J.2. Native coast live oak trees shall be used in neighborhood parkways.
- J.3. If irrigated turf is utilized as part of landscape design, it should not exceed 5% of the lot area.
- J.4. Front yard landscaping shall be installed by the developer prior to occupancy by a resident.
- J.5. Landscape design shall be consistent with applicable Model Water Efficient Landscape Ordinance (MWELO) requirements for water efficiency.
- J.6. All neighborhood and front yard landscape plans shall be prepared by a licensed landscape architect.

1.2.K Lighting

- K.1. Type and design of site and building lighting fixtures shall be “dark-sky” compliant, consistent with the International Dark-Sky Association or County of San Luis Obispo requirements.
- K.2. Building lighting shall complement the architectural style of the building it serves. Refer to Exhibits 1-7, 1-8, and 1-9 for stylistic appropriate lighting.
- K.3. Any lighting utilized as part of a residential neighborhood signs shall be complementary to the individual design aesthetic of the surrounding neighborhood.
- K.4. Special care shall be taken to control glare and direct visibility of security lighting illumination sources, and to confine illumination to the property on which the fixtures are located.

1.2.L Utilitarian

- L.1. Rain gutters, downspouts, vents, and other roof protrusions should complement the adjacent materials and/or colors.
- L.2. Any outdoor mechanical or utility equipment/meters, antennae, “dish type receivers”, etc, whether on a roof, side of a structure, or ground mounted should be appropriately screened from view to not be visible from the street frontage. Method of screening should be architecturally integrated with the adjacent structure in terms of materials, color, shape, and size, or if ground mounted, may include landscaping.
- L.3. Garages for residences should provide storage space for trash/recycling/green waste receptacles inside the garage or if located outside the garage should be screened from view along a side yard.

1.2.M Accessory Structures

- M.1. Accessory structures, including detached garages and carports, accessory dwelling units, grouped mailboxes, storage and maintenance facilities, recreational facilities, picnic shelters, and outdoor shade structures, should incorporate compatible materials, scale, colors, architectural details, and roof slopes as the primary residential buildings they serve.

1.2.N Signage

Signage for the individual neighborhoods within the DRSP shall be subject to the design guidelines outlined below. Where the DRSP is silent, the County of San Luis Obispo Sign Ordinance will apply. In instances where there may be inconsistencies between the DRSP and the County of San Luis Obispo Sign Ordinance, the DRSP shall prevail.

- N.1. Future neighborhoods are required to submit a sign program for review and approval, consistent with the County’s Sign Ordinance.

1.3 Multi-Family Residential Objective Design Standards

The following objective design standards apply to residential multi-family development within the DRSP. Multi-family neighborhoods in the DRSP includes Neighborhoods 1, 2, and 10. The objective design standards also apply to multi-family residential projects within the Flex Commercial and Village Commercial land uses. As part of a permit submittal, an analysis shall be provided to the County demonstrating how a project complies with the relevant objective design standards.

1.3.A Architectural Styles

The architectural character for the DRSP is intended to be representative of the architectural styles typically found within the Nipomo area. A list of permitted architectural styles appropriate for multi-family residential land use has been provided. Refer to Exhibits 1-7 through 1-9 for conceptual graphics that identify individual architectural style elements provided as inspiration for architects and designers when preparing development plans.

A.1 Architectural styles for multi-family neighborhoods within Dana Reserve shall be Agrarian, California Ranch, or Spanish. Exhibits 1-10, 1-11, and 1-12 define these architectural styles and project designs must provide a minimum of four (4) of the identified elements to qualify as the required architectural style.

A.2 All multi-family buildings within a neighborhood shall be designed uniformly with one of the allowed architectural style.


Exhibit 1-10: Agrarian Architectural Character



Multi-Family (DR-MF)

- | | |
|---|---|
| <p>① Vertical accent massing at primary entry - elements with a minimum 2-foot projection/recess carried up to roofline</p> <p>② Steep pitch gable and shed roofs - minimum 4:12</p> <p>③ Wood-like material surrounds at windows and doors</p> <p>④ Accentuated lintels and sills - minimum 2.5-inches height and minimum 1-inch depth</p> | <p>⑤ Accent features - minimum 5 types of accent features (wainscot, wood brackets, metal roofs, custom vents, shutters) provided on a primary and street-facing elevation</p> <p>⑥ Vertical accent material - board and batten siding with minimum of 30% of primary elevation</p> <p>⑦ Metal lantern, sconce, or goose neck lighting that is dark sky compliant</p> |
|---|---|

Exhibit 1-11: Spanish Architectural Character



Multi-Family (DR-MF)

- | | |
|---|---|
| <p>① Asymmetrical massing with side-gable, cross-gable, hipped-and-gabled, hipped, or flat roof type</p> <p>② Low sloping tile roofs - maximum 4:12</p> <p>③ Detailing eaves - maximum eave depth of 18-inches, minimum of 6-inches</p> | <p>④ Accent features - minimum 5 types of accent features (wrought iron, decorative tile, shutters, rafter tails, decorative venting, decorative cornices, and arched openings) provided on a primary and street-facing elevation</p> <p>⑤ Smooth or sand plaster finish</p> <p>⑥ Bronze or iron lantern, sconce, or chandelier lighting that is dark sky compliant</p> |
|---|---|

Exhibit 1-12: California Ranch Architectural Character



Multi-Family (DR-MF)

- | | |
|---|---|
| <p>① Asymmetrical massing with primary fronting gables.</p> <p>② Low pitched hipped or gabled roof with wide eaves - maximum 4:12 pitch and minimum 18-inch eaves.</p> <p>③ Wood-like material surrounds for windows and doors at lap siding - minimum 4-inches in height and 1-inch in depth</p> <p>④ Stone lintel minimum of 6-inches in height and 2-inches in depth protruding from building face</p> <p>⑤ Picture windows facing the street e.g. minimum 4-foot height and width</p> <p>⑥ Recessed windows and doors at stucco without surrounds - minimum 1.5-inches recess</p> | <p>⑦ Precast surrounds at windows or openings at stone or brick have - minimum 2-inches height and minimum 1-inch depth</p> <p>⑧ Accent features - minimum 5 types of accent features (simple moldings, lintels, wood brackets, shutters, wrought iron, decorative venting, picture window, and precast elements) provided on a primary and street-facing elevation</p> <p>⑨ Lap siding and stucco as typical materials. One accent material that is either brick or ashlar stone - minimum of 20% primary building elevation</p> <p>⑩ Metal lantern, sconce, or goose neck lighting that is dark sky compliant</p> |
|---|---|

1.3.B Site Design

- B.1. To create variation in site design, each building shall include a minimum of one (1) of the following elements: varied unit elevations and/or varied height variation shall be used to create a diversity of architectural character.
- B.2. Multi-family neighborhoods abutting commercial land uses shall provide accessible sidewalks, parkway landscaping with a minimum of two street trees varieties and two accent shrub varieties, and limit driveway access points to the minimum number required by County Public Works standards.
- B.3. Neighborhood entry features shall be provided at vehicular points of entry and include a minimum of two (2) of the following elements: landscaping with two street tree varieties and two accent shrub varieties, decorative paving across neighborhood entry streets with minimum width of 20-feet, decorative walls with stone unique type to neighborhood, and/or neighborhood monument signage.
- B.4. The number of pedestrian linkages connecting to residential, commercial, and recreation and open space land uses shall be provided, as identified in Chapter 2, Exhibit 2-2a.

1.3.C Building Form

- C.1. Massing design for buildings shall include a minimum of two (2) of the following elements: variation in wall plane with a minimum 2-foot projection/recess, a minimum 2-foot variation in wall height, and/or a minimum of two roof planes and pitches at different levels..
- C.2. A minimum of one-third of the upper stories above the first story shall be stepped back in order to reduce the scale of the façade that faces the street and to break up the overall massing. In-lieu of an upper stories setback, desired variation may be achieved through inclusion of a porch covering a minimum of 30% of the front facade.


1.3.D Roofs

- D.1. A minimum of two (2) roof planes and pitches, overhangs, and/or accent details shall be incorporated into designs to increase the visual quality and character of a building. Refer to Exhibits 1-10, 1-11, and 1-12 for stylistic appropriate roof planes and pitches, overhangs, and accent details.
- D.2. Roof penetrations for vents shall be consolidated and located on the rear side of roof ridges where practical or roof articulation feature shall screen view or vents and equipment. Vents shall be painted or be a material that matches the roof color.

1.3.E Windows and Doors

- E.1. Windows shall be articulated with a minimum of two (2) of the following elements: accent trim, sills, shutters, window flower boxes, awnings, trellises, and/or other elements authentic to the architectural style of the building. Refer to Exhibits 1-10, 1-11, and 1-12 for stylistic appropriate window articulation elements.
- E.2. Garages shall be a secondary element on a building's main façade through the incorporation of a recess to minimize the visual impact of the garage door and parking apron from the street. Side loaded garages may be provided for up to 30% of a neighborhood's residences.
- E.3. Mirrored glass and/or reflective coating on doors and window glass and garage doors is prohibited.

Building Form, Roofs - Refer to page A-28 for callout text.



1.3.F Entries and Porches

- F.1. Multi-family buildings shall have porches, patios, balconies, or walkways that front onto the street, pocket park, common open space, or open space.
- F.2. Each multi-family unit is required to provide private open space, such as a porch, patio, deck, or balcony. Refer to Chapter 2 for minimum private open space requirements for individual units.
- F.3. Porches and patios shall have a minimum depth of six (6) feet and balconies shall have a minimum depth of four (4) feet (Note: porch posts or columns may protrude into the minimum depth area).

1.3.G Colors and Materials

- G.1. Building designs shall include a minimum of one (1) principal color and a maximum of three (3) accent colors.
- G.2. The primary exterior material for buildings shall be wood, composite wood, stone, stone veneer, granite, slate, brick, brick veneer, stucco, plaster, fiber cement, aluminum/steel (color coated only), or steel. Refer to Exhibits 1-10, 1-11, and 1-12 for stylistic appropriate colors and materials.
- G.3. Changes in material or color shall occur at inside corners of intersecting walls or at architectural features that break up the wall plane, such as columns.

Windows and Doors, Entries and Porches, Colors and Materials - Refer to page A-28 for callout text.



1.3.H Residential Fencing/Walls

- H.1. Perimeter fencing type shall be wood, composite wood-textured, open style metal, stucco wall, stone and/or a combination of the listed materials.
- H.2. Where a side or rear yard is abutting a residential or commercial land use, closed wood fencing or stucco wall and/or similar composite wood-textured material shall be used. Refer to Exhibit 1-4.
- H.3. Where a side or rear yard is abutting, or open space use, wood fencing and/or similar composite wood-textured material or stucco wall shall be used to 4-feet in height with an additional 2-feet comprised on top of a minimum 50% open rail permeable fencing. Refer to Exhibit 1-6.
- H.4. Rear yard fencing adjacent to or across from Recreation or Open Space land uses shall utilize either an open style metal fence type or wood fencing and/or similar composite wood-textured material shall be used to 4-feet in height with an additional 2-feet comprised on top of a minimum 50% open rail permeable fencing. Fencing selection shall be consistent across an individual neighborhood. Refer to the Residential Single-Family Fencing Exhibit.
- H.5. If fencing required at multi-family neighborhoods (Neighborhoods 1, 2, and 10), it shall be located at required setbacks and be open style metal style. Refer to Exhibit 1-5.
- H.6. Finished side of fencing should face street side yards, open spaces, or other public spaces. The finished side of fencing is defined as the primary face of a fence.
- H.7. Use of chain link, razor/barbed wire, non-matte finish vinyl fencing, and temporary fencing, except for construction related temporary fencing, are prohibited.
- H.8. Three-rail, split rail fence of wood or similar composite wood-textured material shall be provided at streets, as shown in the Recreation and Open Space Fencing exhibit.

1.3.I Private and Common Open Spaces

- I.1. All multi-family residences shall have at least one private open space in accordance with the standards in Chapter 2 of the DRSP.
- I.2. Private open space for multi-family residences may include balconies, patios, porches, roof decks, and/or side and rear yards.
- I.3. All multi-family neighborhoods shall provide a minimum of one (1) common open space area that includes a minimum of one (1) active element (e.g. pool, play area, bocce, permanent corn hole, recreation room with exercise equipment) in accordance with the standards in Chapter 2 of the DRSP.

1.3.J Landscape

- J.1. Native trees, plants, and other low water using plant varieties shall be integrated into the neighborhoods consistent with the County Planting List and cover a minimum of 20% of the common area.
- J.2. Native coast live oak trees shall be used in neighborhood parkways.
- J.3. If irrigated turf is utilized as part of landscape design, it shall not exceed 5% of the lot area.
- J.4. Front yard landscaping shall be installed by the developer prior to occupancy by a resident.
- J.5. Landscape design shall be consistent with applicable Model Water Efficient Landscape Ordinance (MWELO) requirements for water efficiency.
- J.6. All neighborhood landscape plans shall be prepared by a licensed landscape architect.

1.3.K Lighting

- K.1. Type and design of site and building lighting fixtures shall be “dark-sky” compliant, consistent with the International Dark-Sky Association or County of San Luis Obispo requirements.
- K.2. Building lighting shall complement the architectural style of the building it serves. Refer to Exhibits 1-10, 1-11, and 1-12 for stylistic appropriate lighting.
- K.3. Special care shall be taken to control glare and direct visibility of security lighting illumination sources, and to confine illumination to the property on which the fixtures are located.

1.3.L Utilitarian

- L.1. Rain gutters, downspouts, vents, and roof protrusions shall match the adjacent building color.
- L.2. Any outdoor mechanical or utility equipment/meters, antennae, “dish type receivers”, etc., whether on a roof, side of a structure, or ground mounted shall be screened from view to not be visible from the street frontage. Method of screening shall be architecturally integrated with the adjacent structure in terms of materials, color, shape, and size, or if ground mounted, may include landscaping.
- L.3. Garages for residences shall provide storage space for trash/recycling/green waste receptacles inside the garage or if located outside the garage shall be screened from view along a side yard. For multi-family residences where consolidated locations are proposed, trash, recycling, and green waste areas shall be located within enclosures and screened from view with solid walls/fencing and/or landscape screening.

L.4. Utility service areas for multi-family buildings are required to be placed within enclosures that are architecturally integrated into the building design, unless otherwise specified by the applicable utility provider.

1.3.M Accessory Structures

M.1. Accessory structures, including detached garages and carports, accessory dwelling units, mailboxes, storage and maintenance facilities, and common area recreational facilities shall include a minimum of two (2) materials, colors, or architectural details as the primary residential buildings they serve.

1.3.N Signage

Signage for the individual neighborhoods within the DRSP shall be subject to the objective design standards below.

N.1. Future neighborhoods are required to submit a sign program for review and approval, consistent with the County's Sign Ordinance.


2.1 COMMERCIAL DESIGN GUIDELINES

The following design guidelines apply to commercial, office, hotel, and educational development within the Village Commercial and Flex Commercial land uses of the DRSP. Residential uses within the Village Commercial and Flex Commercial land uses shall meet the objective design standards of 1.3 Multi-Family Residential Objective Design Standards. As part of a permit application submittal, an analysis shall be provided to the County demonstrating how a project complies with the relevant design guidelines.

2.1.A Architectural Styles

A.1. All buildings shall be designed with an Agrarian style of architecture. However, building(s) within the Flex Commercial land use areas are allowed to use contemporary interpretations of Agrarian style to accommodate the equipment and functional requirements associated with larger structures. Refer to Exhibit 2-1.

Exhibit 2-1: Commercial Architectural Character with Contemporary Interpretations (Village Commercial shown)



- | | |
|--|--|
| ① Vertical accent massing at entries | ⑤ Accentuated lintels and sills |
| ② Long, horizontal shed and gable roofs steep in pitch e.g. 6:12 | ⑥ Accent features like wood brackets and metal vents and roofs |
| ③ Hipped roofs at attached or accent elements | ⑦ Vertical accent material e.g. board and batten siding |
| ④ Wood-like surrounds for windows and doors | |

The graphics shown above are conceptual in nature and are not intended to be reflective of a specific project, rather they are provided as inspiration for architects and designers.

2.1.B Site Design

- B.1. Buildings should be sited close to and oriented toward external streets. Building design should incorporate pedestrian walkways, outdoor seating, and landscape areas where practical.
- B.2. Parking in Village Commercial areas should be internalized behind building groups or oriented away from street frontages to minimize visual impact on the street where practical. In the Flex Commercial land use, landscaping, low walls, berms, and/or other means to minimize views of parking areas while maintaining views of buildings necessary for their success on site should be pursued.
- B.3. Plazas, courtyards, pocket parks, and outdoor cafes should be designed in an inviting manner that encourages pedestrian use through the incorporation of trellises, pergolas, art, seating, and shade trees.
- B.4. Site amenities, including benches, drinking fountains, provisions for bicyclists, and public art, should be utilized and should complement the project's architectural character.
- B.5. Streetscape at the roundabout should utilize special features such as unique street furniture, street lights, increased and planting intensity, unique signage and other special details and enhancements to assure the Village Center is a focal point of the project.


Site Design Concept




2.1.C Building Form

- C.1. The appearance of several smaller buildings, rather than one large building, should be pursued to foster an intimate, pedestrian-friendly scale.
- C.2. Vertical elements such as towers should be used to accent horizontal massing and provide visual interest, especially on corner buildings.
- C.3. For the Village Commercial, buildings shall be designed in a manner such that all sides of the building have been detailed to complement the primary street elevation in architecture, details, and materials. Buildings should be aesthetically pleasing from all angles, especially for buildings that have high visibility. Particularly in the Flex Commercial land use, buildings that require significant utility and service areas shall incorporate screening into the design of the building, site planning, and landscape design.
- C.4. For the Flex Commercial, architectural emphasis should be placed at the primary street elevations, allowing for necessary “back of house” operations at rear.
- C.5. Pedestrian scale should be created through the use of awnings, arches, walls, trellises, arbors, pergolas, and/or other architectural elements. These elements should be integrated into the building design to avoid the look of “tacked on” architectural features.
- C.6. Storefront windows, display cases, and other elements that provide visual interest to facades should be provided. Mirrored glass or reflective coatings are prohibited.
- C.7. Details such as wall surfaces constructed with patterns, changes in materials, building pop-outs, columns, and recessed areas should be used to create shadow patterns and depth on the wall surfaces.
- C.8. Building facades facing paseos or plazas should be articulated with detail and display windows.
- C.9. Murals, trellises, or vines should be placed on large expanses of walls at the rear or sides of buildings to soften the appearance and create visual interest.

Building Form (Flex Commercial Character shown)



The graphics shown above are conceptual in nature and are not intended to be reflective of a specific project, rather they are provided as inspiration for architects and designers.



*Building Form Character (Village Commercial shown) -
Refer to page A-35 for callout text.*

The graphics shown above are conceptual in nature and are not intended to be reflective of a specific project, rather they are provided as inspiration for architects and designers.

2.1.D Roofs

- D.1. A variety of roof planes and pitches, porches, overhangs, and accent details should be incorporated into the commercial designs to increase the visual quality and character of a building, while reducing the bulk and size of the structure.
- D.2. Roofs with hips and gables, are preferred in the Village Commercial land use.
- D.3. Buildings in the Flex Commercial land use are allowed to have flat or low pitched roofs but should incorporate parapets or other architectural elements to break up long horizontal rooflines. Accent mansard roofs consistent with the Agrarian style are allowed, except at building corner locations. Refer to 2.1.L Utilitarian for roof screening design guidelines.

2.1.E Windows and Doors

- E.1. Windows, doors, and service doors visible from the street should incorporate architectural detailing and color that is consistent with the overall architectural style of the building.
- E.2. Windows should be articulated with accent trim, sills, shutters, window flower boxes, awnings, trellises, and/or other elements authentic to the architectural style of the building.


2.1.F Primary Entries

- F.1. Primary entries for commercial uses should be emphasized through the use of building form, architectural detailing, lighting, landscaping, and/or unique paving, among other elements.

2.1.G Colors and Materials

- G.1. Materials and colors should be used in an authentic manner, reinforcing the chosen architectural style.
- G.2. Roof materials and colors consistent with the architectural style of the commercial use should be incorporated to enhance the character of the community.

Roofs, Windows and Doors, Primary Entries, Colors and Materials
- Refer to page A-36 for callout text.



The graphics shown above are conceptual in nature and are not intended to be reflective of a specific project, rather they are provided as inspiration for architects and designers.

G.3. Where appropriate to the architectural style, consider varying materials and textures between the base and body of a building to break up large wall planes and add a visual base to the building.

G.4. Material changes should occur at intersecting planes to appear substantial and integral to the facade. Material or color changes at the outside corners of structures should be avoided.

2.1.H Commercial Fencing

H.1. Where a commercial land use is abutting residential, open space, or recreation land uses, no side, street side, or rear yard fencing is required. Parallel walls between residential and commercial land uses are discouraged. Refer to Chapter 2 of the DRSP for relevant commercial fencing development standards.

H.2. Use of chain link, razor/barbed wire, non-matte finish vinyl fencing, and temporary fencing, except for construction related temporary fencing, are prohibited. Chain link fence may be utilized along the Highway 101 frontage, consistent with Caltrans requirements.

2.1.I Landscape

I.1. Native trees, plants, and other low water using plant varieties are encouraged within the DRSP and should be integrated into the project to the extent practical.

I.2. Native coast live oak trees shall be used within the design of commercial land uses areas, such as for street trees, parkways, and plazas.

I.3. Landscape design shall be consistent with applicable Model Water Efficient Landscape Ordinance (MWELO) requirements for water efficiency.


I.4. All landscape plans shall be prepared by a licensed landscape architect.

2.1.J Highway 101 Landscape Buffer

In order to sensitively address the DRSP adjacency to U.S. Highway 101, the following screening standards apply to commercial land uses located adjacent to U.S. Highway 101.

- J.1. A minimum 40-foot landscape buffer (20-foot PUE and 20-foot landscape buffer on-site - refer to Table 2.7 in Chapter 2) shall be provided along U.S. Highway 101 where commercial land use “back of house” areas are located directly adjacent to U.S. Highway 101. Landscape buffer plantings utilized shall be selected to be compatible with the overall character and aesthetic of the DRSP, such as oak trees and/or other native plantings.
- J.2. To the extent permissible and practical, the existing 20-foot PUE adjacent to U.S. Highway 101 shall be landscaped, consistent with So Cal Gas requirements.
- J.3. Where parking or a drive aisle is to be located directly adjacent to U.S. Highway 101, a berm, headlight hedge, and/or masonry wall no higher than 48-inches shall be provided to minimize cross highway lighting. Where masonry walls are to be used, walls shall be of a consistent design and character along the entire U.S. Highway 101 property line.

Highway 101 Landscape Buffer



J.4. Trash and recycling enclosures and loading areas should be located to minimize views from U.S. Highway 101 and screened through use of vertical growing landscaping or walls.

J.5. Any mechanical or other outdoor equipment, whether on a roof or side of a structure visible from U.S. Highway 101, should be appropriately screened from view. The method of screening should be architecturally compatible with the adjacent structure in terms of materials, colors, shape, and size and be used in combination of vertically growing landscaping, where practical.

2.1.K Lighting

K.1. Pedestrian lighting should incorporate a cohesive design that is consistent with the vision and character of the DRSP.

K.2. Fixtures for pedestrian lighting should be made of durable and high-quality materials for maximum resistance to vandalism and tampering.

K.3. Pedestrian lighting should be utilized in paseos, plazas, parking lots, and other public areas, except for open space land uses , to delineate pedestrian spaces and pathways.

K.4. Parking lot light pole bases should incorporate a cohesive design for consistency throughout the DRSP where required.

K.5. Architectural and landscape lighting should complement the architectural style of the building it serves and be dark sky compliant.

K.6. Architectural and landscape up-lighting, if proposed, should only be used to highlight special features or elements.

K.7. Ambient lighting with exposed bulbs, such as string lights, may be allowed to accent outdoor dining and seating areas, plazas, patios, and event spaces (but must be dark sky compliant).

K.8. Special care shall be taken to control glare and direct visibility of security lighting illumination sources, and to confine illumination to the property on which the fixtures are located.

2.1.L Utilitarian

- L.1. Rain gutters, downspouts, vents, and other roof protrusions should complement the adjacent building materials and/or colors.
- L.2. Any outdoor mechanical equipment, whether on a roof, side of a structure, or ground mounted should be appropriately screened from view. Method of screening should be architecturally integrated with the adjacent structure in terms of materials, color, shape, and size with solid walls/fencing and/or landscape screening.
- L.3. Utility service areas for commercial land uses should be placed within enclosures that are architecturally integrated into the building design.
- L.4. Loading and “back of house” areas should be located to the rear of a site and be adequately screened from view. Walls may be used up to six (6) to eight (8) feet in height to allow for screening and noise buffering.
- L.5. Trash enclosure and recycling storage areas should be located in convenient areas with reduced visual prominence.

2.1.M Signage

Signage for the commercial areas within the DRSP shall be subject to the design guidelines outlined below.

- M.1. Signage for the individual commercial land uses shall be consistent with the County of San Luis Obispo Sign Ordinance.

3.1 Recreation and Open Space Design Guidelines

The following design guidelines apply to Recreation and Open Space land uses within the DRSP. As part of a relevant permit application submittal, an analysis shall be provided to the County demonstrating how a project complies with the relevant design guidelines.

3.1.A Neighborhood Park

- A.1. The Neighborhood Park should be designed to provide passive neighborhood recreation needs.
- A.2. Neighborhood Park features may include bicycle racks, drinking fountains, entry signage and landscaping, picnic areas, irrigation/landscaping, parking, restrooms, trail connections, trash and recycle bins, and/or wayfinding signage.
- A.3. Any on-site parking associated with the Neighborhood Park should be located within a parking lot or other parking space configurations on the north side of the park.
- A.4. Programming of the Neighborhood Park may include shared facilities or related uses with the proposed privately owned and operated child day care facility.
- A.5. Design of the restroom building shall be consistent with an Agrarian architecture theme.

Neighborhood Park Concept



3.1.B Equestrian Staging Area

- B.1. The equestrian staging area should provide a minimum of eight (8) parking spaces that can accommodate a vehicle with trailer configuration to allow for adequately loading/off-loading and saddling of horses.

- B.2. A trailhead should be provided with hitching posts, perimeter fencing, wayfinding signage, and information kiosk.
- B.3. Temporary restroom facilities should be located to minimize visibility from the Frontage Road and adjacent neighborhoods. Landscaping, fencing, and/or other design interventions should be used to minimize visibility of these facilities.

3.1.C Basins and Low-Impact Development

A number of basins as well as roadside low-impact development areas intended to treat and mitigate runoff are proposed as part of the DRSP. The following provides design direction for basins and roadside low-impact development areas within the DRSP.

Equestrian Staging Area Concept



- C.1. Basins shall incorporate fencing, per County standards. Access gates shall be constructed of the same material and include a minimum opening of 14-feet.
- C.2. Trees, shrubs, and ground cover used for screening views of the basins shall be native, drought tolerant, and/or low water using. If landscaping is allowed within the deep basin, it shall be able to thrive during seasonal conditions while maintaining access and functionality of the facility.
- C.3. Basins should contain location appropriate landscaping that is able to thrive during seasonal conditions
- C.4. Roadside low-impact development areas should utilize a combination of decorative rock and gravel, location appropriate landscaping, and necessary inlets and/or catch basins.

3.1.D Recreation and Open Space Fencing

- D.1. Three-rail, split rail fence of wood or similar composite wood-textured material shall be used at public neighborhood parks, pocket parks, and streets, as shown in the Recreation and Open Space Fencing exhibit.
- D.2. Open style metal fence may be use at Equestrian Staging Area and shall be setback ten (10) feet from the property line, as shown on the Recreation and Open Space Fencing Exhibit.
- D.3. Use of razor/barbed wire, non-matte vinyl fencing, and temporary fencing, except for construction related temporary fencing, are prohibited. Chain link may be used to provide security for recreation land uses and basins but shall be black vinyl clad, or equivalent, with posts to match.


3.1.E Landscape

- E.1. Native trees, plants, and other low water using plant varieties are encouraged within the DRSP and should be integrated to the extent practical.
- E.2. Native coast live oak trees shall be used within the design of recreation areas, such as at trails and the neighborhood park.
- E.3. Landscape design shall be consistent with applicable Model Water Efficient Landscape Ordinance (MWELO) requirements for water efficiency.
- E.4. All landscape plans shall be prepared by a licensed landscape architect.

3.1.F Lighting

- F.1. Type and design of street and pedestrian light fixtures shall be “dark-sky” compliant.
- F.2. Street and pedestrian lighting shall incorporate a cohesive design that is consistent with the vision and character of the DRSP.
- F.3. Fixtures for street and pedestrian lighting shall be made of durable and high-quality materials for maximum resistance to vandalism and tampering.
- F.4. Pedestrian lighting shall be utilized in parking lots and other public areas, except for open space land uses, to delineate pedestrian spaces and pathways.
- F.5. Attractive parking lot light pole bases shall incorporate a cohesive design for consistency throughout the DRSP where required.
- F.6. Architectural and landscape lighting shall complement the architectural style of the building it serves.
- F.7. Architectural and landscape up-lighting, if proposed, shall only be used to highlight special features or elements.
- F.8. Ambient lighting with exposed bulbs, such as string lights, may be allowed to accent seating areas and event spaces.
- F.9. Special care shall be taken to control glare and direct visibility of illumination sources, and to confine illumination to the property on which the fixtures are located.

Recreation and Open Space Fencing



3.1.G Utilitarian

- G.1. Rain gutters, downspouts, vents, and other roof protrusions should complement the adjacent materials and/or colors.
- G.2. Any outdoor mechanical equipment, whether on a roof, side of a structure, or ground mounted should be appropriately screened from view to not be visible from the street frontage. Method of screening should be architecturally integrated with the adjacent structure in terms of materials, color, shape, and size, or if ground mounted, may include landscaping.
- G.3. Trash enclosure and recycling storage areas should be located in convenient areas with reduced visual prominence.

3.1.H Signage

- H.1. Pedestrian-oriented projecting, sculptured cantilevered, or individually crafted plaque signs are encouraged within recreation and open space areas, such as at trailheads, neighborhood park, and other open space areas.
- H.2. Recreation and open space signage within the DRSP shall complement the vision and character outlined for the project in terms of material and color use, placement, and design.
- H.3. Directional signs located at or along trails or pathways shall be a maximum size of two (2) square feet in size.
- H.4. Future signage projects are required to submit a sign program for review and approval, consistent with the County's Sign Ordinance.

4.1 Child Day Care Centers Objective Design Standards

The following objective design standards apply to the Child Day Care Center located in the neighborhood park. As part of a permit application submittal, an analysis shall be provided to the County demonstrating how a project complies with the relevant objective design standards.

4.1.A Architectural Styles

A.1. The Child Day Care Center shall be designed with an Agrarian style of architecture.

4.1.B Building Form

B.1. Massing design shall include a minimum of two (2) of the following elements: variation in wall plane with a minimum 2-foot projection/recess, a minimum 2-foot variation in wall height, and/or a minimum of two roof planes and pitches at different levels..

4.1.C Roofs

C.1. A minimum of two (2) roof planes and pitches, overhangs, and/or accent details shall be incorporated into home designs to increase the visual quality and character of a building.

4.1.D Windows and Doors

D.1. Windows shall be articulated with a minimum of two (2) of the following elements: accent trim, sills, shutters, window flower boxes, awnings, trellises, and/or other elements authentic to the architectural style of the building.

D.2. Mirrored glass and/or reflective coating on doors and window glass and garage doors is prohibited.

4.1.E Colors and Materials

E.1. Building designs shall include a minimum of one (1) principal color and a maximum of three (3) accent colors.

E.2. The primary exterior material for buildings shall be wood, composite wood, stone, stone veneer, granite, slate, brick, brick veneer, stucco, plaster, fiber cement, aluminum/steel (color coated only), or steel.

E.3. Changes in material or color shall occur at inside corners of intersecting walls or at architectural features that break up the wall plane, such as columns.

4.1.F Recreation and Open Space Fencing

F.1. Three-rail, split rail fence of wood or similar composite wood-textured material shall be used at public neighborhood parks, pocket parks, and streets, as shown in the Recreation and Open Space Fencing exhibit.

F.2. Open style metal fence may be use at Child Day Care Center and shall be setback ten (10) feet from the property line, as shown on the Recreation and Open Space Fencing Exhibit.

F.3. Use of razor/barbed wire, non-matte vinyl fencing, and temporary fencing, except for construction related temporary fencing, are prohibited. Chain link may be used to provide security for recreation land uses and basins but shall be black vinyl clad, or equivalent, with posts to match.

4.1.G Landscape

- G.1. Native trees, plants, and other low water using plant varieties shall be integrated into the landscape design, consistent with the County Planting List, and cover a minimum of 10% of a lot.
- G.2. If irrigated turf is utilized as part of landscape design, it shall not exceed 5% of the lot area.
- G.3. Front yard landscaping shall be installed by the developer prior to occupancy by the child day care center.
- G.4. Landscape design shall be consistent with applicable Model Water Efficient Landscape Ordinance (MWEL) requirements for water efficiency.
- G.5. All landscape plans shall be prepared by a licensed landscape architect.

4.1.H Lighting

- H.1. Type and design of site and building lighting fixtures shall be “dark-sky” compliant, consistent with the International Dark-Sky Association or County of San Luis Obispo requirements.
- H.2. Special care shall be taken to control glare and direct visibility of security lighting illumination sources, and to confine illumination to the property on which the fixtures are located.

4.1.I Utilitarian

- I.1. Rain gutters, downspouts, vents, and roof protrusions shall match the adjacent building colors.
- I.2. Any outdoor mechanical or utility equipment/meters, antennae, “dish type receivers”, etc., whether on a roof, side of a structure, or ground mounted shall be screened from view to not be visible from the street frontage. Method of screening shall be architecturally integrated with the adjacent structure in terms of materials, color, shape, and size, or if ground mounted, may include landscaping.

4.1.J Signage

- Signage for child day care centers within the DRSP shall be subject to the objective design standards outlined below.
- J.1. Signage for the individual commercial land uses shall be consistent with the County of San Luis Obispo Sign Ordinance.

5.1 Gateways and Wayfinding Signage Design Guidelines

Gateway and wayfinding signage are important elements to bring attention to and direct future residents and visitors of the DRSP. The following design guidelines are relevant to the gateway and wayfinding signage for the DRSP. As part of a relevant permit application submittal, an analysis shall be provided to the County demonstrating how a project complies with the relevant design guidelines.

1. Primary gateway monuments shall be provided at Frontage Road/Willow Road, Collector B/Willow Road, and at the intersection of Frontage Road/1st Intersection. Signage face containing the text portion of the primary gateway monuments will be approximately 12-feet high by 20-feet wide, excluding raised planter area at base of the sign and the vertical support.
2. Secondary gateway monuments shall be provided at Frontage Road/Cherokee Place, Collector B/Cherokee Place, and Collector B/Pomeroy Road.
3. All gateway monuments shall utilize an agrarian architecture theme that reflects the DRSP character, with similar materials and colors as shown in the concepts below.
4. Gateway monuments shall incorporate a combination of decorative walls, accent landscaping, enhanced paving, accent lighting, and specimen trees - preferably coast live oaks.
5. Secondary gateway shall be subordinate to the primary gateways but will maintain consistency in terms of materials and colors and decorative elements utilized.
6. Wayfinding and directional signage should be located at key locations within the DRSP to provide direction to important services and destinations, such as commercial areas, parks, trailheads, or trail crossings.
7. Design of other wayfinding and directional signage shall be in keeping with the DRSP character and then theming of the gateway signage.

Primary Gateway Concept - Frontage Road at Southeast Entry



Primary Gateway Concept - Frontage Road at Willow Road



6.1 Park and Ride and Transit Stops Design Guidelines

The following design guidelines are applicable to the Park and Ride facility and transit stops within the DRSP. As part of a relevant permit application submittal, an analysis shall be provided to the County demonstrating how a project complies with the relevant design guidelines.

1. The Park and Ride shall contain a minimum of eighty (80) parking spaces.
2. Signage and lighting required for the Park and Ride facility shall be consistent with County requirements.
3. Any required shelter, signage, or lighting for transit stops within the DRSP shall be subject to the requirements of the San Luis Obispo Regional Transit Authority.
4. Native trees, plants, and other low water using plant varieties are encouraged within the DRSP and should be integrated to the extent practical.

Park and Ride Concept



B. Phasing and Public Improvements Implementation Matrix

The following phasing and public improvements implementation matrix contains detailed descriptions of the anticipated order of buildout of the DRSP and builds upon the information described in Chapter 5: Infrastructure and Phasing. Phases shown address goals to accommodate orderly development and provision of services. They represent a reasonable approach to extending services and infrastructure throughout the DRSP. In some cases, property owners may wish to develop phases concurrently or in a different order than anticipated. This will be permitted provided all public improvements needed to support proposed development are completed, and that circulation is provided for secondary access, as further discussed in Chapter 7, Implementation and Administration.

		Neighborhood's / Lots									
		1									
Phase		1A	1A	1A	1A	1A	1A	1A	1A	1A	1B
Neighborhood Designations		1 (MF)	2 (MF)	3	5	N/A	Lot 11	Lot 17 & 18	Lot 13-16	Flex Comm	
Lot Numbers (see Master Vesting Tentative Tract No. 3159)		Lot 1	Lot 2	Lot 3	Lot 5	Lot 11	Lot 17 & 18	Lot 13-16	Flex Comm		
Circulation	Collector A to Willow (Includes N. Frontage Road from property boundary to Sandy Dale Dr.)	X	X	X	X	X	X	X	X		
	Park and Ride along Collector A (near Willow)	X	X	X	X	X	X	X	X		
	Willow and Collector A intersection	X	X	X	X	X	X	X	X		
	Portion of Collector C (Eastern 600' +/-)	X	X	X	X	X	X	X	X		
	Local Road D (Connects Collector A & C)	X	X	X	X	X	X	X	X		
	Collector B (From Pomeroy Rd. to Collector C)										
	Collector B (From Collector C to Willow Rd. (Within 24 months. of permit issuance)										
	Portion of Collector B (Northern 1300' +/- from Pomeroy)										
	Collector B (After 150 Dwelling units or within 36 months of permit issuance)										
	Collector B (Pomeroy to Willow)										
	Pomeroy and Collector B intersection										
	Collector B and Willow intersection										
	Hefrick Avenue & Pomeroy Intersection										
Sewer	Conversion of a segment of Hefrick to Emergency Access only										
	Collector C (between Collector B and Local Road D)										
	Collector C (between Collector A and B) & County Park										
	Closure of Hefrick Avenue and Pomeroy Road										
	Extension of Sewer in North Frontage Road and Collector A + Lift Station for DR flows	X	X	X	X	X	X	X	X	X	X
	Sewer in Collector C (Eastern 600' +/-)										
	Sewer in Local Road (North Eastern 675' +/-)	X	X	X	X	X	X	X	X	X	X
	Sewer from Collector A to Collector B - Provide stub for Phase 3										
	Sewer Main in Collector B										
	Lift Station to Serve Neighborhood 9										
	Lift Station to Serve Neighborhood 8										

Note: "X" indicates which prerequisite backbone infrastructure component must be constructed or installed before the development of each lot.

		Neighborhood's / Lots									
		1									
	Phase	1A	1A	1A	1A	1A	1A	1A	1A	1A	1B
	Neighborhood Designations	1 (MF)	2 (MF)	3	5	N/A	Village Comm	Flex Comm			
	Lot Numbers (see Master Vesting Tentative Tract No. 3159)	Lot 1	Lot 2	Lot 3	Lot 5	Lot 11	Lot 17 & 18	Lot 13-16			
Water	Extend Water Infrastructure in North Frontage Road / Collector A to Willow	X	X	X	X	X	X	X			
	Water in Collector C (Eastern 600' +/-)	X	X	X	X	X	X	X			
	Water in Local Road (North Eastern 675' +/-)	X	X	X	X	X	X	X			
	Water in Collector B (connecting Pomeroy and Willow)										
	Water in Collector C (between Collector A and B)										
	Water in Local Road (between NBD 2 and 4)										
Storm Drain	Storm Drain Infrastructure in Collector A (including basins)	X	X	X	X	X	X	X			
	Storm Drain in Collector C (600' +/-)										
	Storm Drain Infrastructure in Collector B (including basins near Pomeroy and on the west side of the Park)										
	Large Basin NBD 9 include the infrastructure										
	Storm Drain Infrastructure in Collector C (including basins near Neighborhood 6)										
Note: "X" indicates which prerequisite backbone infrastructure component must be constructed or installed before the development of each lot.											

	Phase	Neighborhood's / Lots											
		2					3						
		2A	2A	2A	2B	3	3	3	3	3	3	3	3
	Neighborhood Designations Lot Numbers (see Master Vesting Tentative Tract No. 3159)	7	8	Lot 8	Lot 9 & 10	Lot 4	Lot 6	Lot 10	Lot 44	Daycare	Lot 20		
Circulation	Collector A to Willow (Includes N. Frontage Road from property boundary to Sandy Dale Dr.)												
	Park and Ride along Collector A (near Willow)												
	Willow and Collector A Intersection												
	Portion of Collector C (Eastern 600' +/-)												
	Local Road D (Connects Collector A & C)												
	Collector B (From Pomeroy Rd. to Collector C)												
	Collector B (From Collector C to Willow Rd. (Within 24 months. of permit issuance)												
	Portion of Collector B (Northern 1300' +/- from Pomeroy)	X	X		X								
	Collector B (After 150 Dwelling units or within 36 months of permit issuance)	X	X		X								
	Collector B (Pomeroy to Willow)					X	X		X		X		
	Pomeroy and Collector B Intersection	X	X		X								
	Collector B and Willow Intersection	X	X		X								
	Helrick Avenue & Pomeroy Intersection	X	X		X								
	Conversion of a segment of Helrick to Emergency Access only	X	X		X								
Sewer	Collector C (between Collector B and Local Road D)					X	X		X		X		
	Collector C (between Collector A and B) & County Park												
	Closure of Helrick Avenue and Pomeroy Road	X	X		X								
	Extension of Sewer in North Frontage Road and Collector A + Lift Station for DR flows												
	Sewer in Collector C (Eastern 600' +/-)					X	X		X		X		
	Sewer in Local Road (North Eastern 675' +/-)												
	Sewer from Collector A to Collector B - Provide stub for Phase 3	X	X		X								
	Sewer Main in Collector B	X	X		X								
	Lift Station to Serve Neighborhood 9				X								
	Lift Station to Serve Neighborhood 8	X	X		X								
Note: "X" indicates which prerequisite backbone infrastructure component must be constructed or installed before the development of each lot.													

Note: "X" indicates which prerequisite backbone infrastructure component must be constructed or installed before the development of each lot.

		Neighborhood's / Lots									
		2					3				
Phase		2A	2A	2B	3	3	3	3	3	3	3
Neighborhood Designations		7	8	9	4	6	10	Daycare			
Lot Numbers (see Master Vesting Tentative Tract No. 3159)		Lot 7	Lot 8	Lot 9 & 10	Lot 4	Lot 6	Lot 44	Lot 20			
Water	Extend Water Infrastructure in North Frontage Road / Collector A to Willow										
	Water in Collector C (Eastern 600' +/-)										
	Water in Local Road (North Eastern 675' +/-)										
	Water in Collector B (connecting Pomeroy and Willow)	X	X	X							
	Water in Collector C (between Collector A and B)				X	X	X	X	X	X	X
	Water in Local Road (between NBD 2 and 4)				X	X	X	X	X	X	X
Storm Drain	Storm Drain Infrastructure in Collector A (including basins)										
	Storm Drain in Collector C (600' +/-)				X	X	X	X	X	X	X
	Storm Drain Infrastructure in Collector B (including basins near Pomeroy and on the west side of the Park)	X	X	X							
	Large Basin NBD 9 include the infrastructure	X	X	X							
	Storm Drain Infrastructure in Collector C (including basins near Neighborhood 6)				X	X	X	X	X	X	X

Note: "X" indicates which prerequisite backbone infrastructure component must be constructed or installed before the development of each lot.

This Page Intentionally Blank.

C. Mitigation Monitoring and Reporting Program

Refer to the Dana Reserve Specific Plan Final Environmental Impact Report SCH No. 2021060558, Chapter 7 Mitigation Monitoring and Reporting Program, dated April 2024 and the 2025 Addendum.

This Page Intentionally Blank.